

- Install new Hardie panel board-and-batten exterior siding, paint and finish
- Shaft Wall includes:
 - 2hr. UL rated shaft wall per A 4.0 to extend from the 1st floor to expanded attic above the 2nd floor
 - Includes rated ceiling above the proposed elevator
- Finishes include:
 - 1st Floor: New stained concrete flooring, refinished to match the existing
 - New milled cypress wainscot to 7 feet (top pf cab door)
 - 2nd Floor: new heart Pine flooring, to match the existing
 - New door trim and fire doors to elevator vestibule

Elevator

- Elevator includes:
 - One, two stop hole-less hydraulic elevator by Mowrey Elevators
 - Stop elevator controls with Braille buttons and ADA telephone
 - ME 200 cab design
 - Standard finishes
- Electrical includes Supply and install circuits and make connections to new elevator.

A. Old Willis Dairy-Carriage House (Elevator Total cost)	\$127,270
B. Old Willis Dairy-Barn (Elevator Total cost)	<u>\$177,450</u>
Total Cost to add (2) ADA compliant Elevators.....	\$304,720