EVALUATION REPORT OF METAL SALES MANUFACTURING CORPORATION '26 GA. STILE PANEL'

FLORIDA BUILDING CODE 5TH EDITION (2014) FLORIDA PRODUCT APPROVAL FL 11560.9-R2 ROOFING METAL ROOFING

Prepared For:
Metal Sales Manufacturing Corporation
545 South 3rd Street, Suite 200
Louisville, KY 40202
Telephone: (502) 855-4300
Fax: (502) 855-4290

Prepared By:
Bala Sockalingam, Ph.D., P.E.
Florida Professional Engineer #62240
1216 N Lansing Ave., Suite C
Tulsa, OK 74106
Telephone: (918) 492-5992
FAX: (866) 366-1543

This report consists of Evaluation Report (3 Pages including cover) Installation Details (2 Pages)

> Report No. C2009-9 Date: 3.27.15



FL 11560.9-R2 C2009-9 3.27.15 Page 2 of 3

Manufacturer: Metal Sales Manufacturing Corporation

Product Name: Stile

Panel Description: 39.4" wide coverage with (9) 1-3/16" high, 5" wide and 12" long

simulated tile profile

Materials: Min. 26 ga., 40 ksi steel. Galvanized coated steel (ASTM A653) or

Galvalume coated steel (ASTM A792) or painted steel (ASTM A755).

Deck Description: Min. 19/32" thick plywood for new and existing constructions.

Designed and installed as per FBC 2014.

Deck Attachment:

(Minimum)

8d x 2.5" long ring shank nails or #8 x 2" long wood screws @ 6" o.c.

in the plywood field and edges

Minimum underlayment as per FBC 2014 Section 1507.4.5.1 Underlayment:

1/2:12 or greater in accordance with FBC 2014 Section 1507.4.2 Slope:

50.4 psf @ fastener spacing of 36" o.c. (Fastener Pattern 1) Design Uplift Pressure: (Factor of Safety = 2) 106.8 psf @ fastener spacing of 24" o.c. (Fastener Pattern 1)

149.6 psf @ fastener spacing of 12" o.c. (Fastener Pattern 2)

Fastener Pattern:

At panel ends: ¹/₄"-14 x 1-1/2" long ABMP fasteners @ each valley ¹/₄"-14 x 1-1/2" long ABMP fasteners @ each other valley At intermediate:

At panel ends: ¹/₄"-14 x 1-1/2" long ABMP fasteners @ each valley 2 At intermediate: ¹/₄"-14 x 1-1/2" long ABMP fasteners @ each valley

1/8" Diameter x 3/16" long steel pop rivets @ 12" o.c. Sidelap Attachment:

Test Standards: Roof assembly tested in accordance with TAS 125-03 'Standard

Requirements for Metal Roofing Systems'.

Code Compliance: The product described herein has demonstrated compliance with FBC

2014 Section 1507.4

Product Limitations: Design wind loads shall be determined for each project in accordance

with FBC 2014 Section 1609 or ASCE 7-10 using allowable stress design. The maximum fastener spacing listed herein shall not be exceeded. This evaluation report is not applicable in High Velocity Hurricane Zone. Refer to current NOA for use of this product in High Velocity Hurricane Zone. Fire classification is not within scope of this Evaluation Report. Refer to FBC 2014 Section 1505 and current

FL 11560.9-R2 C2009-9 3.27.15 Page 3 of 3

approved roofing materials directory or ASTM E108/UL790 report

from an accredited laboratory for fire ratings of this product.

Supporting Documents: TAS 125-03 Test Reports

Farabaugh Engineering and Testing Inc Project No. T202-05, Reporting Date 10/3/05

Project No. T209-07, Reporting Date 6/14/07, Revised Date 6/27/07



