EVALUATION REPORT OF METAL SALES MANUFACTURING CORPORATION '26 GA. IMAGE II PANEL'

FLORIDA BUILDING CODE 5TH EDITION (2014) FLORIDA PRODUCT APPROVAL FL 11560.4-R2 ROOFING METAL ROOFING

Prepared For: Metal Sales Manufacturing Corporation 545 South 3rd Street, Suite 200 Louisville, KY 40202 Telephone: (502) 855-4300 Fax: (502) 855-4290

Prepared By: Bala Sockalingam, Ph.D., P.E. Florida Professional Engineer #62240 1216 N Lansing Ave., Suite C Tulsa, OK 74106 Telephone: (918) 492-5992 FAX: (866) 366-1543

This report consists of Evaluation Report (2 Pages including cover) Installation Details (1 Page)

> Report No. C2009-4 Date: 3.27.15



Manufacturer: Metal Sales Manufacturing Corporation Product Name: Image II Panel Description: Max. 16" wide coverage with 1" high ribs Min. 26 ga., 50 ksi steel. Galvanized coated steel (ASTM A653) or Materials: Galvalume coated steel (ASTM A792) or painted steel (ASTM A755). Deck Description: Min. 15/32" thick plywood for new and existing constructions. Designed and installed as per FBC 2014. Deck Attachment: 8d x 2.5" long ring shank nails or #8 x 2" long wood screws @ 6" o.c. (Minimum) in the plywood field and @ 4" o.c. at edges New Underlayment: Minimum underlayment as per FBC 2014 Section 1507.4.5.1 Existing Underlayment: One layer of asphalt shingles over one layer of #30 felt. For reroofing (Optional) construction only. Slope: 2:12 or greater in accordance with FBC 2014 Section 1507.4.2 Design Uplift Pressure: 84.25 psf @ fastener spacing of 24" o.c. (Factor of Safety = 2) Fastener Pattern #10-12 pancake head screws along panel seam. Fastener shall be of sufficient length to penetrate through the deck a minimum of $\frac{1}{4}$ ". Test Standards: Roof assembly tested in accordance with TAS 125-03 'Standard Requirements for Metal Roofing Systems'. Code Compliance: The product described herein has demonstrated compliance with FBC 2014 Section 1507.4 **Product Limitations:** Design wind loads shall be determined for each project in accordance with FBC 2014 Section 1609 or ASCE 7-10 using allowable stress design. The maximum fastener spacing listed herein shall not be exceeded. This evaluation report is not applicable in High Velocity Hurricane Zone. Fire classification is not within scope of this Evaluation Report. Refer to FBC 2014 Section 1505 and current approved roofing materials directory or ASTM E108/UL790 report from an accredited laboratory for fire ratings of this product. Supporting Documents: TAS 125 Test Reports Hurricane Test Laboratory, LLC HTL Report #: 0103-0714-09, Reporting Date 9/1/09

