EVALUATION REPORT OF METAL SALES MANUFACTURING CORPORATION '24 GA. MAGNA-LOC PANEL'

FLORIDA BUILDING CODE 6TH EDITION (2017) FLORIDA PRODUCT APPROVAL FL 11560.6-R3 ROOFING METAL ROOFING

Prepared For:
Metal Sales Manufacturing Corporation
545 South 3rd Street, Suite 200
Louisville, KY 40202
Telephone: (502) 855-4300
Fax: (502) 855-4200

Prepared By:
Bala Sockalingam, Ph.D., P.E.
Florida Professional Engineer #62240
1216 N Lansing Ave., Suite C
Tulsa, OK 74106
Telephone: (918) 492-5992
FAX: (866) 366-1543

This report consists of Evaluation Report (3 Pages including cover) Installation Details (1 Page)

> Report No. C2181-6 Date: 9.8.2017



Manufacturer: Metal Sales Manufacturing Corporation

Product Name: Magna-Loc

Panel Description: Standing seam panel with 16" wide coverage and 2" high ribs

Materials: Min. 24 ga., 50 ksi steel. Galvanized coated steel (ASTM A653) or

Galvalume coated steel (ASTM A792) or painted steel (ASTM A755).

Deck Description: Min. 19/32" plywood or min. 3/4" thick wood plank (min SG of 0.42)

for new and existing constructions. Designed by others and installed

as per FBC 2017.

Deck Attachment:

(Minimum)

Minimum attachment: 8d x 2.5" long ring shank nails or #8 x 2" long

wood screws @ 6" o.c. in the field and edges.

Deck fastener spacing @ 3" o.c. in the field and edges in roof zones

installed with MPW-1203-8 clip. Designed as per FBC 2017.

Underlayment: Minimum underlayment as per FBC 2017 Section 1507.4.5.1.

Substrate (optional): Min 1" x 4" No. 2 SYP wood purlins over min. 19/32" thick plywood

deck fastened to supports at maximum 24" o.c. Wood purlins shall be fastened to wood rafters with (2) #9 x 3" long wood screws. The wood purlins will be spaced same as panel fastener spacing along panel length. The wood purlin, purlin to the rafter connection and rafters must be designed by others to the carry the load imposed on the panels

and installed as per FBC 2017.

Slope: 1/4:12 or greater in accordance with FBC 2017 Section 1507.4.2

Design Uplift Pressure: 95.2 psf @ MC 1203 clip spacing of 30" o.c.

101.0 psf @ MC 1203 clip spacing of 15" o.c. 123.5 psf @ MC 1203 clip spacing of 8" o.c. 166.0 psf @ MPW-1203-8 clip spacing of 12" o.c.

Panel Attachment: MC 1203 clip with (2) #12-11 x 1-1/2" long low profile wood screws

per clip

MPW-1203-8 clip with (4) #12-11 x 1-1/2" long low profile wood

screws per clip

Test Standards: Roof assembly tested in accordance with TAS 125-03 'Standard

Requirements for Metal Roofing Systems'.

Code Compliance: The product described herein has demonstrated compliance with FBC

2017 Section 1507.4

FL 11560.6-R3 C2181-6 9.8.2017 Page 3 of 3

Product Limitations:

Design wind loads shall be determined for each project in accordance with FBC 2017 Section 1609 or ASCE 7-10 using allowable stress design. The maximum clip spacing listed herein shall not be exceeded. The design pressure for reduced clip spacing may be computed using rational analysis prepared by a Florida Professional Engineer. This evaluation report is not applicable in High Velocity Hurricane Zone. Refer to current NOA for use of this product in High Velocity Hurricane Zone. Fire classification is not within scope of this Evaluation Report. Refer to FBC 2017 Section 1505 and current approved roofing materials directory or ASTM E108/UL790 report from an accredited laboratory for fire ratings of this product.

Supporting Documents: TAS 125 Test Reports

Farabaugh Engineering and Testing Inc. Project No. T242-08, Reporting Date 8/25/08 Project No. T292-14, Reporting Date 9/19/14

