



September 12, 2016
A&S Courier International, LLC
Mr. Julio Mijares
7620 NW 25th Street, Suite 2
Miami, Florida 33122

Dear Mr. Mijares, in behalf of HL Projects & Construction, LLC (HLPC), I am pleased to submit this quote for **FORTY ONE THOUSAND, ONE HUNDRED AND FIFTY DOLLARDS (\$41,150.00)** to furnish and install one (1) enclosed wheelchair lift to include electrical and structural modifications, shop drawings and permit as required to complete said installation in accordance with the plans prepared by P.A. Architect, Inc.

This quote is based on plans and the general intent of the bid letter which serves to further clarify the basis for the above price. This quote is valid for 60 days.

HLPC can proceed with preparation of layout drawings for review and approval with receipt of one (1) full set of plans and specifications, a copy of the preliminary schedule, and the Subcontract Agreement. We will require receipt of a fully executed subcontract agreement, including any attached amendments, along with payment for pre-production and engineering prior to the release of the elevator equipment for fabrication. An invoice equal to 40% of the above quoted price representing pre-production and engineering costs will be provided for your convenience upon acceptance of this proposal.

Should you have any questions please feel free to contact me at your convenience at (956) 648-9799 or by email at hlugot@gmail.com.

Respectfully,

A handwritten signature in blue ink, appearing to read 'Hernan Lugo', is written over a light yellow rectangular background.

Hernan Lugo, P.E.



EQUIPMENT SPECIFICATIONS

Number of Units:	1
Lifting Height:	12' plus
Rated Load:	600lbs (272 kg)
Drive:	Belt driven Acme screw / 90 VDC ½ hp motor. Optional 24 VDC battery powered unit
Power Supply:	115 VAC – 20 Amp grounded circuit / 220 VAC (optional)
Control Circuit:	24 VAC (Low Voltage Controls)
Platform:	36" x 60" with 36" high solid guard panels and automatic folding ramp
Footprint:	50" x 70"
Speed:	10 fpm
Controls:	Rocker switch w/emergency stop (key switch optional)
Manual Lowering:	Provided
Safety Design Standards:	ASME A18.1, Section 5 – Private Residence Vertical Platform Lifts
Safety Design:	CSA B44.1 / ASME 17.5 – Elevator and Escalator Equipment
Safety Features:	Safety Pan, Final limit, Acme safety nut with monitor, Non-skid Surface
Warranty:	2-Year Parts / 1-Year Unit