



FASTENING SCHEDULE		
DESCRIPTION	NUMBER & TYPE OF FASTENER	SPACING & LOCATION
BLOCKING BETWEEN CEILING JOIST	3-10d BOX	EACH EN., TOE NAIL
BLOCKING BETWEEN RAFTER OR TRUSS	2-8d COMMON	EACH EN., TOE NAIL
FLAT BLOCKING TO TRUSS AND WEB FILLER	16d COMMON	FACE NAIL
CEILING JOIST TO TOP PLATE	10d BOX	EACH JOIST
COLLAR TIE TO RAFTER	10d BOX	FACE NAIL
RAFTER OR ROOF TRUSS TO TOP PLATE	3-16d BOX	TOENAIL
ROOF RAFTERS TO RIDGE VALLEY OR HIP RAFTERS	2-16d COMMON	ENDNAIL
STUD TO STUD	16d COMMON	24" O.C. FACE NAIL
STUD TO STUD AND ABUTTING STUDS	16d COMMON	24" O.C. FACE NAIL
BUILT-UP HEADER	16d COMMON	16" O.C. EACH EDGE, FACE NAIL
CONTINUOUS HEADER TO STUD	4-8d COMMON	TOE NAIL
TOP PLATE TO TOP PLATE	16d COMMON	16" O.C. FACE NAIL
TOP PLATE TO TOP PLATE @ END JOIST	16d COMMON	EACH OF END JOIST
BOTTOM PLATE TO JOIST	16d COMMON	16" O.C. FACE NAIL
1"x6" SHEATHING TO EACH BEARING	2-8d COMMON	FACE NAIL

ISSUE	DATE
3. CITY OF MIAMI COMMENTS	12/23/2022
4. CITY OF MIAMI COMMENTS	01/27/2023

AMERICANO MEDIA GROUP STUDIO
2920 NW 7 ST
MIAMI, FL 33125

PROJECT:
INTERIOR REMODELING

AHU ROOM

VECTOR
Engineering Services

7875 NW 12th Street, Ste. 101
Doral, FL 33126
(786) 762-2204
www.ves-us.com
C.A. #32810

FELIX F. RODRIGUEZ, PE, SE
FLORIDA PE #74481
Civil, Structural, Mechanical
admin@ves-us.com

VDES PROJECT #220078	
DATE	08/15/2022
SHEET	S-02