

Estimate for Jan Powell DBA Ant Hill LLC

**Proposed Work For
Passenger Lift
1590 Village Square Blvd.
Tallahassee, Florida 32309**

May 6, 2022

**Provided By
Kidd Construction, Inc.
3846 Killearn Court
Tallahassee, Florida 32309
CBC 1256257
Ph:(850) 510-2382
Email: tonykiddconstruction@gmail.com**

ELEVATOR/PASSENGER LIFT**Site Work:**

Site work for grade alterations for conforming access at lower level.

Site work to consist of removal of all organic materials in working area, determination of and alteration of grade, slope and footprint for concrete placement.

Subtotal Site Work **\$3,500.00**

Upper Level Walkway:

Alteration of existing stormwater system as required.

Form and pour concrete as required for ADA compliant access to elevator/
passenger lift.

Subtotal Upper Level Walkway **\$4,500.00**

Lower Level Walkway:

Form and pour concrete as required for ADA compliant access to elevator/
passenger lift.

Subtotal Lower Level Walkway **\$3,400.00**

Concrete Pump:

Concrete Pump estimated labor and materials for 8 hours

Subtotal Concrete Pump **\$1,400.00**

Railing/Guardrail:

Aluminum guardrail installed at walkway to be ADA compliant as noted in Civil Plan Set. All guardrail, railing and/or handrail to consist of all aluminum, welded construction, with stainless steel or non-corrosive fasteners fasteners at base.

Subtotal Railing/Guardrail **\$3,400.00**

Elevator/Vertical Passenger Lift:

Lift to consist of 36" x 54" clear platform with battery backup, stationary ramp, EMI interlock, Emergency Light/Alarm and 36" upper landing gate with interlock.

Includes installation

Subtotal Elevator/Passenger Lift: **\$23,740.00**

Notes:

The costs shown above are estimates based upon plans provided by Owner.

Subtotal Costs **\$39,940.00**

May 6, 2022

20% OH & P **\$7,988.00**

ESTIMATED TOTAL COST **\$47,928.00**