Impact Performance
Certification Authorization Report

Viwinco, Inc.

851 Hemlock Rd, Morgantown Business Park
Morgantown, PA 19543, USA

Certification ID:	464-222
Company Code:	464
Certification Date:	8/15/2012
Revision No:	2
Revision Date:	6/6/2025
Expiration Date:	8/3/2028

Product Rating Information:

Model:	Oceanview Imp Awning/Fixed Stacked Comb Ass'y			
Operator Type:	AP			
Configuration:	H/S/J/Mull/All/Snub, GS-5/16" Ann Lami IG			
Referenced Standard:	ASTM E1886-13a/E1996-17			
Product Rating:	Missile Level D, Wind Zone 3, DP +/-50, 60x72			
Rated Dimensions:	**Max Width:**	60 in	**Max Height:**	72 in
Linked Structural CARs:	464-437.0			

Qualifying Test information:

Test Report No:	ATI-B9410.01-109-47
Test Report Expiration:	8/3/2028

This Certification Authorization Report (CAR) is issued by Keystone Certifications, Inc. (KCI) after full validation review, and is based on a standardized evaluation of the product conducted by an independent accredited laboratory in accordance with the specified referenced standard. Actual fenestration product performance may vary based on many factors, including installation, condition of the wall/roof substrate and the age of the product and installation components.

This report indicates the product is eligible for the application of Keystone Certification Program certification labels. Licensee stipulates in affixing certification labels to products, that those products are representative of the specimen evaluated and documented for certification authorization. Only products bearing such a certification label shall be considered certified. The information in this report can be verified at www.keystonecerts.com

ANAB
ANSI National Accreditation Board
ACCREDITED
ISO/IEC 17065
PRODUCT CERTIFICATION BODY

Authorized By: Shaun Shaull 2025.06.06 07:19:14 -04'00'

Keystone Certifications, Inc.
145 Limekiln Rd, Suite 100B
New Cumberland, PA 17070
Phone: 717-932-8500

Revision History

Rev #	Date	Description
0	8/15/2012	Initial Issuance
1	7/28/2022	Granted 3 Year Extension
2	6/6/2025	Granted 3 Year Extension