



5V

FLORIDA PRODUCT APPROVAL

FL 47828.01 R1

26ga 5V on 15/32" plywood

Product Description: 5V style exposed fastener metal roof panel with 24" coverage and nominally 1/2" tall rib.


Material: 26ga (min) steel. Thicker gauge steel is acceptable. Compliant with FBC 1507.4.3 where required.

Fastener: #10 x 1.5" fastener with sealing washer. Compliant with FBC 1507.4.4 and FBC 1711 where required.


Substrate: 15/32" (min) plywood. Thicker plywood is acceptable.

Method	Attachment	Max Design Pressure
Method A	Fasteners in nominally 12"-12" pattern, with fastener rows at 16" o.c.	93.5 psf
Method B	Fasteners in nominally 12"-12" pattern, with fastener rows at 6" o.c.	131 psf

*MDP shown is allowable pressure. Safety factor of 2.0 has been applied.



Evaluated by David Eng, PE
Timberlake Cove, LLC
FL PE 81377 • FL CA 33344
1317 Edgewater Dr Ste 2339
Orlando FL 32804
timberlakecove.com



David Eng

David E Eng
2026.08.21
14:40:27 -
06'00'

This item has been digitally signed and sealed by D.E. Eng, PE, on the date indicated. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies



5V

FLORIDA PRODUCT APPROVAL

FL 47828.01 R1

MetalMax • 900 Cpt. Joe Fulghum Drive Murfreesboro, Tennessee 37129 • Other facilities located throughout the USA • 615-494-1693 • www.MetalMax.com

Underlayment: Comply with FBC 1507.1.1 where required.

Slope: Comply with FBC 1507.4.2 where required.

Re-Roofing: This panel may be installed over a single layer of existing roofing when permitted by local building code or FBC 1511.

Metal Hip & Ridge Cover: Comply with FBC 1504.3.1.1 where applicable.

Compliance statement: This product as described has demonstrated compliance with Florida Building Code 2026 (9th Edition), 1504.3.2 (non-HVHZ), as required by FL Rule 61G20-3, method 1D.

Technical Documentation: This product has been tested to the UL 580/1897 standard by Intertek Testing (TST-1527), report I8426.01-450-44 as referenced in FL28402.1 R3.

Design Process: Compare the maximum allowable loads to the ASD uplift pressures for the project to determine sufficiency and installation requirements. Engineering analysis may be completed by other licensed engineers for project specific approval by local authorities having jurisdiction.

Certification of Independence: David Eng, PE and Timberlake Cove, LLC do not have, nor will acquire a financial interest in any company manufacturing or distributing products under this evaluation. The same entities do not have, nor will acquire, a financial interest in any other entity involved in the approval process of the product.

Exclusions and Limitations: Design of deck and roof structure (to include attachment of plywood or wood plank) shall be completed by others. Fire classification and shear diaphragm design are outside the scope of this evaluation. Accelerated weathering/salt spray is outside the scope of this evaluation. Metal hip and ridge cover is outside the scope of this evaluation.

This report is limited to compliance with structural wind load requirements of FBC 1504.3.2, as required by Rule 61G20-3. Neither Timberlake Cove nor the manufacturer shall be responsible for any conclusions, interpretations, or designs made by others based on this evaluation report. This report is limited solely to documenting compliance with Rule 61G20-3, and makes no express or implied warranty regarding performance of this product. Installation shall be subject to the local building code and authority having jurisdiction; this report shall not be construed to supersede local codes in force.