

REVISIONS			
REV	DESCRIPTION	DATE	APPROVED
G	REVISED COMPONENTS	04/14/26	R.L.

NOTES:

1. THE PRODUCT SHOWN HEREIN IS DESIGNED AND MANUFACTURED TO COMPLY WITH REQUIREMENTS OF THE FLORIDA BUILDING CODE INCLUDING THE HVHZ.
2. WOOD OR METAL FRAMING OPENING TO BE DESIGNED AND ANCHORED TO PROPERLY TRANSFER ALL LOADS TO STRUCTURE. FRAMING OPENING IS THE RESPONSIBILITY OF THE ARCHITECT OR ENGINEER OF RECORD.
3. WHERE 1X BUCK IS NOT USED DISSIMILAR MATERIALS MUST BE SEPARATED WITH APPROVED COATING OR MEMBRANE. SELECTION OF COATING OR MEMBRANE IS THE RESPONSIBILITY OF THE ARCHITECT OR ENGINEER OF RECORD.
4. ALLOWABLE STRESS INCREASE OF 1/3 WAS NOT USED IN THE DESIGN OF THE PRODUCT SHOWN HEREIN. WIND LOAD DURATION FACTOR Cd=1.6 WAS USED FOR WOOD ANCHOR CALCULATIONS.
5. FRAME MATERIAL: EXTRUDED ALUMINUM.
6. UNITS MUST BE GLAZED PER ASTM E1300, SEE SHEET 6 FOR GLASS DETAILS.
7. APPROVED IMPACT PROTECTIVE SYSTEM IS NOT REQUIRED FOR THIS PRODUCT IN WIND BORNE DEBRIS REGIONS.
8. SHIM AS REQUIRED AT EACH INSTALLATION ANCHOR WITH LOAD BEARING SHIM. SHIM WHERE SPACE OF 1/16" OR GREATER OCCURS. MAXIMUM ALLOWABLE SHIM STACK TO BE 1/4".

9. FOR ANCHORING INTO WOOD FRAMING OR 2X BUCK USE 1/4" LAG SCREWS WITH SUFFICIENT LENGTH TO ACHIEVE A 2" MINIMUM EMBEDMENT INTO SUBSTRATE. LOCATE ANCHORS AS SHOWN IN ELEVATIONS AND INSTALLATION DETAILS.
10. FOR ANCHORING INTO MASONRY/CONCRETE USE 1/4" TAPCONS WITH SUFFICIENT LENGTH TO ACHIEVE A 1 1/4" MINIMUM EMBEDMENT INTO SUBSTRATE WITH 2 1/2" MINIMUM EDGE DISTANCE, LOCATE ANCHORS AS SHOWN IN ELEVATION AND INSTALLATION DETAILS.
11. FOR ANCHORING INTO METAL STRUCTURE USE 1/4" SMS OR SELF DRILLING SCREWS WITH SUFFICIENT LENGTH TO ACHIEVE 3 THREADS MINIMUM BEYOND STRUCTURE INTERIOR WALL. LOCATE ANCHORS AS SHOWN IN ELEVATIONS AND INSTALLATION DETAILS.
12. ALL FASTENERS TO BE CORROSION RESISTANT.
13. INSTALLATION ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH ANCHOR MANUFACTURER'S INSTALLATION INSTRUCTIONS AND ANCHORS SHALL NOT BE USED IN SUBSTRATES WITH STRENGTHS LESS THAN THE MINIMUM STRENGTH SPECIFIED BELOW:

A. WOOD – MINIMUM SPECIFIC GRAVITY OF G=0.42

B. METAL STRUCTURE: STEEL 18GA, 33KSI OR ALUMINUM 6063-T5 1/8" THICK MINIMUM

C. CONCRETE – MINIMUM COMPRESSIVE STRENGTH OF 3000 PSI.

D. MASONRY – HOLLOW/FILLED BLOCK WITH COMPRESSIVE STRENGTH OF 2000 PSI.

SIGNED: 04/14/2026

TABLE OF CONTENTS	
SHEET NO.	DESCRIPTION
1	NOTES
2	ELEVATION, GLAZING DETAIL & DESIGN PRESSURE CHART
3 – 4	CROSS SECTIONS
5	INSTALLATION DETAILS
6	COMPONENTS

SOLAR INNOVATIONS, INC.

31 ROBERTS ROAD
PINE GROVE, PA 17963

SERIES SI5200 FLAT WELDED CURB SKYLIGHT
IMPACT
NOTES

DRAWN:
V.L.

DWG NO.
08-02213

REV
G

SCALE NTS


DATE 08/30/13

SHEET 1 OF 6


L. ROBERTO LOMAS P.E.
208 7th Ave, INDIALANTIC, FL 32903
434-688-0609 rllomas@lrlomaspe.com

LUIS R. LOMAS
P.E.
No. 62514
STATE OF
FLORIDA
PROFESSIONAL ENGINEER

Luis R. Lomas P.E.
FL No.: 62514



HORIZONTAL SECTION



MUNTIN DETAIL


VERTICAL SECTION

REVISIONS			
REV	DESCRIPTION	DATE	APPROVED
G	REVISED COMPONENTS	04/14/26	R.L.

- NOTES:
1. INTERIOR AND EXTERIOR FINISHES, BY OTHERS, NOT SHOWN FOR CLARITY.
 2. PERIMETER AND JOINT SEALANT BY OTHERS TO BE DESIGNED IN ACCORDANCE WITH ASTM E2112


SIGNED: 04/14/2026

SOLAR INNOVATIONS, INC. 31 ROBERTS ROAD PINE GROVE, PA 17963		
SERIES SI5200 FLAT WELDED CURB SKYLIGHT IMPACT CROSS SECTIONS		
DRAWN: V.L.	DWG NO. 08-02213	REV G
SCALE NTS	DATE 08/30/13	SHEET 3 OF 6
L. ROBERTO LOMAS P.E. 208 7th Ave, INDIALANTIC, FL 32903 434-688-0609 rllomas@lrlomaspe.com		



Luis R. Lomas P.E.
FL No.: 62514

REVISIONS			
REV	DESCRIPTION	DATE	APPROVED
G	REVISED COMPONENTS	04/14/26	R.L.




NOTES:


1. INTERIOR AND EXTERIOR FINISHES, BY OTHERS, NOT SHOWN FOR CLARITY.
2. PERIMETER AND JOINT SEALANT BY OTHERS TO BE DESIGNED IN ACCORDANCE WITH ASTM E2112

SIGNED: 04/14/2026


SOLAR INNOVATIONS, INC. 31 ROBERTS ROAD PINE GROVE, PA 17963				
SERIES SI5200 FLAT WELDED CURB SKYLIGHT IMPACT CROSS SECTIONS				
DRAWN: V.L.		DWG NO. 08-02213		REV G
SCALE NTS	DATE 08/30/13	SHEET 4 OF 6		
L. ROBERTO LOMAS P.E. 208 7th Ave, INDIALANTIC, FL 32903 434-688-0609 rllomas@lrlomaspe.com				




Luis R. Lomas P.E.
FL No.: 62514




MUNTIN ATTACHMENT DETAIL




BOX MUNTIN ASSEMBLY
ALUMINUM 6063-T6 .078" THICK




MULL JAMB ASSEMBLY
ALUMINUM 6063-T6 .125" THICK



SKYLIGHT FRAME
ALUMINUM 6063-T6 .076" THICK




G3 EXTRUDED CURB CAP
52281
ALUMINUM 6063-T6 .060" THICK



G3 EXTRUDED CURB CAP
S72619
ALUMINUM 6063-T6 .100" THICK

REVISIONS			
REV	DESCRIPTION	DATE	APPROVED
G	REVISED COMPONENTS	04/14/26	R.L.



SOLAR INNOVATIONS, INC.
31 ROBERTS ROAD
PINE GROVE, PA 17963

**SERIES SI5200 FLAT WELDED CURB SKYLIGHT
IMPACT
COMPONENTS**

DRAWN: V.L.	DWG NO. 08-02213	REV G
SCALE NTS	DATE 08/30/13	SHEET 6 OF 6

L. ROBERTO LOMAS P.E.
208 7th Ave, INDIALANTIC, FL 32903
434-688-0609 rllomas@lrlomaspe.com

SIGNED: 04/14/2026

LUIS R. LOMAS
LICENSED PROFESSIONAL ENGINEER
No. 62514
STATE OF FLORIDA

Luis R. Lomas P.E.
FL No.: 62514