



YKK AP AMERICA, Inc.

YHC 300 OG - HVHZ

Curtain Wall Systems

INSTALLATION NOTES:

- ONE (1) INSTALLATION ANCHOR IS REQUIRED AT EACH ANCHOR LOCATION SHOWN, UNLESS OTHERWISE STATED.
- THE NUMBER OF INSTALLATION ANCHORS DEPICTED IS THE MINIMUM NUMBERS OF ANCHORS TO BE USED FOR PRODUCT INSTALLATION.
- INSTALL INDIVIDUAL INSTALLATION ANCHORS WITHIN A TOLERANCE OF ±1/2 INCH OF THE DEPICTED LOCATION IN THE ANCHOR LAYOUT DETAIL (I.E., WITH OUT CONSIDERATION OF TOLERANCE). TOLERANCE ARE NOT CUMULATIVE FROM ONE INSTALLATION ANCHOR TO THE NEXT.
- REFER TO SECTION 7 & 8 FOR ANCHOR TYPE, SUBSTRATE STRENGTH, EMBEDMENT, & EDGE DISTANCE REQUIREMENTS. FOLLOW MANUFACTURER INSTALLATION INSTRUCTIONS FOR INSTALLATION OF ANCHORS.
- MINIMUM EMBEDMENT AND EDGE DISTANCE EXCLUDE WALL FINISHES, INCLUDING BUT NOT LIMITED TO STUCCO, FOAM, BRICK VENEER, AND SIDING.
- INSTALLATION ANCHORS AND ASSOCIATED HARDWARE MUST BE MADE OF CORROSION RESISTANT MATERIAL OR HAVE A CORROSION RESISTANT COATING.
 - FASTENERS USED WITHIN 3,000 FEET OF A SALTWATER COASTLINE AND INSTALLED IN ENCLOSED SPACES SHALL BE GALVANIZED IN ACCORDANCE WITH SECTION 1711.1.1 (E.G., ASTM A153 CLASS D, ASTM A641 CLASS 35, OR EQUIVALENT CORROSION RESISTANCE).
 - CONNECTORS AND METAL PLATES USED WITHIN 3,000 FEET OF A SALTWATER COASTLINE SHALL BE STANDARD GALVANIZED IN ACCORDANCE WITH SECTION 1711.1.2 (E.G., ASTM A653 G90, ASTM A123, OR PROTECTIVE COATING PER TPI 1).
- INSTALLATION ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH ANCHOR MANUFACTURER'S INSTALLATION INSTRUCTIONS, AND ANCHORS SHALL NOT BE USED IN SUBSTRATES WITH STRENGTHS LESS THAN THE MINIMUM STRENGTH SPECIFIED BY THE ANCHOR MANUFACTURER. ADHESIVE ANCHORS MUST BE INSTALLED BY PERSONNEL CERTIFIED FOR THE SPECIFIED ANCHOR INSTALLATION.

INSTRUCTIONS:

USE CHARTS AS FOLLOWS.	
STEP 1	DETERMINE DESIGN WIND LOAD REQUIREMENT BASED ON WIND VELOCITY, BLDG. HEIGHT, WIND ZONE USING APPLICABLE ASCE 7 STANDARD.
STEP 2	SEE CHARTS ON SECTION 6 FOR DESIGN LOAD CAPACITY OF DESIRED GLASS SIZE.
STEP 3	CHECK MULLION CAPACITY FOR A GIVEN SPACING, HEIGHT, SINGLE SPAN, TWIN SPAN, MULTIPLE SPANS AND CORNERS ON SECTION 4.
STEP 4	USING HEAD/SILL ANCHOR DETAILS, SELECT ANCHOR OPTION FROM TABLES ON SECTION 7 & 8 WITH DESIGN RATING MORE THAN DESIGN LOAD SPECIFIED IN STEP 1 ABOVE.
STEP 5	CHECK INTERMEDIATE ANCHOR CAPACITY FOR MULTIPLE SPANS USING CHARTS OR DETAILS ON SECTION 8.
STEP 6	THE LOWEST VALUE RESULTING FROM STEPS 2, 3, 4 AND 5 SHALL APPLY TO ENTIRE SYSTEM.

GENERAL NOTES:

- THE PRODUCT SHOWN HEREIN IS DESIGNED AND MANUFACTURED TO COMPLY WITH THE CURRENT FLORIDA BUILDING CODE, INCLUDING REQUIREMENTS FOR HVHZ.
- ADEQUACY OF THE EXISTING STRUCTURAL CONCRETE/MASONRY , 2X AND STEEL STUD FRAMING AS A MAIN WIND FORCE RESISTING SYSTEM CAPABLE OF WITHSTANDING AND TRANSFERRING APPLIED PRODUCT LOADS TO THE FOUNDATION IS THE RESPONSIBILITY OF THE ENGINEER OR ARCHITECT OF RECORD FOR THE PROJECT OF INSTALLATION.
- 2X BUCKS (WHEN USED) SHALL BE DESIGNED AND ANCHORED TO PROPERLY TRANSFER ALL LOADS TO THE STRUCTURE. BUCK DESIGN AND THE INSTALLATION IS THE RESPONSIBILITY OF THE ENGINEER OR ARCHITECT OF RECORD FOR THE PROJECT OF INSTALLATION.
- THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITION CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN , A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.
- THIS PRODUCT DOES NOT REQUIRE IMPACT PROTECTIVE DEVICES.
- MATERIALS INCLUDING BUT NOT LIMITED TO STEEL/METAL SCREWS, THAT COME INTO CONTACT WITH OTHER DISSIMILAR MATERIALS SHALL MEET THE REQUIREMENTS OF THE CURRENT FLORIDA BUILDING CODE.

TABLE OF CONTENTS	
SECTION	SECTION DESCRIPTION
1	COVER SHEET & GENERAL NOTES
2	ELEVATION
3	VERTICAL SECTIONS
4	HORIZONTAL SECTIONS
5	DOOR CONNECTION DETAILS
6	GLAZING DETAILS
7	F, T & S ANCHOR DETAILS
8	DEAD/WIND LOAD ANCHOR DETAILS
9	COMPONENTS & BILL OF MATERIALS



YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE:
YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM

GENERAL AND INSTALLATION NOTES


PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

BUILDING DROPS

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT

Digitally signed by Hermes F. Norero, P.E.
Reason: I am approving this document
Date: 2026.08.01 16:18:41 -04'00'



FL #:
FL13433

DATE:
7.17.17

DWG. BY:
AR

CHK. BY:
HFN


SCALE:
NTS

DWG. #:
YKK204

SECTION:
1.0

REV.
B





c:\users\sebastianhereros\desktop\ykk 2026 ca\fl13433\ykk 204 - fl13433 dwgs 1 thru 4 - cover, elev. vert & horz dtd.dwg
7/24/2026 10:24 AM



7/24/2026 10:24 AM

c:\users\sebastianherrerros\desktop\ykk 2026 ca\fl13433\ykk 204 - fl13433.dwg 1 thru 4 - cover, elev, vert & horz dtd.dwg

LIGHT DUTY MULLIONS - VERTICAL SECTIONS



WEEPHOLES:
W1 = 5/16" DIA. WEEP HOLES TWO PER D.L. OPNG.
= AT 1/3 POINTS FROM VERTICALS
W2 = 5/16" DIA. WEEP HOLES THREE PER LITE
= AT 3" FROM VERTICALS AND CENTER OF D.L. OPNG.

NOTE:
SOLID SHIM UP TO 1/4" MAY BE USED BETWEEN
ANCHOR & SUBSTRATE INCREASING THE CAULK
JOINT TO 1" ALLOWABLE UNDER THIS
CONDITION.



YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE: YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM
ELEVATION

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744.4738
WEB: www.buildingdrops.com

B.D.
BUILDING DROPS

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26


THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC
AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC
SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE
FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED
ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC
DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:	FL13433
DATE:	7.17.17
DWG. BY:	AR
CHK. BY:	HFN
SCALE:	NTS
DWG. #:	YKK204
SECTION:	3.0
REV.	B

c:\users\sebastianherrerros\desktop\ykk 2026 ca\fl13433 dwgs 1 thru 4 - cover, elev, vert & horz dtl.dwg
7/24/2026 10:24 AM


STANDARD MULLIONS - VERTICAL SECTIONS



1
3.1
VERTICAL SECTION
STANDARD MULLION
MONOLITHIC GLASS

WEEPHOLES:
W1 = 5/16" DIA. WEEP HOLES TWO PER D.L. OPNG.
= AT 1/3 POINTS FROM VERTICALS
W2 = 5/16" DIA. WEEP HOLES THREE PER LITE
= AT 3" FROM VERTICALS AND CENTER OF D.L. OPNG.

NOTE:
SOLID SHIM UP TO 1/4" MAY BE USED BETWEEN
ANCHOR & SUBSTRATE INCREASING THE CAULK
JOINT TO 1" ALLOWABLE UNDER THIS
CONDITION.



2
3.1
VERTICAL SECTION
STANDARD MULLION
INSULATING GLASS



Quality
inspires™

YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE:
YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM


VERTICAL SECTIONS

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com



BUILDING DROPS

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26
THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT		



HERMES F. NORERO
LICENSE
No. 73778
STATE OF
FLORIDA
PROFESSIONAL ENGINEER
HERMES F. NORERO, P.E.
BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
FBPE CERT. OF AUTHORIZATION No. 29578

FL #:

FL13433

DATE:

7.17.17

DWG. BY:

AR

CHK. BY:

HFN

SCALE:

NTS

DWG. #:

YKK204

SECTION:

3.1

REV.


B

[Page 4 of 59]

7/24/2026 10:24 AM

c:\users\sebastianherrerros\desktop\ykk 2026 ca\fl13433\ykk 204 - fl13433 dwgs 1 thru 4 - cover, elev, vert & horz dtd.dwg


HEAVY DUTY MULLIONS - VERTICAL SECTIONS



1
3.2
VERTICAL SECTION
HEAVY DUTY MULLION
MONOLITHIC GLASS

WEEPHOLES:
W1 = 5/16" DIA. WEEP HOLES TWO PER D.L.
OPNG.
= AT 1/3 POINTS FROM VERTICALS
W2 = 5/16" DIA. WEEP HOLES THREE PER LITE
= AT 3" FROM VERTICALS AND CENTER OF
D.L. OPNG.

NOTE:
SOLID SHIM UP TO 1/4" MAY BE USED BETWEEN
ANCHOR & SUBSTRATE INCREASING THE CAULK
JOINT TO 1" ALLOWABLE UNDER THIS
CONDITION.



2
3.2
VERTICAL SECTION
HEAVY DUTY MULLION
INSULATING GLASS




YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE: YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM
VERTICAL SECTION
PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC
AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC
SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE
FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED
ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC
DOCUMENTS FOR USE WITH THIS DOCUMENT




FL #:	FL13433
DATE:	7.17.17
DWG. BY:	AR
CHK. BY:	HFN
SCALE:	NTS
DWG. #:	YKK204
SECTION:	3.2
REV.	B

7/24/2026 10:24 AM

c:\users\sebastianhereros\desktop\ykk 2026 cc\113433 dwgs 1 thru 4 - cover, elev, vert & horz dtl.dwg

LIGHT DUTY MULLIONS - HORIZONTAL SECTIONS




1 HORIZONTAL SECTION
4.0 LIGHT DUTY MULLION
MONOLITHIC GLASS

2 HORIZONTAL SECTION
4.0 LIGHT DUTY MULLION
MONOLITHIC GLASS

3 HORIZONTAL SECTION
4.0 LIGHT DUTY MULLION
MONOLITHIC GLASS

MAX. DESIGN LOAD- PSF	MIN. GAP	MAX. GAP
90	1/2"	1"

NOTE:
JOINT AT JAMBS IS NON-STRUCTURAL AND SHALL BE SUFFICIENT TO PROVIDE PROPER WEATHERPROOFING. SEALANT JOINT SIZE MAY VARY IN ACCORDANCE WITH SEALANT MANUFACTURER'S GUIDELINES AND RECOMMENDATION AND SHALL BE REVIEWED BY THE AUTHORITY HAVING JURISDICTION.



4 HORIZONTAL SECTION
4.0 LIGHT DUTY MULLION
INSULATING GLASS

5 HORIZONTAL SECTION
4.0 LIGHT DUTY MULLION
INSULATING GLASS

6 HORIZONTAL SECTION
4.0 LIGHT DUTY MULLION
INSULATING GLASS




YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE: YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM
HORIZONTAL SECTIONS
PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:	FL13433
DATE:	7.17.17
DWG. BY:	AR
CHK. BY:	HFN
SCALE:	NTS
DWG. #:	YKK204
SECTION:	4.0
REV.	B

YKK
ap ®

Quality
inspires


[Page 7 of 59]

8 HORIZONTAL SECTION

4.1 STANDARD MULLION (REINFORCED) INSULATING GLASS

7/24/2026 10:24 AM

c:\users\sebastianh\desktop\ykk 2026 cc\113433\dwgs 1 thru 4 - cover, elev, vert & horz dtl.dwg




1 HORIZONTAL SECTION
4.2 HEAVY DUTY MULLION MONOLITHIC GLASS

2 HORIZONTAL SECTION
4.2 HEAVY DUTY MULLION MONOLITHIC GLASS

3 HORIZONTAL SECTION
4.2 HEAVY DUTY MULLION MONOLITHIC GLASS

MAX. DESIGN LOAD-PSF	MIN. GAP	OPENING WIDTH MAX. GAP
145	3/4"	1"
120	5/8"	1"
96	1/2"	1"

NOTE:
JOINT AT JAMBS IS NON-STRUCTURAL AND SHALL BE SUFFICIENT TO PROVIDE PROPER WEATHERPROOFING. SEALANT JOINT SIZE MAY VARY IN ACCORDANCE WITH SEALANT MANUFACTURER'S GUIDELINES AND RECOMMENDATION AND SHALL BE REVIEWED BY THE AUTHORITY HAVING JURISDICTION.



4 HORIZONTAL SECTION
4.2 HEAVY DUTY MULLION INSULATING GLASS

5 HORIZONTAL SECTION
4.2 HEAVY DUTY MULLION INSULATING GLASS

6 HORIZONTAL SECTION
4.2 HEAVY DUTY MULLION INSULATING GLASS



YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE: **YHC - 300 OG (HVHZ) CURTAIN WALL SYSTEM**


HORIZONTAL SECTIONS

PREPARED BY: **BUILDING DROPS, INC.**
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

B.D. BUILDING DROPS

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26







THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #:	FL13433
DATE:	7.17.17
DWG. BY:	AR
CHK. BY:	HFN
SCALE:	NTS
DWG. #:	YKK204
SECTION:	4.2
REV.	B

c:\users\sebastianherrerros\desktop\ykk 2026\c:\fl13433\dwgs 1 thru 4 - cover, elev, vert & horz dtl.dwg
7/24/2026 10:24 AM

LIGHT DUTY CORNER MULLIONS - HORIZONTAL SECTIONS




YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE: YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM
HORIZONTAL SECTIONS (CORNERS)
PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744.4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:	FL13433
DATE:	7.17.17
DWG. BY:	AR
CHK. BY:	HFN
SCALE:	NTS
DWG. #:	YKK204
SECTION:	4.3
REV.	B

7/24/2026 10:24 AM

LIGHT DUTY MULLION CAPACITY CHARTS



NOTES

- 1. DESIGN PRESSURES ARE LIMITED BY THE MULLION FIBERSTRESS AND DEFLECTION CAPACITY PER FBC CURRENT SPECIFICATIONS FOR HVHZ
- 2. SELECT DESIGN PRESSURE AND PANEL WIDTH (W) AND OBTAIN THE MAXIMUM ALLOWABLE DESIGN PRESSURE FOR MULLION.
- 3. FOR HORIZONTAL MULLIONS CAPACITY, SEE HORIZONTAL MULLION CHART.
- 4. WHEN PANEL WIDTHS ARE NOT EQUAL, USE THE AVERAGE WIDTH ON THE CHART.

CASE 1: SINGLE SPAN WITH UNREINFORCED MULLION
CASE 2: SINGLE SPAN WITH REINFORCED MULLION FULL HEIGHT
CASE 3: TWIN SPAN WITH REINFORCED MULLION AT INTERMEDIATE SUPPORT ONLY

LIGHT DUTY HORIZONTAL MULLIONS (+/- PSF)	
WIDTH, W (in) 'Span'	Ext. (+) Int. (-)
48	65

















STANDARD DUTY HORIZONTAL MULLIONS (+/- PSF)	
WIDTH, W (in) 'Span'	Ext. (+) Int. (-)
74	65



MULLIONS

- VERTICAL MEMBER SINGLE SPAN NOTES:
- 1. DETAILS HAVE BEEN SHOWN FOR ILLUSTRATIVE PURPOSES. FOR DETAILS OF FULL ASSEMBLY PLEASE REFER TO APPLICABLE DETAILS ON SECTION 3.
 - 2. TABULATED DESIGN PRESSURE VALUES ARE BASED ON LIMITATIONS OF DEFLECTION, FIBERSTRESS, & END REACTION PER MULLION SPAN ('L') AND MULLION SPACING ('W').
 - 3. FOR SITE CONDITIONS WHICH EXCEED LIMITATIONS SHOWN, FURTHER ENGINEERING MAY BE REQUIRED ON A CASE BY CASE BASIS.
 - 4. FOR T, F, OR S CLIP ANCHORS, PLEASE REFER TO SECTION 7 & 8 FOR ANCHOR SELECTION, SUBSTRATE REQUIREMENTS, AND FURTHER LIMITATIONS OF USE.

REFER TO 4.5 FOR LIGHT DUTY MULLION CAPACITY TABLES



YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001


TITLE: YHC - 300 OG (HVHZ) CURTAIN WALL SYSTEM

MULLION CAPACITY CHART

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:

FL13433

DATE: 7.17.17

DWG. BY: AR

CHK. BY: HFN

SCALE: NTS

DWG. #: YKK204

SECTION:

4.4

REV. B

[Page 10 of 59]

c:\users\sebastianherrerros\desktop\ykk 2026 ca\fl13433\ykk 204 - fl13433.dwg
7/24/2026 10:24 AM
c:\users\sebastianherrerros\desktop\ykk 2026 ca\fl13433\ykk 204 - fl13433.dwg
1 thru 4 - cover, elev, vert & horz dtl.dwg

LIGHT DUTY MULLION LOAD CAPACITY CHARTS

JAMB/MULLION LOAD CAPACITY (+/- PSF)				
NOMINAL DIMS.		CASE 1	CASE 2	CASE 3*
		MULLION 'M1' & 'M2'	MULLION 'M3' & 'M4'	MULLION 'M5', 'M6', 'M31' & 'M32'
WIDTH 'W' (in.)	SPAN HEIGHT 'H' (in.)	EXT. (+) INT. (-)	EXT. (+) INT. (-)	EXT. (+) INT. (-)
24	78	65.0	65.0	65.0
30		65.0	65.0	65.0
36		65.0	65.0	65.0
42		65.0	65.0	65.0
48		65.0	65.0	65.0
54		65.0	65.0	65.0
60		65.0	65.0	65.0
66		65.0	65.0	65.0
72		65.0	65.0	65.0
24	84	65.0	65.0	65.0
30		65.0	65.0	65.0
36		65.0	65.0	65.0
42		65.0	65.0	65.0
48		65.0	65.0	65.0
54		65.0	65.0	65.0
60		65.0	65.0	65.0
66		65.0	65.0	65.0
72		65.0	65.0	65.0
24	90	65.0	65.0	65.0
30		65.0	65.0	65.0
36		65.0	65.0	65.0
42		65.0	65.0	65.0
48		65.0	65.0	65.0
54		65.0	65.0	65.0
60		65.0	65.0	65.0
66		65.0	65.0	65.0
72		65.0	65.0	65.0
24	96	65.0	65.0	65.0
30		65.0	65.0	65.0
36		65.0	65.0	65.0
42		65.0	65.0	65.0
48		65.0	65.0	65.0
54		65.0	65.0	65.0
60		65.0	65.0	65.0
66		65.0	65.0	65.0
72		65.0	65.0	65.0
24	102	65.0	65.0	65.0
30		65.0	65.0	65.0
36		65.0	65.0	65.0
42		65.0	65.0	65.0
48		65.0	65.0	65.0
54		65.0	65.0	65.0
60		65.0	65.0	65.0
66		65.0	65.0	65.0
72		65.0	65.0	65.0

JAMB/MULLION LOAD CAPACITY (+/- PSF)				
NOMINAL DIMS.		CASE 1	CASE 2	CASE 3*
		MULLION 'M1' & 'M2'	MULLION 'M3' & 'M4'	MULLION 'M5', 'M6', 'M31' & 'M32'
WIDTH 'W' (in.)	SPAN HEIGHT 'H' (in.)	EXT. (+) INT. (-)	EXT. (+) INT. (-)	EXT. (+) INT. (-)
24	108	65.0	65.0	65.0
30		65.0	65.0	65.0
36		65.0	65.0	65.0
42		65.0	65.0	65.0
48		65.0	65.0	65.0
54		65.0	65.0	65.0
60		65.0	65.0	65.0
66		65.0	65.0	65.0
72		65.0	65.0	65.0
24	114	65.0	65.0	65.0
30		65.0	65.0	65.0
36		65.0	65.0	65.0
42		65.0	65.0	65.0
48		65.0	65.0	65.0
54		65.0	65.0	65.0
60		65.0	65.0	65.0
66		65.0	65.0	65.0
72		65.0	65.0	65.0
24	120	65.0	65.0	65.0
30		65.0	65.0	65.0
36		65.0	65.0	65.0
42		65.0	65.0	65.0
48		65.0	65.0	65.0
54		65.0	65.0	65.0
60		65.0	65.0	65.0
66		65.0	65.0	65.0
72		65.0	65.0	65.0
24	126	65.0	65.0	65.0
30		65.0	65.0	65.0
36		65.0	65.0	65.0
42		65.0	65.0	65.0
48		65.0	65.0	65.0
54		65.0	65.0	65.0
60		65.0	65.0	65.0
66		62.4	65.0	65.0
72		57.2	65.0	65.0

JAMB/MULLION LOAD CAPACITY (+/- PSF)				
NOMINAL DIMS.		CASE 1	CASE 2	CASE 3*
		MULLION 'M1' & 'M2'	MULLION 'M3' & 'M4'	MULLION 'M5', 'M6', 'M31' & 'M32'
WIDTH 'W' (in.)	SPAN HEIGHT 'H' (in.)	EXT. (+) INT. (-)	EXT. (+) INT. (-)	EXT. (+) INT. (-)
24	132	65.0	65.0	65.0
30		65.0	65.0	65.0
36		65.0	65.0	65.0
42		65.0	65.0	65.0
48		65.0	65.0	65.0
54		65.0	65.0	65.0
60		59.7	65.0	65.0
66		54.2	65.0	65.0
72		49.7	65.0	65.0
24	138	65.0	65.0	65.0
30		65.0	65.0	65.0
36		65.0	65.0	65.0
42		65.0	65.0	65.0
48		65.0	65.0	65.0
54		58.0	65.0	65.0
60		52.2	65.0	65.0
66		47.5	65.0	65.0
72		43.5	65.0	65.0
24	144	65.0	65.0	65.0
30		65.0	65.0	65.0
36		65.0	65.0	65.0
42		65.0	65.0	65.0
48		57.4	65.0	65.0
54		51.1	65.0	65.0
60		45.9	65.0	65.0
66		41.8	65.0	65.0
72		38.3	65.0	65.0
24	150	65.0	65.0	65.0
30		65.0	65.0	65.0
36		65.0	65.0	65.0
42		58.1	65.0	65.0
48		50.8	65.0	65.0
54		45.2	65.0	65.0
60		40.7	65.0	65.0
66		37.0	65.0	65.0
72		33.9	65.0	65.0

*SLEEVE REINFORCEMENT @ WL + DL, 29" LONG



YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE:
YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM
MULLION CAPACITY CHART

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744.4738
WEB: www.buildingdrops.com




REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26
THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT		
 HERMES F. NORERO, P.E. BUILDING DROPS, INC. 1900 NE MIAMI CT, SUITE 2-15 MIAMI, FL 33132 FBPE CERT. OF AUTHORIZATION No. 29578		
FL #: FL13433		
DATE: 7.17.17		
DWG. BY: AR	CHK. BY: HFN	
SCALE: NTS		
DWG. #: YKK204		
SECTION: 4.5		REV. B


[Page 11 of 59]

7/24/2026 10:24 AM
c:\users\sebastianhereros\desktop\ykk 2026 ca\113433\ykk 204 - fl13433 dwgs 1 thru 4 - cover, elev, vert & horz dtd.dwg


STANDARD DUTY CORNER MULLIONS - HORIZONTAL SECTIONS




1 HORIZONTAL SECTION
4.6 STANDARD DUTY MULLION
90° OUTSIDE CORNER - MONOLITHIC GLASS




2 HORIZONTAL SECTION
4.6 STANDARD DUTY MULLION
90° INSIDE CORNER - MONOLITHIC GLASS




3 HORIZONTAL SECTION
4.6 STANDARD DUTY MULLION
90° OUTSIDE CORNER - MONOLITHIC GLASS



4 HORIZONTAL SECTION
4.6 STANDARD DUTY MULLION
90° OUTSIDE CORNER - INSULATING GLASS



5 HORIZONTAL SECTION
4.6 STANDARD DUTY MULLION
90° INSIDE CORNER - INSULATING GLASS



6 HORIZONTAL SECTION
4.6 STANDARD DUTY MULLION
90° OUTSIDE CORNER - INSULATING GLASS




YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE: YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM
HORIZONTAL SECTIONS (CORNERS)
PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:	FL13433
DATE:	7.17.17
DWG. BY:	AR
CHK. BY:	HFN
SCALE:	NTS
DWG. #:	YKK204
SECTION:	4.6
REV.	B

STANDARD DUTY MULLION CAPACITY CHARTS

NOTES

- 1. DESIGN PRESSURES ARE LIMITED BY THE MULLION FIBERSTRESS AND DEFLECTION CAPACITY PER CURRENT FBC SPECIFICATIONS FOR HVHZ
- 2. SELECT DESIGN PRESSURE AND PANEL WIDTH (W) AND OBTAIN THE MAXIMUM ALLOWABLE DESIGN PRESSURE FOR MULLION.
- 3. FOR HORIZONTAL MULLIONS CAPACITY, SEE HORIZONTAL MULLION CHART.
- 4. WHEN PANEL WIDTHS ARE NOT EQUAL, USE THE AVERAGE WIDTH ON THE CHART.

CASE 1: SINGLE SPAN WITH UNREINFORCED MULLION


CASE 2: SINGLE SPAN WITH REINFORCED MULLION FULL HEIGHT

CASE 3: TWIN SPAN WITH REINFORCED MULLION AT INTERMEDIATE SUPPORT ONLY

JAMB/MULLION LOAD CAPACITY (+/- PSF)				
NOMINAL DIMS.		CASE 1	CASE 2	CASE 3*
WIDTH 'W' (in.)	SPAN HEIGHT 'H' (in.)	MULLIO N 'M7' & 'M8'	MULLIO N 'M9' & 'M10'	MULLIO N 'M11' & 'M12'
		EXT. (+) INT. (-)	EXT. (+)	EXT. (+) INT. (-)
36	78	90.0	90.0	90.0
42		90.0	90.0	90.0
48		90.0	90.0	90.0
54		90.0	90.0	90.0
60		90.0	90.0	90.0
66		90.0	90.0	90.0
72	84	90.0	90.0	90.0
36		90.0	90.0	90.0
42		90.0	90.0	90.0
48		90.0	90.0	90.0
54		90.0	90.0	90.0
60		90.0	90.0	90.0
66	90	90.0	90.0	90.0
72		90.0	90.0	90.0
36		90.0	90.0	90.0
42		90.0	90.0	90.0
48		90.0	90.0	90.0
54		90.0	90.0	90.0
60	96	90.0	90.0	90.0
66		90.0	90.0	90.0
72		90.0	90.0	90.0
36		90.0	90.0	90.0
42		90.0	90.0	90.0
48		90.0	90.0	90.0
54	102	90.0	90.0	90.0
60		90.0	90.0	90.0
66		90.0	90.0	90.0
72		90.0	90.0	90.0
36		90.0	90.0	90.0
42		90.0	90.0	90.0
48	108	90.0	90.0	90.0
54		90.0	90.0	90.0
60		90.0	90.0	90.0
66		90.0	90.0	90.0
72		90.0	90.0	90.0
36		90.0	90.0	90.0
42	114	90.0	90.0	90.0
48		90.0	90.0	90.0
54		90.0	90.0	90.0
60		90.0	90.0	90.0
66		90.0	90.0	90.0
72		90.0	90.0	90.0
36	120	90.0	90.0	90.0
42		90.0	90.0	90.0
48		90.0	90.0	90.0
54		90.0	90.0	90.0
60		90.0	90.0	90.0
66		90.0	90.0	90.0
72		90.0	90.0	90.0


JAMB/MULLION LOAD CAPACITY (+/- PSF)				
NOMINAL DIMS.		CASE 1	CASE 2	CASE 3*
WIDTH 'W' (in.)	SPAN HEIGHT 'H' (in.)	MULLIO N 'M7' & 'M8'	MULLIO N 'M9' & 'M10'	MULLIO N 'M11' & 'M12'
		EXT. (+) INT. (-)	EXT. (+)	EXT. (+) INT. (-)
36	123	90.0	90.0	90.0
42		90.0	90.0	90.0
48		90.0	90.0	90.0
54		90.0	90.0	90.0
60		90.0	90.0	90.0
66		90.0	90.0	90.0
72	126	61.4	90.0	90.0
36		90.0	90.0	90.0
42		90.0	90.0	90.0
48		90.0	90.0	90.0
54		90.0	90.0	90.0
60		90.0	90.0	90.0
66	132	62.4	90.0	90.0
72		57.2	90.0	90.0
36		90.0	90.0	90.0
42		85.2	90.0	90.0
48		74.6	90.0	90.0
54		66.3	90.0	90.0
60	138	59.7	90.0	90.0
66		54.2	90.0	90.0
72		49.7	90.0	90.0
36		87.0	90.0	90.0
42		74.6	90.0	90.0
48		65.3	90.0	90.0
54	144	58.0	90.0	90.0
60		52.2	90.0	90.0
66		47.5	90.0	90.0
72		43.5	90.0	90.0
36		76.6	90.0	90.0
42		65.6	90.0	90.0
48	150	57.4	90.0	90.0
54		51.1	90.0	90.0
60		45.9	90.0	90.0
66		41.8	90.0	90.0
72		38.3	83.2	89.2
36		67.8	90.0	90.0
42		58.1	90.0	90.0
48		50.8	90.0	90.0
54		45.2	90.0	90.0
60		40.7	90.0	90.0
66		37.0	83.6	90.0
72		33.9	76.6	85.6

STANDARD DUTY HORIZONTAL MULLIONS (+/- PSF)	
WIDTH, W (in) 'Span'	Ext. (+) Int. (-)
72	90



SINGLE SPAN


REINFORCING LENGTH = FRAME HEIGHT - 12 IN.



DOUBLE SPAN

MULLIONS

SECTIONS @ F/T ANCHOR SPLICE/WIND LOAD/DEAD LOAD LOCATION



VERTICAL MEMBER SINGLE SPAN NOTES:

- 1. DETAILS HAVE BEEN SHOWN FOR ILLUSTRATIVE PURPOSES. FOR DETAILS OF FULL ASSEMBLY PLEASE REFER TO APPLICABLE DETAILS ON SECTION 3.
- 2. TABULATED DESIGN PRESSURE VALUES ARE BASED ON LIMITATIONS OF DEFLECTION, FIBERSTRESS, & END REACTION PER MULLION SPAN ('L') AND MULLION SPACING ('W').
- 3. FOR SITE CONDITIONS WHICH EXCEED LIMITATIONS SHOWN, FURTHER ENGINEERING MAY BE REQUIRED ON A CASE BY CASE BASIS.
- 4. FOR T, F, OR S CLIP ANCHORS, PLEASE REFER TO SECTION 7 & 8 FOR ANCHOR SELECTION, SUBSTRATE REQUIREMENTS, AND FURTHER LIMITATIONS OF USE.



YKK AP AMERICA

101 MARIETTA STREET NW, SUITE 2100

ATLANTA, GA 30303

PH: (478)277-1955 FAX: (678)838-6001

TITLE: YHC - 300 OG (HVHZ) CURTAIN WALL SYSTEM

MULLION CAPACITY CHARTS


PREPARED BY: BUILDING DROPS, INC.

1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

BUILDING DROPS

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:

FL13433

DATE:

7.17.17

DWG. BY:

AR

CHK. BY:

HFN

SCALE:

NTS

DWG. #:

YKK204

SECTION:

4.7

REV.


B

[Page 13 of 59]


c:\users\sebastianherrerros\desktop\ykk 2026 ca\fl13433\ykk 204 - fl13433.dwg 1 thru 4 - cover, elev, vert & horz dtd.dwg 7/24/2026 10:24 AM

STANDARD DUTY CORNER MULLIONS - CAPACITY CHART

CORNER MULLION W/O REINFORCING
SINGLE SPAN WITH HORIZONTAL



CORNER MULLION W/ALUM REINFORCING
TWIN SPAN WITH HORIZONTAL




MULLION LOAD CAPACITY (+/- PSF)				
NOMINAL DIMS.		CASE 1	CASE 2	CASE 3*
AVG. MUL. SPACING (W)	SPAN HEIGHT 'H' (in.)	EXT. (+) INT. (-)	EXT. (+) INT. (-)	EXT. (+) INT. (-)
36	78	90.0	90.0	90.0
42		90.0	90.0	90.0
48		90.0	90.0	90.0
54		90.0	90.0	90.0
60		90.0	90.0	90.0
66		90.0	90.0	90.0
72	84	90.0	90.0	90.0
36		90.0	90.0	90.0
42		90.0	90.0	90.0
48		90.0	90.0	90.0
54		90.0	90.0	90.0
60		90.0	90.0	90.0
66	90	90.0	90.0	90.0
72		90.0	90.0	90.0
36		90.0	90.0	90.0
42		90.0	90.0	90.0
48		90.0	90.0	90.0
54		90.0	90.0	90.0
60	96	90.0	90.0	90.0
66		90.0	90.0	90.0
72		90.0	90.0	90.0
36		90.0	90.0	90.0
42		90.0	90.0	90.0
48		90.0	90.0	90.0
54	102	90.0	90.0	90.0
60		90.0	90.0	90.0
66		90.0	90.0	90.0
72		90.0	90.0	90.0
36		90.0	90.0	90.0
42		90.0	90.0	90.0
48	108	90.0	90.0	90.0
54		90.0	90.0	90.0
60		90.0	90.0	90.0
66		90.0	90.0	90.0
72		90.0	90.0	90.0
36		90.0	90.0	90.0
42	114	90.0	90.0	90.0
48		90.0	90.0	90.0
54		90.0	90.0	90.0
60		90.0	90.0	90.0
66		90.0	90.0	90.0
72		90.0	90.0	90.0

MULLION LOAD CAPACITY (+/- PSF)				
NOMINAL DIMS.		CASE 1	CASE 2	CASE 3*
AVG. MUL. SPACING (W)	SPAN HEIGHT 'H' (in.)	EXT. (+) INT. (-)	EXT. (+) INT. (-)	EXT. (+) INT. (-)
36	120	90.0	90.0	90.0
42		90.0	90.0	90.0
48		90.0	90.0	90.0
54		90.0	90.0	90.0
60		90.0	90.0	90.0
66		90.0	90.0	90.0
72	126	90.0	90.0	90.0
36		90.0	90.0	90.0
42		90.0	90.0	90.0
48		90.0	90.0	90.0
54		90.0	90.0	90.0
60		90.0	90.0	90.0
66	132	85.8	90.0	90.0
72		90.0	90.0	90.0
36		90.0	90.0	90.0
42		90.0	90.0	90.0
48		90.0	90.0	90.0
54		90.0	90.0	90.0
60	138	85.3	90.0	90.0
66		78.2	90.0	86.5
72		90.0	90.0	90.0
36		90.0	90.0	90.0
42		90.0	90.0	90.0
48		90.0	90.0	90.0
54	144	90.0	90.0	90.0
60		90.0	90.0	90.0
66		85.8	90.0	90.0
72		78.0	90.0	90.0
36		71.5	90.0	82.7
42		90.0	90.0	90.0
48	150	90.0	90.0	90.0
54		87.6	90.0	90.0
60		78.8	90.0	90.0
66		71.6	90.0	86.5
72		65.7	85.9	79.3
36		90.0	90.0	90.0
42	156	90.0	90.0	90.0
48		90.0	90.0	90.0
54		88.0	90.0	90.0
60		78.3	90.0	90.0
66		70.4	90.0	90.0
72		64.0	86.4	83.0

*SLEEVE REINFORCEMENT @ WL + DL, 29" LONG


- NOTE:
- USE 'F' ANCHOR CLIP DETAIL AT JAMB AND 'T' ANCHOR CLIP DETAIL AT MULLION SEE SECTION 7 FOR DETAILS
 - THIS TABLE IS APPLICABLE FOR TWIN SPAN WITHOUT EXPANSION JOINT

CASE 1




CORNER MULLION
C1

CASE 2




CORNER MULLION
C2

CASE 3




CORNER MULLION
W/ STEEL REINF.
C3




CORNER MULLION
W/ STEEL REINF.
C4

CASE 3



CORNER MULLION
W/ ALUM REINF.
C6



CORNER MULLION
W/ ALUM REINF.
C5



YKK AP AMERICA

101 MARIETTA STREET NW, SUITE 2100

ATLANTA, GA 30303

PH: (478)277-1955 FAX: (678)838-6001

TITLE: YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM


CORNER MULLIONS

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

BUILDING DROPS

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #: FL13433

DATE: 7.17.17

DWG. BY: AR

CHK. BY: HFN

SCALE: NTS

DWG. #: YKK204


SECTION: 4.8

REV. B


[Page 14 of 59]

c:\users\sebastianh\desktop\ykk 2026 ca\113433\ykk 204 - fl13433.dwg 1 thru 4 - cover, elev, vert & horz dtl.dwg 7/24/2026 10:24 AM


HEAVY DUTY CORNER MULLIONS - HORIZONTAL SECTIONS




1 HORIZONTAL SECTION
4.9 HEAVY DUTY MULLION
90° OUTSIDE CORNER - MONOLITHIC GLASS




2 HORIZONTAL SECTION
4.9 HEAVY DUTY MULLION
90° INSIDE CORNER - MONOLITHIC GLASS




5 HORIZONTAL SECTION
4.9 HEAVY DUTY MULLION
90° OUTSIDE CORNER - MONOLITHIC GLASS



3 HORIZONTAL SECTION
4.9 HEAVY DUTY MULLION
90° OUTSIDE CORNER - INSULATING GLASS



4 HORIZONTAL SECTION
4.9 HEAVY DUTY MULLION
90° INSIDE CORNER - INSULATING GLASS



6 HORIZONTAL SECTION
4.9 HEAVY DUTY MULLION
90° OUTSIDE CORNER - INSULATING GLASS




YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE: YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM
HORIZONTAL SECTION CORNERS
HIGH PRESSURE
PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT




FL #:	FL13433
DATE:	7.17.17
DWG. BY:	AR
CHK. BY:	HFN
SCALE:	NTS
DWG. #:	YKK204
SECTION:	4.9
REV.	B

HEAVY DUTY MULLION CAPACITY CHARTS (STANDARD PRESSURES)

NOTES


- 1. DESIGN PRESSURES ARE LIMITED BY THE MULLION FIBERSTRESS AND DEFLECTION CAPACITY PER CURRENT FBC SPECIFICATIONS FOR HVHZ
- 2. SELECT DESIGN PRESSURE AND PANEL WIDTH (W) AND OBTAIN THE MAXIMUM ALLOWABLE DESIGN PRESSURE FOR MULLION.
- 3. FOR HORIZONTAL MULLIONS CAPACITY, SEE HORIZONTAL MULLION CHART.
- 4. WHEN PANEL WIDTHS ARE NOT EQUAL, USE THE AVERAGE WIDTH ON THE CHART.

- CASE 1: SINGLE SPAN WITH UNREINFORCED MULLION
- CASE 2: SINGLE SPAN WITH REINFORCED MULLION FULL HEIGHT
- CASE 3: TWIN SPAN WITH REINFORCED MULLION AT INTERMEDIATE SUPPORT ONLY



SINGLE SPAN

REINFORCING LENGTH = FRAME HEIGHT - 12 IN.




DOUBLE SPAN

SECTIONS @F/T ANCHOR/ SPLICE/WIND LOAD/ DEAD LOAD LOCATION


MULLIONS

M19




UNREINFORCED
HEAVY DUTY MULLION
(E9-3182)

M20




UNREINFORCED
HEAVY DUTY MULLION
(E9-3183)

M21




REINFORCED
HEAVY DUTY MULLION
(E9-3182)

M22




REINFORCED
STANDARD DUTY MULLION
(E9-3183)

M23




SLEEVE REINFORCEMENT
HEAVY DUTY MULLION
(E9-3182)


M24



SLEEVE REINFORCEMENT
HEAVY DUTY MULLION
(E9-3183)




HEAVY DUTY HORIZONTAL
(E9-3189)



HEAVY DUTY HORIZONTAL
(E9-3187)



HEAVY DUTY HORIZONTAL
(E9-3190)



HEAVY DUTY HORIZONTAL
(E9-3185)

- 14A MULLION ANCHOR SLEEVE (HD)
(3" LONG AT TOP & BOTTOM)
- 44A MULLION SPLICE SLEEVE (HD)
(6" LONG AT SPLICE)
- 46A MULLION WL/DL REINFORCEMENT SLEEVE (HD)
(29" LONG AT MID-POINT ANCHOR)

REFER TO 4.10A FOR HEAVY DUTY MULLION CAPACITY TABLES (STANDARD PRESSURE)

VERTICAL MEMBER SINGLE SPAN NOTES:

- 1. DETAILS HAVE BEEN SHOWN FOR ILLUSTRATIVE PURPOSES. FOR DETAILS OF FULL ASSEMBLY PLEASE REFER TO APPLICABLE DETAILS ON SECTION 3.
- 2. TABULATED DESIGN PRESSURE VALUES ARE BASED ON LIMITATIONS OF DEFLECTION, FIBERSTRESS, & END REACTION PER MULLION SPAN ('L') AND MULLION SPACING ('W').
- 3. FOR SITE CONDITIONS WHICH EXCEED LIMITATIONS SHOWN, FURTHER ENGINEERING MAY BE REQUIRED ON A CASE BY CASE BASIS.
- 4. FOR T, F, OR S CLIP ANCHORS, PLEASE REFER TO SECTION 7 & 8 FOR ANCHOR SELECTION, SUBSTRATE REQUIREMENTS, AND FURTHER LIMITATIONS OF USE.



YKK AP AMERICA

101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM
MULLION CAPACITY CHARTS

PREPARED BY: BUILDING DROPS, INC.

1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:

FL13433

DATE: 7.17.17

DWG. BY: AR

CHK. BY: HFN

SCALE: NTS

DWG. #: YKK204

SECTION:

4.10

REV.

B

HEAVY DUTY MULLION CAPACITY CHARTS (STANDARD PRESSURES)

JAMB/MULLION LOAD CAPACITY (+/- PSF)				
NOMINAL DIMS.		CASE 1	CASE 2	CASE 3*
		MULLION 'M19' & 'M20'	MULLION 'M21' & 'M22'	MULLION 'M23' & 'M24'
WIDTH 'W' (in.)	SPAN HEIGHT 'H' (in.)	EXT. (+) INT. (-)	EXT. (+) INT. (-)	EXT. (+) INT. (-)
36	144	90.0	90.0	90.0
42		90.0	90.0	90.0
48		90.0	90.0	90.0
54		90.0	90.0	90.0
60		90.0	90.0	90.0
66		90.0	90.0	90.0
72		90.0	90.0	90.0
36	150	90.0	90.0	90.0
42		90.0	90.0	90.0
48		90.0	90.0	90.0
54		90.0	90.0	90.0
60		90.0	90.0	90.0
66		90.0	90.0	90.0
72		83.0	90.0	90.0
36	156	90.0	90.0	90.0
42		90.0	90.0	90.0
48		90.0	90.0	90.0
54		90.0	90.0	90.0
60		90.0	90.0	90.0
66		83.7	90.0	90.0
72		76.7	90.0	90.0
36	162	90.0	90.0	90.0
42		90.0	90.0	90.0
48		90.0	90.0	90.0
54		90.0	90.0	90.0
60		85.4	90.0	90.0
66		77.6	90.0	90.0
72		71.2	90.0	90.0
36	168	-	90.0	90.0
42		-	90.0	90.0
48		-	90.0	90.0
54		-	90.0	90.0
60		-	90.0	90.0
66		-	90.0	90.0
72		-	90.0	90.0
36	174	-	90.0	90.0
42		-	90.0	90.0
48		-	90.0	90.0
54		-	90.0	90.0
60		-	90.0	90.0
66		-	90.0	90.0
72		-	90.0	90.0

JAMB/MULLION LOAD CAPACITY (+/- PSF)				
NOMINAL DIMS.		CASE 2	CASE 3*	
		MULLION 'M21' & 'M22'	MULLION 'M23' & 'M24'	
WIDTH 'W' (in.)	SPAN HEIGHT 'H' (in.)	EXT. (+) INT. (-)	EXT. (+) INT. (-)	
36	180	90.0	90.0	
42		90.0	90.0	
48		90.0	90.0	
54		90.0	90.0	
60		90.0	90.0	
66		90.0	90.0	
72		90.0	90.0	
36	186	90.0	90.0	
42		90.0	90.0	
48		90.0	90.0	
54		90.0	90.0	
60		90.0	90.0	
66		90.0	90.0	
72		90.0	90.0	
36	192	90.0	90.0	
42		90.0	90.0	
48		90.0	90.0	
54		90.0	90.0	
60		90.0	90.0	
66		90.0	89.8	
72		90.0	82.3	
36	198	90.0	90.0	
42		90.0	90.0	
48		90.0	90.0	
54		90.0	90.0	
60		90.0	90.0	
66		90.0	81.9	
72		84.7	75.0	
36	204	90.0	90.0	
42		90.0	90.0	
48		90.0	90.0	
54		90.0	90.0	
60		90.0	82.3	
66		87.1	74.8	
72		79.8	68.6	
36	210	90.0	90.0	
42		90.0	90.0	
48		90.0	90.0	
54		90.0	83.9	
60		90.0	75.5	
66		82.2	68.6	
72		75.3	62.9	

JAMB/MULLION LOAD CAPACITY (+/- PSF)				
NOMINAL DIMS.		CASE 2	CASE 3*	
		MULLION 'M21' & 'M22'	MULLION 'M23' & 'M24'	
WIDTH 'W' (in.)	SPAN HEIGHT 'H' (in.)	EXT. (+) INT. (-)	EXT. (+) INT. (-)	
36	216	90.0	90.0	
42		90.0	90.0	
48		90.0	86.7	
54		90.0	77.1	
60		85.4	69.4	
66		77.7	63.1	
72		71.2	57.8	
36	222	90.0	90.0	
42		90.0	90.0	
48		90.0	79.9	
54		89.9	71.0	
60		80.9	63.9	
66		73.5	58.1	
72		67.4	53.2	
36	228	90.0	90.0	
42		90.0	84.2	
48		90.0	73.7	
54		85.2	65.5	
60		76.7	59.0	
66		69.7	53.6	
72		63.9	49.1	
36	234	90.0	90.0	
42		90.0	77.9	
48		90.0	68.2	
54		80.9	60.6	
60		72.8	54.6	
66		66.2	49.6	
72		60.7	45.5	
36	240	90.0	84.3	
42		90.0	72.2	
48		86.1	63.2	
54		76.5	56.2	
60		68.9	50.6	
66		62.6	46.0	
72		57.4	42.1	
36	246	90.0	78.3	
42		90.0	67.1	
48		79.6	58.7	
54		70.7	52.2	
60		63.7	47.0	
66		57.9	42.7	
72		53.0	39.1	

JAMB/MULLION LOAD CAPACITY (+/- PSF)				
NOMINAL DIMS.		CASE 2	CASE 3*	
		MULLION 'M21' & 'M22'	MULLION 'M23' & 'M24'	
WIDTH 'W' (in.)	SPAN HEIGHT 'H' (in.)	EXT. (+) INT. (-)	EXT. (+) INT. (-)	
36	252	90.0	72.8	
42		84.2	62.4	
48		73.7	54.6	
54		65.5	48.5	
60		58.9	43.7	
66		53.6	39.7	
72		49.1	36.4	
36	258	90.0	67.8	
42		78.1	58.1	
48		68.3	50.9	
54		60.8	45.2	
60		54.7	40.7	
66		49.7	37.0	
72		45.6	33.9	
36	264	84.7	63.3	
42		72.6	54.3	
48		63.5	47.5	
54		56.5	42.2	
60		50.8	38.0	
66		46.2	34.5	
72		42.3	31.7	
36	270	78.8	59.2	
42		67.6	50.7	
48		59.1	44.4	
54		52.6	39.5	
60		47.3	35.5	
66		43.0	32.3	
72		39.4	29.6	
36	276	73.5	55.4	
42		63.0	47.5	
48		55.1	41.6	
54		49.0	36.9	
60		44.1	33.2	
66		40.1	30.2	
72		36.8	27.7	
36	282	68.7	51.9	
42		58.9	44.5	
48		51.5	39.0	
54		45.8	34.6	
60		41.2	31.2	
66		37.5	28.3	
72		34.3	26.0	

*SLEEVE REINFORCEMENT @ WL + DL, 29" LONG

JAMB/MULLION LOAD CAPACITY (+/- PSF)				
NOMINAL DIMS.		CASE 2	CASE 3*	
		MULLION 'M21' & 'M22'	MULLION 'M23' & 'M24'	
WIDTH 'W' (in.)	SPAN HEIGHT 'H' (in.)	EXT. (+) INT. (-)	EXT. (+) INT. (-)	
36	288	64.2	48.8	
42		55.1	41.8	
48		48.2	36.6	
54		42.8	32.5	
60		38.5	29.3	
66		35.0	26.6	
72		32.1	24.4	
36	294	60.2	45.8	
42		51.6	39.3	
48		45.1	34.4	
54		40.1	30.6	
60		36.1	27.5	
66		32.8	25.0	
72		30.1	22.9	
36	300	56.4	43.1	
42		48.4	37.0	
48		42.3	32.4	
54		37.6	28.8	
60		33.9	25.9	
66		30.8	23.5	
72		28.2	21.6	
36	306	53.0	40.7	
42		45.4	34.8	
48		39.8	30.5	
54		35.3	27.1	
60		31.8	24.4	
66		28.9	22.2	
72		26.5	20.3	
36	312	49.8	38.4	
42		42.7	32.9	
48		37.4	28.8	
54		33.2	25.6	
60		29.9	23.0	
66		27.2	20.9	
72		24.9	19.2	
36	318	46.9	36.9	
42		40.2	31.7	
48		35.2	27.7	
54		31.3	24.6	
60		28.2	22.2	
66		25.6	20.1	
72		23.5	18.5	
36	324	44.2	35.6	
42		37.9	30.5	
48		33.2	26.7	
54		29.5	23.7	
60		26.5	21.3	
66		24.1	19.4	
72		22.1	17.8	

HEAVY DUTY HORIZONTAL MULLIONS (+/- PSF)	
MAX. WIDTH, W (in.) 'Span'	EXT. (+) INT. (-)
72	90

REFER TO SECTION 4.10 FOR HEAVY DUTY MULLION DETAILS.




YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE:
YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM
MULLION CAPACITY CHARTS

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:
FL13433

DATE:
7.17.17

DWG. BY:
AR

CHK. BY:
HFN

SCALE:
NTS

DWG. #:
YKK204

SECTION:
4.10A

REV.
B

[Page 17 of 59]

HEAVY DUTY MULLION CAPACITY CHARTS (HIGH PRESSURES)


NOTES

- DESIGN PRESSURES ARE LIMITED BY THE MULLION FIBERSTRESS AND DEFLECTION CAPACITY PER CURRENT FBC SPECIFICATIONS FOR HVHZ
- SELECT DESIGN PRESSURE AND PANEL WIDTH (W) AND OBTAIN THE MAXIMUM ALLOWABLE DESIGN PRESSURE FOR MULLION.
- FOR HORIZONTAL MULLIONS CAPACITY, SEE HORIZONTAL MULLION CHART.
- WHEN PANEL WIDTHS ARE NOT EQUAL, USE THE AVERAGE WIDTH ON THE CHART.


CASE 1: SINGLE SPAN WITH UNREINFORCED MULLION

CASE 2: SINGLE SPAN WITH REINFORCED MULLION FULL HEIGHT

CASE 3: TWIN SPAN WITH REINFORCED MULLION AT INTERMEDIATE SUPPORT ONLY



SINGLE SPAN




DOUBLE SPAN


REINFORCING LENGTH = FRAME HEIGHT - 12 IN.

MULLIONS


SECTIONS @ F/T ANCHOR / SPLICE/WIND LOAD/ DEAD LOAD LOCATION




UNREINFORCED
HEAVY DUTY MULLION
(E9-3182)




UNREINFORCED
HEAVY DUTY MULLION
(E9-3183)




REINFORCED
HEAVY DUTY MULLION
(E9-3182)



REINFORCED
STANDARD DUTY MULLION
(E9-3183)



SLEEVE REINFORCEMENT
HEAVY DUTY MULLION
(E9-3182)




SLEEVE REINFORCEMENT
HEAVY DUTY MULLION
(E9-3183)


REFER TO 4.11A FOR HEAVY DUTY MULLION
CAPACITY TABLES (HIGH PRESSURE)

VERTICAL MEMBER SINGLE SPAN NOTES:


- DETAILS HAVE BEEN SHOWN FOR ILLUSTRATIVE PURPOSES. FOR DETAILS OF FULL ASSEMBLY PLEASE REFER TO APPLICABLE DETAILS ON SECTION 3.
- TABULATED DESIGN PRESSURE VALUES ARE BASED ON LIMITATIONS OF DEFLECTION, FIBERSTRESS, & END REACTION PER MULLION SPAN ('L') AND MULLION SPACING ('W').
- FOR SITE CONDITIONS WHICH EXCEED LIMITATIONS SHOWN, FURTHER ENGINEERING MAY BE REQUIRED ON A CASE BY CASE BASIS.
- FOR T, F, OR S CLIP ANCHORS, PLEASE REFER TO SECTION 7 & 8 FOR ANCHOR SELECTION, SUBSTRATE REQUIREMENTS, AND FURTHER LIMITATIONS OF USE.



HEAVY DUTY HORIZONTAL
(E9-3189)



HEAVY DUTY HORIZONTAL
(E9-3190)



HEAVY DUTY HORIZONTAL
(E9-3187)



HEAVY DUTY HORIZONTAL
(E9-3185)

- 14A MULLION ANCHOR SLEEVE (HD)
(3" LONG AT TOP & BOTTOM)
- 44A MULLION SPLICE SLEEVE (HD)
(6" LONG AT SPLICE)
- 46A MULLION WL/DL REINFORCEMENT SLEEVE (HD)
(29" LONG AT MID-POINT ANCHOR)



YKK AP AMERICA

101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE: YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM
MULLION CAPACITY CHARTS


PREPARED BY: BUILDING DROPS, INC.

1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #: FL13433

DATE: 7.17.17

DWG. BY: AR
CHK. BY: HFN

SCALE: NTS

DWG. #: YKK204

SECTION: 4.11
REV. B

HEAVY DUTY MULLION CAPACITY CHARTS (HIGH PRESSURES)

JAMB/MULLION LOAD CAPACITY (+/- PSF)				
NOMINAL DIMS.		CASE 1	CASE 2	CASE 3*
		MULLION 'M25' & 'M26'	MULLION 'M27' & 'M28'	MULLION 'M29' & 'M30'
WIDTH 'W' (in.)	SPAN HEIGHT 'H' (in.)	EXT. (+) INT. (-)	EXT. (+) INT. (-)	EXT. (+) INT. (-)
36	144	130.0	130.0	130.0
42		130.0	130.0	130.0
48		130.0	130.0	130.0
54		120.1	130.0	130.0
60		108.1	130.0	130.0
66		98.2	130.0	130.0
72		90.1	130.0	130.0
36	150	130.0	130.0	130.0
42		130.0	130.0	130.0
48		124.5	130.0	130.0
54		110.7	130.0	130.0
60		99.6	130.0	130.0
66		90.5	130.0	130.0
72		83.0	130.0	130.0
36	156	130.0	130.0	130.0
42		130.0	130.0	130.0
48		115.1	130.0	130.0
54		102.3	130.0	130.0
60		92.1	130.0	130.0
66		83.7	130.0	130.0
72		76.7	130.0	128.4
36	162	130.0	130.0	130.0
42		122.0	130.0	130.0
48		106.7	130.0	130.0
54		94.9	130.0	130.0
60		85.4	130.0	130.0
66		77.6	130.0	130.0
72		71.2	126.6	123.7
36	168	130.0	130.0	130.0
42		113.4	130.0	130.0
48		99.3	130.0	130.0
54		88.2	130.0	130.0
60		79.4	130.0	130.0
66		72.2	128.4	125.5
72		66.2	117.7	115.0
36	174	123.4	130.0	130.0
42		105.7	130.0	130.0
48		92.5	130.0	130.0
54		82.2	130.0	130.0
60		74.0	130.0	128.7
66		67.3	119.7	117.0
72		61.7	109.7	107.2

JAMB/MULLION LOAD CAPACITY (+/- PSF)				
NOMINAL DIMS.		CASE 1	CASE 2	CASE 3*
		MULLION 'M25' & 'M26'	MULLION 'M27' & 'M28'	MULLION 'M29' & 'M30'
WIDTH 'W' (in.)	SPAN HEIGHT 'H' (in.)	EXT. (+) INT. (-)	EXT. (+) INT. (-)	EXT. (+) INT. (-)
36	180	114.1	130.0	130.0
42		97.8	130.0	130.0
48		85.6	130.0	130.0
54		76.1	130.0	130.0
60		68.5	123.0	119.8
66		62.2	111.8	109.0
72		57.1	102.5	99.9
36	186	103.4	130.0	130.0
42		88.7	130.0	130.0
48		77.6	130.0	130.0
54		69.0	128.0	120.7
60		62.1	115.2	108.6
66		56.4	104.7	98.7
72		51.7	96.0	90.5
36	192	94.0	130.0	130.0
42		80.6	130.0	130.0
48		70.5	130.0	123.4
54		62.7	120.1	109.7
60		56.4	108.1	98.8
66		51.3	98.3	89.8
72		47.0	90.1	82.3
36	198	85.7	130.0	130.0
42		73.5	130.0	128.6
48		64.3	127.1	112.6
54		57.2	113.0	100.0
60		51.4	101.7	90.0
66		46.8	92.4	81.9
72		42.9	84.7	75.0
36	204	78.4	130.0	130.0
42		67.2	130.0	117.6
48		58.8	119.7	102.9
54		52.3	106.4	91.5
60		47.0	95.8	82.3
66		42.8	87.1	74.8
72		39.2	79.8	68.6
36	210	71.9	130.0	125.8
42		61.6	129.1	107.8
48		53.9	113.0	94.3
54		47.9	100.4	83.9
60		43.1	90.4	75.5
66		39.2	82.2	68.6
72		35.9	75.3	62.9

JAMB/MULLION LOAD CAPACITY (+/- PSF)			
NOMINAL DIMS.		CASE 2	CASE 3*
		MULLION 'M27' & 'M28'	MULLION 'M29' & 'M30'
WIDTH 'W' (in.)	SPAN HEIGHT 'H' (in.)	EXT. (+) INT. (-)	EXT. (+) INT. (-)
36	216	130.0	115.6
42		122.0	99.1
48		106.8	86.7
54		94.9	77.1
60		85.4	69.4
66		77.7	63.1
72		71.2	57.8
36	222	130.0	106.5
42		115.5	91.3
48		101.1	79.9
54		89.9	71.0
60		80.9	63.9
66		73.5	58.1
72		67.4	53.2
36	228	127.8	98.3
42		109.5	84.2
48		95.8	73.7
54		85.2	65.5
60		76.7	59.0
66		69.7	53.6
72		63.9	49.1
36	234	121.3	90.9
42		104.0	77.9
48		91.0	68.2
54		80.9	60.6
60		72.8	54.6
66		66.2	49.6
72		60.7	45.5
36	240	114.8	84.3
42		98.4	72.2
48		86.1	63.2
54		76.5	56.2
60		68.9	50.6
66		62.6	46.0
72		57.4	42.1
36	246	106.1	78.3
42		90.9	67.1
48		79.6	58.7
54		70.7	52.2
60		63.7	47.0
66		57.9	42.7
72		53.0	39.1

NOMINAL DIMS.		JAMB/MULLION LOAD CAPACITY (+/- PSF)	
		CASE 2	CASE 3*
		MULLION 'M27' & 'M28'	MULLION 'M29' & 'M30'
WIDTH 'W' (in.)	SPAN HEIGHT 'H' (in.)	EXT. (+) INT. (-)	EXT. (+) INT. (-)
36	252	98.2	72.8
42		84.2	62.4
48		73.7	54.6
54		65.5	48.5
60		58.9	43.7
66		53.6	39.7
72		49.1	36.4
36	258	91.1	67.8
42		78.1	58.1
48		68.3	50.9
54		60.8	45.2
60		54.7	40.7
66		49.7	37.0
72		45.6	33.9
36	264	84.7	63.3
42		72.6	54.3
48		63.5	47.5
54		56.5	42.2
60		50.8	38.0
66		46.2	34.5
72		42.3	31.7
36	270	78.8	59.2
42		67.6	50.7
48		59.1	44.4
54		52.6	39.5
60		47.3	35.5
66		43.0	32.3
72		39.4	29.6
36	276	73.5	55.4
42		63.0	47.5
48		55.1	41.6
54		49.0	36.9
60		44.1	33.2
66		40.1	30.2
72		36.8	27.7
36	282	68.7	51.9
42		58.9	44.5
48		51.5	39.0
54		45.8	34.6
60		41.2	31.2
66		37.5	28.3
72		34.3	26.0

NOMINAL DIMS.		JAMB/MULLION LOAD CAPACITY (+/- PSF)	
		CASE 2	CASE 3*
		MULLION 'M27' & 'M28'	MULLION 'M29' & 'M30'
WIDTH 'W' (in.)	SPAN HEIGHT 'H' (in.)	EXT. (+) INT. (-)	EXT. (+) INT. (-)
36	288	60.2	45.8
42		51.6	39.3
48		45.1	34.4
54		40.1	30.6
60		36.1	27.5
66		32.8	25.0
72		30.1	22.9
36	294	56.4	43.1
42		48.4	37.0
48		42.3	32.4
54		37.6	28.8
60		33.9	25.9
66		30.8	23.5
72		28.2	21.6
36	300	53.0	40.7
42		45.4	34.8
48		39.8	30.5
54		35.3	27.1
60		31.8	24.4
66		28.9	22.2
72		26.5	20.3
36	306	49.8	38.4
42		42.7	32.9
48		37.4	28.8
54		33.2	25.6
60		29.9	23.0
66		27.2	20.9
72		24.9	19.2
36	312	46.9	36.9
42		40.2	31.7
48		35.2	27.7
54		31.3	24.6
60		28.2	22.2
66		25.6	20.1
72		23.5	18.5
36	318	44.2	35.6
42		37.9	30.5
48		33.2	26.7
54		29.5	23.7
60		26.5	21.3
66		24.1	19.4
72		22.1	17.8
36	324	44.2	35.6
42		37.9	30.5
48		33.2	26.7
54		29.5	23.7
60		26.5	21.3
66		24.1	19.4
72		22.1	17.8

HEAVY DUTY HORIZONTAL MULLIONS (+/- PSF)	
MAX. WIDTH, W (in.) 'Span'	EXT. (+) INT. (-)
72	130

REFER TO SECTION 4.11 FOR
HEAVY DUTY MULLION DETAILS.

*SLEEVE REINFORCEMENT @ WL + DL, 29" LONG



YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE:
YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM


HORIZONTAL CORNER SECTIONS

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744.4738
WEB: www.buildingdrops.com

BUILDING DROPS

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:
FL13433

DATE:
7.17.17

DWG. BY:
AR

CHK. BY:
HFN

SCALE:
NTS

DWG. #:
YKK204

SECTION:
4.11A


REV.
B

[Page 19 of 59]


7/24/2026 10:25 AM

c:\users\sebastianherrerros\desktop\ykk 2026 ca\113433\ykk 204 - fl13433 dwgs 5 & 6.dwg


LIGHT DUTY MULLION DOOR DETAILS




1
5.0 CONNECTION DETAIL
FRAME MULLION / DOOR HEAD
LIGHT DUTY / MONOLITHIC GLASS




4
5.0 CONNECTION DETAIL
FRAME MULLION / DOOR HEAD
LIGHT DUTY / INSULATING GLASS




2
5.0 CONNECTION DETAIL
FRAME MULLION / DOOR JAMB
LIGHT DUTY / MONOLITHIC GLASS



3
5.0 CONNECTION DETAIL
FRAME MULLION / DOOR JAMB
LIGHT DUTY / MONOLITHIC GLASS




5
5.0 CONNECTION DETAIL
FRAME MULLION / DOOR JAMB
LIGHT DUTY / INSULATING GLASS



6
5.0 CONNECTION DETAIL
FRAME MULLION / DOOR JAMB
LIGHT DUTY / INSULATING GLASS

DOOR JAMB MULLION CAPACITY



MAX. DOOR OPNG, WIDTH	A	DP (+/- PSF)
78-1/2"	60"	90.0

- NOTE:
- FOR DOOR HEIGHT LESS THAN OR EQUAL TO 98-1/2" USE ABOVE TABLE.
 - DOORS SHALL BE UNDER SEPARATE APPROVALS.



YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE:
YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM
DOOR DETAILS

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

BUILDING DROPS

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26


THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT

HERMES F. NORERO, P.E.
BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
FBPE CERT. OF AUTHORIZATION No. 29578


FL #:	FL13433
DATE:	7.17.17
DWG. BY:	AR
CHK. BY:	HFN
SCALE:	NTS
DWG. #:	YKK204
SECTION:	5.0
REV.	B

c:\users\sebastianherrerros\desktop\ykk 2026 ca\fl13433\ykk 204 - fl13433 dwgs 5 & 6.dwg 7/24/2026 10:25 AM


STANDARD DUTY MULLION DOOR DETAILS (MONOLITHIC GLASS)




1
5.1 CONNECTION DETAIL
FRAME MULLION / DOOR HEAD
STANDARD DUTY / MONOLITHIC GLASS




4
5.1 CONNECTION DETAIL
FRAME MULLION / DOOR JAMB
STANDARD DUTY / MONOLITHIC GLASS



2
5.1 CONNECTION DETAIL
FRAME MULLION / DOOR JAMB
STANDARD DUTY / MONOLITHIC GLASS



3
5.1 CONNECTION DETAIL
FRAME MULLION / DOOR JAMB
STANDARD DUTY / MONOLITHIC GLASS



MAX. DOOR OPNG, WIDTH	A	DP (+/- PSF)
78-1/2"	60"	90.0

- NOTE:**
- FOR DOOR HEIGHT LESS THAN OR EQUAL TO 98-1/2" USE ABOVE TABLE.
 - DOORS SHALL BE UNDER SEPARATE APPROVALS.

CONCRETE AND METAL STRUCTURE NOT BY YKK AP AMERICA INC. MUST SUSTAIN LOADS IMPOSED BY GLAZING SYSTEM AND TRANSFER THEM TO THE BUILDING STRUCTURE.



YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE:
YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM

DOOR DETAILS

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

BUILDING DROPS

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:
FL13433

DATE: **7.17.17**

DWG. BY: **AR** CHK. BY: **HFN**


SCALE: **NTS**

DWG. #: **YKK204**


SECTION: **5.1** REV. **B**

7/24/2026 10:25 AM
c:\users\sebastianherrerros\desktop\ykk 2026 ca\fl13433\ykk 204 - fl13433 dwgs 5 & 6.dwg


STANDARD DUTY MULLION DOOR DETAILS (INSULATING GLASS)




1
5.2 CONNECTION DETAIL
FRAME MULLION / DOOR HEAD
STANDARD DUTY / INSULATING GLASS



2
5.2 CONNECTION DETAIL
FRAME MULLION / DOOR JAMB
STANDARD DUTY / INSULATING GLASS



3
5.2 CONNECTION DETAIL
FRAME MULLION / DOOR JAMB
STANDARD DUTY / INSULATING GLASS




4
5.2 CONNECTION DETAIL
FRAME MULLION / DOOR JAMB
STANDARD DUTY / MONOLITHIC GLASS

DOOR JAMB MULLION CAPACITY

MAX. DOOR OPNG. WIDTH	A	DP (+/- PSF)
78-1/2"	60"	90.0

NOTE:

- FOR DOOR HEIGHT LESS THAN OR EQUAL TO 98-1/2" USE ABOVE TABLE.
- DOORS SHALL BE UNDER SEPARATE APPROVALS.



YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE: YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM
DOOR DETAILS
PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT




FL #:	FL13433
DATE:	7.17.17
DWG. BY:	AR
CHK. BY:	HFN
SCALE:	NTS
DWG. #:	YKK204
SECTION:	5.2
REV.	B


7/24/2026 10:25 AM

c:\users\sebastianherrerros\desktop\ykk 2026 ca\fl13433\ykk 204 - fl13433 dwgs 5 & 6.dwg


HEAVY DUTY MULLION DOOR DETAILS



1
5.3 **DOOR DETAIL**
FRAME MULLION / DOOR HEAD
HEAVY DUTY / MONOLITHIC GLASS




3
5.3 **DOOR DETAIL**
FRAME MULLION / DOOR JAMB
HEAVY DUTY / MONOLITHIC GLASS



4
5.3 **DOOR DETAIL**
FRAME MULLION / DOOR JAMB
HEAVY DUTY / MONOLITHIC GLASS


DOOR JAMB MULLION CAPACITY




ANCHOR TYPE 'S'
SEE NOTE BELOW

MAX. DOOR OPNG, WIDTH	A	DP (+/- PSF)
78-1/2"	60"	90.0


- NOTE:**
- FOR DOOR HEIGHT LESS THAN OR EQUAL TO 98-1/2" USE ABOVE TABLE.
 - DOORS SHALL BE UNDER SEPARATE APPROVALS.



6
5.3 **DOOR DETAIL**
FRAME MULLION / DOOR HEAD
HEAVY DUTY / INSULATING GLASS



7
5.3 **DOOR DETAIL**
FRAME MULLION / DOOR HEAD JAMB
HEAVY DUTY / INSULATING GLASS



8
5.3 **DOOR DETAIL**
FRAME MULLION / DOOR JAMB
HEAVY DUTY / INSULATING GLASS



YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE: **YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM**


DOOR DETAILS

PREPARED BY: **BUILDING DROPS, INC.**
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

BD
BUILDING DROPS

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT




FL #:	FL13433
DATE:	7.17.17
DWG. BY:	AR
CHK. BY:	HFN
SCALE:	NTS
DWG. #:	YKK204
SECTION:	5.3
REV.	B

MONOLITHIC SMALL MISSILE IMPACT GLASS OPTIONS

NOTES:



- 1. CHART VALUES PROVIDE MAXIMUM DESIGN PRESSURES ACCORDING TO ASTM E1300 FOR GIVEN GLASS DIMENSIONS 'a' AND 'b' (a ≥ b), AND CH. 17 OF THE FBC FOR SIZES OTHER THAN TESTED
- 2. DO NOT EXCEED MULLION CAPACITY SELECTED OR ANCHOR CAPACITY IN DESIGN PRESSURE CHARTS
- 3. ALLOW FOR SPLAY OF 2.5° AT EACH SIDE FOR A TOTAL SPLAY OF 5° AT ALL GLASS LOCATIONS.



REFER TO 6.0A FOR MONOLITHIC GLASS CAPACITY CHARTS - LARGE MISSILE IMPACT

- * NOTE:
- 1. GLASS CAPACITIES ON THIS SHEET ARE BASED ON ASTM E1300 (3 SEC. GUSTS) AND CHAPTER 17 OF THE CURRENT FBC FOR SIZES OTHER THAN TESTED.
 - 2. SETTING BLOCK DUROMETER HARDNESS OF 70-90 (SHORE A) AS REFERENCED IN CHAPTER 24.
 - 3. SETTING BLOCKS TO BE LOCATED AT 1/4 SPAN LENGTH FOR GLASS WIDER THAN 36" AS PER CHAPTER 24.
 - 4. D.L.O. MAY NOT EXCEED MAX DIMENSIONS IN GLASS CHARTS FOR GLASS TYPE.

PANEL DIMENSIONS



YKK

ap

Quality
inspires™

YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE:
YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM

GLAZING DETAILS

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744.4738
WEB: www.buildingdrops.com

BD

BUILDING DROPS

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT

HERMES F. NORERO

LICENSE

No. 73778

STATE OF FLORIDA

PROFESSIONAL ENGINEER

HERMES F. NORERO, P.E.

FLORIDA PROFESSIONAL ENGINEER

BUILDING DROPS, INC.

1900 NE MIAMI CT, SUITE 2-15

MIAMI, FL 33132

FBPE CERT. OF AUTHORIZATION No. 29578

FL #:

FL13433

DATE:

7.17.17

DWG. BY:

AR

CHK. BY:

HFN

SCALE:

NTS

DWG. #:

YKK204

SECTION:

6.0

REV.

B

[Page 24 of 59]

7/24/2026 10:25 AM

c:\users\sebastianhereros\desktop\ykk 2026 cc\113433\ykk 204 - fl13433 dwgs 5 & 6.dwg

MONOLITHIC GLASS LOAD CAPACITY (S.M.I)

GLASS LOAD CAPACITY (PSF)					
NOMINAL DIMS.		GLASS TYPES A & B		GLASS TYPES C	
D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	EXT. (+)	INT. (-)	EXT. (+)	INT. (-)
24	60	130.0	130.0	90.0	90.0
30		130.0	130.0	90.0	90.0
36		130.0	130.0	90.0	90.0
39		130.0	130.0	90.0	90.0
42		130.0	130.0	90.0	90.0
48		130.0	130.0	90.0	90.0
54		130.0	130.0	90.0	90.0
60		123.5	123.5	85.5	85.5
72		123.5	123.5	85.5	85.5
78		123.5	123.5	85.5	85.5
84		123.5	123.5	85.5	85.5
24	66	130.0	130.0	90.0	90.0
30		130.0	130.0	90.0	90.0
36		130.0	130.0	90.0	90.0
39		130.0	130.0	90.0	90.0
42		130.0	130.0	90.0	90.0
48		130.0	130.0	90.0	90.0
54		130.0	130.0	90.0	90.0
60		123.5	123.5	85.5	85.5
66		112.3	112.3	77.7	77.7
72		112.3	112.3	77.7	77.7
78		112.3	112.3	77.7	77.7
84		77.7	77.7	-	-
24	72	130.0	130.0	90.0	90.0
30		130.0	130.0	90.0	90.0
36		130.0	130.0	90.0	90.0
39		130.0	130.0	90.0	90.0
42		130.0	130.0	90.0	90.0
48		130.0	130.0	90.0	90.0
54		130.0	130.0	90.0	90.0
60		123.5	123.5	85.5	85.5
66		112.3	112.3	77.7	77.7
72		102.9	102.9	71.3	71.3
78		71.3	71.3	-	-
84		71.3	71.3	-	-

GLASS TABLE NOTES:

- GLASS CAPACITIES ON THIS SHEET ARE BASED ON ASTM E1300 (3 SEC. GUSTS).
- GLASS CAPACITIES ARE LIMITED BY THE RESULTS OF COMPARATIVE ANALYSIS IN ACCORDANCE WITH CHAPTER 17 OF THE CURRENT FBC.
- WHERE REQUIRED, TEMPERED GLASS IS REQUIRED TO BE USED TO COMPLY WITH SAFETY GLAZING REQUIREMENTS OUTLINED IN CHAPTER 24 OF THE CURRENT FBC.
- ALL GLASS LITES THAT EXCEED 36" IN WIDTH SHALL USE APPROVED SETTING BLOCKS IN ACCORDANCE WITH CHAPTER 24 OF THE CURRENT FBC.
- REFER TO FIGURE 1 FOR ILLUSTRATION OF DAYLIGHT OPENING DIMENSIONS.

GLASS LOAD CAPACITY (PSF)					
NOMINAL DIMS.		GLASS TYPES A & B		GLASS TYPES C	
D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	EXT. (+)	INT. (-)	EXT. (+)	INT. (-)
24	78	130.0	130.0	90.0	90.0
30		130.0	130.0	90.0	90.0
36		130.0	130.0	90.0	90.0
39		130.0	130.0	90.0	90.0
42		130.0	130.0	90.0	90.0
48		130.0	130.0	90.0	90.0
54		130.0	130.0	90.0	90.0
60		123.5	123.5	85.5	85.5
66		112.3	112.3	77.7	77.7
72		71.3	71.3	-	-
78		65.8	65.8	-	-
84		65.8	65.8	-	-
24	84	130.0	130.0	90.0	90.0
30		130.0	130.0	90.0	90.0
36		130.0	130.0	90.0	90.0
39		130.0	130.0	90.0	90.0
42		130.0	130.0	90.0	90.0
48		130.0	130.0	90.0	90.0
54		130.0	130.0	90.0	90.0
60		123.5	123.5	85.5	85.5
66		77.7	77.7	-	-
72		71.3	71.3	-	-
78		65.8	65.8	-	-
24	90	130.0	130.0	90.0	90.0
30		130.0	130.0	90.0	90.0
36		130.0	130.0	90.0	90.0
39		130.0	130.0	90.0	90.0
42		130.0	130.0	90.0	90.0
48		130.0	130.0	90.0	90.0
54		130.0	130.0	90.0	90.0
60		85.5	85.5	-	-
66		77.7	77.7	-	-
72		71.3	71.3	-	-
24	94.5	130.0	130.0	90.0	90.0
30		130.0	130.0	90.0	90.0
36		130.0	130.0	90.0	90.0
39		130.0	130.0	90.0	90.0
42		130.0	130.0	90.0	90.0
48		130.0	130.0	90.0	90.0
54		130.0	130.0	90.0	90.0
57		130.0	130.0	90.0	90.0
60		85.5	85.5	-	-
66		77.7	77.7	-	-
72		71.3	71.3	-	-

GLASS LOAD CAPACITY (PSF)					
NOMINAL DIMS.		GLASS TYPES A & B		GLASS TYPES C	
D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	EXT. (+)	INT. (-)	EXT. (+)	INT. (-)
24	102	130.0	130.0	90.0	90.0
30		130.0	130.0	90.0	90.0
36		130.0	130.0	90.0	90.0
39		130.0	130.0	90.0	90.0
42		130.0	130.0	90.0	90.0
48		130.0	130.0	90.0	90.0
54		90.0	90.0	-	-
60		85.5	85.5	-	-
66		77.7	77.7	-	-
24	108	130.0	130.0	90.0	90.0
30		130.0	130.0	90.0	90.0
36		130.0	130.0	90.0	90.0
39		130.0	130.0	90.0	90.0
42		130.0	130.0	90.0	90.0
48		130.0	130.0	90.0	90.0
54		90.0	90.0	-	-
60		85.5	85.5	-	-
24	114	130.0	130.0	90.0	90.0
30		130.0	130.0	90.0	90.0
36		130.0	130.0	90.0	90.0
39		130.0	130.0	90.0	90.0
42		130.0	130.0	90.0	90.0
48		90.0	90.0	-	-
54		90.0	90.0	-	-
60		85.5	85.5	-	-
24	120	130.0	130.0	90.0	90.0
30		130.0	130.0	90.0	90.0
36		130.0	130.0	90.0	90.0
39		130.0	130.0	90.0	90.0
42		130.0	130.0	90.0	90.0
48		90.0	90.0	-	-
54		90.0	90.0	-	-
57		90.0	90.0	-	-

REFER TO SECTION 6.0 FOR MONOLITHIC
SMALL MISSILE IMPACT GLAZING DETAILS.

D.L.O. WIDTH = PANEL WIDTH - 3"
D.L.O. HEIGHT = PANEL HEIGHT - 6"



YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE:
YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM

GLAZING DETAILS

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT

HERMES F. NORERO, P.E.
BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
FBPE CERT. OF AUTHORIZATION No. 29578

FL #:
FL13433

DATE:
7.17.17

DWG. BY:
AR

CHK. BY:
HFN

SCALE:
NTS

DWG. #:
YKK204








SECTION:
6.0A

REV.
B

MONOLITHIC LARGE MISSILE IMPACT GLASS OPTIONS

NOTES:

- 1. CHART VALUES PROVIDE MAXIMUM DESIGN PRESSURES ACCORDING TO ASTM E1300 FOR GIVEN GLASS DIMENSIONS 'a' AND 'b' (a ≥ b), AND CH. 17 OF THE FBC FOR SIZES OTHER THAN TESTED
- 2. DO NOT EXCEED MULLION CAPACITY SELECTED OR ANCHOR CAPACITY IN DESIGN PRESSURE CHARTS
- 3. ALLOW FOR SPLAY OF 2.5° AT EACH SIDE FOR A TOTAL SPLAY OF 5° AT ALL GLASS LOCATIONS.





REFER TO 6.1A FOR MONOLITHIC GLASS CAPACITY CHARTS - LARGE MISSILE IMPACT

- * NOTE:
- 1. GLASS CAPACITIES ON THIS SHEET ARE BASED ON ASTM E1300 (3 SEC. GUSTS) AND CHAPTER 17 OF THE CURRENT FBC FOR SIZES OTHER THAN TESTED.
 - 2. SETTING BLOCK DUROMETER HARDNESS OF 70-90 (SHORE A) AS REFERENCED IN CHAPTER 24.
 - 3. SETTING BLOCKS TO BE LOCATED AT 1/4 SPAN LENGTH FOR GLASS WIDER THAN 36" AS PER CHAPTER 24.
 - 4. D.L.O. MAY NOT EXCEED MAX DIMENSIONS IN GLASS CHARTS FOR GLASS TYPE.

PANEL DIMENSIONS

('a' ≥ 'b')



YKK AP AMERICA

101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001


TITLE: YHC - 300 OG (HVHZ) CURTAIN WALL SYSTEM

GLAZING DETAILS

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #: FL13433

DATE: 7.17.17

DWG. BY: AR
CHK. BY: HFN

SCALE: NTS

DWG. #: YKK204

SECTION: 6.1
REV. B

YKK
ap
Quality
inspires

UILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744.4738
WEB: www.buildingdrops.com



PREPARED BY
BID
BUILDING DROPS


GLASS LOAD CAPACITY (PSF)							
NOMINAL DIMS.		GLASS TYPE 'D'		GLASS TYPE 'G'		GLASS TYPES 'J'	
D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	EXT. (+)	INT. (-)	EXT. (+)	INT. (-)	EXT. (+)	INT. (-)
24	84	45.0	45.0	55.0	55.0	65.0	65.0
30		45.0	45.0	55.0	55.0	65.0	65.0
36		45.0	45.0	55.0	55.0	65.0	65.0
39		45.0	45.0	55.0	55.0	65.0	65.0
42		45.0	45.0	55.0	55.0	65.0	65.0
48		-	-	55.0	55.0	65.0	65.0
54		-	-	55.0	55.0	65.0	65.0
60		-	-	52.3	52.3	61.8	61.8
24	90	45.0	45.0	55.0	55.0	65.0	65.0
30		45.0	45.0	55.0	55.0	65.0	65.0
36		45.0	45.0	55.0	55.0	65.0	65.0
39		45.0	45.0	55.0	55.0	65.0	65.0
42		-	-	55.0	55.0	65.0	65.0
48		-	-	55.0	55.0	65.0	65.0
54		-	-	55.0	55.0	65.0	65.0
60		-	-	55.0	55.0	65.0	65.0
24	94.5	45.0	45.0	55.0	55.0	65.0	65.0
30		45.0	45.0	55.0	55.0	65.0	65.0
36		45.0	45.0	55.0	55.0	65.0	65.0
39		-	-	55.0	55.0	65.0	65.0
42		-	-	55.0	55.0	65.0	65.0
48		-	-	55.0	55.0	65.0	65.0
54		-	-	55.0	55.0	65.0	65.0
60		-	-	55.0	55.0	65.0	65.0
24	102	45.0	45.0	55.0	55.0	65.0	65.0
30		45.0	45.0	55.0	55.0	65.0	65.0
36		-	-	55.0	55.0	65.0	65.0
39		-	-	55.0	55.0	65.0	65.0
42		-	-	55.0	55.0	65.0	65.0
48		-	-	55.0	55.0	65.0	65.0
24	108	45.0	45.0	55.0	55.0	65.0	65.0
30		45.0	45.0	55.0	55.0	65.0	65.0
36		-	-	55.0	55.0	65.0	65.0
39		-	-	55.0	55.0	65.0	65.0
42		-	-	55.0	55.0	65.0	65.0
48		-	-	55.0	55.0	65.0	65.0
24	114	45.0	45.0	55.0	55.0	65.0	65.0
30		45.0	45.0	55.0	55.0	65.0	65.0
36		-	-	55.0	55.0	65.0	65.0
39		-	-	55.0	55.0	65.0	65.0
42		-	-	55.0	55.0	65.0	65.0
48		-	-	55.0	55.0	65.0	65.0
24	120	45.0	45.0	55.0	55.0	65.0	65.0
30		45.0	45.0	55.0	55.0	65.0	65.0
36		-	-	55.0	55.0	65.0	65.0
39		-	-	55.0	55.0	65.0	65.0
42		-	-	55.0	55.0	65.0	65.0
48		-	-	55.0	55.0	65.0	65.0

D.L.O. WIDTH = PANEL WIDTH - 3"
D.L.O. HEIGHT = PANEL HEIGHT - 6"

GLASS LOAD CAPACITY (PSF)					
NOMINAL DIMS.		GLASS TYPES 'E & F'		GLASS TYPES 'H' & 'I'	
D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	EXT. (+)	INT. (-)	EXT. (+)	INT. (-)
24	90	90.0	90.0	130.0	130.0
30		90.0	90.0	130.0	130.0
36		90.0	90.0	130.0	130.0
39		90.0	90.0	130.0	130.0
42		90.0	90.0	130.0	130.0
48		90.0	90.0	130.0	130.0
54		90.0	90.0	130.0	130.0
60		85.5	85.5	-	-
66		77.7	77.7	-	-
72		71.3	71.3	-	-
24	94.5	90.0	90.0	130.0	130.0
30		90.0	90.0	130.0	130.0
36		90.0	90.0	130.0	130.0
39		90.0	90.0	130.0	130.0
42		90.0	90.0	130.0	130.0
48		90.0	90.0	130.0	130.0
54		90.0	90.0	130.0	130.0
57		90.0	90.0	130.0	130.0
60		85.5	85.5	-	-
66		77.7	77.7	-	-
72	71.3	71.3	-	-	
24	102	90.0	90.0	130.0	130.0
30		90.0	90.0	130.0	130.0
36		90.0	90.0	130.0	130.0
39		90.0	90.0	130.0	130.0
42		90.0	90.0	130.0	130.0
48		90.0	90.0	130.0	130.0
54		90.0	90.0	-	-
60		85.5	85.5	-	-
66		77.7	77.7	-	-
24	108	90.0	90.0	130.0	130.0
30		90.0	90.0	130.0	130.0
36		90.0	90.0	130.0	130.0
39		90.0	90.0	130.0	130.0
42		90.0	90.0	130.0	130.0
48		90.0	90.0	130.0	130.0
54		90.0	90.0	-	-
60		85.5	85.5	-	-
24		114	90.0	90.0	130.0
30	90.0		90.0	130.0	130.0
36	90.0		90.0	130.0	130.0
39	90.0		90.0	130.0	130.0
42	90.0		90.0	130.0	130.0
48	90.0		90.0	-	-
54	90.0		90.0	-	-
60	85.5		85.5	-	-
24	120		90.0	90.0	130.0
30		90.0	90.0	130.0	130.0
36		90.0	90.0	130.0	130.0
39		90.0	90.0	130.0	130.0
42		90.0	90.0	130.0	130.0
48		90.0	90.0	-	-
54		90.0	90.0	-	-
57		90.0	90.0	-	-

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT






SECTION:	REV.
E 1 A	B

INSULATING SMALL MISSILE IMPACT GLASS OPTIONS

NOTES:

- CHART VALUES PROVIDE MAXIMUM DESIGN PRESSURES ACCORDING TO ASTM E1300 FOR GIVEN GLASS DIMENSIONS 'a' AND 'b' ($a \geq b$), AND CH. 17 OF THE FBC FOR SIZES OTHER THAN TESTED
- DO NOT EXCEED MULLION CAPACITY SELECTED OR ANCHOR CAPACITY IN DESIGN PRESSURE CHARTS
- ALLOW FOR SPLAY OF 2.5° AT EACH SIDE FOR A TOTAL SPLAY OF 5° AT ALL GLASS LOCATIONS.



1/2" AIR SPACE CONSISTING OF:

- SPACER: ALUMINUM BOX SPACER
- PRIMARY SEALANT: POLYISOBUTYLENE (PIB)
- SECONDARY SEALANT: STRUCTURAL SILICONE INTENDED FOR FABRICATION OF INSULATING GLASS UNITS




* NOTE:

- GLASS CAPACITIES ON THIS SHEET ARE BASED ON ASTM E1300 (3 SEC. GUSTS) AND CHAPTER 17 OF THE CURRENT FBC FOR SIZES OTHER THAN TESTED.
- SETTING BLOCK DUROMETER HARDNESS OF 70-90 (SHORE A) AS REFERENCED IN CHAPTER 24.
- SETTING BLOCKS TO BE LOCATED AT 1/4 SPAN LENGTH FOR GLASS WIDER THAN 36" AS PER CHAPTER 24.
- D.L.O. MAY NOT EXCEED MAX DIMENSIONS IN GLASS CHARTS FOR GLASS TYPE.

REFER TO 6.2A FOR INSULATING GLASS CAPACITY CHARTS - SMALL MISSILE IMPACT

PANEL DIMENSIONS

('a' $\geq$ 'b')



YKK AP AMERICA

101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE: YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM


GLAZING DETAILS

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

BUILDING DROPS

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:	FL13433
DATE:	7.17.17
DWG. BY:	AR
CHK. BY:	HFN
SCALE:	NTS
DWG. #:	YKK204
SECTION:	6.2
REV.	B

7/24/2026 10:25 AM

c:\users\sebastianherrerros\desktop\ykk 2026 ca\fl13433\ykk 204 - fl13433.dwg

INSULATING GLASS LOAD CAPACITY (S.M.I)

GLASS LOAD CAPACITY (PSF)					
NOMINAL DIMS.		GLASS TYPES K & L		GLASS TYPES M	
D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	EXT. (+)	INT. (-)	EXT. (+)	INT. (-)
24	60	130.0	130.0	90.0	90.0
30		130.0	130.0	90.0	90.0
36		130.0	130.0	90.0	90.0
39		130.0	130.0	90.0	90.0
42		130.0	130.0	90.0	90.0
48		130.0	130.0	90.0	90.0
54		130.0	130.0	90.0	90.0
60		123.5	123.5	85.5	85.5
66		123.5	123.5	85.5	85.5
72		123.5	123.5	85.5	85.5
78		123.5	123.5	85.5	85.5
84		123.5	123.5	85.5	85.5
24	66	130.0	130.0	90.0	90.0
30		130.0	130.0	90.0	90.0
36		130.0	130.0	90.0	90.0
39		130.0	130.0	90.0	90.0
42		130.0	130.0	90.0	90.0
48		130.0	130.0	90.0	90.0
54		130.0	130.0	90.0	90.0
60		123.5	123.5	85.5	85.5
66		112.3	112.3	77.7	77.7
72		112.3	112.3	77.7	77.7
78		112.3	112.3	77.7	77.7
84		77.7	77.7	-	-
24	72	130.0	130.0	90.0	90.0
30		130.0	130.0	90.0	90.0
36		130.0	130.0	90.0	90.0
39		130.0	130.0	90.0	90.0
42		130.0	130.0	90.0	90.0
48		130.0	130.0	90.0	90.0
54		130.0	130.0	90.0	90.0
60		123.5	123.5	85.5	85.5
66		112.3	112.3	77.7	77.7
72		102.9	102.9	71.3	71.3
78		71.3	71.3	-	-
84		71.3	71.3	-	-
24	78	130.0	130.0	90.0	90.0
30		130.0	130.0	90.0	90.0
36		130.0	130.0	90.0	90.0
39		130.0	130.0	90.0	90.0
42		130.0	130.0	90.0	90.0
48		130.0	130.0	90.0	90.0
54		130.0	130.0	90.0	90.0
60		123.5	123.5	85.5	85.5
66		112.3	112.3	77.7	77.7
72		71.3	71.3	-	-
78		65.8	65.8	-	-
84		65.8	65.8	-	-
24	84	130.0	130.0	90.0	90.0
30		130.0	130.0	90.0	90.0
36		130.0	130.0	90.0	90.0
39		130.0	130.0	90.0	90.0
42		130.0	130.0	90.0	90.0
48		130.0	130.0	90.0	90.0
54		130.0	130.0	90.0	90.0
60		123.5	123.5	85.5	85.5
66		77.7	77.7	-	-
72		71.3	71.3	-	-
78		65.8	65.8	-	-

GLASS LOAD CAPACITY (PSF)					
NOMINAL DIMS.		GLASS TYPES K & L		GLASS TYPES M	
D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	EXT. (+)	INT. (-)	EXT. (+)	INT. (-)
24	90	130.0	130.0	90.0	90.0
30		130.0	130.0	90.0	90.0
36		130.0	130.0	90.0	90.0
39		130.0	130.0	90.0	90.0
42		130.0	130.0	90.0	90.0
48		130.0	130.0	90.0	90.0
54		130.0	130.0	90.0	90.0
60		85.5	85.5	-	-
66		77.7	77.7	-	-
72		71.3	71.3	-	-
24	94.5	130.0	130.0	90.0	90.0
30		130.0	130.0	90.0	90.0
36		130.0	130.0	90.0	90.0
39		130.0	130.0	90.0	90.0
42		130.0	130.0	90.0	90.0
48		130.0	130.0	90.0	90.0
54		130.0	130.0	90.0	90.0
57		130.0	130.0	90.0	90.0
60		85.5	85.5	-	-
66		77.7	77.7	-	-
72		71.3	71.3	-	-
24	102	130.0	130.0	90.0	90.0
30		130.0	130.0	90.0	90.0
36		130.0	130.0	90.0	90.0
39		130.0	130.0	90.0	90.0
42		130.0	130.0	90.0	90.0
48		130.0	130.0	90.0	90.0
54		90.0	90.0	-	-
60		85.5	85.5	-	-
66		77.7	77.7	-	-
24	108	130.0	130.0	90.0	90.0
30		130.0	130.0	90.0	90.0
36		130.0	130.0	90.0	90.0
39		130.0	130.0	90.0	90.0
42		130.0	130.0	90.0	90.0
48		130.0	130.0	90.0	90.0
54		90.0	90.0	-	-
60		85.5	85.5	-	-
24	114	130.0	130.0	90.0	90.0
30		130.0	130.0	90.0	90.0
36		130.0	130.0	90.0	90.0
39		130.0	130.0	90.0	90.0
42		130.0	130.0	90.0	90.0
48		90.0	90.0	-	-
54		90.0	90.0	-	-
60		85.5	85.5	-	-
24	120	130.0	130.0	90.0	90.0
30		130.0	130.0	90.0	90.0
36		130.0	130.0	90.0	90.0
39		130.0	130.0	90.0	90.0
42		130.0	130.0	90.0	90.0
48		90.0	90.0	-	-
54		90.0	90.0	-	-
57		90.0	90.0	-	-

- GLASS TABLE NOTES:
1. GLASS CAPACITIES ON THIS SHEET ARE BASED ON ASTM E1300 (3 SEC. GUSTS).

2. GLASS CAPACITIES ARE LIMITED BY THE RESULTS OF COMPARATIVE ANALYSIS IN ACCORDANCE WITH CHAPTER 17 OF THE CURRENT FBC.

3. WHERE REQUIRED, TEMPERED GLASS IS REQUIRED TO BE USED TO COMPLY WITH SAFETY GLAZING REQUIREMENTS OUTLINED IN CHAPTER 24 OF THE CURRENT FBC.

4. ALL GLASS LITES THAT EXCEED 36" IN WIDTH SHALL USE APPROVED SETTING BLOCKS IN ACCORDANCE WITH CHAPTER 24 OF THE CURRENT FBC.

5. REFER TO FIGURE 1 FOR ILLUSTRATION OF DAYLIGHT OPENING DIMENSIONS.

REFER TO SECTION 6.2 FOR INSULATING SMALL MISSILE IMPACT GLAZING DETAILS.

D.L.O. WIDTH = PANEL WIDTH - 3"
D.L.O. HEIGHT = PANEL HEIGHT - 6"



Quality
inspires™

YKK AP AMERICA

101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE:
YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM

GLAZING DETAILS


PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744.4738
WEB: www.buildingdrops.com



BUILDING DROPS

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



HERMES F. NORERO
LICENSE
No. 73778
STATE OF
FLORIDA
PROFESSIONAL ENGINEER
HERMES F. NORERO, P.E.
BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
FBPE CERT. OF AUTHORIZATION No. 29578

FL #:
FL13433

DATE:
7.17.17

DWG. BY:
AR

CHK. BY:
HFN

SCALE:
NTS

DWG. #:
YKK204

SECTION:
6.2A








REV.
B

[Page 29 of 59]

INSULATING LARGE MISSILE IMPACT GLASS OPTIONS

NOTES:

1. CHART VALUES PROVIDE MAXIMUM DESIGN PRESSURES ACCORDING TO ASTM E1300 FOR GIVEN GLASS DIMENSIONS 'a' AND 'b' ($a \geq b$), AND CH. 17 OF THE FBC FOR SIZES OTHER THAN TESTED
2. DO NOT EXCEED MULLION CAPACITY SELECTED OR ANCHOR CAPACITY IN DESIGN PRESSURE CHARTS
3. ALLOW FOR SPLAY OF 2.5° AT EACH SIDE FOR A TOTAL SPLAY OF 5° AT ALL GLASS LOCATIONS.



* NOTE:



1. GLASS CAPACITIES ON THIS SHEET ARE BASED ON ASTM E1300 (3 SEC. GUSTS) AND CHAPTER 17 OF THE CURRENT FBC FOR SIZES OTHER THAN TESTED.
2. SETTING BLOCK DUROMETER HARDNESS OF 70-90 (SHORE A) AS REFERENCED IN CHAPTER 24.
3. SETTING BLOCKS TO BE LOCATED AT 1/4 SPAN LENGTH FOR GLASS WIDER THAN 36" AS PER CHAPTER 24.
4. D.L.O. MAY NOT EXCEED MAX DIMENSIONS IN GLASS CHARTS FOR GLASS TYPE.

1/2" AIR SPACE CONSISTING OF:

- SPACER: ALUMINUM BOX SPACER
- PRIMARY SEALANT: POLYISOBUTYLENE (PIB)
- SECONDARY SEALANT: STRUCTURAL SILICONE INTENDED FOR FABRICATION OF INSULATING GLASS UNITS

REFER TO 6.3A & 6.3B FOR
INSULATING GLASS CAPACITY
CHARTS - LARGE MISSILE IMPACT

PANEL DIMENSIONS



YKK AP AMERICA

101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE: YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM


GLAZING DETAILS

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

BUILDING DROPS

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:	FL13433
DATE:	7.17.17
DWG. BY:	AR
CHK. BY:	HFN
SCALE:	NTS
DWG. #:	YKK204
SECTION:	6.3
REV.	B

[Page 30 of 59]

7/24/2026 10:25 AM

c:\users\sebastianhereros\desktop\ykk 2026 ca\fl13433 dwgs 5 & 6.dwg

INSULATING GLASS LOAD CAPACITY (L.M.I)

GLASS LOAD CAPACITY (PSF)							
NOMINAL DIMS.		GLASS TYPE 'N'		GLASS TYPE 'Q'		GLASS TYPES 'S'	
D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	EXT. (+)	INT. (-)	EXT. (+)	INT. (-)	EXT. (+)	INT. (-)
24	60	45.0	45.0	55.0	55.0	65.0	65.0
30		45.0	45.0	55.0	55.0	65.0	65.0
36		45.0	45.0	55.0	55.0	65.0	65.0
39		45.0	45.0	55.0	55.0	65.0	65.0
42		45.0	45.0	55.0	55.0	65.0	65.0
48		42.2	42.2	55.0	55.0	65.0	65.0
54		37.5	37.5	55.0	55.0	65.0	65.0
60		33.8	33.8	52.3	52.3	61.8	61.8
66		-	-	52.3	52.3	61.8	61.8
72		-	-	52.3	52.3	61.8	61.8
78		-	-	52.3	52.3	61.8	61.8
84		-	-	52.3	52.3	61.8	61.8
24	66	45.0	45.0	55.0	55.0	65.0	65.0
30		45.0	45.0	55.0	55.0	65.0	65.0
36		45.0	45.0	55.0	55.0	65.0	65.0
39		45.0	45.0	55.0	55.0	65.0	65.0
42		45.0	45.0	55.0	55.0	65.0	65.0
48		42.2	42.2	55.0	55.0	65.0	65.0
54		37.5	37.5	55.0	55.0	65.0	65.0
60		-	-	52.3	52.3	61.8	61.8
66		-	-	47.5	47.5	56.1	56.1
72		-	-	47.5	47.5	56.1	56.1
78		-	-	47.5	47.5	56.1	56.1
84		-	-	47.5	47.5	56.1	56.1
24	72	45.0	45.0	55.0	55.0	65.0	65.0
30		45.0	45.0	55.0	55.0	65.0	65.0
36		45.0	45.0	55.0	55.0	65.0	65.0
39		45.0	45.0	55.0	55.0	65.0	65.0
42		45.0	45.0	55.0	55.0	65.0	65.0
48		42.2	42.2	55.0	55.0	65.0	65.0
54		-	-	55.0	55.0	65.0	65.0
60		-	-	52.3	52.3	61.8	61.8
66		-	-	47.5	47.5	56.1	56.1
72		-	-	43.5	43.5	51.5	51.5
78		-	-	43.5	43.5	51.5	51.5
84		-	-	43.5	43.5	51.5	51.5
24	78	45.0	45.0	55.0	55.0	65.0	65.0
30		45.0	45.0	55.0	55.0	65.0	65.0
36		45.0	45.0	55.0	55.0	65.0	65.0
39		45.0	45.0	55.0	55.0	65.0	65.0
42		45.0	45.0	55.0	55.0	65.0	65.0
48		-	-	55.0	55.0	65.0	65.0
54		-	-	55.0	55.0	65.0	65.0
60		-	-	52.3	52.3	61.8	61.8
66		-	-	47.5	47.5	56.1	56.1
72		-	-	47.5	47.5	56.1	56.1
78		-	-	47.5	47.5	56.1	56.1
84		-	-	47.5	47.5	56.1	56.1

GLASS TABLE NOTES:

- GLASS CAPACITIES ON THIS SHEET ARE BASED ON ASTM E1300 (3 SEC. GUSTS).
- GLASS CAPACITIES ARE LIMITED BY THE RESULTS OF COMPARATIVE ANALYSIS IN ACCORDANCE WITH CHAPTER 17 OF THE CURRENT FBC.
- WHERE REQUIRED, TEMPERED GLASS IS REQUIRED TO BE USED TO COMPLY WITH SAFETY GLAZING REQUIREMENTS OUTLINED IN CHAPTER 24 OF THE CURRENT FBC.
- ALL GLASS LITES THAT EXCEED 36" IN WIDTH SHALL USE APPROVED SETTING BLOCKS IN ACCORDANCE WITH CHAPTER 24 OF THE CURRENT FBC.
- REFER TO FIGURE 1 FOR ILLUSTRATION OF DAYLIGHT OPENING DIMENSIONS.

GLASS LOAD CAPACITY (PSF)							
NOMINAL DIMS.		GLASS TYPE 'N'		GLASS TYPE 'Q'		GLASS TYPES 'S'	
D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	EXT. (+)	INT. (-)	EXT. (+)	INT. (-)	EXT. (+)	INT. (-)
24	84	45.0	45.0	55.0	55.0	65.0	65.0
30		45.0	45.0	55.0	55.0	65.0	65.0
36		45.0	45.0	55.0	55.0	65.0	65.0
39		45.0	45.0	55.0	55.0	65.0	65.0
42		45.0	45.0	55.0	55.0	65.0	65.0
48		-	-	55.0	55.0	65.0	65.0
54		-	-	52.3	52.3	61.8	61.8
60		-	-	52.3	52.3	61.8	61.8
66		-	-	52.3	52.3	61.8	61.8
72		-	-	52.3	52.3	61.8	61.8
78		-	-	52.3	52.3	61.8	61.8
84		-	-	52.3	52.3	61.8	61.8
24	90	45.0	45.0	55.0	55.0	65.0	65.0
30		45.0	45.0	55.0	55.0	65.0	65.0
36		45.0	45.0	55.0	55.0	65.0	65.0
39		45.0	45.0	55.0	55.0	65.0	65.0
42		-	-	55.0	55.0	65.0	65.0
48		-	-	55.0	55.0	65.0	65.0
54		-	-	55.0	55.0	65.0	65.0
60		-	-	55.0	55.0	65.0	65.0
66		-	-	55.0	55.0	65.0	65.0
72		-	-	55.0	55.0	65.0	65.0
78		-	-	55.0	55.0	65.0	65.0
84		-	-	55.0	55.0	65.0	65.0
24	94.5	45.0	45.0	55.0	55.0	65.0	65.0
30		45.0	45.0	55.0	55.0	65.0	65.0
36		45.0	45.0	55.0	55.0	65.0	65.0
39		-	-	55.0	55.0	65.0	65.0
42		-	-	55.0	55.0	65.0	65.0
48		-	-	55.0	55.0	65.0	65.0
54		-	-	55.0	55.0	65.0	65.0
60		-	-	55.0	55.0	65.0	65.0
66		-	-	55.0	55.0	65.0	65.0
72		-	-	55.0	55.0	65.0	65.0
78		-	-	55.0	55.0	65.0	65.0
84		-	-	55.0	55.0	65.0	65.0
24	102	45.0	45.0	55.0	55.0	65.0	65.0
30		45.0	45.0	55.0	55.0	65.0	65.0
36		-	-	55.0	55.0	65.0	65.0
39		-	-	55.0	55.0	65.0	65.0
42		-	-	55.0	55.0	65.0	65.0
48		-	-	55.0	55.0	65.0	65.0
54		-	-	55.0	55.0	65.0	65.0
60		45.0	45.0	55.0	55.0	65.0	65.0
66		-	-	55.0	55.0	65.0	65.0
72		-	-	55.0	55.0	65.0	65.0
78		-	-	55.0	55.0	65.0	65.0
84		-	-	55.0	55.0	65.0	65.0
24	108	45.0	45.0	55.0	55.0	65.0	65.0
30		45.0	45.0	55.0	55.0	65.0	65.0
36		-	-	55.0	55.0	65.0	65.0
39		-	-	55.0	55.0	65.0	65.0
42		-	-	55.0	55.0	65.0	65.0
48		-	-	55.0	55.0	65.0	65.0
54		-	-	55.0	55.0	65.0	65.0
60		45.0	45.0	55.0	55.0	65.0	65.0
66		-	-	55.0	55.0	65.0	65.0
72		-	-	55.0	55.0	65.0	65.0
78		-	-	55.0	55.0	65.0	65.0
84		-	-	55.0	55.0	65.0	65.0
24	114	45.0	45.0	55.0	55.0	65.0	65.0
30		45.0	45.0	55.0	55.0	65.0	65.0
36		-	-	55.0	55.0	65.0	65.0
39		-	-	55.0	55.0	65.0	65.0
42		-	-	55.0	55.0	65.0	65.0
48		-	-	55.0	55.0	65.0	65.0
54		-	-	55.0	55.0	65.0	65.0
60		45.0	45.0	55.0	55.0	65.0	65.0
66		-	-	55.0	55.0	65.0	65.0
72		-	-	55.0	55.0	65.0	65.0
78		-	-	55.0	55.0	65.0	65.0
84		-	-	55.0	55.0	65.0	65.0
24	120	45.0	45.0	55.0	55.0	65.0	65.0
30		-	-	55.0	55.0	65.0	65.0
36		-	-	55.0	55.0	65.0	65.0
39		-	-	55.0	55.0	65.0	65.0
42		-	-	55.0	55.0	65.0	65.0
48		-	-	55.0	55.0	65.0	65.0
54		-	-	55.0	55.0	65.0	65.0
60		45.0	45.0	55.0	55.0	65.0	65.0
66		-	-	55.0	55.0	65.0	65.0
72		-	-	55.0	55.0	65.0	65.0
78		-	-	55.0	55.0	65.0	65.0
84		-	-	55.0	55.0	65.0	65.0

REFER TO SECTION 6.3 FOR INSULATING LARGE MISSILE IMPACT GLAZING DETAILS.

D.L.O. WIDTH = PANEL WIDTH - 3"
D.L.O. HEIGHT = PANEL HEIGHT - 6"

GLASS LOAD CAPACITY (PSF)					
NOMINAL DIMS.		GLASS TYPES 'R'		GLASS TYPES 'P' & 'O'	
D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	EXT. (+)	INT. (-)	EXT. (+)	INT. (-)
24	60	90.0	90.0	130.0	130.0
30		90.0	90.0	130.0	130.0
36		90.0	90.0	130.0	130.0
39		90.0	90.0	130.0	130.0
42		90.0	90.0	130.0	130.0
48		90.0	90.0	130.0	130.0
54		90.0	90.0	130.0	130.0
60		85.5	85.5	124.6	124.6
66		85.5	85.5	124.6	124.6
72		85.5	85.5	124.6	124.6
78		85.5	85.5	124.6	124.6
84		85.5	85.5	124.6	124.6
24	66	90.0	90.0	130.0	130.0
30		90.0	90.0	130.0	130.0
36		90.0	90.0	130.0	130.0
39		90.0	90.0	130.0	130.0
42		90.0	90.0	130.0	130.0
48		90.0	90.0	130.0	130.0
54		90.0	90.0	130.0	130.0
60		85.5	85.5	124.6	124.6
66		77.7	77.7	113.3	113.3
72		77.7	77.7	113.3	113.3
78		77.7	77.7	113.3	113.3
84		77.7	77.7	-	-
24	72	90.0	90.0	130.0	130.0
30		90.0	90.0	130.0	130.0
36		90.0	90.0	130.0	130.0
39		90.0	90.0	130.0	130.0
42		90.0	90.0	130.0	130.0
48		90.0	90.0	130.0	130.0
54		90.0	90.0	130.0	130.0
60		85.5	85.5	124.6	124.6
66		77.7	77.7	113.3	113.3
72		71.3	71.3	103.8	103.8
78		71.3	71.3	-	-
84		71.3	71.3	-	-
24	78	90.0	90.0	130.0	130.0
30		90.0	90.0	130.0	130.0
36		90.0	90.0	130.0	130.0
39		90.0	90.0	130.0	130.0
42		90.0	90.0	130.0	130.0
48		90.0	90.0	130.0	130.0
54		90.0	90.0	130.0	130.0
60		85.5	85.5	124.6	124.6
66		77.7	77.7	113.3	113.3
72		71.3	71.3	-	-
78		65.8	65.8	-	-
84		65.8	65.8	-	-
24	84	90.0	90.0	130.0	130.0
30		90.0	90.0	130.0	130.0
36		90.0	90.0	130.0	130.0
39		90.0	90.0	130.0	130.0
42		90.0	90.0	130.0	130.0
48		90.0	90.0	130.0	130.0
54		90.0	90.0	130.0	130.0
60		85.5	85.5	124.6	124.6
66		77.7	77.7	-	-
72		71.3	71.3	-	-
78		65.8	65.8	-	-

7/24/2026 10:25 AM

c:\users\sebastianherrerros\desktop\ykk 2026 ca\fl13433\ykk 204 - fl13433.dwg s 5 & 6.dwg

INSULATING GLASS LOAD CAPACITY - L.M.I (CONT.)

GLASS LOAD CAPACITY (PSF)		
NOMINAL DIMS.		GLASS TYPE 'U'
D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	EXT. (+) INT. (-)
24	60	130.0
30		130.0
36		130.0
39		130.0
42		130.0
48		130.0
54		130.0
60		124.6
66		124.6
72		124.6
78		124.6
84		124.6
24	66	130.0
30		130.0
36		130.0
39		130.0
42		130.0
48		130.0
54		130.0
60		124.6
66		113.3
72		113.3
78		113.3
84		77.7
24	72	130.0
30		130.0
36		130.0
39		130.0
42		130.0
48		130.0
54		130.0
60		124.6
66		113.3
72		103.8
78		71.3
84		71.3
24	78	130.0
30		130.0
36		130.0
39		130.0
42		130.0
48		130.0
54		130.0
60		124.6
66		113.3
72		71.3
78		65.8
84		65.8
24	84	130.0
30		130.0
36		130.0
39		130.0
42		130.0
48		130.0
54		130.0
60		124.6
66		77.7
72		71.3
78		65.8

GLASS LOAD CAPACITY (PSF)		
NOMINAL DIMS.		GLASS TYPE 'U'
D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	EXT. (+)
24	90	130.0
30		130.0
36		130.0
39		130.0
42		130.0
48		130.0
54		130.0
60		124.6
66		77.7
72		71.3
24	94.5	130.0
30		130.0
36		130.0
39		130.0
42		130.0
48		130.0
54		130.0
54		130.0
60		85.5
66		77.7
72		71.3
24	102	130.0
30		130.0
36		130.0
39		130.0
42		130.0
48		130.0
54		90.0
60		85.5
66		77.7
24	108	130.0
30		130.0
36		130.0
39		130.0
42		130.0
48		130.0
54		90.0
60		85.5
24	114	130.0
30		130.0
36		130.0
39		130.0
42		130.0
48		130.0
54		90.0
60		85.5
24	120	130.0
30		130.0
36		130.0
39		130.0
42		130.0
48		90.0
54		90.0
57		90.0



YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001


TITLE: YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM
GLAZING DETAILS

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744.4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:	FL13433	
DATE:	7.17.17	
DWG. BY:	AR	CHK. BY: HFN
SCALE:	NTS	
DWG. #:	YKK204	
SECTION:	6.3B	REV. B

[Page 32 of 59]


F, T, & S ANCHOR TYPES

TYPE	DIAMETER	ANCHOR TYPE	SUBSTRATE	MINIMUM EDGE DISTANCE	MINIMUM EMBEDMENT
A	1/2"	HILTI KWIK BOLT TZ	MIN. 3000 PSI CONCRETE 'UNCRACKED'	3 1/4"	3 5/8"
			MIN. 3000 PSI CONCRETE 'CRACKED OR UNCRACKED'	4 1/2"	
			MIN. 4000 PSI CONCRETE 'UNCRACKED'	3 1/4"	
			MIN. 4000 PSI CONCRETE 'CRACKED OR UNCRACKED'	3 3/4"	
B	1/2"	HILTI HAS + HIT HY200 ADHESIVE ANCHOR	MIN. 4000 PSI CONCRETE 'CRACKED OR UNCRACKED'	5"	5"
C	1/2"	DEWALT SCREW-BOLT+	MIN. 3000 PSI CONCRETE 'UNCRACKED'	5"	4 1/4"
			MIN. 3000 PSI CONCRETE 'CRACKED OR UNCRACKED'	6 3/8"	
D	1/2"	ASTM A325 OR SAE GR. 5 THREADED BOLT WITH NUT & WASHER OR DRILL & TAP, OR DEWALT TAP-FLEX GR. 5 SELF TAPPING BOLT	MIN. 1/4" THICK, A36 STEEL	3/4"	MIN. 3 THREADS PENETRATION BEYOND STEEL STRUCTURE OR NUT
E	1/2"	SIMPSON TITEN HD	MIN. 4000 PSI CONCRETE 'UNCRACKED'	3 5/8"	4"
F	1/2"	HILTI KWIK BOLT TZ2	MIN. 4000 PSI CONCRETE 'UNCRACKED'	4"	3 1/4"
G	1/2"	SELF-TAPPING OR THREADED BOLT, MIN. SAE GR. 5 OR ASTM A325	MIN. 3/16" THICK A36 STEEL	3/4"	- FOR SELF-TAPPING OR DRILL & TAPPED HOLES, MIN. 3 THREADS PENETRATION BEYOND STEEL STRUCTURE. - FOR STANDARD DRILLED HOLES, PENETRATION TO BE SUFFICIENT TO MAINTAIN FULL ENGAGEMENT WITH NUT & WASHER
H	3/8"	SIMPSON TITEN HD	MIN. 4000 PSI CONCRETE 'CRACKED OR UNCRACKED'	3 5/8"	3 1/4"
I	3/8"	HILTI KWIK BOLT TZ2	MIN. 4000 PSI CONCRETE 'UNCRACKED'	4"	2 5/16"
J	5/16"	DEWALT DRIL-FLEX OR HILTI KWIK-FLEX SELF-DRILLING	MIN. 16 GAUGE STEEL, MIN. Fy = 33KSI	3/4"	MIN. 3 THREADS PENETRATION BEYOND STEEL STRUCTURE
K	#14	DEWALT CRETE FLEX SS4	MIN. 3500 PSI CONCRETE 'UNCRACKED'	1 3/4"	1 3/4"
	1/4"	DEWALT ULTRAACON+	MIN. 4000 PSI CONCRETE	1 1/2"	1 3/4"
L	1/4"	HILTI KWIK-CONII+	MIN. 2000 PSI CONCRETE UNCRACKED	1 3/4"	1 3/4"
M	M12	HALFEN TEE-BOLT GR. 8.8 FOR USE WITH HT3512 & HT6112 HALFEN CAST IN CHANNELS	MIN. 4000 PSI CONCRETE 'CRACKED OR UNCRACKED'	3"	PER HALFEN'S SPECIFICATIONS HT3512 = 3 1/8" HT6112 = 6 3/8"
N	3/8"	DEWALT SCREW-BOLT+	MIN 3000 PSI CONCRETE	3 7/8"	2 1/2"
O	#14	WOOD SCREW	WOOD (MIN SG. = 0.55)	1"	1 1/4"
	1/4"	GR 5 SM SCREW			
	1/4"	DEWALT ULTAACON+			


MULLION SPACING OR BAY WIDTH, 'W', FOR T-ANCHORS	$W = \frac{W1 + W2}{2}$
MULLION SPACING OR BAY WIDTH, 'W', FOR F-ANCHORS AT JAMBS	$W = W1$
MULLION SPACING OR BAY WIDTH, 'W', FOR F-ANCHORS AT VERTICAL MULL WITH DOORS	$*W = \frac{W1 + W2}{2}$

*REFER TO SECTION 2 FOR ILLUSTRATION OF DETERMINING MAX. TRIBUTARY WIDTH

- NOTE:
- ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH ANCHOR MANUFACTURER'S INSTALLATION INSTRUCTIONS.
 - REFER TO ANCHOR LAYOUTS AT RIGHT FOR LOCATIONS AND DETERMINING MAX. LENGTHS (L) AND TRIBUTARY WIDTHS (W).
 - FOR SITE CONDITIONS NOT SHOWN IN THE DETAILS HEREIN OR EDGE DISTANCE REQUIREMENTS TO BE MODIFIED, ANCHORS MAY BE ENGINEERED ON A SITE SPECIFIC BASIS.
 - REFER TO SECTION 8 DETAILS FOR ANCHOR CONFIGURATIONS.
 - REFER TO SECTION 7 DETAILS FOR T, F, & S ANCHOR TYPE CAPACITIES.
 - FOR ANCHOR TYPE 'M', FINAL SELECTION OF HALFEN CAST IN CHANNEL & T-BOLTS SHALL BE VERIFIED BY HALFEN USA IN ACCORDANCE WITH SITE SPECIFIC LOADS PRIOR TO INSTALLATION.



SINGLE SPAN ANCHOR LAYOUT



MULTI SPAN ANCHOR LAYOUT - TYP.



YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE:
YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM


F, T & S - ANCHOR DETAILS

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

**BUILDING DROPS**

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:
FL13433

DATE:
7.17.17

DWG. BY:
AR

CHK. BY:
HFN

SCALE:
NTS

DWG. #:
YKK204

SECTION:
7.0


REV.
B

[Page 33 of 59]

7/24/2026 10:25 AM

c:\users\sebastianherrerros\desktop\ykk 2026 ca\113433\ykk 204 - fl 13433.dwg - fl 13433.dwg


INSTALLATION ANCHOR
TYPES B, C, D, E, F, G, H, & I



1
7.1 HORIZONTAL SECTION
F-ANCHOR
CONFIG 1

NOTE:
1. ANCHORS SHOWN HEREIN ARE FOR ILLUSTRATION PURPOSES ONLY. ACTUAL ANCHOR IDENTIFICATION SHALL BE PER ANCHOR MANUFACTURERS INSTALLATION INSTRUCTIONS
2. ANCHOR BOLT EXTENSIONS MAY BE CLIPPED TO T.O. HEX NUT AND SHEAR BLOCKS MAY BE NOTCHED TO ALLOW FOR ANCHOR CLEARANCE.
3. REFER TO INSTALLATION ANCHOR REQUIREMENTS FOR MINIMUM EDGE DISTANCES (E.D.), EMBEDMENTS (EMBED), & PROPERTIES OF OPENING SUBSTRATE, SECTIONS 7 & 8.


INSTALLATION ANCHOR
TYPES B, C, D, E, F, G, H, & I



2
7.1 HORIZONTAL SECTION
T-ANCHOR
CONFIG 1

NOTE:
1. STANDARD DUTY MEMBERS SHOWN. LIGHT DUTY WITH SAME END ANCHORS ARE SIMILAR. HEAVY DUTY MULLIONS ARE SIMILAR WITH E1-3034 (INTERMEDIATE VERTICAL MULLION) ITEM #93 & E1-3035 (JAMB MULLION) ITEM #94 END ANCHORS.


SEE NOTES 1-3



CONCRETE OR STEEL SUBSTRATE
BY OTHERS.
SEE INSTALLATION ANCHOR
REQUIREMENTS

EXTERIOR VIEW
F-ANCHOR (TYPICAL)

SEE NOTES 1-3



CONCRETE OR STEEL SUBSTRATE
BY OTHERS.
SEE INSTALLATION ANCHOR
REQUIREMENTS

EXTERIOR VIEW
T-ANCHOR (TYPICAL)




YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE: YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM
F & T - ANCHOR DETAILS
PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744.4738
WEB: www.buildingdrops.com

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26


THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:	FL13433
DATE:	7.17.17
DWG. BY:	AR
CHK. BY:	HFN
SCALE:	NTS
DWG. #:	YKK204
SECTION:	7.1
REV.	B

7/24/2026 10:25 AM


c:\users\sebastianherrerros\desktop\ykk 2026 ca\113433\ykk 204 - fl 13433.dwg 7 - fl 13433.dwg



3
7.2 HORIZONTAL SECTION
F-ANCHOR
CONFIG 2

4
7.2 HORIZONTAL SECTION
T-ANCHOR
CONFIG 2


NOTE:
1. STANDARD DUTY MEMBERS SHOWN.
LIGHT DUTY WITH SAME END ANCHORS
ARE SIMILAR. HEAVY DUTY MULLIONS
ARE SIMILAR WITH E1-3034
(INTERMEDIATE VERTICAL MULLION)
ITEM #93 & E1-3035 (JAMB MULLION)
ITEM #94 END ANCHORS.




5
7.2 HORIZONTAL SECTION
F-ANCHOR
CONFIG 3

6
7.2 HORIZONTAL SECTION
T-ANCHOR
CONFIG 3

EDGE OF OPENING SUBSTRATE
BY OTHERS.
SEE INSTALLATION ANCHOR
REQUIREMENTS



7
7.2 HORIZONTAL SECTION
F-ANCHOR
CONFIG 7



8
7.2 HORIZONTAL SECTION
T-ANCHOR
CONFIG 7



YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE:
YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM

F & T - ANCHOR DETAILS


PREPARED BY: BUILDING DROPS, INC.

1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC
AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC
SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE
FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED
ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC
DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:

FL13433

DATE: **7.17.17**

DWG. BY:
AR

CHK. BY:
HFN

SCALE: **NTS**

DWG. #: **YKK204**

SECTION:


7.2

REV.

B

7/24/2026 10:25 AM
c:\users\sebastianherrerros\desktop\ykk 2026 ca\fl13433\ykk 204 - fl13433 dwgs 7 - fl13433 anchor.dwg


TYPE M ANCHORS
FOR USE WITH HALFEN HT3512
CAST IN PLACE ANCHOR CHANNELS



9 HORIZONTAL SECTION
7.3 F-ANCHOR
CONFIG 1

- NOTE:
1. ANCHORS SHOWN HEREIN HAVE BEEN SPECIFIED PER ANCHOR MANUFACTURER'S RECOMMENDATIONS. CAST IN ANCHOR CHANNELS, HT3512 SHALL BE USED WITH F-ANCHORS AND HT6112 SHALL BE USED WITH T-ANCHORS.
 2. ANCHOR BOLT EXTENSIONS MAY BE CLIPPED TO T.O. HEX NUT AND SHEAR BLOCKS MAY BE NOTCHED TO ALLOW FOR ANCHOR CLEARANCE.
 3. REFER TO INSTALLATION ANCHOR REQUIREMENTS FOR MINIMUM EDGE DISTANCES (E.D.), EMBEDMENTS (EMBED), & PROPERTIES OF OPENING SUBSTRATE


TYPE M ANCHORS
FOR USE WITH HALFEN HT6112
CAST IN PLACE ANCHOR CHANNELS



10 HORIZONTAL SECTION
7.3 T-ANCHOR
CONFIG 1

- NOTE:
1. STANDARD DUTY MEMBERS SHOWN. LIGHT DUTY WITH SAME END ANCHORS ARE SIMILAR. HEAVY DUTY MULLIONS ARE SIMILAR WITH E1-3034 (INTERMEDIATE VERTICAL MULLION) ITEM #93 & E1-3035 (JAMB MULLION) ITEM #94 END ANCHORS.

EDGE OF OPENING SUBSTRATE
BY OTHERS.
SEE INSTALLATION ANCHOR
REQUIREMENTS




EXTERIOR VIEW
F-ANCHOR (TYPICAL)

HALFEN USA 3817 HTA
SERIES ANCHOR CHANNEL
HT3512 FOR USE W/
F-ANCHORS

SEE NOTES 1-3

CONCRETE SUBSTRATE
BY OTHERS.
SEE INSTALLATION ANCHOR
REQUIREMENTS



EXTERIOR VIEW
T-ANCHOR (TYPICAL)

HALFEN USA 5234 HTA SERIES
ANCHOR CHANNEL,
HT 6112, FOR USE W/ T-ANCHORS

CONCRETE SUBSTRATE
BY OTHERS.
SEE INSTALLATION ANCHOR
REQUIREMENTS



YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001


TITLE: YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM
F & T - ANCHOR DETAILS

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

B.D. BUILDING DROPS


REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:	FL13433
DATE:	7.17.17
DWG. BY:	AR
CHK. BY:	HFN
SCALE:	NTS
DWG. #:	YKK204
SECTION:	7.3
REV.	B

7/24/2026 10:25 AM
c:\users\sebastianherrerros\desktop\ykk 2026 ca\113433\ykk 204 - fl 13433 dwgs 7 - fl 13433 anchor dts.dwg




11 HORIZONTAL SECTION
7.4 F-ANCHOR CONFIG 1


12 HORIZONTAL SECTION
7.4 T-ANCHOR CONFIG 1

NOTE:
1. ANCHORS SHOWN HEREIN ARE FOR ILLUSTRATION PURPOSES ONLY. ACTUAL ANCHOR IDENTIFICATION SHALL BE PER ANCHOR MANUFACTURERS INSTALLATION INSTRUCTIONS
2. ANCHOR BOLT EXTENSIONS MAY BE CLIPPED TO T.O. HEX NUT AND SHEAR BLOCKS MAY BE NOTCHED TO ALLOW FOR ANCHOR CLEARANCE.
3. REFER TO INSTALLATION ANCHOR REQUIREMENTS FOR MINIMUM EDGE DISTANCES (E.D.), EMBEDMENTS (EMBED), & PROPERTIES OF OPENING SUBSTRATE

NOTE:
1. STANDARD DUTY MEMBERS SHOWN. LIGHT DUTY WITH SAME END ANCHORS ARE SIMILAR. HEAVY DUTY MULLIONS ARE SIMILAR WITH E1-3034 (INTERMEDIATE VERTICAL MULLION) ITEM #93 & E1-3035 (JAMB MULLION) ITEM #94 END ANCHORS.



EXTERIOR VIEW
F-ANCHOR (TYPICAL)



EXTERIOR VIEW
T-ANCHOR (TYPICAL)

YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE: YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM
F & T - ANCHOR DETAILS

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT

HERMES F. NORERO, P.E.
FLORIDA PROFESSIONAL ENGINEER
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
FBPE CERT. OF AUTHORIZATION No. 29578

FL #: **FL13433**

DATE: **7.17.17**

DWG. BY: AR	CHK. BY: HFN
--------------------	---------------------

SCALE: **NTS**

DWG. #: **YKK204**

SECTION: 7.4	REV. B
---------------------	---------------

[Page 37 of 59]

TITLE: *YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM*


F & T - ANCHOR DETAILS

BUILDING BY: BUILDING DROPS, INC.
1900 NE MIAMI CT. SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744.4738
WEB: www.buildingdrops.com

**BUILDING DROPS**

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #: **FL13433**

DATE: 7.17.17

DWG. BY: AR	CHK. BY: HFN
-----------------------	------------------------

SCALE: NTS

DWG. #: YKK204

SECTION: 7 E	REV. B
--------------	--------

7.5

[Page 38 of 59]



NOTE:

1. STANDARD DUTY MEMBERS SHOWN (DETAIL 13/7.5)
LIGHT DUTY WITH SAME END ANCHORS ARE SIMILAR.
2. HEAVY DUTY MULLIONS SHOWN (DETAIL 13A/7.5)


7/24/2026 10:25 AM



16 HORIZONTAL SECTION

7.6 S-ANCHOR
CONFIG 6

EXTERIOR VIEW



7/24/2026 10:25 AM

SINGLE SPAN & MULTI SPAN
T & F ANCHOR CAPACITIES

MAX. ANCHOR CAPACITY - DESIGN PRESSURES (+/- PSF)																
MAX. AVG. WIDTH 'W' (in.)	MAX. SPAN 'H' (in.)	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
36	78	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
42		130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
48		130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
54		130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
60		130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
66		125.9	130.0	130.0	130.0	130.0	130.0	130.0	130.0	125.9	130.0	130.0	125.9	130.0	125.9	125.9
72		115.4	130.0	130.0	130.0	130.0	130.0	130.0	130.0	115.4	130.0	130.0	115.4	130.0	115.4	115.4
36	84	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
42		130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
48		130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
54		130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
60		128.6	130.0	130.0	130.0	130.0	130.0	130.0	130.0	128.6	130.0	130.0	128.6	130.0	128.6	128.6
66		116.9	130.0	130.0	130.0	130.0	130.0	130.0	130.0	116.9	130.0	130.0	116.9	130.0	116.9	116.9
72		107.1	130.0	130.0	130.0	130.0	130.0	130.0	129.0	107.1	130.0	130.0	107.1	130.0	107.1	107.1
36	90	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
42		130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
48		130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
54		130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
60		120.0	130.0	130.0	130.0	130.0	130.0	130.0	120.0	130.0	130.0	130.0	120.0	130.0	120.0	120.0
66		109.1	130.0	130.0	130.0	130.0	130.0	130.0	130.0	109.1	130.0	130.0	109.1	130.0	109.1	109.1
72		100.0	130.0	125.0	130.0	130.0	130.0	130.0	120.4	100.0	130.0	130.0	100.0	130.0	100.0	100.0
36	96	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
42		130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
48		130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
54		125.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	125.0	130.0	130.0	125.0	130.0	125.0	125.0
60		112.5	130.0	130.0	130.0	130.0	130.0	130.0	130.0	112.5	130.0	130.0	112.5	130.0	112.5	112.5
66		102.3	130.0	127.8	130.0	130.0	130.0	130.0	123.1	102.3	130.0	130.0	102.3	130.0	102.3	102.3
72		93.8	130.0	117.2	130.0	130.0	130.0	130.0	112.9	93.8	130.0	130.0	93.8	130.0	93.8	93.8
36	102	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
42		130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
48		130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
54		117.6	130.0	130.0	130.0	130.0	130.0	130.0	130.0	117.6	130.0	130.0	117.6	130.0	117.6	117.6
60		105.9	130.0	130.0	130.0	130.0	130.0	130.0	127.5	105.9	130.0	130.0	105.9	130.0	105.9	105.9
66		96.3	130.0	120.3	130.0	130.0	130.0	130.0	115.9	96.3	130.0	130.0	96.3	130.0	96.3	96.3
72		88.2	130.0	110.3	130.0	130.0	130.0	130.0	106.2	88.2	130.0	130.0	88.2	130.0	88.2	88.2
36	108	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
42		130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
48		125.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	125.0	130.0	130.0	125.0	130.0	125.0	125.0
54		111.1	130.0	130.0	130.0	130.0	130.0	130.0	130.0	111.1	130.0	130.0	111.1	130.0	111.1	111.1
60		100.0	130.0	125.0	130.0	130.0	130.0	130.0	120.4	100.0	130.0	130.0	100.0	130.0	100.0	100.0
66		90.9	130.0	113.6	130.0	130.0	130.0	130.0	109.5	90.9	130.0	130.0	90.9	130.0	90.9	90.9
72		83.3	130.0	104.2	130.0	130.0	130.0	129.2	100.3	83.3	129.2	129.2	83.3	130.0	83.3	83.3
36	114	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
42		130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
48		118.4	130.0	130.0	130.0	130.0	130.0	130.0	130.0	118.4	130.0	130.0	118.4	130.0	118.4	118.4
54		105.3	130.0	130.0	130.0	130.0	130.0	130.0	126.7	105.3	130.0	130.0	105.3	130.0	105.3	105.3
60		94.7	130.0	118.4	130.0	130.0	130.0	130.0	114.1	94.7	130.0	130.0	94.7	130.0	94.7	94.7
66		86.1	130.0	107.7	130.0	130.0	130.0	130.0	103.7	86.1	130.0	130.0	86.1	130.0	86.1	86.1
72		78.9	130.0	98.7	130.0	130.0	130.0	122.4	95.1	78.9	122.4	122.4	78.9	130.0	78.9	78.9

NOTE:

- REFER TO SECTION 7.0 THRU 7.6 FOR DETAILS OF ANCHOR REQUIREMENTS. AND DETERMINING MAX. SPAN 'L' AND TRIBUTARY WIDTHS 'W'
- SEE SECTION 2, TWIN SPAN ELEVATION FOR LOCATION OF F-ANCHOR WHEN USED AT VERTICAL MULLION BETWEEN DOOR AND D.I.O.

MAX. ANCHOR CAPACITY - DESIGN PRESSURES (+/- PSF)																
MAX. AVG. WIDTH 'W' (in.)	MAX. SPAN 'H' (in.)	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
36	120	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
42		128.6	130.0	130.0	130.0	130.0	130.0	130.0	130.0	128.6	130.0	130.0	128.6	130.0	128.6	128.6
48		112.5	130.0	130.0	130.0	130.0	130.0	130.0	130.0	112.5	130.0	130.0	112.5	130.0	112.5	112.5
54		100.0	130.0	125.0	130.0	130.0	130.0	130.0	120.4	100.0	130.0	130.0	100.0	130.0	100.0	100.0
60		90.0	130.0	112.5	130.0	130.0	130.0	130.0	108.4	90.0	130.0	130.0	90.0	130.0	90.0	90.0
66		81.8	130.0	102.3	130.0	130.0	130.0	126.8	98.5	81.8	126.8	126.8	81.8	130.0	81.8	81.8
72		75.0	130.0	93.8	130.0	130.0	130.0	116.3	90.3	75.0	116.3	116.3	75.0	130.0	75.0	75.0
36	126	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
42		122.4	130.0	130.0	130.0	130.0	130.0	130.0	130.0	122.4	130.0	130.0	122.4	130.0	122.4	122.4
48		107.1	130.0	130.0	130.0	130.0	130.0	130.0	129.0	107.1	130.0	130.0	107.1	130.0	107.1	107.1
54		95.2	130.0	119.0	130.0	130.0	130.0	130.0	114.7	95.2	130.0	130.0	95.2	130.0	95.2	95.2
60		85.7	130.0	107.1	130.0	130.0	130.0	130.0	103.2	85.7	130.0	130.0	85.7	130.0	85.7	85.7
66		77.9	130.0	97.4	130.0	130.0	130.0	120.8	93.8	77.9	120.8	120.8	77.9	130.0	77.9	77.9
72		71.4	129.0	89.3	129.0	129.0	129.0	110.7	86.0	71.4	110.7	110.7	71.4	129.0	71.4	71.4
36	132	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
42		116.9	130.0	130.0	130.0	130.0	130.0	130.0	130.0	116.9	130.0	130.0	116.9	130.0	116.9	116.9
48		102.3	130.0	127.8	130.0	130.0	130.0	130.0	123.1	102.3	130.0	130.0	102.3	130.0	102.3	102.3
54		90.9	130.0	113.6	130.0	130.0	130.0	130.0	109.5	90.9	130.0	130.0	90.9	130.0	90.9	90.9
60		81.8	130.0	102.3	130.0	130.0	130.0	126.8	98.5	81.8	126.8	126.8	81.8	130.0	81.8	81.8
66		74.4	130.0	93.0	130.0	130.0	130.0	115.3	89.6	74.4	115.3	115.3	74.4	130.0	74.4	74.4
72		68.2	123.2	85.2	123.1	123.1	123.2	105.7	82.1	68.2	105.7	105.7	68.2	123.2	68.2	68.2
36	138	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0
42		111.8	130.0	130.0	130.0	130.0	130.0	130.0	130.0	111.8	130.0	130.0	111.8	130.0	111.8	111.8
48		97.8	130.0	122.3	130.0	130.0	130.0	130.0	117.8	97.8	130.0	130.0	97.8	130.0	97.8	97.8
54		87.0	130.0	108.7	130.0	130.0	130.0	130.0	104.7	87.0	130.0	130.0	87.0	130.0	87.0	87.0
60		78.3	130.0	97.8	130.0	130.0	130.0	121.3	94.2	78.3	121.3	121.3	78.3	130.0	78.3	78.3
66		71.1	128.5	88.9	128.5	128.5	128.5	110.3	85.7	71.1	110.3	110.3	71.1	128.5	71.1	71.1
72		65.2	117.8	81.5	117.8	117.8	117.8	101.1	78.5	65.2	101.1	101.1	65.2	117.8	65.2	65.2
36	144	125.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	125.0	130.0	130.0	125.0	130.0	125.0	125.0
42		107.1	130.0	130.0	130.0	130.0	130.0	130.0	129.0	107.1	130.0	130.0	107.1	130.0	107.1	107.1
48		93.8	130.0	117.2	130.0	130.0	130.0	130.0	112.9	93.8	130.0	130.0	93.8	130.0	93.8	93.8
54		83.3	130.0	104.2	130.0	130.0	130.0	129.2	100.3	83.3	129.2	129.2	83.3	130.0	83.3	83.3
60		75.0	130.0	93.8	130.0	130.0	130.0	116.3	90.3	75.0	116.3	116.3	75.0	130.0	75.0	75.0
66		68.2	123.2	85.2	123.1	123.1	123.2	105.7	82.1	68.2	105.7	105.7	68.2	123.2	68.2	68.2
72		62.5	112.9	78.1	112.8	112.9	112.9	96.9	75.3	62.5	96.9	96.9	62.5	112.9	62.5	62.5
36	150	120.0	130.0	130.0	130.0	130.0	130.0	130.0	130.0	120.0	130.0	130.0	120.0	130.0	120.0	120.0
42		102.9	130.0	128.6	130.0	130.0	130.0	130.0	123.8	102.9	130.0	130.0	102.9	130.0	102.9	102.9
48		90.0	130.0	112.5	130.0	130.0	130.0	130.0	108.4	90.0	130.0	130.0	90.0	130.0	90.0	90.0
54		80.0	130.0	100.0	130.0	130.0	130.0	124.0	96.3	80.0	124.0	124.0	80.0	130.0	80.0	80.0
60		72.0	130.0	90.0	130.0	130.0	130.0	111.6	86.7	72.0	111.6	111.6	72.0	130.0	72.0	72.0
66		65.5	118.2	81.8	118.2	118.2	118.2	101.5	78.8	65.5	101.5	101.5	65.5	118.2	65.5	65.5
72		60.0	108.4	75.0	108.3	108.3	108.4	93.0	72.2	60.0	93.0	93.0	60.0	108.4	60.0	60.0
36	156	115.4	130.0	130.0	130.0	130.0	130.0	130.0	115.4	130.0	130.0	115.4	130.0	115.4	115.4	115.4
42		98.9	130.0	123.6	130.0	130.0	130.0	130.0	119.1	98.9	130.0	130.0	98.9	130.0	98.9	98.9
48		86.5	130.0	108.2	130.0	130.0	130.0	130.0	104.2	86.5	130.0	130.0	86.5	130.0	86.5	86.5
54		76.9	130.0	96.2	130.0	130.0	130.0	119.2	92.6	76.9	119.2	119.2	76.9	130.0	76.9	76.9
60		69.2	125.0	86.5	125.0	125.0	125.0	107.3	83.4	69.2	107.3	107.3	69.2	125.0	69.2	69.2
66		62.9	113.7	78.7	113.6	113.7	113.7	97.6	75.8	62.9	97.6	97.6	62.9	113.7	62.9	62.9
72		57.7	104.2	72.1	104.2	104.2	104.2	89.4	69.5	57.7	89.4	89.4	57.7	104.2	57.7	57.7
36	162	111.1	130.0	130.0	130.0	130.0	130.0	130.0	130.0	111.1	130.0	130.0	111.1	130.0	111.1	111.1
42		95.2	130.0	119.0	130.0	130.0	130.0	130.0	114.7	95.2	130.0	130.0	95.2	130.0	95.2	95.2
48		83.3	130.0	104.2	130.0	130.0	130.0	129.2	100.3	83.3	129.2	129.2	83.3	130.0	83.3	83.3
54		74.1	130.0	92.6	130.0	130.0	130.0	114.8	89.2	74.1	114.8	114.8	74.1	130.0	74.1	74.1
60		66.7	120.4	83.3	120.4	120.4	120.4	103.3	80.3	66.7	103.3	103.3	66.7	120.4	66.7	66.7
66		60.6	109.5	75.8	109.4	109.4	109.5	93.9	73.0	60.6	93.9	93.9	60.6	109.5	60.6	60.6
72		55.6	100.3	69.4	100.3	100.3	100.3	86.1	66.9	55.6	86.1	86.1	55.6	100.3	55.6	55.6

SINGLE SPAN & MULTI SPAN T & F ANCHOR CAPACITIES (CONT)

MAX. ANCHOR CAPACITY FOR SINGLE SPAN - DESIGN PRESSURES (+/- PSF)																
MAX. AVG. WIDTH 'W' (in.)	MAX. SPAN 'H' (in.)	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
36	168	107.1	130	130	130	130	130	130	129	107.1	130	130	107.1	130	107.1	107.1
42		91.8	130	114.8	130	130	130	130	110.6	91.8	130	130	91.8	130	91.8	91.8
48		80.4	130	100.4	130	130	130	130	124.6	96.8	80.4	124.6	124.6	80.4	130	80.4
54		71.4	129	89.3	129	129	129	110.7	86	71.4	110.7	110.7	71.4	129	71.4	71.4
60		64.3	116.1	80.4	116.1	116.1	116.1	99.6	77.4	64.3	99.6	99.6	64.3	116.1	64.3	64.3
66		58.4	105.6	73.1	105.5	105.5	105.6	90.6	70.4	58.4	90.6	90.6	58.4	105.6	58.4	58.4
72	174	53.6	96.8	67	96.7	96.7	96.8	83	64.5	53.6	83	83	53.6	96.8	53.6	53.6
36		103.4	130	129.3	130	130	130	130	124.6	103.4	130	130	103.4	130	103.4	103.4
42		88.7	130	110.8	130	130	130	130	106.8	88.7	130	130	88.7	130	88.7	88.7
48		77.6	130	97	130	130	130	120.3	93.4	77.6	120.3	120.3	77.6	130	77.6	77.6
54		69	124.6	86.2	124.5	124.5	124.6	106.9	83	69	106.9	106.9	69	124.6	69	69
60		62.1	112.1	77.6	112.1	112.1	112.1	96.2	74.7	62.1	96.2	96.2	62.1	112.1	62.1	62.1
66	180	56.4	101.9	70.5	101.9	101.9	101.9	87.5	67.9	56.4	87.5	87.5	56.4	101.9	56.4	56.4
72		51.7	93.4	64.7	93.4	93.4	93.4	80.2	62.3	51.7	80.2	80.2	51.7	93.4	51.7	51.7
36		100	130	125	130	130	130	130	120.4	100	130	130	100	130	100	100
42		85.7	130	107.1	130	130	130	130	103.2	85.7	130	130	85.7	130	85.7	85.7
48		75	130	93.8	130	130	130	116.3	90.3	75	116.3	116.3	75	130	75	75
54		66.7	120.4	83.3	120.4	120.4	120.4	103.3	80.3	66.7	103.3	103.3	66.7	120.4	66.7	66.7
60	186	60	108.4	75	108.3	108.3	108.4	93	72.2	60	93	93	60	108.4	60	60
66		54.5	98.5	68.2	98.5	98.5	98.5	84.5	65.7	54.5	84.5	84.5	54.5	98.5	54.5	54.5
72		50	90.3	62.5	90.3	90.3	90.3	77.5	60.2	50	77.5	77.5	50	90.3	50	50
36		96.8	130	121	130	130	130	130	116.5	96.8	130	130	96.8	130	96.8	96.8
42		82.9	130	103.7	130	130	130	128.6	99.9	82.9	128.6	128.6	82.9	130	82.9	82.9
48		72.6	130	90.7	130	130	130	112.5	87.4	72.6	112.5	112.5	72.6	130	72.6	72.6
54	192	64.5	116.5	80.6	116.5	116.5	116.5	100	77.7	64.5	100	100	64.5	116.5	64.5	64.5
60		58.1	104.9	72.6	104.8	104.9	104.9	90	69.9	58.1	90	90	58.1	104.9	58.1	58.1
66		52.8	95.3	66	95.3	95.3	95.3	81.8	63.6	52.8	81.8	81.8	52.8	95.3	52.8	52.8
72		48.4	87.4	60.5	87.4	87.4	87.4	75	58.3	48.4	75	75	48.4	87.4	48.4	48.4
36		93.8	130	117.2	130	130	130	130	112.9	93.8	130	130	93.8	130	93.8	93.8
42		80.4	130	100.4	130	130	130	124.6	96.8	80.4	124.6	124.6	80.4	130	80.4	80.4
48	198	70.3	127	87.9	127	127	127	109	84.7	70.3	109	109	70.3	127	70.3	70.3
54		62.5	112.9	78.1	112.8	112.9	112.9	96.9	75.3	62.5	96.9	96.9	62.5	112.9	62.5	62.5
60		56.3	101.6	70.3	101.6	101.6	101.6	87.2	67.7	56.3	87.2	87.2	56.3	101.6	56.3	56.3
66		51.1	92.4	63.9	92.3	92.3	92.4	79.3	61.6	51.1	79.3	79.3	51.1	92.4	51.1	51.1
72		46.9	84.7	58.6	84.6	84.6	84.7	72.7	56.4	46.9	72.7	72.7	46.9	84.7	46.9	46.9
36		90.9	130	113.6	130	130	130	130	109.5	90.9	130	130	90.9	130	90.9	90.9
42	204	77.9	130	97.4	130	130	130	120.8	93.8	77.9	120.8	120.8	77.9	130	77.9	77.9
48		68.2	123.2	85.2	123.1	123.1	123.2	105.7	82.1	68.2	105.7	105.7	68.2	123.2	68.2	68.2
54		60.6	109.5	75.8	109.4	109.4	109.5	93.9	73	60.6	93.9	93.9	60.6	109.5	60.6	60.6
60		54.5	98.5	68.2	98.5	98.5	98.5	84.5	65.7	54.5	84.5	84.5	54.5	98.5	54.5	54.5
66		49.6	89.6	62	89.5	89.5	89.6	76.9	59.7	49.6	76.9	76.9	49.6	89.6	49.6	49.6
72		45.5	82.1	56.8	82.1	82.1	82.1	70.5	54.7	45.5	70.5	70.5	45.5	82.1	45.5	45.5
36	210	88.2	130	110.3	130	130	130	130	106.2	88.2	130	130	88.2	130	88.2	88.2
42		75.6	130	94.5	130	130	130	117.2	91.1	75.6	117.2	117.2	75.6	130	75.6	75.6
48		66.2	119.5	82.7	119.5	119.5	119.5	102.6	79.7	66.2	102.6	102.6	66.2	119.5	66.2	66.2
54		58.8	106.2	73.5	106.2	106.2	106.2	91.2	70.8	58.8	91.2	91.2	58.8	106.2	58.8	58.8
60		52.9	95.6	66.2	95.6	95.6	95.6	82.1	63.7	52.9	82.1	82.1	52.9	95.6	52.9	52.9
66		48.1	86.9	60.2	86.9	86.9	86.9	74.6	57.9	48.1	74.6	74.6	48.1	86.9	48.1	48.1
72	210	44.1	79.7	55.1	79.7	79.7	79.7	68.4	53.1	44.1	68.4	68.4	44.1	79.7	44.1	44.1
36		85.7	130	107.1	130	130	130	130	103.2	85.7	130	130	85.7	130	85.7	85.7
42		73.5	130	91.8	130	130	130	113.9	88.5	73.5	113.9	113.9	73.5	130	73.5	73.5
48		64.3	116.1	80.4	116.1	116.1	116.1	99.6	77.4	64.3	99.6	99.6	64.3	116.1	64.3	64.3
54		57.1	103.2	71.4	103.2	103.2	103.2	88.6	68.8	57.1	88.6	88.6	57.1	103.2	57.1	57.1
60		51.4	92.9	64.3	92.9	92.9	92.9	79.7	61.9	51.4	79.7	79.7	51.4	92.9	51.4	51.4
66	210	46.8	84.4	58.4	84.4	84.4	84.4	72.5	56.3	46.8	72.5	72.5	46.8	84.4	46.8	46.8
72		42.9	77.4	53.6	77.4	77.4	77.4	66.4	51.6	42.9	66.4	66.4	42.9	77.4	42.9	42.9

NOTE:

1. REFER TO SECTION 7.0 THRU 7.6 FOR DETAILS OF ANCHOR REQUIREMENTS. AND DETERMINING MAX. SPAN 'L' AND TRIBUTARY WIDTHS 'W'
2. SEE SECTION 2, TWIN SPAN ELEVATION FOR LOCATION OF F-ANCHOR WHEN USED AT VERTICAL MULLION BETWEEN DOOR AND D.L.O.

MAX. ANCHOR CAPACITY FOR SINGLE SPAN - DESIGN PRESSURES (+/- PSF)																
MAX. AVG. WIDTH 'W' (in.)	MAX. SPAN 'H' (in.)	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
36	216	83.3	130	104.2	130	130	130	129.2	100.3	83.3	129.2	129.2	83.3	130	83.3	83.3
42		71.4	129	89.3	129	129	129	110.7	86	71.4	110.7	110.7	71.4	129	71.4	71.4
48		62.5	112.9	78.1	112.8	112.9	112.9	96.9	75.3	62.5	96.9	96.9	62.5	112.9	62.5	62.5
54		55.6	100.3	69.4	100.3	100.3	100.3	86.1	66.9	55.6	86.1	86.1	55.6	100.3	55.6	55.6
60		50	90.3	62.5	90.3	90.3	90.3	77.5	60.2	50	77.5	77.5	50	90.3	50	50
66		45.5	82.1	56.8	82.1	82.1	82.1	70.5	54.7	45.5	70.5	70.5	45.5	82.1	45.5	45.5
72	222	41.7	75.3	52.1	75.2	75.2	75.3	64.6	50.2	41.7	64.6	64.6	41.7	75.3	41.7	41.7
36		81.1	130	101.4	130	130	130	125.7	97.6	81.1	125.7	125.7	81.1	130	81.1	81.1
42		69.5	125.5	86.9	125.5	125.5	125.5	107.7	83.7	69.5	107.7	107.7	69.5	125.5	69.5	69.5
48		60.8	109.8	76	109.8	109.8	109.8	94.3	73.2	60.8	94.3	94.3	60.8	109.8	60.8	60.8
54		54.1	97.6	67.6	97.6	97.6	97.6	83.8	65.1	54.1	83.8	83.8	54.1	97.6	54.1	54.1
60		48.6	87.9	60.8	87.8	87.8	87.9	75.4	58.6	48.6	75.4	75.4	48.6	87.9	48.6	48.6
66	228	44.2	79.9	55.3	79.9	79.9	79.9	68.6	53.2	44.2	68.6	68.6	44.2	79.9	44.2	44.2
72		40.5	73.2	50.7	73.2	73.2	73.2	62.8	48.8	40.5	62.8	62.8	40.5	73.2	40.5	40.5
36		78.9	130	98.7	130	130	130	122.4	95.1	78.9	122.4	122.4	78.9	130	78.9	78.9
42		67.7	122.2	84.6	122.2	122.2	122.2	104.9	81.5	67.7	104.9	104.9	67.7	122.2	67.7	67.7
48		59.2	106.9	74	106.9	106.9	106.9	91.8	71.3	59.2	91.8	91.8	59.2	106.9	59.2	59.2
54		52.6	95.1	65.8	95	95	95.1	81.6	63.4	52.6	81.6	81.6	52.6	95.1	52.6	52.6
60	234	47.4	85.6	59.2	85.5	85.5	85.6	73.4	57	47.4	73.4	73.4	47.4	85.6	47.4	47.4
66		43.1	77.8	53.8	77.8	77.8	77.8	66.7	51.8	43.1	66.7	66.7	43.1	77.8	43.1	43.1
72		39.5	71.3	49.3	71.3	71.3	71.3	61.2	47.5	39.5	61.2	61.2	39.5	71.3	39.5	39.5
36		76.9	130	96.2	130	130	130	119.2	92.6	76.9	119.2	119.2	76.9	130	76.9	76.9
42		65.9	119.1	82.4	119	119.1	119.1	102.2	79.4	65.9	102.2	102.2	65.9	119.1	65.9	65.9
48		57.7	104.2	72.1	104.2	104.2	104.2	89.4	69.5	57.7	89.4	89.4	57.7	104.2	57.7	57.7
54	240	51.3	92.6	64.1	92.6	92.6	92.6	79.5	61.7	51.3	79.5	79.5	51.3	92.6	51.3	51.3
60		46.2	83.4	57.7	83.3	83.3	83.4	71.5	55.6	46.2	71.5	71.5	46.2	83.4	46.2	46.2
66		42	75.8	52.4	75.8	75.8	75.8	65	50.5	42	65	65	42	75.8	42	42
72		38.5	69.5	48.1	69.4	69.5	69.5	59.6	46.3	38.5	59.6	59.6	38.5	69.5	38.5	38.5
36		75	130	93.8	130	130	130	116.3	90.3	75	116.3	116.3	75	130	75	75
42		64.3	116.1	80.4	116.1	116.1	116.1	99.6	77.4	64.3	99.6	99.6	64.3	116.1	64.3	64.3
48	246	56.3	101.6	70.3	101.6	101.6	101.6	87.2	67.7	56.3	87.2	87.2	56.3	101.6	56.3	56.3
54		50	90.3	62.5	90.3	90.3	90.3	77.5	60.2	50	77.5	77.5	50	90.3	50	50
60		45	81.3	56.3	81.3	81.3	81.3	69.8	54.2	45	69.8	69.8	45	81.3	45	45
66		40.9	73.9	51.1	73.9	73.9	73.9	63.4	49.3	40.9	63.4	63.4	40.9	73.9	40.9	40.9
72		37.5	67.7	46.9	67.7	67.7	67.7	58.1	45.2	37.5	58.1	58.1	37.5	67.7	37.5	37.5
36		73.2	130	91.5	130	130	130	113.4	88.1	73.2	113.4	113.4	73.2	130	73.2	73.2
42	246	62.7	113.3	78.4	113.2	113.3	113.3	97.2	75.5	62.7	97.2	97.2	62.7	113.3	62.7	62.7
48		54.9	99.1	68.6	99.1	99.1	99.1	85.1	66.1	54.9	85.1	85.1	54.9	99.1	54.9	54.9
54		48.8	88.1	61	88.1	88.1	88.1	75.6	58.7	48.8	75.6	75.6	48.8	88.1	48.8	48.8
60		43.9	79.3	54.9	79.3	79.3	79.3	68	52.9	43.9	68	68	43.9	79.3	43.9	43.9
66		39.9	72.1	49.9	72.1	72.1	72.1	61.9	48.1	39.9	61.9	61.9	39.9	72.1	39.9	39.9
72		36.6	66.1	45.7	66.1	66.1	66.1	56.7	44	36.6	56.7	56.7	36.6	66.1	36.6	36.6

7/24/2026 10:25 AM

SINGLE SPAN & MULTI SPAN
F ANCHOR CAPACITIES WHEN USED AT DOOR
JAMB TO SIDELITE LOCATIONS

MAX. ANCHOR CAPACITY - DESIGN PRESSURES (+/- PSF)																
MAX. AVG. WIDTH 'W' (in.)	MAX. SPAN 'H' (in.)	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
36	78	115.4	130	130	130	130	130	130	130	115.4	130	115.4	115.4	130	115.4	115.4
42		98.9	130	123.6	130	130	130	130	119.1	98.9	130	98.9	98.9	130	98.9	98.9
48		86.5	130	108.2	130	130	130	130	104.2	86.5	130	86.5	86.5	130	86.5	86.5
54		76.9	130	96.2	130	130	130	119.2	92.6	76.9	119.2	76.9	76.9	130	76.9	76.9
60		69.2	125	86.5	125	125	125	107.3	83.4	69.2	107.3	69.2	69.2	125	69.2	69.2
66		62.9	113.7	78.7	113.6	113.7	113.7	97.6	75.8	62.9	97.6	62.9	113.7	62.9	62.9	62.9
72		57.7	104.2	72.1	104.2	104.2	104.2	89.4	69.5	57.7	89.4	57.7	104.2	57.7	57.7	57.7
36	84	107.1	130	130	130	130	130	130	129	107.1	130	107.1	107.1	130	107.1	107.1
42		91.8	130	114.8	130	130	130	130	110.6	91.8	130	91.8	91.8	130	91.8	91.8
48		80.4	130	100.4	130	130	130	124.6	96.8	80.4	124.6	80.4	80.4	130	80.4	80.4
54		71.4	129	89.3	129	129	129	110.7	86	71.4	110.7	71.4	71.4	129	71.4	71.4
60		64.3	116.1	80.4	116.1	116.1	116.1	99.6	77.4	64.3	99.6	64.3	64.3	116.1	64.3	64.3
66		58.4	105.6	73.1	105.5	105.5	105.6	90.6	70.4	58.4	90.6	58.4	58.4	105.6	58.4	58.4
72		53.6	96.8	67	96.7	96.7	96.8	83	64.5	53.6	83	53.6	53.6	96.8	53.6	53.6
36	90	100	130	125	130	130	130	130	120.4	100	130	100	100	130	100	100
42		85.7	130	107.1	130	130	130	130	103.2	85.7	130	85.7	85.7	130	85.7	85.7
48		75	130	93.8	130	130	130	116.3	90.3	75	116.3	75	75	130	75	75
54		66.7	120.4	83.3	120.4	120.4	120.4	103.3	80.3	66.7	103.3	66.7	66.7	120.4	66.7	66.7
60		60	108.4	75	108.3	108.3	108.4	93	72.2	60	93	60	60	108.4	60	60
66		54.5	98.5	68.2	98.5	98.5	98.5	84.5	65.7	54.5	84.5	54.5	54.5	98.5	54.5	54.5
72		50	90.3	62.5	90.3	90.3	90.3	77.5	60.2	50	77.5	50	50	90.3	50	50
36	96	93.8	130	117.2	130	130	130	130	112.9	93.8	130	93.8	93.8	130	93.8	93.8
42		80.4	130	100.4	130	130	130	124.6	96.8	80.4	124.6	80.4	80.4	130	80.4	80.4
48		70.3	127	87.9	127	127	127	109	84.7	70.3	109	70.3	70.3	127	70.3	70.3
54		62.5	112.9	78.1	112.8	112.9	112.9	96.9	75.3	62.5	96.9	62.5	62.5	112.9	62.5	62.5
60		56.3	101.6	70.3	101.6	101.6	101.6	87.2	67.7	56.3	87.2	56.3	56.3	101.6	56.3	56.3
66		51.1	92.4	63.9	92.3	92.3	92.4	79.3	61.6	51.1	79.3	51.1	51.1	92.4	51.1	51.1
72		46.9	84.7	58.6	84.6	84.6	84.7	72.7	56.4	46.9	72.7	46.9	46.9	84.7	46.9	46.9
36	102	88.2	130	110.3	130	130	130	130	106.2	88.2	130	88.2	88.2	130	88.2	88.2
42		75.6	130	94.5	130	130	130	117.2	91.1	75.6	117.2	75.6	75.6	130	75.6	75.6
48		66.2	119.5	82.7	119.5	119.5	119.5	102.6	79.7	66.2	102.6	66.2	66.2	119.5	66.2	66.2
54		58.8	106.2	73.5	106.2	106.2	106.2	91.2	70.8	58.8	91.2	58.8	58.8	106.2	58.8	58.8
60		52.9	95.6	66.2	95.6	95.6	95.6	82.1	63.7	52.9	82.1	52.9	52.9	95.6	52.9	52.9
66		48.1	86.9	60.2	86.9	86.9	86.9	74.6	57.9	48.1	74.6	48.1	48.1	86.9	48.1	48.1
72		44.1	79.7	55.1	79.7	79.7	79.7	68.4	53.1	44.1	68.4	44.1	44.1	79.7	44.1	44.1
36	108	83.3	130	104.2	130	130	130	129.2	100.3	83.3	129.2	83.3	83.3	130	83.3	83.3
42		71.4	129	89.3	129	129	129	110.7	86	71.4	110.7	71.4	71.4	129	71.4	71.4
48		62.5	112.9	78.1	112.8	112.9	112.9	96.9	75.3	62.5	96.9	62.5	62.5	112.9	62.5	62.5
54		55.6	100.3	69.4	100.3	100.3	100.3	86.1	66.9	55.6	86.1	55.6	55.6	100.3	55.6	55.6
60		50	90.3	62.5	90.3	90.3	90.3	77.5	60.2	50	77.5	50	50	90.3	50	50
66		45.5	82.1	56.8	82.1	82.1	82.1	70.5	54.7	45.5	70.5	45.5	45.5	82.1	45.5	45.5
72		41.7	75.3	52.1	75.2	75.3	75.3	64.6	50.2	41.7	64.6	41.7	41.7	75.3	41.7	41.7
36	114	78.9	130	98.7	130	130	130	122.4	95.1	78.9	122.4	78.9	78.9	130	78.9	78.9
42		67.7	122.2	84.6	122.2	122.2	122.2	104.9	81.5	67.7	104.9	67.7	67.7	122.2	67.7	67.7
48		59.2	106.9	74	106.9	106.9	106.9	91.8	71.3	59.2	91.8	59.2	59.2	106.9	59.2	59.2
54		52.6	95.1	65.8	95	95	95.1	81.6	63.4	52.6	81.6	52.6	52.6	95.1	52.6	52.6
60		47.4	85.6	59.2	85.5	85.5	85.6	73.4	57	47.4	73.4	47.4	47.4	85.6	47.4	47.4
66		43.1	77.8	53.8	77.8	77.8	77.8	66.7	51.8	43.1	66.7	43.1	43.1	77.8	43.1	43.1
72		39.5	71.3	49.3	71.3	71.3	71.3	61.2	47.5	39.5	61.2	39.5	39.5	71.3	39.5	39.5

NOTE:

- REFER TO SECTION 7.0 THRU 7.6 FOR DETAILS OF ANCHOR REQUIREMENTS. AND DETERMINING MAX. SPAN 'L' AND TRIBUTARY WIDTHS 'W'
- SEE SECTION 2, TWIN SPAN ELEVATION FOR LOCATION OF F-ANCHOR WHEN USED AT VERTICAL MULLION BETWEEN DOOR AND D.I.O.

MAX. ANCHOR CAPACITY - DESIGN PRESSURES (+/- PSF)																
MAX. AVG. WIDTH 'W' (in.)	MAX. SPAN 'H' (in.)	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
36	120	75	130	93.8	130	130	130	116.3	90.3	75	116.3	75	75	130	75	75
42		64.3	116.1	80.4	116.1	116.1	116.1	99.6	77.4	64.3	99.6	64.3	64.3	116.1	64.3	64.3
48		56.3	101.6	70.3	101.6	101.6	101.6	87.2	67.7	56.3	87.2	56.3	56.3	101.6	56.3	56.3
54		50	90.3	62.5	90.3	90.3	90.3	77.5	60.2	50	77.5	50	50	90.3	50	50
60		45	81.3	56.3	81.3	81.3	81.3	69.8	54.2	45	69.8	45	45	81.3	45	45
66		40.9	73.9	51.1	73.9	73.9	73.9	63.4	49.3	40.9	63.4	40.9	40.9	73.9	40.9	40.9
72		37.5	67.7	46.9	67.7	67.7	67.7	58.1	45.2	37.5	58.1	37.5	37.5	67.7	37.5	37.5
36	126	71.4	129	89.3	129	129	129	110.7	86	71.4	110.7	71.4	71.4	129	71.4	71.4
42		61.2	110.6	76.5	110.5	110.6	110.6	94.9	73.7	61.2	94.9	61.2	61.2	110.6	61.2	61.2
48		53.6	96.8	67	96.7	96.7	96.8	83	64.5	53.6	83	53.6	53.6	96.8	53.6	53.6
54		47.6	86	59.5	86	86	86	73.8	57.3	47.6	73.8	47.6	47.6	86	47.6	47.6
60		42.9	77.4	53.6	77.4	77.4	77.4	66.4	51.6	42.9	66.4	42.9	42.9	77.4	42.9	42.9
66		39	70.4	48.7	70.3	70.4	70.4	60.4	46.9	39	60.4	39	39	70.4	39	39
72		35.7	64.5	44.6	64.5	64.5	64.5	55.4	43	35.7	55.4	35.7	35.7	64.5	35.7	35.7
36	132	68.2	123.2	85.2	123.1	123.1	123.2	105.7	82.1	68.2	105.7	68.2	68.2	123.2	68.2	68.2
42		58.4	105.6	73.1	105.5	105.5	105.6	90.6	70.4	58.4	90.6	58.4	58.4	105.6	58.4	58.4
48		51.1	92.4	63.9	92.3	92.3	92.4	79.3	61.6	51.1	79.3	51.1	51.1	92.4	51.1	51.1
54		45.5	82.1	56.8	82.1	82.1	82.1	70.5	54.7	45.5	70.5	45.5	45.5	82.1	45.5	45.5
60		40.9	73.9	51.1	73.9	73.9	73.9	63.4	49.3	40.9	63.4	40.9	40.9	73.9	40.9	40.9
66		37.2	67.2	46.5	67.1	67.2	67.2	57.6	44.8	37.2	57.6	37.2	37.2	67.2	37.2	37.2
72		34.1	61.6	42.6	61.6	61.6	61.6	52.8	41	34.1	52.8	34.1	34.1	61.6	34.1	34.1
36	138	65.2	117.8	81.5	117.8	117.8	117.8	101.1	78.5	65.2	101.1	65.2	65.2	117.8	65.2	65.2
42		55.9	101	69.9	100.9	100.9	101	86.6	67.3	55.9	86.6	55.9	55.9	101	55.9	55.9
48		48.9	88.3	61.1	88.3	88.3	88.3	75.8	58.9	48.9	75.8	48.9	48.9	88.3	48.9	48.9
54		43.5	78.5	54.3	78.5	78.5	78.5	67.4	52.3	43.5	67.4	43.5	43.5	78.5	43.5	43.5
60		39.1	70.7	48.9	70.7	70.7	70.7	60.7	47.1	39.1	60.7	39.1	39.1	70.7	39.1	39.1
66		35.6	64.3	44.5	64.2	64.2	64.3	55.1	42.8	35.6	55.1	35.6	35.6	64.3	35.6	35.6
72		32.6	58.9	40.8	58.9	58.9	58.9	50.5	39.3	32.6	50.5	32.6	32.6	58.9	32.6	32.6
36	144	62.5	112.9	78.1	112.8	112.9	112.9	96.9	75.3	62.5	96.9	62.5	62.5	112.9	62.5	62.5
42		53.6	96.8	67	96.7	96.7	96.8	83	64.5	53.6	83	53.6	53.6	96.8	53.6	53.6
48		46.9	84.7	58.6	84.6	84.6	84.7	72.7	56.4	46.9	72.7	46.9	46.9	84.7	46.9	46.9
54		41.7	75.3	52.1	75.2	75.2	75.3	64.6	50.2	41.7	64.6	41.7	41.7	75.3	41.7	41.7
60		37.5	67.7	46.9	67.7	67.7	67.7	58.1	45.2	37.5	58.1	37.5	37.5	67.7	37.5	37.5
66		34.1	61.6	42.6	61.6	61.6	61.6	52.8	41	34.1	52.8	34.1	34.1	61.6	34.1	34.1
72		31.3	56.4	39.1	56.4	56.4	56.4	48.4	37.6	31.3	48.4	31.3	31.3	56.4	31.3	31.3
36	150	60	108.4	75	108.3	108.3	108.4	93	72.2	60	93	60	60	108.4	60	60
42		51.4	92.9	64.3	92.9	92.9	92.9	79.7	61.9	51.4	79.7	51.4	51.4	92.9	51.4	51.4
48		45	81.3	56.3	81.3	81.3	81.3	69.8	54.2	45	69.8	45	45	81.3	45	45
54		40	72.2	50	72.2	72.2	72.2	62	48.2	40	62	40	40	72.2	40	40
60		36	65	45	65	65	65	55.8	43.3	36	55.8	36	36	65	36	36
66		32.7	59.1	40.9	59.1	59.1	59.1	50.7	39.4	32.7	50.7	32.7	32.7	59.1	32.7	32.7
72		30	54.2	37.5	54.2	54.2	54.2	46.5	36.1	30	46.5	30	30	54.2	30	30
36	156	57.7	104.2	72.1	104.2	104.2	104.2	89.4	69.5	57.7	89.4	57.7	57.7	104.2	57.7	57.7
42		49.5	89.3	61.8	89.3	89.3	89.3	76.6	59.5	49.5	76.6	49.5	49.5	89.3	49.5	49.5
48		43.3	78.2	54.1	78.1	78.1	78.2	67.1	52.1	43.3	67.1	43.3	43.3	78.2	43.3	43.3
54		38.5	69.5	48.1	69.4	69.5	69.5	59.6	46.3	38.5	59.6	38.5	38.5	69.5	38.5	38.5
60		34.6	62.5	43.3	62.5	62.5	62.5	53.7	41.7	34.6	53.7	34.6	34.6	62.5	34.6	34.6
66		31.5	56.8	39.3	56.8	56.8	56.8	48.8	37.9	31.5	48.8	31.5	31.5	56.8	31.5	31.5
72		28.8	52.1	36.1	52.1	52.1	52.1	44.7	34.7	28.8	44.7	28.8	28.8	52.1	28.8	28.8
36	162	55.6	100.3	69.4	100.3	100.3	100.3	86.1	66.9	55.6	86.1	55.6	55.6	100.3	55.6	55.6
42		47.6	86	59.5	86	86	86	73.8	57.3	47.6	73.8	47.6	47.6	86	47.6	47.6
48		41.7	75.3	52.1	75.2	75.2	75.3	64.6	50.2	41.7	64.6	41.7	41.7	75.3	41.7	41.7
54		37	66.9	46.3	66.9	66.9	66.9	57.4	44.6	37	57.4	37	37	66.9	37	37
60		33.3	60.2	41.7	60.2	60.2	60.2	51.7	40.1	33.3	51.7	33.3	33.3	60.2	33.3	33.3
66		30.3	54.7	37.9	54.7	54.7	54.7	47	36.5	30.3	47	30.3	30.3	54.7	30.3	30.3
72		27.8	50.2	34.7	50.2	50.2	50.2	43.1	33.4	27.8	43.1	27.8	27.8	50.2	27.8	27.8

7/24/2026 10:25 AM

c:\users\sebastianherrerros\desktop\ykk 2026 ca\fl13433\ykk 204 - fl13433 dwgs 7 - fl13433.dwg

SINGLE SPAN & MULTI SPAN
S ANCHOR CAPACITIES

MAX. ANCHOR CAPACITY FOR SINGLE SPAN - DESIGN PRESSURES (+/- PSF)						
MAX. AVG. WIDTH 'W' (in.)	MAX. SPAN 'H' (in.)	H	I	J	K	L
36	78	113.0	114.0	130.0	46.0	114.0
42		97.0	98.0	130.0	39.0	98.0
48		85.0	86.0	129.0	34.0	86.0
54		75.0	76.0	115.0	30.0	76.0
60		68.0	68.0	103.0	27.0	68.0
66		62.0	62.0	94.0	25.0	62.0
72	84	56.0	57.0	86.0	23.0	57.0
36		105.0	106.0	130.0	42.0	106.0
42		90.0	91.0	130.0	36.0	91.0
48		79.0	80.0	120.0	32.0	80.0
54		70.0	71.0	106.0	28.0	71.0
60		63.0	64.0	96.0	25.0	64.0
66	90	57.0	58.0	87.0	23.0	58.0
72		52.0	53.0	80.0	21.0	53.0
36		98.0	99.0	130.0	40.0	99.0
42		84.0	85.0	128.0	34.0	85.0
48		74.0	74.0	112.0	30.0	74.0
54		65.0	66.0	99.0	26.0	66.0
60	96	59.0	59.0	89.0	24.0	59.0
66		53.0	54.0	81.0	21.0	54.0
72		49.0	49.0	74.0	20.0	49.0
36		92.0	93.0	130.0	37.0	93.0
42		79.0	80.0	120.0	32.0	80.0
48		69.0	70.0	105.0	28.0	70.0
54	102	61.0	62.0	93.0	25.0	62.0
60		55.0	56.0	84.0	22.0	56.0
66		50.0	50.0	76.0	20.0	50.0
72		46.0	46.0	70.0	18.0	46.0
36		87.0	87.0	130.0	35.0	87.0
42		74.0	75.0	113.0	30.0	75.0
48	108	65.0	65.0	99.0	26.0	65.0
54		58.0	58.0	88.0	23.0	58.0
60		52.0	52.0	79.0	21.0	52.0
66		47.0	47.0	72.0	19.0	47.0
72		43.0	43.0	66.0	17.0	43.0
36		82.0	82.0	124.0	33.0	82.0
42	114	70.0	71.0	106.0	28.0	71.0
48		61.0	62.0	93.0	25.0	62.0
54		54.0	55.0	83.0	22.0	55.0
60		49.0	49.0	74.0	20.0	49.0
66		44.0	45.0	68.0	18.0	45.0
72		41.0	41.0	62.0	16.0	41.0
36		77.0	78.0	118.0	31.0	78.0
42		66.0	67.0	101.0	27.0	67.0
48		58.0	58.0	88.0	23.0	58.0
54		51.0	52.0	78.0	21.0	52.0
60		46.0	47.0	70.0	18.0	47.0
66		42.0	42.0	64.0	17.0	42.0
72		38.0	39.0	59.0	15.0	39.0

NOTE:

- REFER TO SECTION 7.0 THRU 7.6 FOR DETAILS OF ANCHOR REQUIREMENTS. AND DETERMINING MAX. SPAN 'L' AND TRIBUTARY WIDTHS 'W'
- SEE SECTION 2, TWIN SPAN ELEVATION FOR LOCATION OF F-ANCHOR WHEN USED AT VERTICAL MULLION BETWEEN DOOR AND D.L.O.

MAX. ANCHOR CAPACITY FOR SINGLE SPAN - DESIGN PRESSURES (+/- PSF)						
MAX. AVG. WIDTH 'W' (in.)	MAX. SPAN 'H' (in.)	H	I	J	K	L
36	120	74.0	74.0	112.0	30.0	74.0
42		63.0	64.0	96.0	25.0	64.0
48		55.0	56.0	84.0	22.0	56.0
54		49.0	49.0	74.0	20.0	49.0
60		44.0	44.0	67.0	18.0	44.0
66		40.0	40.0	61.0	16.0	40.0
72	126	37.0	37.0	56.0	15.0	37.0
36		70.0	71.0	106.0	28.0	71.0
42		60.0	60.0	91.0	24.0	60.0
48		52.0	53.0	80.0	21.0	53.0
54		46.0	47.0	71.0	19.0	47.0
60		42.0	42.0	64.0	17.0	42.0
66	132	38.0	38.0	58.0	15.0	38.0
72		35.0	35.0	53.0	14.0	35.0
36		67.0	67.0	102.0	27.0	67.0
42		57.0	58.0	87.0	23.0	58.0
48		50.0	50.0	76.0	20.0	50.0
54		44.0	45.0	68.0	18.0	45.0
60	138	40.0	40.0	61.0	16.0	40.0
66		36.0	37.0	55.0	14.0	37.0
72		33.0	33.0	51.0	13.0	33.0
36		64.0	64.0	97.0	26.0	64.0
42		55.0	55.0	83.0	22.0	55.0
48		48.0	48.0	73.0	19.0	48.0
54	144	42.0	43.0	65.0	17.0	43.0
60		38.0	38.0	58.0	15.0	38.0
66		35.0	35.0	53.0	14.0	35.0
72		32.0	32.0	48.0	13.0	32.0
36		61.0	62.0	93.0	25.0	62.0
42		52.0	53.0	80.0	21.0	53.0
48	150	46.0	46.0	70.0	18.0	46.0
54		41.0	41.0	62.0	16.0	41.0
60		37.0	37.0	56.0	15.0	37.0
66		33.0	33.0	51.0	13.0	33.0
72		30.0	31.0	46.0	12.0	31.0
36		59.0	59.0	89.0	24.0	59.0
42		50.0	51.0	76.0	20.0	51.0
48		44.0	44.0	67.0	18.0	44.0
54		39.0	39.0	59.0	16.0	39.0
60		35.0	35.0	53.0	14.0	35.0
66		32.0	32.0	48.0	13.0	32.0
72		29.0	29.0	44.0	12.0	29.0



YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE:
YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM

S - ANCHOR DETAILS

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744.4738
WEB: www.buildingdrops.com

BUILDING DROPS

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT

HERMES F. NORERO, P.E.
BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
FBPE CERT. OF AUTHORIZATION No. 29578

FL #:
FL13433

DATE:
7.17.17

DWG. BY:
AR

CHK. BY:
HFN

SCALE:
NTS


DWG. #:
YKK204

SECTION:
7.9


REV.
B

7/24/2026 10:26 AM


c:\users\sebastianh\desktop\ykk 2026 cc\113433\ykk 204 - fl13433 dwgs 8 - wind-dead load anchor.dtl's.dwg



17.0 HORIZONTAL SECTION
WIND/DEAD LOAD ANCHOR AT JAMB




EXTERIOR VIEW
WIND/DEAD LOAD ANCHOR AT JAMB




WL / DL ANCHOR CAPACITY		
MAX. SPAN 'L'	MULLION	MAX. DESIGN PRESSURE
150"	STD. DUTY	+/- 90 PSF
	HEAVY DUTY	+/- 130 PSF

- WIND / DEAD LOAD ANCHOR NOTES:**
- WIND/DEAD LOAD ANCHORS HAVE BEEN EVALUATED TO THE FOLLOWING:
 - WL = +/- 6,300 LBS (UNFACTORED) @ DOUBLE ANGLE SUPPORTS
 - WL = +/- 3,150 LBS (UNFACTORED) @ SINGLE ANGLE SUPPORTS
 - MAX. SPAN = 12'-6"
 - MAX. TRIB WIDTH = 74"
 - ALTERNATE WIND & DEAD LOAD ANCHORS MAY BE DESIGNED FOR ALTERNATE SITE CONDITIONS AND STEEL ANGLE DESIGN ON A JOB TO JOB BASIS FOR THE APPLICABLE WIND LOADS AS DETERMINED IN ACCORDANCE WITH CH. 16 OF THE FLORIDA BLDG. CODE BY A FLORIDA REGISTERED PROFESSIONAL ENGINEER.


NOTE:
1) ALTERNATE WIND & DEAD LOAD ANCHORS MAY BE DESIGNED FOR ALTERNATE SITE CONDITIONS AND STEEL ANGLE DESIGN ON A JOB TO JOB BASIS FOR THE APPLICABLE WIND LOADS AS DETERMINED IN ACCORDANCE WITH CH. 16 OF THE FLORIDA BLDG. CODE BY A FLORIDA REGISTERED PROFESSIONAL ENGINEER.




EXTERIOR VIEW
WIND/DEAD LOAD ANCHOR AT VERTICAL MULLION




18.0 HORIZONTAL SECTION
WIND/DEAD LOAD ANCHOR AT VERTICAL MULLION



VERTICAL SECTION
WIND LOAD ANCHOR (DEAD LOAD ANCHOR SIMILAR) AT STEEL SUBSTRATE LOW / STANDARD PRESSURE CONNECTION



19.0 VERTICAL SECTION
MULLION SPLICE



VERTICAL SECTION
WIND LOAD ANCHOR (DEAD LOAD ANCHOR SIMILAR) AT STEEL SUBSTRATE HIGH PRESSURE CONNECTION



YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001


TITLE:
YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM
WIND LOAD / DEAD LOAD ANCHOR DETAILS

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:
FL13433

DATE: 7.17.17


DWG. BY: AR
CHK. BY: HFN

SCALE: NTS

DWG. #: YKK204

SECTION: 8.0
REV. B


7/24/2026 10:26 AM



20
8.1 **HORIZONTAL SECTION**
WIND/DEAD LOAD ANCHOR
AT JAMB


WIND / DEAD LOAD ANCHOR NOTES:

1. WIND/DEAD LOAD ANCHORS HAVE BEEN EVALUATED TO THE FOLLOWING:
 - WL = +/- 6,300 LBS (UNFACTORED) @ DOUBLE ANGLE SUPPORTS
 - WL = +/- 3,150 LBS (UNFACTORED) @ SINGLE ANGLE SUPPORTS
 - MAX. SPAN = 12'-6"
 - MAX. TRIB WIDTH = 74"
2. (2) 1/2" HH GR. 5 OR ASTM A325 THREADED BOLTS PER ANGLE
 - MIN. FULL ENGAGEMENT WITH NUT & WASHER OR
 - THREADED INTO TAPPED HOLE W/ MIN. 3 THREADS PENETRATION BEYOND STEEL STRUCTURE
 - MIN. 1 1/2" EDGE DISTANCE.
3. ALTERNATE WIND & DEAD LOAD ANCHORS MAY BE DESIGNED FOR ALTERNATE SITE CONDITIONS AND STEEL ANGLE DESIGN ON A JOB TO JOB BASIS FOR THE APPLICABLE WIND LOADS AS DETERMINED IN ACCORDANCE WITH CH. 16 OF THE FLORIDA BLDG. CODE BY A FLORIDA REGISTERED PROFESSIONAL ENGINEER.




21
8.1 **HORIZONTAL SECTION**
WIND/DEAD LOAD ANCHOR
AT VERTICAL MULLION

WL / DL ANCHOR CAPACITY		
MAX. SPAN 'L'	MULLION	MAX. DESIGN PRESSURE
150"	STD.DUTY	+/- 90 PSF
	HEAVY DUTY	+/- 130 PSF




VERTICAL SECTION
WIND LOAD ANCHOR
(DEAD LOAD ANCHOR SIMILAR)
AT STEEL SUBSTRATE
LOW / STANDARD PRESSURE CONNECTION




EXTERIOR VIEW
WIND/DEAD LOAD ANCHOR
AT JAMB

EXTERIOR VIEW
WIND/DEAD LOAD ANCHOR
AT VERTICAL MULLION



VERTICAL SECTION
WIND LOAD ANCHOR
(DEAD LOAD ANCHOR SIMILAR)
AT STEEL SUBSTRATE
HIGH PRESSURE CONNECTION



YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001


TITLE:
YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM
WIND LOAD / DEAD LOAD
ANCHOR DETAILS

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:

FL13433

DATE: **7.17.17**

DWG. BY:
AR

CHK. BY:
HFN

SCALE: **NTS**

DWG. #: **YKK204**

SECTION:


REV.

8.1

B

7/24/2026 10:26 AM


c:\users\sebastianherrerros\desktop\ykk 2026 ca\fl13433\ykk 204 - fl13433 dwgs 8 - wind-dead load anchor.dwg




22.2 HORIZONTAL SECTION
WIND/DEAD
LOAD ANCHOR
AT JAMB

WIND LOAD ANCHOR NOTES:


- WIND LOAD ANCHORS HAVE BEEN EVALUATED TO THE FOLLOWING:
 - WL = +/- 6,500 LBS (UNFACTORED) @ DOUBLE ANGLE SUPPORTS
 - WL = +/- 3,250 LBS (UNFACTORED) @ SINGLE ANGLE SUPPORTS
 - MAX. SPAN = 12'-6"
 - MAX. TRIB WIDTH = 74"
- (2) 1/2" HILTI KWIK BOLT TZ ANCHORS PER ANGLE
 - MIN. EMBEDMENT = 3 5/8"
 - MAX. C.C. SPACING = 4 1/2"
 - MIN. EDGE DISTANCE = 4 1/2"
 - MIN. 3000 PSI CONCRETE 'CRACKED' OR 'UNCRACKED'(2) 1/2" DEWALT SCREW-BOLT+ PER ANGLE
 - MIN. EMBEDMENT = 4 1/4"
 - MAX. C.C. SPACING = 4 1/2"
 - MIN. EDGE DISTANCE = 5"
 - MIN. 3000 PSI CONCRETE 'UNCRACKED'(2) 3/8" SIMPSON TITEN HD PER ANGLE
 - MIN. EMBEDMENT = 3 1/4"
 - MAX. C.C. SPACING = 4 1/2"
 - MIN. EDGE DISTANCE = 3 5/8"
 - MIN. 4000 PSI CONCRETE 'CRACKED' OR 'UNCRACKED'
- FOR SLABS LESS THAN 8" IN THICKNESS, DESIGN MAY BE PROVIDED ON JOB TO JOB BASIS FOR REVIEW & APPROVAL BY AHJ
- ALTERNATE WIND & DEAD LOAD ANCHORS MAY BE DESIGNED FOR ALTERNATE SITE CONDITIONS AND STEEL ANGLE DESIGN ON A JOB TO JOB BASIS FOR THE APPLICABLE WIND LOADS AS DETERMINED IN ACCORDANCE WITH CH. 16 OF THE FLORIDA BLDG. CODE BY A FLORIDA REGISTERED PROFESSIONAL ENGINEER.



EXTERIOR VIEW
WIND/DEAD LOAD ANCHOR
AT JAMB




EXTERIOR VIEW
WIND/DEAD LOAD ANCHOR
AT VERTICAL MULLION




23.8.2 HORIZONTAL SECTION
WIND/DEAD LOAD ANCHOR
AT VERTICAL MULLION

WL / DL ANCHOR CAPACITY		
MAX. SPAN 'L'	MULLION	MAX. DESIGN PRESSURE
150"	STD.DUTY	+/- 90 PSF
	HEAVY DUTY	+/- 130 PSF



VERTICAL SECTION
WIND LOAD ANCHOR (DEAD LOAD ANCHOR SIMILAR)
AT STEEL SUBSTRATE LOW / STAND. PRESSURE CONNECTION



VERTICAL SECTION
WIND/DEAD LOAD ANCHOR AT STEEL SUBSTRATE
(DEAD LOAD ANCHOR SIMILAR)
HIGH PRESSURE CONNECTION



YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE:
**YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM**
WIND LOAD / DEAD LOAD
ANCHOR DETAILS


PREPARED BY: **BUILDING DROPS, INC.**

1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:

FL13433

DATE: **7.17.17**

DWG. BY:
AR

CHK. BY:
HFN

SCALE: **NTS**

DWG. #: **YKK204**


SECTION:

REV.

8.2

B

c:\users\sebastianh\desktop\ykk 2026 ca\113433\ykk 204 - fl13433.dwg 8 - wind-dead load anchor details.dwg
7/24/2026 10:26 AM



ALL ANGLES AND PLATES
TO BE A-36 STEEL
Fy = 36 KSI MIN.


WIND LOAD ANCHOR

WIND + DEAD LOAD ANCHOR



MAX. DESIGN LOAD STD. DUTY = +/- 90 PSF
MAX. DESIGN LOAD HEAVY. DUTY = +/- 130 PSF

NOTE:
1) ALTERNATE WIND & DEAD LOAD
ANCHORS MAY BE DESIGNED FOR
ALTERNATE SITE CONDITIONS AND
STEEL ANGLE DESIGN ON A JOB TO JOB
BASIS FOR THE APPLICABLE WIND
LOADS AS DETERMINED IN
ACCORDANCE WITH CH. 16 OF THE
FLORIDA BLDG. CODE BY A FLORIDA
REGISTERED PROFESSIONAL ENGINEER.


24 CORNER MULL. ANCH. 8.3 ANCHORS INTO METAL STRUCTURES LOW/STANDARD PRESSURE MULL




CORNER MULL FRONT VIEW
WIND/DEAD LOAD ANCHOR
AT STEEL SUBSTRATE
LOW/ STANDARD/ HIGH PRESSURE CONNECTION



24A CORNER MULL. ANCH. 8.3 ANCHORS INTO METAL STRUCTURES HIGH PRESSURE MULL



VERTICAL SECTION
WIND LOAD ANCHOR
(DEAD LOAD ANCHOR SIMILAR)
AT STEEL SUBSTRATE
LOW / STANDARD PRESSURE CONNECTION



VERTICAL SECTION
WIND LOAD ANCHOR
(DEAD LOAD ANCHOR SIMILAR)
AT STEEL SUBSTRATE
HIGH PRESSURE CONNECTION

WIND LOAD ANCHOR NOTES:
1. WIND/DEAD LOAD ANCHORS HAVE
BEEN EVALUATED TO THE
FOLLOWING:
• WL = +/- 6,300 LBS (UNFACTORED)
AT DOUBLE ANGLE SUPPORTS
• WL = +/- 3,150 LBS (UNFACTORED)
AT SINGLE ANGLE SUPPORTS
• MAX. SPAN = 12'-6"
• MAX. TRIB WIDTH = 74"
DEAD LOAD ANCHORS HAVE BEEN
EVALUATED TO THE FOLLOWING:
• DL = 1,219 LBS (UNFACTORED) @
DOUBLE ANGLE SUPPORTS
• DL SHALL BE DETERMINED BY
ENGINEER OF RECORD.



YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001


TITLE:
YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM
WIND LOAD / DEAD LOAD
ANCHOR DETAILS

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC
AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC
SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE
FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED
ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC
DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:
FL13433



DATE: **7.17.17**

DWG. BY: **AR** CHK. BY: **HFN**

SCALE: **NTS**

DWG. #: **YKK204**

SECTION: **8.3** REV. **B**



ALL ANGLES AND PLATES
TO BE A-36 STEEL
Fy = 36 KSI MIN.


WIND LOAD ANCHOR

WIND + DEAD LOAD ANCHOR

MAX. DESIGN LOAD STD. DUTY = +/- 90 PSF
MAX. DESIGN LOAD HEAVY. DUTY = +/- 130 PSF


NOTE:

1) ALTERNATE WIND & DEAD LOAD ANCHORS MAY BE DESIGNED FOR ALTERNATE SITE CONDITIONS AND STEEL ANGLE DESIGN ON A JOB TO JOB BASIS FOR THE APPLICABLE WIND LOADS AS DETERMINED IN ACCORDANCE WITH CH. 16 OF THE FLORIDA BLDG. CODE BY A FLORIDA REGISTERED PROFESSIONAL ENGINEER.




25A CORNER MULL. ANCH.

8.4 ANCHORS INTO METAL STRUCTURES HIGH PRESSURE MULL



VERTICAL SECTION

WIND LOAD ANCHOR
(DEAD LOAD ANCHOR SIMILAR)
AT STEEL SUBSTRATE
LOW / STANDARD PRESSURE CONNECTION



VERTICAL SECTION

WIND LOAD ANCHOR
(DEAD LOAD ANCHOR SIMILAR)
AT STEEL SUBSTRATE
HIGH PRESSURE CONNECTION



YKK AP AMERICA

101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE: YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM

WIND LOAD / DEAD LOAD
ANCHOR DETAILS


PREPARED BY: BUILDING DROPS, INC.

900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744.4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:

FL13433

DATE: 7.17.17

DWG. BY:
AR

CHK. BY:	HFN
----------	-----

SCALE: NTS


DWG. #: YKK204

SECTION:

REV


8.4

[Page 49 of 59]




7/24/2026 10:26 AM

- DEAD & WIND LOAD ANCHOR NOTES:
1. DEAD LOAD ANCHORS HAVE BEEN EVALUATED TO THE FOLLOWING:
 - DL = 1,219 LBS (UNFACTORED) @ DOUBLE ANGLE SUPPORTS
 - DL SHALL BE DETERMINED BY ENGINEER OF RECORD.
 2. ALTERNATE WIND & DEAD LOAD ANCHORS MAY BE DESIGNED FOR ALTERNATE SITE CONDITIONS AND STEEL ANGLE DESIGN ON A JOB TO JOB BASIS FOR THE APPLICABLE WIND LOADS AS DETERMINED IN ACCORDANCE WITH CH. 16 OF THE FLORIDA BLDG. CODE BY A FLORIDA REGISTERED PROFESSIONAL ENGINEER.
 3. (2) BOLTS (ITEM #63) SHALL BE THROUGH BOLTED IN STANDARD HOLES AT DEAD LOAD ANCHORS AND MAX. 2" LONG SLOTTED HOLTES AT WIND LOAD ANCHORS.




27
8.6 HORIZONTAL SECTION
ANGLED CORNER
WL OR DL ANCHOR

SEE NOTE 4
(2) 3/8" THICK A36 STEEL
GUSSET PLATES
W/ 1/4" X 1" FILLET
WELDS AT 3" O.C., BOTH
SIDES



CORNER MULL FRONT VIEW
WIND/DEAD LOAD ANCHOR
AT STEEL SUBSTRATE
LOW/ STANDARD/ HIGH PRESSURE CONNECTION



VERTICAL SECTION
WIND LOAD ANCHOR
(DEAD LOAD ANCHOR SIMILAR)
AT STEEL SUBSTRATE
LOW / STANDARD/HIGH PRESSURE CONNECTION

CORNER MULLION ANCHOR TABLE FOR STANDARD DUTY MULLION					
NOMINAL DIMENSIONS		WL ANCHOR	WL ANCHOR	DL+WL ANCHOR	DL+WL ANCHOR
WIDTH (IN.)	HEIGHT (IN.)	TYPE A, C & H 'UNCRACKED'	TYPE A, C & H 'CRACKED'	TYPE A, C & H 'UNCRACKED'	TYPE A, C & H 'CRACKED'
30	108	90.0	90.0	90.0	80.0
36		90.0	78.0	90.0	67.0
42		85.0	66.0	81.0	57.0
48		75.0	58.0	71.0	50.0
54		66.0	52.0	63.0	44.0
60	114	60.0	46.0	56.0	40.0
30		90.0	88.0	90.0	76.0
36		90.0	73.0	89.0	63.0
42		81.0	63.0	77.0	54.0
48		71.0	55.0	67.0	47.0
54	120	63.0	49.0	59.0	42.0
60		56.0	44.0	53.0	38.0
30		90.0	84.0	90.0	72.0
36		90.0	70.0	85.0	60.0
42		77.0	60.0	73.0	52.0
48	126	67.0	52.0	64.0	45.0
54		60.0	46.0	56.0	40.0
60		54.0	42.0	51.0	36.0
30		90.0	80.0	90.0	69.0
36		85.0	66.0	81.0	57.0
42	132	73.0	57.0	69.0	49.0
48		64.0	50.0	61.0	43.0
54		57.0	44.0	54.0	38.0
30		90.0	76.0	90.0	66.0
36		81.0	63.0	77.0	55.0
42	138	70.0	54.0	66.0	47.0
48		61.0	47.0	58.0	41.0
54		54.0	42.0	51.0	36.0
30		90.0	73.0	89.0	63.0
36		78.0	61.0	74.0	52.0
42	144	67.0	52.0	63.0	45.0
48		58.0	45.0	55.0	39.0
30		90.0	70.0	85.0	60.0
36		75.0	58.0	71.0	50.0
42		64.0	50.0	61.0	43.0
48	150	56.0	43.0	53.0	37.0
30		86.0	67.0	82.0	58.0
36		72.0	56.0	68.0	48.0
42		61.0	48.0	58.0	41.0
48		54.0	42.0	51.0	36.0




YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE:
YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM
WIND LOAD / DEAD LOAD
ANCHOR DETAILS

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:
FL13433

DATE:
7.17.17

DWG. BY:
AR

CHK. BY:
HFN

SCALE:
NTS


DWG. #:
YKK204

SECTION:
8.6

REV.
B

DEAD & WIND LOAD ANCHOR NOTES:

- DEAD LOAD ANCHORS HAVE BEEN EVALUATED TO THE FOLLOWING:
 - DL = 1,219 LBS (UNFACTORED) @ DOUBLE ANGLE SUPPORTS
 - DL SHALL BE DETERMINED BY ENGINEER OF RECORD.
- (2) 1/2" HH GR. 5 OR ASTM A325 THREADED BOLTS PER ANGLE
 - MIN. FULL ENGAGEMENT WITH NUT & WASHER
 - OR
 - THREADED INTO TAPPED HOLE W/ MIN. 3 THREADS PENETRATION BEYOND STEEL STRUCTURE
 - MIN. 1 1/2" EDGE DISTANCE.
 - MIN. 1/4" THICK STEEL
- ALTERNATE WIND & DEAD LOAD ANCHORS MAY BE DESIGNED FOR ALTERNATE SITE CONDITIONS AND STEEL ANGLE DESIGN ON A JOB TO JOB BASIS FOR THE APPLICABLE WIND LOADS AS DETERMINED IN ACCORDANCE WITH CH. 16 OF THE FLORIDA BLDG. CODE BY A FLORIDA REGISTERED PROFESSIONAL ENGINEER.
- (2) BOLTS (ITEM #63) SHALL BE THROUGH BOLTED IN STANDARD HOLES AT DEAD LOAD ANCHORS AND MAX. 2" LONG SLOTTED HOLTES AT WIND LOAD ANCHORS.



CORNER MULLION ANCHOR TABLE FOR HEAVY DUTY MULLION					
NOMINAL DIMENSIONS		WL ANCHOR	WL ANCHOR	DL+WL ANCHOR	DL+WL ANCHOR
WIDTH (IN.)	HEIGHT (IN.)	TYPE A, C & H 'UNCRACKED'	TYPE A, C & H 'CRACKED'	TYPE A, C & H 'UNCRACKED'	TYPE A, C & H 'CRACKED'
30	108	120.0	93.6	114.0	80.9
36		100.0	78.0	95.0	67.5
42		85.7	66.9	81.4	57.8
48		75.0	58.5	71.3	50.6
54		66.7	52.0	63.3	45.0
60	114	60.0	46.8	57.0	40.5
30		113.7	88.7	108.0	76.7
36		94.7	73.9	90.0	63.9
42		81.2	63.3	77.1	54.8
48		71.1	55.4	67.5	47.9
54	120	63.2	49.3	60.0	42.6
60		56.8	44.3	54.0	38.3
30		108.0	84.2	102.6	72.8
36		90.0	70.2	85.5	60.7
42		77.1	60.2	73.3	52.0
48	126	67.5	52.7	64.1	45.5
54		60.0	46.8	57.0	40.5
60		54.0	42.1	51.3	36.4
30		102.9	80.2	97.7	69.4
36		85.7	66.9	81.4	57.8
42	132	73.5	57.3	69.8	49.6
48		64.3	50.1	61.1	43.4
54		57.1	44.6	54.3	38.5
60		51.4	40.1	48.9	34.7
30		98.2	76.6	93.3	66.2
36	138	81.8	63.8	77.7	55.2
42		70.1	54.7	66.6	47.3
48		61.4	47.9	58.3	41.4
54		54.5	42.5	51.8	36.8
60		49.1	38.3	46.6	33.1
30	144	93.9	73.3	89.2	63.3
36		78.3	61.0	74.3	52.8
42		67.1	52.3	63.7	45.2
48		58.7	45.8	55.8	39.6
54		52.2	40.7	49.6	35.2
60	150	47.0	36.6	44.6	31.7
30		90.0	70.2	85.5	60.7
36		75.0	58.5	71.3	50.6
42		64.3	50.1	61.1	43.4
48		56.3	43.9	53.4	37.9
54		50.0	39.0	47.5	33.7
60		45.0	35.1	42.8	30.4
30		86.4	67.4	82.1	58.3
36		72.0	56.2	68.4	48.6
42		61.7	48.1	58.6	41.6
48		54.0	42.1	51.3	36.4
54		48.0	37.4	45.6	32.4
60		43.2	33.7	41.0	29.1

YKK
ap

Quality
inspires™

YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE:
YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM
WIND LOAD / DEAD LOAD
ANCHOR DETAILS

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

BD
BUILDING DROPS

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT

HERMES F. NORERO
LICENSE
No. 73778
STATE OF
FLORIDA
PROFESSIONAL ENGINEER

HERMES F. NORERO, P.E.
BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
FBPE CERT. OF AUTHORIZATION No. 29578

FL #:
FL13433

DATE:
7.17.17

DWG. BY:
AR


CHK. BY:
HFN

SCALE:
NTS

DWG. #:
YKK204

SECTION:
8.7



REV.
B



WIND LOAD ANCHOR
(DEAD LOAD ANCHOR SIMILAR)
AT STEEL SUBSTRATE
LOW / STANDARD/HIGH PRESSURE CONNECTION

NOTE:
1) ALTERNATE WIND & DEAD LOAD ANCHORS MAY BE DESIGNED FOR ALTERNATE SITE CONDITIONS AND STEEL ANGLE DESIGN ON A JOB TO JOB BASIS FOR THE APPLICABLE WIND LOADS AS DETERMINED IN ACCORDANCE WITH CH. 16 OF THE FLORIDA BLDG. CODE BY A FLORIDA REGISTERED PROFESSIONAL ENGINEER.

**OUTSIDE CORNER
WL OR DL ANCHOR**



1. DEAD LOAD ANCHORS HAVE BEEN EVALUATED TO THE FOLLOWING:
 - DL = 1,219 LBS (UNFACTORED) @ DOUBLE ANGLE SUPPORTS
 - DL SHALL BE DETERMINED BY ENGINEER OF RECORD.
2. (2) 1/2" HILTI KWIK BOLT TZ ANCHORS PER ANGLE
 - MIN. EMBEDMENT = 3 5/8"
 - MAX. C.C. SPACING = 4 1/2"
 - MIN. EDGE DISTANCE = 4 1/2"
 - MIN. 3000 PSI CONCRETE 'CRACKED' OR 'UNCRACKED'
- (2) 1/2" DEWALT SCREW-BOLT+ PER ANGLE
 - MIN. EMBEDMENT = 4 1/4"
 - MAX. C.C. SPACING = 4 1/2"
 - MIN. EDGE DISTANCE = 5"
 - MIN. 3000 PSI CONCRETE 'UNCRACKED'
- (2) 3/8" SIMPSON TITEN HD PER ANGLE
 - MIN. EMBEDMENT = 3 1/4"
 - MAX. C.C. SPACING = 4 1/2"
 - MIN. EDGE DISTANCE = 3 5/8"
 - MIN. 4000 PSI CONCRETE 'CRACKED' OR 'UNCRACKED'
3. FOR SLABS LESS THAN 8" IN THICKNESS, DESIGN MAY BE PROVIDED ON JOB TO JOB BASIS FOR REVIEW & APPROVAL BY AHJ
4. (2) BOLTS (ITEM #63) SHALL BE THROUGH BOLTED IN STANDARD HOLES AT DEAD LOAD ANCHORS AND MAX. 2" LONG SLOTTED HOLTES AT WIND LOAD ANCHORS.

TITLE: *YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM*

**WIND LOAD / DEAD LOAD
ANCHOR DETAILS**


PREPARED BY: BUILDING DROPS, INC.

1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954) 399-8478
FAX: (954) 744-4738
WEB: www.buildingdrops.com

 BUILDING DROPS

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL13433

DWG. BY: AR	CHK. BY: HFN
-----------------------	------------------------

DWG. #: YKK204

SECTION:	REV.
----------	------

8.8

WIND/DEAD LOAD TABLES
STANDARD DUTY MULLION

WIND/DEAD LOAD TABLES
HEAVY DUTY MULLION

WIND LOAD FOR STD MULLION			
NOMINAL DIMENSIONS		ANCHOR TYPE A, C & H 'UNCRACKED'	ANCHOR TYPE A, C & H 'CRACKED'
WIDTH (IN.)	HEIGHT (IN.)		
30	108	90.0	90.0
36		90.0	90.0
42		90.0	90.0
48		90.0	90.0
54		90.0	90.0
60		90.0	85.3
30	114	90.0	90.0
36		90.0	90.0
42		90.0	90.0
48		90.0	90.0
54		90.0	89.8
60		90.0	80.8
30	120	90.0	90.0
36		90.0	90.0
42		90.0	90.0
48		90.0	90.0
54		90.0	85.3
60		88.8	76.8
30	126	90.0	90.0
36		90.0	90.0
42		90.0	90.0
48		90.0	90.0
54		90.0	80.3
30	132	90.0	90.0
36		90.0	90.0
42		90.0	90.0
48		90.0	87.3
54		89.7	77.6
30	138	90.0	90.0
36		90.0	90.0
42		90.0	90.0
48		90.0	83.5
54		90.0	80.0
30	144	90.0	90.0
36		90.0	90.0
42		90.0	90.0
48		90.0	80.0
54		90.0	90.0
30	150	90.0	90.0
36		90.0	90.0
42		90.0	87.8
48		88.8	76.8

WIND + DEAD LOAD FOR STD MULLION			
NOMINAL DIMENSIONS		ANCHOR TYPE A, C & H 'UNCRACKED'	ANCHOR TYPE A, C & H 'CRACKED'
WIDTH (IN.)	HEIGHT (IN.)		
30	108	90.0	90.0
36		90.0	90.0
42		90.0	90.0
48		90.0	90.0
54		90.0	85.9
60		90.0	77.3
30	114	90.0	90.0
36		90.0	90.0
42		90.0	90.0
48		90.0	90.0
54		90.0	81.4
60		85.4	73.3
30	120	90.0	90.0
36		90.0	90.0
42		90.0	90.0
48		90.0	87.0
54		90.0	77.3
60		81.1	69.6
30	126	90.0	90.0
36		90.0	90.0
42		90.0	90.0
48		90.0	82.9
54		85.8	73.7
30	132	90.0	90.0
36		90.0	90.0
42		90.0	90.0
48		90.0	79.1
54		81.9	70.3
30	138	90.0	90.0
36		90.0	90.0
42		90.0	86.5
48		88.2	75.7
54		90.0	90.0
30	144	90.0	90.0
36		90.0	90.0
42		90.0	82.0
48		84.5	72.5
54		90.0	90.0
30	150	90.0	90.0
36		90.0	90.0
42		90.0	79.5
48		80.1	69.6

WIND LOAD FOR HD MULLION			
NOMINAL DIMENSIONS		ANCHOR TYPE A, C & H 'UNCRACKED'	ANCHOR TYPE A, C & H 'CRACKED'
WIDTH (IN.)	HEIGHT (IN.)		
30	108	130.0	130.0
36		130.0	130.0
42		130.0	121.9
48		123.3	106.7
54		109.6	94.8
60		98.7	85.3
66		89.7	77.6
72		82.2	71.1
30	114	130.0	130.0
36		130.0	130.0
42		130.0	115.5
48		116.8	101.1
54		103.9	89.8
60		93.5	80.8
66		85.0	73.5
72		77.9	67.4
30	120	130.0	130.0
36		130.0	128.0
42		126.9	109.7
48		111.0	96.0
54		98.7	85.3
60		88.8	76.8
66		80.7	69.8
72		74.0	64.0
30	126	130.0	130.0
36		130.0	121.9
42		120.8	104.5
48		105.7	91.4
54		94.0	81.3
60		84.6	73.1
66		76.9	66.5
30	132	130.0	130.0
36		130.0	116.4
42		115.3	99.7
48		100.9	87.3
54		89.7	77.6
60		80.7	69.8
66		73.4	63.5
30	138	130.0	130.0
36		128.7	111.3
42		110.3	95.4
48		96.5	83.5
54		85.8	74.2
60		77.2	66.8
30	144	130.0	128.0
36		123.3	106.7
42		105.7	91.4
48		92.5	80.0
54		82.2	71.1
60		74.0	64.0
30	150	130.0	122.9
36		118.4	102.4
42		101.5	87.8
48		88.8	76.8
54		78.9	68.3
60		71.0	61.4

WIND + DEAD LOAD FOR HD MULLION			
NOMINAL DIMENSIONS		ANCHOR TYPE A, C & H 'UNCRACKED'	ANCHOR TYPE A, C & H 'CRACKED'
WIDTH (IN.)	HEIGHT (IN.)		
30	108	130.0	130.0
36		130.0	128.9
42		128.8	110.5
48		112.7	96.7
54		100.1	85.9
60		90.1	77.3
30	114	130.0	130.0
36		130.0	122.1
42		122.0	104.7
48		106.7	91.6
54		94.9	81.4
60		85.4	73.3
30	120	130.0	130.0
36		130.0	116.0
42		115.9	99.4
48		101.4	87.0
54		90.1	77.3
60		81.1	69.6
30	126	130.0	130.0
36		128.8	110.5
42		110.4	94.7
48		96.6	82.9
54		85.8	73.7
60		77.3	66.3
30	132	130.0	126.5
36		122.9	105.5
42		105.4	90.4
48		92.2	79.1
54		81.9	70.3
60		73.7	63.3
30	138	130.0	121.0
36		117.6	100.9
42		100.8	86.5
48		88.2	75.7
54		78.4	67.2
60		70.5	60.5
30	144	130.0	116.0
36		112.7	96.7
42		96.6	82.9
48		84.5	72.5
54		75.1	64.4
60		67.6	58.0
30	150	129.8	111.4
36		108.2	92.8
42		92.7	79.5
48		81.1	69.6
54		72.1	61.9
60		64.9	55.7

YKK

ap

Quality inspires™

YKK AP AMERICA

101 MARIETTA STREET NW, SUITE 2100

ATLANTA, GA 30303

PH: (478)277-1955 FAX: (678)838-6001

TITLE:
YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM
WIND LOAD / DEAD LOAD
ANCHOR DETAILS

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

BD

BUILDING DROPS

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT

HERMES F. NORERO

LICENSE

No. 73778

STATE OF FLORIDA

PROFESSIONAL ENGINEER

HERMES F. NORERO, P.E.

BUILDING DROPS, INC.

1900 NE MIAMI CT, SUITE 2-15

MIAMI, FL 33132

FBPE CERT. OF AUTHORIZATION No. 29578

FL #:

FL13433

DATE:

7.17.17

DWG. BY:

AR

CHK. BY:

HFN

SCALE:

NTS

DWG. #:

YKK204

SECTION:


8.9

REV.

B

7/24/2026 10:26 AM

c:\users\sebastianherrerros\desktop\ykk 2026 ca\fl13433 dwgs 9 - components & bom.dwg



YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE: YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM


COMPONENTS

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744.4738
WEB: www.buildingdrops.com

BUILDING DROPS

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26


THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT




FL #:	FL13433
DATE:	7.17.17
DWG. BY:	AR
CHK. BY:	HFN
SCALE:	NTS
DWG. #:	YKK204
SECTION:	9.0
REV.	B

7/24/2026 10:26 AM


c:\users\sebastianhereros\desktop\ykk 2026 ca\113433 dwgs 9 - components & bom.dwg




- (14A) MULLION ANCHOR SLEEVE
(3" LONG AT TOP & BOTTOM)
- (44A) MULLION SPLICE SLEEVE
(6" LONG AT SPLICE)
- (46A) MULLION REINFORCEMENT SLEEVE
(29" LONG AT ANCHOR)




(31) INTERIOR MULLION COVER



(40) LOW PRESSURE HORIZONTAL
(MONO)




(40A) LOW PRESSURE HORIZONTAL
(INS)




(15) WIND LOAD ANCHOR
(STANDARD MULLION)

(90) WIND LOAD ANCHOR
(HEAVY DUTY MULLION)




(28) 90° CORNER ADAPTOR
(MONO)




(16) DEAD LOAD ANCHOR
(STANDARD MULLION)

(91) DEAD LOAD ANCHOR
(HEAVY DUTY MULLION)




(28A) 90° CORNER ADAPTOR
(INS)




(35) S-ANCHOR (STD)


(64) S-ANCHOR (HD)




(41) FLUSH FILLER
(SHALLOW MULLION)



(58) POCKET FILLER
(INS)




(45) OPEN BACK HEAD/ HORIZONTAL (INS)




(16A) DEAD LOAD ANCHOR
(STANDARD MULLION)


(92) DEAD LOAD ANCHOR
(HEAVY DUTY MULLION)




(29) 90° CORNER FACE COVER
(MONO)




(29A) 90° CORNER FACE COVER
(INS)




(38) LOW PRESSURE MULLION
(MONO)




(47) LIGHT DUTY OPEN BACK HEAD/HORIZONTAL
(INS)




(26) REINFORCEMENT CHANNEL




(30) 90° CORNER INTERIOR COVER BASE




(37) GLAZING ADAPTOR




(38A) LOW PRESSURE MULLION
(INS)




(56) INTERIOR MULLION
COVER




(57) POCKET FILLER
(MONO)




(26A) REINFORCEMENT CHANNEL




(26B) REINFORCEMENT CHANNEL




(27) 90° CORNER PRESSURE PLATE
(MONO)



(27A) 90° CORNER PRESSURE PLATE
(INS)



(39) LOW PRESSURE OPEN BACK
HEAD/HORIZ./SILL (MONO)



(39A) LOW PRESSURE OPEN BACK
HEAD/HORIZ./SILL (INS)



YKK AP AMERICA

101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303

PH: (478)277-1955 FAX: (678)838-6001

TITLE:
YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM

COMPONENTS


PREPARED BY: BUILDING DROPS, INC.

1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC
AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC
SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE
FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED
ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC
DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:

FL13433

DATE: 7.17.17

DWG. BY:
AR

CHK. BY:
HFN

SCALE: NTS

DWG. #: YKK204


SECTION:

REV.


9.1

B

7/24/2026 10:26 AM




62 90° CORNER INTERIOR COVER




66 WIND LOAD (STANDARD MULLION)

68 WIND LOAD (STANDARD MULLION)




67 DEAD LOAD (STANDARD MULLION)

69 DEAD LOAD (STANDARD MULLION)




66 WIND LOAD (STANDARD MULLION)

67 DEAD LOAD (STANDARD MULLION)



68 WIND LOAD (STANDARD MULLION)

69 DEAD LOAD (STANDARD MULLION)




70 WIND LOAD (STANDARD MULLION)

71 DEAD LOAD (STANDARD MULLION)

84 WIND LOAD (HD MULLION)

85 DEAD LOAD (HD MULLION)




72 WIND LOAD (STANDARD MULLION)

73 DEAD LOAD (STANDARD MULLION)

86 WIND LOAD (HD MULLION)

87 DEAD LOAD (HD MULLION)



74 WIND LOAD (STANDARD MULLION)

75 DEAD LOAD (STANDARD MULLION)

88 WIND LOAD (HD MULLION)

89 DEAD LOAD (HD MULLION)



YKK AP AMERICA

101 MARIETTA STREET NW, SUITE 2100

ATLANTA, GA 30303

PH: (478)277-1955 FAX: (678)838-6001


TITLE:
YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM

BILL OF MATERIALS

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com


REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT




FL #:	FL13433
DATE:	7.17.17
DWG. BY:	AR
CHK. BY:	HFN
SCALE:	NTS
DWG. #:	YKK204
SECTION:	9.2
REV.	B

7/24/2026 10:26 AM




80 WIND LOAD
(HD MULLION)

82 WIND LOAD
(HD MULLION)




81 DEAD LOAD
(HD MULLION)

83 DEAD LOAD
(HD MULLION)




80 WIND LOAD ANCHOR
(HEAVY DUTY MULLION)

81 DEAD LOAD ANCHOR
(HEAVY DUTY MULLION)




82 WIND LOAD ANCHOR
(HEAVY DUTY MULLION)

83 DEAD LOAD ANCHOR
(HEAVY DUTY MULLION)



104 1-1/2" X 1-1/2" X 1/8" ANGLE



105 1" X 1" X 1/8" ANGLE



YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE: YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM

BILL OF MATERIALS

PREPARED BY: BUILDING DROPS, INC.

1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744.4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:

FL13433

DATE: **7.17.17**

DWG. BY:
AR

CHK. BY:
HFN

SCALE: **NTS**

DWG. #: **YKK204**

SECTION:

9.3

REV.

B

7/24/2026 10:26 AM

ITEM	PART NO.	DESCRIPTION	MATERIAL
1	E9-3103	VERTICAL MULLION (MONO)	6063-T6
1A	E9-3101	VERTICAL MULLION (INS)	6063-T6
1B	E9-3182	HD VERTICAL MULLION (MONO)	6063-T6
1C	E9-3183	HD VERTICAL MULLION (INS)	6063-T6
2	AS-3179	PERIMETER PRESSURE PLATE (MONO)	6063-T5
2A	AS-3178	PERIMETER PRESSURE PLATE (INS)	6063-T5
3	AS-3173	PRESSURE PLATE (MONO)	6063-T5
3A	AS-3172	PRESSURE PLATE (INS)	6063-T5
4	E9-3161	FACE COVER	6063-T5
5	E9-3162	FLUSH FILLER	6063-T5
5A	E9-3188	FLUSH FILLER (DEEP MULL)	6063-T6
6	E9-3105	OPEN BACK HEAD/HORIZ./SILL (MONO)	6063-T5
6A	E9-3104	OPEN BACK SILL (INS)	6063-T5
6B	E9-3189	HD OPEN BACK HEAD/HORIZ./SILL (MONO)	6063-T6
6C	E9-3187	HD OPEN BACK HEAD/HORIZ./SILL (INS)	6063-T6
7	E9-3106	HORIZONTAL (MONO)	6063-T5
7A	E9-3102	HORIZONTAL (INS)	6063-T5
7B	E9-3190	HD HORIZONTAL (MONO)	6063-T6
7C	E9-3185	HD HORIZONTAL (INS)	6063-T6
8	E2-0379	EXT/INT GLAZING GASKET	EPDM
9	E2-0353	INTERIOR GLAZING SILICONE SPACER	EPDM
10	E2-0623	SETTING BLOCK (MONO)	EPDM (90±5)
10A	E2-0611	SETTING BLOCK (INS)	EPDM (85±5)
11	E1-3001	SHEAR BLOCK (STD)	6063-T5
12	E1-3004	JAMB F ANCHOR (STD)	6063-T5
13	E1-3003	MULLION T ANCHOR (STD)	6061-T6
14	E1-3006	MULLION ANCHOR SLEEVE (STD) (3" LONG @ TOP & BOTTOM)	6063-T5
14A	E1-3033	MULLION ANCHOR SLEEVE (HD) (3" LONG @ TOP & BOTTOM)	6063-T5
15	E1-1204	WINDLOAD ANCHOR (STD)	A36 STEEL
16	E1-1205	DEADLOAD ANCHOR (STD)	A36 STEEL
16A	-	DEAD LOAD (NOT BY YKK AP)	A36 STEEL
17	HD-2520-W3-SS	1/4"-20 X 1-1/4" HWHMS	STAINLESS STEEL
18	FC-1220	#12 X 1-1/4" FHMS TYPE AB	ZINC PLATED STEEL
19	HF-2510-W1	#1/4"-20 X 5/8" HWHS TYPE F	ZINC PLATED STEEL
20	PC-1010	#10 X 5/8" PHSMS TYPE AB	ZINC PLATED STEEL
21	HM-5072	1/2"-13 X 4-1/2" HHMS BOLT (GR 5)	ZINC PLATED STEEL
22	PC-1210	#12 X 5/8" PHSMS TYPE AB	ZINC PLATED STEEL
23	E1-3040	SHEAR BLOCK (HD)	6063-T5
24	TEK-1012	#10-16 X 3/4" TEK HWHS	ZINC PLATED STEEL
25	PC-1010	#10 X 5/8" PHSMS TYPE AB	ZINC PLATED STEEL
26	E1-0175	REINFORCEMENT CHANNEL (2-1/2" X 4-1/2" X 1/4")	A36 STEEL
26A	E1-3031	REINFORCEMENT CHANNEL (2-1/2" X 7-1/4" X 1/4")	A36 STEEL
26B	-	REINFORCEMENT CHANNEL (2-1/2" X 5" X 3/8") (NOT BY YKK AP)	A36 STEEL
27	AS-3177	90° CORNER PRESSURE PLATE (MONO)	6063-T5
27A	AS-3175	90° CORNER PRESSURE PLATE (INS)	6063-T5
28	E9-3146	90° CORNER ADAPTOR (MONO)	6063-T5

ITEM	PART NO.	DESCRIPTION	MATERIAL
28A	E9-3145	90° CORNER ADAPTOR (INS)	6063-T5
29	E9-3176	90° CORNER FACE COVER (MONO)	6063-T5
29A	E9-3174	90° CORNER FACE COVER (INS)	6063-T5
30	E9-1280	90° CORNER INTERIOR COVER BASE	6063-T5
31	E9-3165	90° CORNER INTERIOR COVER	6063-T5
32	PC-1008	#10 X 1/2" PHSMS TYPE AB	ZINC PLATED STEEL
33	E1-0190	DEADLOAD ANCHOR FOR 90° CORNER	A36 STEEL
33A	-	STEEL ANGLE	A36 STEEL
34	E1-0191	WINDLOAD ANCHOR FOR 90° CORNER	A36 STEEL
34A	-	STEEL ANGLE	A36 STEEL
35	E1-3039	S ANCHOR (STD)	6063-T6
36	E2-0386	ISOLATOR TAPE	PVC SPONGE
37	E9-3147	GLAZING ADAPTOR	6063-T5
38	E9-3107	LOW PRESSURE MULLION (MONO)	6063-T6
38A	E9-3111	LOW PRESSURE MULLION (INS)	6063-T6
39	E9-8168	LOW PRESSURE OPEN BACK HEAD/SILL/HORIZ (MONO)	6063-T5
39A	E9-3112	LOW PRESSURE OPEN BACK HEAD/SILL/HORIZ (INS)	6063-T6
40	E9-8167	LOW PRESSURE HORIZONTAL (MONO)	6063-T5
40A	E9-3113	LOW PRESSURE HORIZONTAL (INS)	6063-T5
41	E9-8169	FLUSH FILLER (SHALLOW)	6063-T5
42	E1-3011	MULLION END CAP (MONO)	alum sheet
43	E1-3036	SHEAR BLOCK (SHALLOW)	6063-T5
44	E1-3005	MULLION SPLICE SLEEVE (STD) (6" LONG @ SPLICE)	6063-T5
44A	E1-3037	MULLION SPLICE SLEEVE (HD) (6" LONG @ SPLICE)	6063-T5
45	E9-3159	OPEN BACK HEAD/HORIZONTAL (INS)	6063-T5
46	E1-3007	MULLION REINFORCEMENT SLEEVE (STD) (29" LONG @ ANCHOR)	6063-T5
46A	E1-3030	MULLION REINFORCEMENT SLEEVE (HD) (29" LONG @ ANCHOR)	6063-T5
47	E9-3127	LIGHT DUTY OPEN BACK HEAD/HORIZONTAL (INS)	6063-T5
48	FC-1410	#14 X 5/8" FHMS TYPE AB	ZINC PLATED STEEL
49	HM-5000	1/2"-13 NUT HHMS	ZINC PLATED STEEL
50	WS-5000	1/2" LOCK WASHER	ZINC PLATED STEEL
51	WW-5000	1/2" FLAT WASHER	ZINC PLATED STEEL
52	FF-0808	#8-32 X 1/2" FHMS TYPE F	ZINC PLATED STEEL
53	N/A	#8-32 X 3-1/2" FHMSM @ 16" OC	ZINC PLATED STEEL
54	FC-1212	#12 X 3/4" FHMS TYPE AB	ZINC PLATED STEEL
55	-	-	-
56	E9-3186	INTERIOR MULLION COVER	6063-T6
57	E9-3109	POCKET FILLER (MONO)	6063-T5
58	E9-3110	POCKET FILLER (INS)	6063-T5
59	PC-1008	#10 X 1/2" PHSMS TYPE AB	ZINC PLATED STEEL
60	E1-3018	MULLION T ANCHOR FOR 90° CORNER	-
61	E2-0103	THERMAL ISOLATOR	EPDM (85±5)
62	E9-3160	90° CORNER INTERIOR COVER (HD)	6063-T5
63	-	1/2"-13 HHMS BOLT (GRADE 5) OF SUFFICIENT LENGTH TO ACHIEVE FULL ENGAGEMENT W/ NUT SAE GR5 OR ASTM A325	-
64	E1-3038	S ANCHOR (HD)	6063-T6

ITEM	PART NO.	DESCRIPTION	MATERIAL
65	E1-3010	MULLION END CAP (INS)	alum sheet
66	-	WINDLOAD ANCHOR (STD MULLION)(NOT BY YKK AP)	A36 STEEL
67	-	DEADLOAD ANCHOR (STD MULLION)(NOT BY YKK AP)	A36 STEEL
68	-	WINDLOAD ANCHOR (STD MULLION)(NOT BY YKK AP)	A36 STEEL
69	-	DEADLOAD ANCHOR (STD MULLION)(NOT BY YKK AP)	A36 STEEL
70	-	WINDLOAD ANCHOR (STD MULLION)(NOT BY YKK AP)	A36 STEEL
71	-	DEADLOAD ANCHOR (STD MULLION)(NOT BY YKK AP)	A36 STEEL
72	-	WINDLOAD ANCHOR (STD MULLION)(NOT BY YKK AP)	A36 STEEL
73	-	DEADLOAD ANCHOR (STD MULLION)(NOT BY YKK AP)	A36 STEEL
74	-	WINDLOAD ANCHOR (STD MULLION)(NOT BY YKK AP)	A36 STEEL
75	-	DEADLOAD ANCHOR (STD MULLION)(NOT BY YKK AP)	A36 STEEL
76	E1-3016	90° CORNER SHEAR CLIP (RH)	6063-T5
77	E1-3017	90° CORNER SHEAR CLIP (LH)	6063-T5
78	E1-3028	90° CORNER SHEAR CLIP (HD)(RH)	6063-T5
79	E1-3029	90° CORNER SHEAR CLIP (HD)(LH)	6063-T5
80	-	WINDLOAD ANCHOR (HD MULLION)(NOT BY YKK AP)	A36 STEEL
81	-	DEADLOAD ANCHOR (HD MULLION)(NOT BY YKK AP)	A36 STEEL
82	-	WINDLOAD ANCHOR (HD MULLION)(NOT BY YKK AP)	A36 STEEL
83	-	DEADLOAD ANCHOR (HD MULLION)(NOT BY YKK AP)	A36 STEEL
84	-	WINDLOAD ANCHOR (HD MULLION)(NOT BY YKK AP)	A36 STEEL
85	-	DEADLOAD ANCHOR (HD MULLION)(NOT BY YKK AP)	A36 STEEL
86	-	WINDLOAD ANCHOR (HD MULLION)(NOT BY YKK AP)	A36 STEEL
87	-	DEADLOAD ANCHOR (HD MULLION)(NOT BY YKK AP)	A36 STEEL
88	-	WINDLOAD ANCHOR (HD MULLION)(NOT BY YKK AP)	A36 STEEL
89	-	DEADLOAD ANCHOR (HD MULLION)(NOT BY YKK AP)	A36 STEEL
90	E1-1280	WINDLOAD ANCHOR (HD)	A36 STEEL
91	E1-1281	DEADLOAD ANCHOR (HD)	A36 STEEL
92	-	DEADLOAD ANCHOR (NOT BY YKK AP)	A36 STEEL
93	E1-3034	JAMB F ANCHOR (HD)	6063-T5
94	E1-3035	MULLION T ANCHOR (HD)	6063-T5
95	E1-3032	SHEAR BLOCK (HD HORIZONTAL)	6063-T5
96	E3-0103	NYLON SLIP PAD	NYLON
106	E2-0356	ISOLATOR TAPE	PVC Sponge
104	E9-9303	1-1/2" X 1-1/2" X 1/8" ANGLE	6063-T5
105	E9-9302	1" X 1" X 1/8" ANGLE	6063-T5
106	E2-0537	SIDE BLOCK	EPDM (85±5)
107	HM-2516-W3	#1/4"-20 X 1" HWHMS	ZINC PLATED STEEL
108	FC-1456	#14 X 3 1/2" FHMS TYPE AB	ZINC PLATED STEEL



YKK AP AMERICA
101 MARIETTA STREET NW, SUITE 2100
ATLANTA, GA 30303
PH: (478)277-1955 FAX: (678)838-6001

TITLE:
YHC - 300 OG (HVHZ)
CURTAIN WALL SYSTEM

BILL OF MATERIALS

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

BUILDING DROPS

REMARKS	BY	DATE
MISC. UPDATES	LS	6.02.26
2026 FBC CODE UPDATE	SH	07.06.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT

HERMES F. NORERO, P.E.
BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
FBPE CERT. OF AUTHORIZATION No. 29578

FL #:
FL13433

DATE:
7.17.17

DWG. BY:
AR

CHK. BY:
HFN

SCALE:
NTS

DWG. #:
YKK204

SECTION:
9.4

REV.
B

[Page 59 of 59]

c:\users\sebastian\hereros\desktop\ykk 2026 ca\fl13433\dwgs 9 - components & bom.dwg