

ANDERSEN CORPORATION

400 SERIES GLIDING PATIO DOOR

(NON-HVHZ)(NON-IMPACT)

INSTALLATION NOTES:

1. ONE (1) INSTALLATION ANCHOR IS REQUIRED AT EACH ANCHOR LOCATION SHOWN, UNLESS OTHERWISE STATED.
2. THE NUMBER OF INSTALLATION ANCHORS DEPICTED IS THE MINIMUM NUMBER OF ANCHORS TO BE USED FOR PRODUCT INSTALLATION.
3. INSTALL INDIVIDUAL INSTALLATION ANCHORS WITHIN A TOLERANCE OF ±1/2 INCH OF THE DEPICTED LOCATION IN THE ANCHOR LAYOUT DETAIL (I.E., WITHOUT CONSIDERATION OF TOLERANCES). TOLERANCES ARE NOT CUMULATIVE FROM ONE INSTALLATION ANCHOR TO THE NEXT.
4. SHIM AS REQUIRED AT EACH INSTALLATION ANCHOR WITH LOAD BEARING SHIM(S). MAXIMUM ALLOWABLE SHIM STACK TO BE 3/8 INCH. SHIM WHERE SPACE OF 1/16 INCH OR GREATER OCCURS. SHIM(S) SHALL BE CONSTRUCTED OF HIGH DENSITY PLASTIC OR BETTER.
5. FOR INSTALLATION THROUGH 1X BUCK TO CONCRETE/MASONRY, OR DIRECTLY INTO CONCRETE/MASONRY, USE 3/16 ITW TAPCONS OF SUFFICIENT LENGTH TO ACHIEVE 1 1/4 INCH MINIMUM EMBEDMENT.
6. FOR INSTALLATION THROUGH 2X BUCK USE #10 SCREW OF SUFFICIENT LENGTH TO ACHIEVE 1 1/2 INCH MINIMUM EMBEDMENT INTO WOOD SUBSTRATE.
6. FOR INSTALLATION THROUGH METAL STUD USE #10 SELF-TAPPING SCREW OF SUFFICIENT LENGTH TO ACHIEVE 3 THREADS MINIMUM PENETRATION BEYOND METAL FRAME SUBSTRATE.
7. MINIMUM EMBEDMENT AND EDGE DISTANCE EXCLUDE WALL FINISHES, INCLUDING BUT NOT LIMITED TO STUCCO, FOAM, BRICK VENEER, AND SIDING.
8. INSTALLATION ANCHORS AND ASSOCIATED HARDWARE MUST BE MADE OF CORROSION RESISTANT MATERIAL OR HAVE A CORROSION RESISTANT COATING.
9. FOR HOLLOW BLOCK AND GROUT FILLED BLOCK, DO NOT INSTALL INSTALLATION ANCHORS INTO MORTAR JOINTS. EDGE DISTANCE IS MEASURED FROM FREE EDGE OF BLOCK OR EDGE OF MORTAR JOINT INTO FACE SHELL OF BLOCK.
10. INSTALLATION ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH ANCHOR MANUFACTURER'S INSTALLATION INSTRUCTIONS, AND ANCHORS SHALL NOT BE USED IN SUBSTRATES WITH STRENGTHS LESS THAN THE MINIMUM STRENGTH SPECIFIED BY THE ANCHOR MANUFACTURER.
11. INSTALLATION ANCHOR CAPACITIES FOR PRODUCTS HEREIN ARE BASED ON SUBSTRATE MATERIALS WITH THE FOLLOWING PROPERTIES:

A. WOOD - MINIMUM SPECIFIC GRAVITY OF 0.55.

B. CONCRETE -MINIMUM COMPRESSIVE STRENGTH OF 3000 PSI.

C. GROUT-FILLED CMU- UNIT STRENGTH CONFORMS TO ASTM C-90 WITH MINIMUM COMPRESSIVE STRENGTH OF 2000 PSI AND GROUT CONFORMS TO ASTM C 476, MINIMUM GROUT COMPRESSIVE STRENGTH OF 2000 PSI.

D. HOLLOW BLOCK CMU - UNIT STRENGTH CONFORMS TO ASTM C-90 WITH MINIMUM COMPRESSIVE STRENGTH OF 2000 PSI.

E. STEEL - MINIMUM YIELD STRENGTH OF 33 KSI. MINIMUM WALL THICKNESS OF 33 MILS (20 GAUGE).

F. ALUMINUM - MINIMUM 6063-T5 ALLOY. MINIMUM WALL THICKNESS OF 1/8".

GENERAL NOTES:

1. THE PRODUCT SHOWN HEREIN IS DESIGNED AND MANUFACTURED TO COMPLY WITH THE CURRENT FLORIDA BUILDING CODE (FBC), **EXCLUDING** HVHZ AND HAS BEEN EVALUATED ACCORDING TO THE FOLLOWING:

- AAMA/WDMA/CSA 101/ I.S.2/A440-17
2. ADEQUACY OF THE EXISTING STRUCTURAL CONCRETE/MASONRY, 2X AND METAL STUD FRAMING AS A MAIN WIND FORCE RESISTING SYSTEM CAPABLE OF WITHSTANDING AND TRANSFERRING APPLIED PRODUCT LOADS TO THE FOUNDATION IS THE RESPONSIBILITY OF THE ENGINEER OR ARCHITECT OF RECORD FOR THE PROJECT OF INSTALLATION.
3. 1X AND 2X BUCKS (WHEN USED) SHALL BE DESIGNED AND ANCHORED TO PROPERLY TRANSFER ALL LOADS TO THE STRUCTURE. BUCK DESIGN AND INSTALLATION IS THE RESPONSIBILITY OF THE ENGINEER OR ARCHITECT OF RECORD FOR THE PROJECT OF INSTALLATION.
4. THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.
5. APPROVED IMPACT PROTECTIVE SYSTEM **IS REQUIRED** TO PROTECT THIS PRODUCT IN AREAS REQUIRING IMPACT RESISTANCE.
6. DOOR FRAME MATERIAL: *WOOD, ALUMINUM, AND PVC*
7. GLASS SHALL MEET THE REQUIREMENTS OF ASTM E1300 GLASS CHARTS. SEE SHEET 7 FOR GLAZING DETAIL.
8. *DESIGNATIONS "X" AND "O" STAND FOR THE FOLLOWING:*

X: *OPERABLE PANEL*

O: *FIXED PANEL*
9. CUSTOM SIZES AVAILABLE UPON REQUEST. CUSTOM DESIGN PRESSURE WILL BE ASSIGNED EQUAL TO NEXT LARGER STANDARD SIZE.

TABLE OF CONTENTS	
SHEET	SHEET DESCRIPTION
1	GENERAL AND INSTALLATION NOTES
2	ELEVATIONS AND ANCHOR LAYOUTS
3	ELEVATION AND ANCHOR LAYOUT
4	VERTICAL SECTIONS
5	HORIZONTAL SECTIONS
6	COMPONENTS & BILL OF MATERIALS
7	COMPONENTS & GLAZING DETAIL
8	SIDELITE MULL TABLE (ONE-WAY)
9	TRANSOM MULL TABLE (TWO-WAY)
10	ANCHOR DETAILS

DESIGN PRESSURE RATING			
MODEL & CONFIGURATION		DESIGN PRESSURE	MISSILE IMPACT RATING
FWG80611	OX	+40.0 / -40.0 PSF	NON-IMPACT
FWG160611	OXXO	+25.0 / -25.0 PSF	NON-IMPACT
FWG8080	OX	+40.0 / -40.0 PSF	NON-IMPACT
FWG16080	OXXO	+35.0 / -35.0 PSF	NON-IMPACT
FWGSTAT ALL SIZES	O	+40.0 / -40.0 PSF	NON-IMPACT



100 FOURTH AVE NORTH
BAYPORT, MN 55003-1096
PH: (651) 264-5150 FX: (651) 264-5485

TITLE:

400 SERIES GLIDING
PATIO DOOR
(NON-HVHZ)(NON-IMPACT)

GENERAL AND INSTALLATION NOTES

PREPARED BY:

BUILDING DROPS, INC.

398 E. DANIA BEACH BLVD., STE. 338
DANIA BEACH, FL 33004
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

BUILDING DROPS

REMARKS	BY	DATE
5TH FBC CODE CHANGE	SM	4.10.15
6TH FBC CODE CHANGE	HR	8.9.17
7TH FBC CODE CHANGE	SR	3.18.20
8TH FBC CODE CHANGE	SH	5.24.23

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT

Digitally signed by Hermes F. Norero, P.E.
Reason: I am approving this document
Date: 2023.09.14 20:26:42 -0400

HERMES F. NORERO, P.E.

FLORIDA # 73778

BUILDING DROPS, INC

398 E. DANIA BEACH BLVD. # 338

DANIA BEACH, FL 33004

FBPE CERT. OF AUTHORIZATION No. 29578

FL #:

FL14429

DATE:

08.09.17

DWG. BY:

HR

CHK. BY:

HFN

SCALE:

NTS

DWG. #:


AWD117

SHEET:


1

OF 10


s:\projects\andersen windows\c-23-0347 - fbc 2023 code change (8th edition)\dwg\fl14429\awd117.dwg 6/16/2023 12:01 PM




ELEVATION



ANCHOR LAYOUT



ELEVATION



ANCHOR LAYOUT

- SEALANT OPTIONS
- TREMCO SPECTREM 2
 - DOW 795
 - PECORA 895
 - GE SILPRUF SCS-2000

ANCHOR SCHEDULE					
SUBSTRATE	ANCHOR TYPE	MIN. EMBEDMENT (IN.)	EDGE DISTANCE (IN.)	O.C. SPACING (IN.)	
				HEAD	JAMB
WOOD	#10 WOOD SCREW	1-1/2	3/4	19-3/4	19
CONCRETE/MASONRY	3/16" ITW TAPCON	1-1/4	2-1/4	28-7/8	35
STEEL	#10 TEK SCREW	3 THREADS	1/2	19-3/4	19




100 FOURTH AVE NORTH
BAYPORT, MN 55003-1096
PH: (651) 264-5150 FX: (651) 264-5485

TITLE: 400 SERIES GLIDING PATIO DOOR (NON-HVHZ)(NON-IMPACT) ELEVATIONS AND ANCHOR LAYOUTS

PREPARED BY: BUILDING DROPS, INC. 398 E. DANIA BEACH BLVD., STE. 338 DANIA BEACH, FL 33004 PH: (954)395-8478 FAX: (954)744-4738 WEB: www.buildingdrops.com

REMARKS	BY	DATE
5TH FBC CODE CHANGE	SM	4.10.15
6TH FBC CODE CHANGE	HR	8.9.17
7TH FBC CODE CHANGE	SR	3.18.20
8TH FBC CODE CHANGE	SH	5.24.23

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #: FL14429

DATE: 08.09.17

DWG. BY: HR CHK. BY: HFN

SCALE: NTS

DWG. #: AWD117

TITLE: 400 SERIES GLIDING
PATIO DOOR
(NON-HVHZ)(NON-IMPACT)

ELEVATION AND ANCHOR LAYOUT

PREPARED BY:


BD
BUILDING DROPS

BUILDING DROPS, INC.
398 E. DANIA BEACH BLVD., STE. 338
DANIA BEACH, FL 33004
PH: (954) 399-8478
FAX: (954) 744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
5TH FBC CODE CHANGE	SM	4.10.15
6TH FBC CODE CHANGE	HR	8.9.17
7TH FBC CODE CHANGE	SR	3.18.20
8TH FBC CODE CHANGE	SH	5.24.23

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:

FL14429

DATE: 08.09.17

DWG. BY:
HR

CHK. BY:
HFN


SCALE: NTS

DWG. #: AWD117


SHEET:

3

OF 10




ELEVATION




ANCHOR LAYOUT


6/16/2023 12:01 PM
s:\projects\andersen windows\lcc-23-0347 - fbc 2023 code change (8th edition)\dwgs\fin4429\awd117.dwg




C
4 **VERTICAL SECTION**
HEAD - 2X WOOD/CONCRETE/MASONRY
THROUGH FRAME



A
4 **VERTICAL SECTION**
SILL - 6'8" & 6'11"



D
4 **VERTICAL SECTION**
HEAD - 1X WOOD/CONCRETE/MASONRY
THROUGH FRAME



B
4 **VERTICAL SECTION**
SILL - 8'0"



100 FOURTH AVE NORTH
BAYPORT, MN 55003-1096
PH: (651) 264-5150 FX: (651) 264-5485

TITLE: 400 SERIES GLIDING
PATIO DOOR
(NON-HVHZ)(NON-IMPACT)

VERTICAL SECTIONS


PREPARED BY:

BUILDING DROPS, INC.
398 E. DANIA BEACH BLVD., STE. 338
DANIA BEACH, FL 33004
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
5TH FBC CODE CHANGE	SM	4.10.15
6TH FBC CODE CHANGE	HR	8.9.17
7TH FBC CODE CHANGE	SR	3.18.20
8TH FBC CODE CHANGE	SH	5.24.23

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #: **FL14429**

DATE: **08.09.17**

DWG. BY:
HR

CHK. BY:
HFN

SCALE: **NTS**


DWG. #: **AWD117**

SHEET:


4

OF 10


6/16/2023 12:01 PM
s:\projects\andersen windows\c-23-0347 - fbc 2023 code change (8th edition)\dwgs\fl14429\awd117.dwg




F5 HORIZONTAL SECTION
JAMB - METAL STUD FRAME
THROUGH FRAME




H5 HORIZONTAL SECTION
INTERLOCK



E5 HORIZONTAL SECTION
ASTRAGAL



G5 HORIZONTAL SECTION
OP. JAMB - 1X WOOD/CONCRETE/MASONRY
THROUGH FRAME



N5 HORIZONTAL SECTION
STAT. JAMB - 1X WOOD/CONCRETE/MASONRY
THROUGH FRAME



100 FOURTH AVE NORTH
BAYPORT, MN 55003-1096
PH: (651) 264-5150 FX: (651) 264-5485

TITLE: 400 SERIES GLIDING
PATIO DOOR
(NON-HVHZ)(NON-IMPACT)

HORIZONTAL SECTIONS

PREPARED BY:

BUILDING DROPS, INC.

398 E. DANIA BEACH BLVD., STE. 338
DANIA BEACH, FL 33004


PH: (954)399-8478
FAX: (954)744-4738

WEB: www.buildingdrops.com



REMARKS	BY	DATE
5TH FBC CODE CHANGE	SM	4.10.15
6TH FBC CODE CHANGE	HR	8.9.17
7TH FBC CODE CHANGE	SR	3.18.20
8TH FBC CODE CHANGE	SH	5.24.23

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT





















FL #:	FL14429
DATE:	08.09.17
DWG. BY:	HR
CHK. BY:	HFN
SCALE:	NTS
DWG. #:	AWD117
SHEET:	5

6/16/2023 12:01 PM
s:\projects\andersen windows\lcc-23-0347 - fbc 2023 code change (8th edition)\dwgs\fl14429\awd117.dwg

BILL OF MATERIALS				
NO	PART NUMBER	DESCRIPTION	MATERIAL	MANUFACTURER
1		FRAME HEAD	WOOD	ANDERSEN
2A		OP. FRAME JAMB	WOOD	ANDERSEN
2B		STAT. FRAME JAMB	WOOD	ANDERSEN
2C		SIDELITE FRAME JAMB	WOOD	ANDERSEN
3A		FRAME SILL EXTERIOR	ALUMINUM	ANDERSEN
3B		FRAME SILL INTERIOR	ALUMINUM	ANDERSEN
3C		FRAME SILL THERMAL BREAK	PVC	ANDERSEN
4		HEAD CAP FLASHING	ALUMINUM	ANDERSEN
5		FLANGE FIN	PVC	ANDERSEN
6		PANEL GLAZING STOP	WOOD	ANDERSEN
7		SILL EXTENSION	WOOD	ANDERSEN
8		PANEL BOTTOM RAIL	WOOD	ANDERSEN
9		PANEL TOP & SIDE RAIL	WOOD	ANDERSEN
10		SCREEN PANEL BOTTOM RAIL	ALUMINUM	ANDERSEN
11		SCREEN PANEL TOP RAIL	ALUMINUM	ANDERSEN
12A		STAT. INTERLOCK	ALUMINUM	ANDERSEN
12B		OP. INTERLOCK	ALUMINUM	ANDERSEN
13		SCREEN STILE	ALUMINUM	ANDERSEN
14		STATIONARY BOTTOM RAIL FILLER	ALUMINUM	ANDERSEN
15		STATIONARY UNIT BRACKET	ALUMINUM	ANDERSEN
16		HEAD JAMB BUMPER	PVC	ANDERSEN
17		USED		ANDERSEN
18		SCREEN & HANDLE	ALUMINUM	ANDERSEN
19		DOOR HANDLE	-	ANDERSEN
20		ASTRAGAL	FIBERGLASS	ANDERSEN

NOTE: ALL WOOD TO BE PONDEROSA PINE OR EQUAL (MIN. SG = 0.40)




TITLE:
400 SERIES GLIDING
PATIO DOOR
(NON-HVHZ)(NON-IMPACT)
COMPONENTS & BILL OF MATERIALS

PREPARED BY:
BUILDING DROPS, INC.
398 E. DANIA BEACH BLVD., STE. 338
DANIA BEACH, FL 33004
PH: (954)395-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

REMARKS	BY	DATE
5TH FBC CODE CHANGE	SM	4.10.15
6TH FBC CODE CHANGE	HR	8.9.17
7TH FBC CODE CHANGE	SR	3.18.20
8TH FBC CODE CHANGE	SH	5.24.23

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:
FL14429

DATE: **08.09.17**


DWG. BY: **HR** CHK. BY: **HFN**

SCALE: **NTS**


DWG. #: **AWD117**

SHEET:
6
OF 10


14 STATIONARY BOTTOM RAIL FILLER
PVC




20 ASTRAGAL
FIBERGLASS




15 STATIONARY UNIT BRACKET
ALUMINUM




16 HEAD JAMB BUMPER
PVC



18 SCREEN & HANDLE
PVC



- NOTE:
1. ALL GLAZING MEETS SAFETY GLAZING REQUIREMENTS AS PER ASTM E1330 AND CH 24 OF THE FBC.
 2. SETTING BLOCK DUROMETER HARDNESS OF 70-90 (SHORE A) AS REFERENCED IN CHAPTER 24.
 3. SETTING BLOCKS TO BE LOCATED AT 1/4 SPAN LENGTH FOR GLASS WIDER THAN 36" AS PER CHAPTER 24.
 4. D.L.O. MAY NOT EXCEED MAX DIMENSIONS SHOWN IN ELEVATIONS.



GLAZING DETAIL 1




TITLE: 400 SERIES GLIDING
PATIO DOOR
(NON-HVHZ)(NON-IMPACT)
COMPONENTS & GLAZING DETAIL

PREPARED BY:
BUILDING DROPS, INC.
398 E. DANIA BEACH BLVD., STE. 338
DANIA BEACH, FL 33004
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

BD
BUILDING DROPS

REMARKS	BY	DATE
5TH FBC CODE CHANGE	SM	4.10.15
6TH FBC CODE CHANGE	HR	8.9.17
7TH FBC CODE CHANGE	SR	3.18.20
8TH FBC CODE CHANGE	SH	5.24.23

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:

FL14429

DATE: 08.09.17

DWG. BY: HR

CHK. BY: HFN

SCALE: NTS

DWG. #: AWD117

SHEET:


7

OF 10


Maximum design pressure capacity chart (psf):									
L - Mull Length (in)	W - Tributary Width (in)								
	18.0	21.0	24.0	27.0	30.0	33.0	36.0	42.0	48.0
24.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0
30.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0	150.0
36.0	150.0	150.0	150.0	149.2	143.9	140.8	139.9	139.9	139.9
42.0	150.0	137.0	125.9	117.8	111.9	107.7	104.9	102.8	102.8
48.0	129.1	115.1	104.9	97.3	91.5	87.2	83.9	79.9	78.7
54.0	111.9	99.2	89.9	82.9	77.5	73.2	69.9	65.4	62.9
60.0	98.7	87.2	78.7	72.2	67.1	63.1	59.9	55.3	52.5
66.0	88.3	77.8	69.9	63.9	59.2	55.5	52.5	48.0	45.0
72.0	79.9	70.2	62.9	57.4	53.0	49.5	46.6	42.3	39.3
78.0	73.0	63.9	57.2	52.0	48.0	44.7	42.0	37.9	35.0
84.0	67.1	58.7	52.5	47.6	43.8	40.7	38.1	34.3	31.5
90.0	62.2	54.3	48.4	43.9	40.3	37.4	35.0	31.3	28.6
96.0	57.9	50.5	45.0	40.7	37.3	34.5	32.3	28.8	26.2

NOTE:

- 1) MULLION CHART APPLIES TO MULLION ASSEMBLIES, SEE TYP. DETAIL I/8, WHEN USED TO MULL DOORS IN CONFIGURATIONS SHOWN IN TYP. ELEVATION A AT RIGHT.
- 2) DESIGN PRESSURE VALUES ARE POSITIVE AND NEGATIVE IN PSF.
- 3) MAXIMUM DEFLECTION HAS BEEN LIMITED TO L/175.
- 4) DESIGN PRESSURE OF ASSEMBLY IS LIMITED TO THE LESSER DESIGN PRESSURE OF THE JAMB-TO-JAMB WOOD MULLION OR THE INDIVIDUAL DOOR UNIT OF INSTALLATION.
- 5) MULLION CHART ABOVE APPLIES TO MULLED ASSEMBLIES CONSISTING OF 400 SERIES FRENCHWOOD GLIDING DOOR UNITS AND FRENCHWOOD STAT UNITS.
- 6) ADJACENT DOORS SHALL BE FASTENED TO THE ROUGH OPENING WITH ADDITIONAL ANCHORS IN ACCORDANCE WITH DETAILS L/10 & M/10, SHEET 10.



ELEVATION A
TRIBUTARY WIDTH = $W = (A+B)/2$



I
8 **HORIZONTAL SECTION**
FWGD-FWG STAT



100 FOURTH AVE NORTH
BAYPORT, MN 55003-1096
PH: (651) 264-5150 FX: (651) 264-5485

TITLE: 400 SERIES GLIDING
PATIO DOOR
(NON-HVHZ)(NON-IMPACT)

SIDELITE MULL TABLE (ONE-WAY)


PREPARED BY:

BUILDING DROPS, INC.
398 E. DANIA BEACH BLVD., STE. 338
DANIA BEACH, FL 33004
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
5TH FBC CODE CHANGE	SM	4.10.15
6TH FBC CODE CHANGE	HR	8.9.17
7TH FBC CODE CHANGE	SR	3.18.20
8TH FBC CODE CHANGE	SH	5.24.23

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT




FL #:	FL14429
DATE:	08.09.17
DWG. BY:	HR
CHK. BY:	HFN
SCALE:	NTS
DWG. #:	AWD117
SHEET:	8


s:\projects\andersen windows\cc-23-0347 - fbc 2023 code change (8th edition)\dwgs\fin4429\awd117.dwg 6/16/2023 12:01 PM

Maximum design pressure capacity chart (psf):									
L - Mull Length (in)	W - Tributary Width (in)								
	24.0	30.0	36.0	42.0	48.0	54.0	60.0	66.0	72.0
24.0	150.0	150.0	150.0	150.0	150.0	139.9	125.9	114.4	104.9
30.0	150.0	150.0	150.0	143.9	125.9	111.9	100.7	91.5	83.9
36.0	150.0	150.0	139.9	119.9	104.9	93.2	83.9	76.3	69.9
42.0	150.0	143.9	119.9	102.8	89.9	79.9	71.9	65.4	59.9
48.0	150.0	125.9	104.9	89.9	78.7	69.9	62.9	57.2	52.5
54.0	139.9	111.9	93.2	79.9	69.9	62.2	55.9	50.9	46.6
60.0	125.9	100.7	83.9	71.9	62.9	55.9	50.4	45.8	42.0
66.0	111.4	89.1	74.3	63.6	55.7	49.5	44.6	40.5	37.1
72.0	93.6	74.9	62.4	53.5	46.8	41.6	37.4	34.0	31.2
78.0	79.7	63.8	53.2	45.6	39.9	35.4	31.9	29.0	26.6
84.0	68.8	55.0	45.8	39.3	34.4	30.6	27.5	25.0	22.9
90.0	59.9	47.9	39.9	34.2	29.9	26.6	24.0	21.8	20.0
96.0	52.6	42.1	35.1	30.1	26.3	23.4	21.1	19.1	17.5
102.0	46.6	37.3	31.1	26.6	23.3	20.7	18.7	17.0	15.5
108.0	41.6	33.3	27.7	23.8	20.8	18.5	16.6	15.1	-
114.0	37.3	29.9	24.9	21.3	18.7	16.6	-	-	-
120.0	33.7	27.0	22.5	19.3	16.8	-	-	-	-
126.0	30.6	24.4	20.4	17.5	15.3	-	-	-	-
132.0	27.8	22.3	18.6	15.9	-	-	-	-	-
138.0	24.5	19.6	16.3	-	-	-	-	-	-
144.0	21.5	17.2	-	-	-	-	-	-	-

- NOTE:
- 1) MULLION CHART APPLIES TO MULLION ASSEMBLIES, SEE TYP. DETAIL J/9, WHEN USED TO MULL DOORS IN CONFIGURATIONS SHOWN IN TYP ELEVATION B AT RIGHT.
 - 2) DESIGN PRESSURE VALUES ARE POSITIVE AND NEGATIVE IN PSF.
 - 3) MAXIMUM DEFLECTION HAS BEEN LIMITED TO L/175.
 - 4) DESIGN PRESSURE OF ASSEMBLY IS LIMITED TO THE LESSER DESIGN PRESSURE OF THE JAMB-TO-JAMB WOOD MULLION OR THE INDIVIDUAL DOOR UNIT OF INSTALLATION.
 - 5) MULLION CHART ABOVE APPLIES TO MULLED ASSEMBLIES CONSISTING OF 400 SERIES FRENCHWOOD GLIDING DOOR UNITS AND ELLIPTICAL (ET) TRANSOM UNITS.
 - 6) ADJACENT DOORS SHALL BE FASTENED TO THE ROUGH OPENING WITH ADDITIONAL ANCHORS IN ACCORDANCE WITH DETAILS K/10 SHEET 10.



ELEVATION B
TRIBUTARY WIDTH = W = (A+B)/2



J
9
VERTICAL SECTION
ET TRANSOM - FWGD



100 FOURTH AVE NORTH
BAYPORT, MN 55003-1096
PH: (651) 264-5150 FX: (651) 264-5485


TITLE: 400 SERIES GLIDING
PATIO DOOR
(NON-HVHZ)(NON-IMPACT)
TRANSOM MULL TABLE (TWO-WAY)

PREPARED BY:
BUILDING DROPS, INC.
398 E. DANIA BEACH BLVD., STE. 338
DANIA BEACH, FL 33004
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com




REMARKS	BY	DATE
5TH FBC CODE CHANGE	SM	4.10.15
6TH FBC CODE CHANGE	HR	8.9.17
7TH FBC CODE CHANGE	SR	3.18.20
8TH FBC CODE CHANGE	SH	5.24.23

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT




FL #:	FL14429
DATE:	08.09.17
DWG. BY:	CHK. BY:
HR	HFN
SCALE:	NTS
DWG. #:	AWD117
SHEET:	9

s:\projects\andersen windows\cc-23-0347 - fbc 2023 code change (8th edition)\dwgs\fin4429\awd117.dwg 6/16/2023 12:01 PM




EXTERIOR VIEW

MULLION ANCHOR DETAIL - JAMB
THROUGH FRAME - TYP.



EXTERIOR VIEW

MULLION ANCHOR DETAIL - HEAD
THROUGH FRAME - TYP.



EXTERIOR VIEW

MULLION ANCHOR DETAIL - SILL
THROUGH FRAME - TYP.



ANDERSEN
WINDOWS & DOORS

100 FOURTH AVE NORTH
BAYPORT, MN 55003-1096
PH: (651) 264-5150 FX: (651) 264-5485

TITLE: 400 SERIES GLIDING
PATIO DOOR
(NON-HVHZ)(NON-IMPACT)

MULLION DETAILS


PREPARED BY:

BUILDING DROPS, INC.
398 E. DANIA BEACH BLVD., STE. 338
DANIA BEACH, FL 33004
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
5TH FBC CODE CHANGE	SM	4.10.15
6TH FBC CODE CHANGE	HR	8.9.17
7TH FBC CODE CHANGE	SR	3.18.20
8TH FBC CODE CHANGE	SH	5.24.23

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #: **FL14429**

DATE: **08.09.17**

DWG. BY: **HR** CHK. BY: **HFN**

SCALE: **NTS**

DWG. #: **AWD117**

SHEET: **10**
OF 10