CROFT, LLC

SERIES 9100 WOODBUCK MULLION AND SERIES 9100 HEAVY-DUTY MULLION (HORIZONTAL) (WZ3)(IMPACT)

SHEET


2

3


SERIES 9100 MULL-HEAVY DUTY T-MULL DP CHART & DETAILS

NOTES:


- 1. THE PRODUCT SHOWN HEREIN IS DESIGNED AND MANUFACTURED TO COMPLY WITH THE 7TH EDITION FBC, SECTION 1709.8.
- MULLION INSTALLATION DETAILS APPLY TO EXTRUDED MULLIONS WITH EXTRUDED ALUMINUM ANCHOR CLIP WHEN USED TO MULL WINDOWS SIDE BY SIDE
- 3. APPROVED IMPACT PROTECTIVE SYSTEM IS NOT REQUIRED ON THESE PRODUCTS IN WIND BORNE DEBRIS REGIONS ZONE 3 OR LESS SUCH THAT ADJOINING WINDOWS ARE IMPACT RATED.
- 4. APPROVED IMPACT PROTECTIVE SYSTEM <u>IS REQUIRED</u> ON THESE PRODUCTS IN WIND BORNE DEBRIS REGION ZONE 4.
- 5. USE TWO (2) #10 WOOD SCREWS, PER CLIP, OF SUFFICIENT LENGTH TO ACHIEVE MINIMUM EMBEDMENT OF 1 1/2" INTO WOOD FRAMING. (SEE INSTALLATION DETAILS ON SHEET 2).
- 6. USE TWO (2) $\frac{3}{16}$ " ITW TAPCONS, PER CLIP, OF SUFFICIENT LENGTH TO ACHIEVE MINIMUM EMBEDMENT OF $1\frac{3}{4}$ " INTO CONCRETE OR 1" WHEN INTO HOLLOW BLOCK CMU. (SEE INSTALLATION DETAILS ON SHEET 2).
- USE ONE (1) ¼" ITW TAPCON, PER CLIP, OF SUFFICIENT LENGTH TO ACHIEVE MINIMUM EMBEDMENT OF 1¾" WHEN ANCHORED INTO CONCRETE.
- USE TWO (2) #10-16 SELF-DRILLING SCREWS, PER CLIP, OF SUFFICIENT LENGTH TO ACHIEVE A
 MINIMUM 3 THREADS PENETRATION BEYOND STEEL SUBSTRATE. (SEE INSTALLATION DETAILS
 ON SHEET 2).
- 2X WOOD BUCKS AND STEEL STUDS TO BE DESIGNED AND ANCHORED TO PROPERLY TRANSFER ALL LOADS TO STRUCTURE AND IS THE RESPONSIBILITY OF THE ARCHITECT OR ENGINEER OF RECORD.
- 10. SEE CHARTS & NOTES ON SHEETS 3-5 FOR DESIGN PRESSURE RATINGS.
- 11. THIS MULLION IS ONLY VALID WHEN USED IN CONJUNCTION WITH <u>ALL APPLICABLE</u> CROFT, LLC PRODUCTS.
- 12. ALL WINDOWS USED WITH THIS MULLION SHALL BE QUALIFIED UNDER SEPARATE APPROVAL. THE LESSER DESIGN PRESSURE RATING OF THE WINDOW OR THE MULLION OF INSTALLATION SHALL GOVERN THE OVERALL DESIGN PRESSURE OF THE ASSEMBLY.
- 13. MULLION MATERIAL: 6063-T5 ALUMINUM.
- 14. CLIP MATERIAL: 6063-T5 ALUMINUM.
- 15. INSTALLATION ANCHOR CAPACITIES FOR PRODUCTS
 HEREIN ARE BASED ON SUBSTRATE MATERIALS WITH THE
 FOLLOWING PROPERTIES:
 - A. WOOD MINIMUM SPECIFIC GRAVITY OF 0.55.
 - B. CONCRETE MINIMUM COMPRESSIVE STRENGTH OF 3000 PSI.
 - C. CMU SHALL CONFORM TO MINIMUM REQUIREMENTS OF ASTM C90
 - D. STEEL MINIMUM YIELD STRENGTH OF 33 KSI. MINIMUM 18 GA. WALL THICKNESS.



HORIZONTAL MULLION FOR STACKED WINDOWS




T-MULL CONFIGURATION



P.O. BOX 826

MCCOMB, MS 39649



SERIES 9100 WOODBUCK MULL DESIGN PRESSURE CHART


Maximum design pressure capacity chart Series 9100 Woodbuck Horizontal Mullion - Stacked Windows

Design pressures are limited either by mullion or anchor screw or anchor clip capacity.


Heig	ght (in)	Unit width (in)												
Window	Transom	24.0	27.0	30.0	33.0	36.0	39.0	42.0	45.0	48.0				
24.0	12.0	150.0	150.0	150.0	150.0	150.0	150.0	143.0	130.7	114.4				
30.0	15.0	150.0	150.0	150.0	150.0	150.0	138.1	124.1	109.9	95.1				
36.0	18.0	150.0	150.0	150.0	150.0	145.2	127.1	113.0	96.9	83.2				
42.0	21.0	150.0	150.0	150.0	150.0	139.2	121.2	106.7	89.2	75.8				
48.0	24.0	150.0	150.0	150.0	150.0	134.5	116.9	102.1	85.0	71.5				
54.0	27.0	150.0	150.0	150.0	150.0	131.2	113.7	98.4	81.7	68.8				
60.0	30.0	150.0	150.0	150.0	150.0	128.9	111.2	95.4	79.1	66.5				
66.0	33.0	150.0	150.0	150.0	150.0	127.5	109.6	93.1	77.0	64.6				
72.0	36.0	150.0	150.0	150.0	150.0	127.1	108.6	91.4	75.4	63.1				
78.0	39.0	150.0	150.0	150.0	150.0	127.1	108.3	90.4	74.2	61.9				
84.0	42.0	150.0	150.0	150.0	150.0	127.1	108.3	90.1	73.5	61.0				
90.0	45.0	150.0	150.0	150.0	150.0	127.1	108.3	90.1	73.2	60.5				
96.0	48.0	150.0	150.0	150.0	150.0	127.1	108.3	90.1	73.2	60.4				

NOTES FOR SERIES 9100 WOODBUCK MULLION FOR STACK WINDOW AND MULLION CLIP INSTALLATIONS

- 1. THE DESIGN PRESSURES IN THIS CHART ARE FOR THE MULLIONS LISTED ABOVE WHEN USED WITH THE CLIP LISTED ABOVE.
- 2. FOR HORIZONTAL MULL CLIPS IN WOOD FRAMING INSTALLATION USE TWO (2) #10 WOOD SCREWS AT EACH MULLION CLIP. ANCHORS MUST BE OF SUFFICIENT LENGTH TO ACHIEVE A 1 1/2" MINIMUM EMBEDMENT INTO FRAMING. SEE SHEET 2 FOR DETAILS.
- 3. FOR HORIZONTAL MULL CLIPS IN STEEL FRAME INSTALLATION, USE (2) TWO #10-16 SELF-DRILLING SCREWS AT EACH ANCHOR CLIP WITH SUFFICIENT LENGTH TO ACHIEVE A MINIMUM 3 THREAD PENETRATION BEYOND STEEL SUBSTRATE. SEE SHEET 2 FOR DETAILS.
- FOR HORIZONTAL MULL CLIPS IN CONCRETE OR CMU INSTALLATION USE TWO (2) 3/16" ITW TAPCONS AT EACH MULLION CLIP. ANCHORS MUST BE OF SUFFICIENT LENGTH TO ACHIEVE A 1" MINIMUM EMBEDMENT INTO CMU (HOLLOW BLOCK) OR 1 3/4" EMBEDMENT INTO CONCRETE. SEE SHEET 2 FOR DETAILS. FOR ALTERNATE INSTALLATION TO CONCRETE, SEE NOTE 5 BELOW.
- 5. FOR HORIZONTAL MULL CLIPS IN CONCRETE INSTALLATION USE ONE (1) 1/4" ITW TAPCON AT EACH MULLION CLIP. ANCHORS MUST BE OF SUFFICIENT LENGTH TO ACHIEVE A 13/4" EMBEDMENT INTO CONCRETE. SEE SHEET 2 FOR DETAILS.
- CHART APPLIES ONLY TO SERIES 9100 WOODBUCK MULLION AS SPECIFIED ABOVE WHEN USED TO MULL WINDOWS STACKED ONE ABOVE THE OTHER.
- 7. READ WINDOW HEIGHT AND MULL SPAN IN INCHES. DESIGN PRESSURE VALUES ON THIS CHART ARE POSITIVE AND NEGATIVE POUNDS PER SQUARE FOOT (PSF).
- DESIGN PRESSURE VALUES APPLY TO MULLION WHERE TWO OR MORE WINDOWS ARE LISTED IN A SINGLE OPENING. LESSER DESIGN PRESSURE OF INDIVIDUAL WINDOW OR MULLION OF INSTALLATION SHALL GOVERN.
- 9. REFER TO EVALUATION REPORT# 7647 FOR MORE MULLION SPECIFICATIONS.



SERIES 9100 WOODBUCK MULL DETAIL



SERIES 9000 MULLION CLIP DETAIL

FOR USE WITH ALL SERIES 9000 MULLIONS




SERIES 9100 HORIZONTAL MULLIONS (WZ3)(IMPACT) SERIES 9100 WOODBUCK I DP CHART & DETAILS

DBY:
BUILDING DROPS, I

REMARKS BY DATE MTJ 6/13 MULLS & CLIPS REV. FBC 2014 UPDATE FBC 2017 UPDATE 6/17 FBC 2020 UPDATE

SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIA FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSE



FL15527

DATE: 04.18.12 DWG. BY: CHK. BY:

MSS

NTS SCALE:

CRF012 DWG. #:

SHEET



OF 5

HFN

SERIES 9100 MULLION-HEAVY DUTY DESIGN PRESSURE CHARTS


Maximum design pressure capacity chart Series 9100 Horizontal Mullion - Heavy Duty - Stacked Windows

Design pressures are limited either by mullion or anchor screw or anchor clip capacity.

Heig	Unit width (in)											
Window	Transom	24.0	27.0	30.0	33.0	36.0	39.0	42.0	45.0	48.0		
24.0	12.0	150.0	150.0	150.0	150.0	150.0	146.6	124.6	107.3	93.5		
30.0	15.0	150.0	150.0	150.0	150.0	150.0	124.6	105.0	89.7	77.7		
36.0	18.0	150.0	150.0	150.0	150.0	138.5	112.5	93.5	79.1	68.0		
42.0	21.0	150.0	150.0	150.0	150.0	131.6	106.3	87.2	72.8	61.9		
48.0	24.0	150.0	150.0	150.0	150.0	126.2	101.7	83.4	69.4	58.4		
54.0	27.0	150.0	150.0	150.0	150.0	122.1	98.2	80.4	66.8	56.2		
60.0	30.0	150.0	150.0	150.0	150.0	119.2	95.4	77.9	64.6	54.3		
66.0	33.0	150.0	150.0	150.0	150.0	117.4	93.5	76.0	62.9	52.8		
72.0	36.0	150.0	150.0	150.0	150.0	116.8	92.3	74.7	61.5	51.5		
78.0	39.0	150.0	150.0	150.0	150.0	116.8	91.9	73.9	60.6	50.5		
84.0	42.0	150.0	150.0	150.0	150.0	116.8	91.9	73.6	60.0	49.9		
90.0	45.0	150.0	150.0	150.0	150.0	116.8	91.9	73.6	59.8	49.4		
96.0	48.0	150.0	150.0	150.0	150.0	116.8	91.9	73.6	59.8	49.3		



- 1. THE DESIGN PRESSURES IN THIS CHART ARE FOR THE MULLIONS LISTED ABOVE WHEN USED WITH THE CLIP LISTED ABOVE.
- 2. FOR HORIZONTAL MULL CLIPS IN WOOD FRAMING INSTALLATION USE TWO (2) #10 WOOD SCREWS AT EACH MULLION CLIP. ANCHORS MUST BE OF SUFFICIENT LENGTH TO ACHIEVE A 1 1/2" MINIMUM EMBEDMENT INTO FRAMING. SEE SHEET 2 FOR DETAILS.
- 3. FOR HORIZONTAL MULL CLIPS IN STEEL FRAME INSTALLATION, USE (2) TWO #10-16 SELF-DRILLING SCREWS AT EACH ANCHOR CLIP WITH SUFFICIENT LENGTH TO ACHIEVE A MINIMUM 3 THREAD PENETRATION BEYOND STEEL SUBSTRATE. SEE SHEET 2 FOR DETAILS.
- 4. FOR HORIZONTAL MULL CLIPS IN CONCRETE OR CMU INSTALLATION USE TWO (2) 3/16" ITW TAPCONS AT EACH MULLION CLIP. ANCHORS MUST BE OF SUFFICIENT LENGTH TO ACHIEVE A 1" MINIMUM EMBEDMENT INTO CMU (HOLLOW BLOCK) OR 1 3/4" EMBEDMENT INTO CONCRETE. SEE SHEET 2 FOR DETAILS. FOR ALTERNATE INSTALLATION TO CONCRETE, SEE NOTE 5 BELOW.
- 5. FOR HORIZONTAL MULL CLIPS IN CONCRETE INSTALLATION USE ONE (1) 1/4" ITW TAPCON AT EACH MULLION CLIP. ANCHORS MUST BE OF SUFFICIENT LENGTH TO ACHIEVE A 13/4" EMBEDMENT INTO CONCRETE. SEE SHEET 2 FOR DETAILS.
- 6. CHART APPLIES ONLY TO SERIES 9100 HEAVY DUTY MULLION AS SPECIFIED ABOVE WHEN USED TO MULL WINDOWS STACKED ONE ABOVE THE OTHER.
- 7. READ WINDOW HEIGHT AND MULL SPAN IN INCHES. DESIGN PRESSURE VALUES ON THIS CHART ARE POSITIVE AND NEGATIVE POUNDS PER SQUARE FOOT (PSF).
- 8. DESIGN PRESSURE VALUES APPLY TO MULLION WHERE TWO OR MORE WINDOWS ARE LISTED IN A SINGLE OPENING. LESSER DESIGN PRESSURE OF INDIVIDUAL WINDOW OR MULLION OF INSTALLATION SHALL GOVERN.
- 9. REFER TO EVALUATION REPORT# 7647 FOR MORE MULLION SPECIFICATIONS.



SERIES 9100 MULLION-HEAVY DUTY DETAIL




P.O. BOX 826 MCCOMB, MS 39649 PH.: 601-684-6121 FX: 601-783-3188

(WZ3)(IMPACT)
SERIES 9100 MULLION-HEA'
DP CHART & DETAIL SERIES 9100 HORIZONTAL MULL

DBY:
BUILDING DROPS, I

REMARKS BY DATE MULLS & CLIPS REV. MTJ 6/13 FBC 2014 UPDATE FBC 2017 UPDATE 6/17 FBC 2020 UPDATE

SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIAT FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSE



FL15527

DATE: 04.18.12 CHK. BY:

DWG. BY: MSS HFN

SCALE:

CRF012 DWG. #:

SHEET



NTS

OF 5

SERIES 9100 MULLION-HEAVY DUTY DESIGN PRESSURE CHARTS

Maximum design pressure capacity chart (psf) Series 9100 Horizontal Mullion - Heavy Duty - T-Mullion Configuration


Design pressures are limited either by mullion or anchor screw or anchor clip capacity.

|--|

9	` '								` '									
Window	Transom	24.0	27.0	30.0	33.0	36.0	39.0	42.0	45.0	48.0	54.0	60.0	66.0	72.0	78.0	84.0	90.0	96.0
24.0	12.0	150.0	150.0	150.0	150.0	150.0	150.0	142.4	130.6	120.4	104.0	91.5	80.2	67.2	57.1	49.2	42.8	37.5
30.0	15.0	150.0	150.0	150.0	150.0	145.8	132.0	120.4	110.5	101.9	88.0	77.0	64.7	54.2	46.0	39.6	34.4	30.2
36.0	18.0	150.0	150.0	150.0	141.7	127.1	115.0	104.9	96.2	88.8	76.7	66.0	54.3	45.5	38.6	33.2	28.8	25.3
42.0	21.0	150.0	150.0	143.0	126.5	113.3	102.4	93.4	85.7	79.0	68.3	57.1	46.9	39.2	33.3	28.6	24.9	21.8
48.0	24.0	150.0	149.8	130.2	115.0	102.8	92.8	84.5	77.5	71.5	61.7	50.4	41.4	34.6	29.3	25.2	21.9	19.2
54.0	27.0	150.0	139.0	120.4	106.0	94.6	85.3	77.5	71.0	65.5	56.3	45.2	37.1	31.0	26.3	22.5	19.6	17.1
60.0	30.0	150.0	130.6	112.6	98.8	88.0	79.2	71.9	65.8	60.6	51.2	41.1	33.7	28.1	23.8	20.4	17.7	15.5
66.0	33.0	148.2	124.0	106.4	93.1	82.6	74.2	67.3	61.5	56.6	47.0	37.7	30.9	25.7	21.8	18.7	16.2	14.2
72.0	36.0	143.0	118.7	101.4	88.3	78.2	70.1	63.4	57.9	53.2	43.6	34.9	28.5	23.8	20.1	17.2	14.9	13.1
78.0	39.0	139.2	114.6	97.3	84.5	74.5	66.6	60.2	54.8	50.3	40.6	32.5	26.5	22.1	18.7	16.0	13.9	12.1
84.0	42.0	136.6	111.5	94.1	81.3	71.5	63.7	57.5	52.3	47.9	38.1	30.4	24.9	20.7	17.5	15.0	13.0	11.3
90.0	45.0	135.0	109.2	91.5	78.7	68.9	61.3	55.1	50.0	45.8	36.0	28.7	23.4	19.5	16.4	14.1	12.2	10.6
96.0	48.0	134.5	107.6	89.5	76.5	66.8	59.2	53.1	48.1	44.0	34.1	27.1	22.1	18.4	15.5	13.3	11.5	10.0

NOTES FOR SERIES 9100 MULLION-HEAVY DUTY FOR T-MULLION CONFIGURATIONS AND MULLION CLIP INSTALLATIONS

- 1. THE DESIGN PRESSURES IN THIS CHART ARE FOR THE MULLIONS LISTED ABOVE WHEN USED WITH THE CLIP LISTED ABOVE.
- 2. FOR HORIZONTAL MULL CLIPS IN WOOD FRAMING INSTALLATION USE TWO (2) #10 WOOD SCREWS AT EACH MULLION CLIP. ANCHORS MUST BE OF SUFFICIENT LENGTH TO ACHIEVE A 1 1/2" MINIMUM EMBEDMENT INTO FRAMING. SEE SHEET 2 FOR DETAILS.
- FOR HORIZONTAL MULL CLIPS IN STEEL FRAME INSTALLATION, USE (2) TWO #10-16 SELF-DRILLING SCREWS AT EACH ANCHOR CLIP WITH SUFFICIENT LENGTH TO ACHIEVE A MINIMUM 3 THREAD PENETRATION BEYOND STEEL SUBSTRATE. SEE SHEET 2 FOR DETAILS.
- 4. FOR HORIZONTAL MULL CLIPS IN CONCRETE OR CMU INSTALLATION USE TWO (2) 3/16" ITW TAPCONS AT EACH MULLION CLIP. ANCHORS MUST BE OF SUFFICIENT LENGTH TO ACHIEVE A 1" MINIMUM EMBEDMENT INTO CMU (HOLLOW BLOCK) OR 1 3/4" EMBEDMENT INTO CONCRETE. SEE SHEET 2 FOR DETAILS. FOR ALTERNATE INSTALLATION TO CONCRETE, SEE NOTE 5 BELOW.
- FOR HORIZONTAL MULL CLIPS IN CONCRETE INSTALLATION USE ONE (1) 1/4" ITW TAPCON AT EACH MULLION CLIP, ANCHORS MUST BE OF SUFFICIENT LENGTH TO ACHIEVE A 13/4" EMBEDMENT INTO CONCRETE. SEE SHEET 2 FOR DETAILS.
- CHART APPLIES ONLY TO SERIES 9100 MULLION-HEAVY DUTY AS SPECIFIED ABOVE WHEN USED TO MULL TRANSOM WINDOWS STACKED ABOVE TWIN WINDOWS IN T-MULLION CONFIGURATION.
- 7. READ WINDOW HEIGHT AND MULL SPAN IN INCHES. DESIGN PRESSURE VALUES ON THIS CHART ARE POSITIVE AND NEGATIVE POUNDS PER SQUARE FOOT (PSF).
- DESIGN PRESSURE VALUES APPLY TO MULLION WHERE TWO OR MORE WINDOWS ARE LISTED IN A SINGLE OPENING. LESSER DESIGN PRESSURE OF INDIVIDUAL WINDOW OR MULLION OF INSTALLATION SHALL GOVERN.
- 9. REFER TO EVALUATION REPORT# 7647 FOR MORE MULLION SPECIFICATIONS.



T-MULLION H-CLIP DETAIL



P.O. BOX 826 MCCOMB, MS 39649 PH.: 601-684-6121 FX: 601-783-3188

SERIES 9100 HORIZONTAL MULLIONS (WZ3)(IMPACT) SERIES 9100 MULL-HEAVY DP CHART & DETAILS


REMARKS

FBC 2020 UPDATE

BY DATE MULLS & CLIPS REV. MTJ 6/13 FBC 2014 UPDATE FBC 2017 UPDATE HR | 6/17

D BY:
BUILDING DROPS, I

SITE, IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIAT FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSE ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL15527

DATE: 04.18.12 DWG. BY: CHK. BY: MSS HFN

NTS SCALE:

CRF012 DWG. #:

SHEET

OF 5