

INSTALLATION NOTES:

1. ONE (1) INSTALLATION ANCHOR CLIP IS REQUIRED AT EACH ANCHOR LOCATION SHOWN, UNLESS OTHERWISE STATED.
2. INSTALL INDIVIDUAL INSTALLATION ANCHORS WITHIN A TOLERANCE OF ±1/2 INCH OF THE DEPICTED LOCATION IN THE ANCHOR LAYOUT DETAIL (I.E., WITHOUT CONSIDERATION OF TOLERANCES). TOLERANCES ARE NOT CUMULATIVE FROM ONE INSTALLATION ANCHOR TO THE NEXT.
3. THROUGH FRAME/CLIP: SHIM AS REQUIRED AT EACH INSTALLATION ANCHOR WITH LOAD BEARING SHIM(S). NAIL FIN: SHIM AS NEEDED TO ACHIEVE PLUMB AND SQUARE INSTALLATION. MAXIMUM ALLOWABLE SHIM STACK TO BE 1/4 INCH. SHIM WHERE SPACE OF 1/16 INCH OR GREATER OCCURS. SHIM(S) SHALL BE CONSTRUCTED OF HIGH DENSITY PLASTIC OR BETTER.
4. INSTALLATION CLIP: FOR INSTALLATION THROUGH 1X BUCK TO CONCRETE/MASONRY, OR DIRECTLY INTO CONCRETE/MASONRY, USE ONE (1) 3/16 INCH HWH ITW TAPCON PER INSTALLATION CLIP OF SUFFICIENT LENGTH TO ACHIEVE 1 1/4 INCH MINIMUM EMBEDMENT.
5. INSTALLATION CLIP: FOR INSTALLATION INTO 2X BUCK USE TWO (2) #8 WOOD SCREWS OR ONE (1) #10 WOOD SCREW PER INSTALLATION CLIP OF SUFFICIENT LENGTH TO ACHIEVE 1 1/2 INCH MINIMUM EMBEDMENT INTO WOOD SUBSTRATE.
6. INSTALLATION CLIP: FOR INSTALLATION THROUGH METAL STUD USE TWO (2) #10 SELF-TAPPING SCREWS PER INSTALLATION CLIP OF SUFFICIENT LENGTH TO ACHIEVE 3 THREADS MINIMUM PENETRATION BEYOND METAL FRAME SUBSTRATE.
7. THROUGH FRAME: FOR INSTALLATION INTO 2X BUCK USE #10 WOOD SCREWS OF SUFFICIENT LENGTH TO ACHIEVE 1 1/2 INCH MINIMUM EMBEDMENT INTO WOOD SUBSTRATE.
8. THROUGH FRAME: FOR INSTALLATION THROUGH 1X BUCK TO CONCRETE/MASONRY, OR DIRECTLY INTO CONCRETE/MASONRY, USE ONE (1) 3/16 INCH ITW TAPCON OF SUFFICIENT LENGTH TO ACHIEVE 1 1/4 INCH MINIMUM EMBEDMENT.
9. THROUGH FRAME: FOR INSTALLATION INTO METAL SUBSTRATES USE #10 SELF-TAPPING SCREWS OF SUFFICIENT LENGTH TO ACHIEVE 3 THREADS MINIMUM PENETRATION BEYOND METAL FRAME.
10. NAIL FIN: FOR INSTALLATION INTO 2X BUCK USE #8 WOOD SCREWS OF SUFFICIENT LENGTH TO ACHIEVE 1 1/2 INCH MINIMUM EMBEDMENT INTO WOOD SUBSTRATE.
11. NAIL FIN: FOR INSTALLATION INTO METAL SUBSTRATES USE #8 SELF-TAPPING SCREWS OF SUFFICIENT LENGTH TO ACHIEVE 3 THREADS MINIMUM PENETRATION BEYOND METAL FRAME SUBSTRATE.
12. MINIMUM EMBEDMENT AND EDGE DISTANCE EXCLUDE WALL FINISHES, INCLUDING BUT NOT LIMITED TO STUCCO, FOAM, BRICK VENEER, AND SIDING.
13. INSTALLATION ANCHORS AND ASSOCIATED HARDWARE MUST BE MADE OF CORROSION RESISTANT MATERIAL OR HAVE A CORROSION RESISTANT COATING.
14. FOR HOLLOW BLOCK AND GROUT FILLED BLOCK, DO NOT INSTALL INSTALLATION ANCHORS INTO MORTAR JOINTS. EDGE DISTANCE IS MEASURED FROM FREE EDGE OF BLOCK OR EDGE OF MORTAR JOINT INTO FACE SHELL OF BLOCK.
15. INSTALLATION ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH ANCHOR MANUFACTURER'S INSTALLATION INSTRUCTIONS, AND ANCHORS SHALL NOT BE USED IN SUBSTRATES WITH STRENGTHS LESS THAN THE MINIMUM STRENGTH SPECIFIED BY THE ANCHOR MANUFACTURER.
16. INSTALLATION ANCHOR CAPACITIES FOR PRODUCTS HEREIN ARE BASED ON SUBSTRATE MATERIALS WITH THE FOLLOWING PROPERTIES:

A. WOOD - MINIMUM SPECIFIC GRAVITY OF 0.55.

B. CONCRETE -MINIMUM COMPRESSIVE STRENGTH OF 3000 PSI.

C. GROUT-FILLED CMU- UNIT STRENGTH CONFORMS TO ASTM C-90 WITH MINIMUM COMPRESSIVE STRENGTH OF 2000 PSI AND GROUT CONFORMS TO ASTM C 476, MINIMUM GROUT COMPRESSIVE STRENGTH OF 2000 PSI.

D. HOLLOW BLOCK CMU - UNIT STRENGTH CONFORMS TO ASTM C-90 WITH MINIMUM COMPRESSIVE STRENGTH OF 2000 PSI.

E. STEEL - MINIMUM YIELD STRENGTH OF 33 KSI. MINIMUM WALL THICKNESS OF 48 MILS (18 GAUGE).

F. ALUMINUM - MINIMUM WALL THICKNESS OF ⅜". 6063-T5 ALLOY OR BETTER.

ANDERSEN CORPORATION

400 SERIES TILT WASH FIXED WINDOWS

(NON-HVHZ)(NON-IMPACT)

GENERAL NOTES:

1. THE PRODUCT SHOWN HEREIN IS DESIGNED AND MANUFACTURED TO COMPLY WITH THE CURRENT FLORIDA BUILDING CODE (FBC), **EXCLUDING** HVHZ. THE PRODUCT HAS BEEN EVALUATED ACCORDING TO THE FOLLOWING:

• AAMA/WDMA/CSA 101/I.S.2/A440-17
2. ADEQUACY OF THE EXISTING STRUCTURAL CONCRETE/MASONRY, 2X AND METAL STUD FRAMING AS A MAIN WIND FORCE RESISTING SYSTEM CAPABLE OF WITHSTANDING AND TRANSFERRING APPLIED PRODUCT LOADS TO THE FOUNDATION IS THE RESPONSIBILITY OF THE ENGINEER OR ARCHITECT OF RECORD FOR THE PROJECT OF INSTALLATION.
3. 1X AND 2X BUCKS (WHEN USED) SHALL BE DESIGNED AND ANCHORED TO PROPERLY TRANSFER ALL LOADS TO THE STRUCTURE. BUCK DESIGN AND INSTALLATION IS THE RESPONSIBILITY OF THE ENGINEER OR ARCHITECT OF RECORD FOR THE PROJECT OF INSTALLATION.
4. THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.
5. APPROVED IMPACT PROTECTIVE SYSTEM **IS REQUIRED** TO PROTECT THIS PRODUCT IN AREAS REQUIRING IMPACT RESISTANCE.
6. WINDOW FRAME MATERIAL: PONDEROSA PINE (MIN S.G. = 0.45)/VINYL
7. GLASS MEETS THE REQUIREMENTS OF ASTM E1300 GLASS CHARTS. SEE SHEETS 4 FOR GLAZING DETAILS.
8. DESIGNATIONS "X" AND "O" STAND FOR THE FOLLOWING:

X: OPERABLE PANEL

O: FIXED PANEL

TABLE OF CONTENTS	
SHEET	SHEET DESCRIPTION
1	GENERAL & INSTALLATION NOTES
2	ELEVATIONS
3	ANCHOR LAYOUTS & ANCHOR SCHEDULE
4	GLAZING DETAILS
5	DH VERTICAL SECTIONS & HORIZONTAL SECTION
6	DH VERTICAL SECTIONS & HORIZONTAL SECTION
7	TWT VERTICAL SECTIONS & HORIZONTAL SECTION
8	TWT VERTICAL SECTIONS & HORIZONTAL SECTION
9	CTN VERTICAL SECTIONS
10	HORIZONTAL SECTIONS, ONE-WAY WOOD MULL DP TABLE & MULL DETAILS (W/ V-NOTCH GUSSET)
11	TWO-WAY DP STEEL MULL TABLE & MULL DETAILS

DESIGN PRESSURE RATING		
SIZE	MODEL/SERIES	DESIGN PRESSURE
67 ⁵ / ₁₆ " X 76 ⁷ / ₈ "	DOUBLE HUNG PICTURE WINDOW (DHP)	+50.0 / -65.0 PSF
75 ¹ / ₁₆ " X 39 ¹ / ₁₆ "	TILT WASH TRANSOM WINDOW (TWT)	+/- 50.0 PSF
75 ⁵ / ₁₆ " X 40"	CIRCLE TOP NARROLINE WINDOW (CTN)	+/- 50.0 PSF

NOTE: REFER TO SHEET 3 FOR DESIGN PRESSURE & SIZE LIMITATIONS BASED ON INSTALLATION METHOD.



ANDERSEN
WINDOWS & DOORS

100 FOURTH AVE NORTH
BAYPORT, MN 55003-1096

PH: (651) 264-5150 FX: (651) 264-5485

TITLE:

400 SERIES TILT WASH
FIXED WINDOWS
(NON-HVHZ)(NON-IMPACT)

GENERAL & INSTALLATION NOTES

PREPARED BY:


BUILDING DROPS, INC.
1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
7TH FBC CODE CHANGE	SR	3.20.20
8TH FBC CODE CHANGE	SH	5.25.23
DP & GLAZING UPD.	SH	9.26.24
GLAZING UPDATE	SH	2.23.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.

Digitally signed by Hermes F. Norero, P.E.
Reason: I am approving this document
Date: 2026.04.02 14:19:58 -07'00'



FL #:

FL15905

DATE:

08.15.17

DWG. BY:

CL

CHK. BY:

HFN

SCALE:

NTS

DWG. #:


AWD140

SHEET:


1

OF 11


c:\Users\sebastianhereros\building drops, inc\building drops, inc\projects\andersen corporation\fb-26-0227 - fl15905 400 series tilt wash fixed windows - triple ig qualification - awd140.dwg 2/23/2026 10:05 AM





ELEVATION
DOUBLE HUNG PICTURE WINDOW
MAX. DESIGN PRESSURE = +50/-65 PSF
*LIMITED TO +/- 40 PSF AT MAX. SIZE OF 48" X 76-7/8" WHEN INSTALLED THROUGH NAIL FIN



ELEVATION
TILT WASH TRANSOM WINDOW
MAX. DESIGN PRESSURE = +50/-50 PSF



ELEVATION
CIRCLE TOP NARROLINE WINDOW
MAX. DESIGN PRESSURE = +50/-50 PSF



NOTE:
WINDOW WIDTH (W) AND HEIGHT (H) ARE INTERCHANGEABLE FOR ALL SIZES SHOWN HEREIN. NOT TO EXCEED TESTED SQ. FT. AREA AND LONG LEG & SHORT LEG DIMENSIONS, AS SHOWN IN ELEVATIONS.



100 FOURTH AVE NORTH
BAYPORT, MN 55003-1096
PH: (651) 264-5150 FX: (651) 264-5485

TITLE: 400 SERIES TILT WASH
FIXED WINDOWS
(NON-HVHZ)/(NON-IMPACT)
ELEVATIONS


PREPARED BY: BUILDING DROPS, INC.

1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132
PH: (954) 399-8478
FAX: (954) 744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
7TH FBC CODE CHANGE	SR	3.20.20
8TH FBC CODE CHANGE	SH	5.25.23
DP & GLAZING UPD.	SH	9.26.24
GLAZING UPDATE	SH	2.23.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #: FL15905

DATE: 08.15.17

DWG. BY: CL CHK. BY: HFN


SCALE: NTS

DWG. #: AWD140


SHEET:

2


OF 11



ANCHOR LAYOUT
DOUBLE HUNG PICTURE WINDOW



ANCHOR LAYOUT
TILT WASH TRANSOM WINDOW



ANCHOR LAYOUT
CIRCLE TOP NARROLINE WINDOW

PRODUCT TYPE	UNIT MAX. O.A. SIZE	MAX. DESIGN PRESSURE	INSTALLATION METHOD	INSTALLATION SUBSTRATE	INSTALLATION ANCHOR	QTY PER LOCATION	MIN. EMBEDMENT	MIN. EDGE DISTANCE	LONG LEG MAX. O.C. SPACING	SHORT LEG MAX. O.C. SPACING
DOUBLE-HUNG PICTURE WINDOW (DHP)	67-5/16" X 76-7/8"	+50/-65 PSF	THROUGH FRAME	WOOD (MIN. S.G. = 0.55)	#10 WOOD SCREW	1	1 1/2"	3/4"	13"	13-7/8"
				CONCRETE (MIN. F'C = 3000 PSI) CMU (ASTM C90)	3/16" ITW TAPCON	1	1 1/4"	1-3/4"	13"	13-7/8"
				STEEL STUD (MIN. Fy= 33 KSI, 0.048" THICK) 6063-T5 ALUMINUM (MIN. 1/8" THICK)	#10 TEK SCREW	1	3 THREADS PENETRATION	3/4"	13"	13-7/8"
			INSTALLATION CLIP	WOOD (MIN. S.G. = 0.55)	#8 WOOD SCREWS	2	1 1/2"	3/4"	13"	13-7/8"
				CONCRETE (MIN. F'C = 3000 PSI) CMU (ASTM C90)	3/16" ITW TAPCON	1	1 1/4"	1-3/4"	13"	13-7/8"
				STEEL STUD (MIN. Fy= 33 KSI, 0.048" THICK) 6063-T5 ALUMINUM (MIN. 1/8" THICK)	#8 TEK SCREWS	2	3 THREADS PENETRATION	3/4"	13"	13-7/8"
	48" x 76-7/8"	+/- 40 PSF	NAIL FIN	WOOD (MIN. S.G. = 0.55)	#8 WOOD SCREWS	1	1 1/2"	3/4"	7"	7"
				STEEL STUD (MIN. Fy= 33 KSI, 0.048" THICK) 6063-T5 ALUMINUM (MIN. 1/8" THICK)	#8 TEK SCREWS	1	3 THREADS PENETRATION	3/4"	7"	7"
				WOOD (MIN. S.G. = 0.55)	#10 WOOD SCREW	1	1 1/2"	3/4"	16"	13-3/4"
TILT WASH TRANSOM (TWT)	75-1/16" X 39-1/16"	+/- 50 PSF	THROUGH FRAME	CONCRETE (MIN. F'C = 3000 PSI) CMU (ASTM C90)	3/16" ITW TAPCON	1	1 1/4"	1-3/4"	16"	13-3/4"
				STEEL STUD (MIN. Fy= 33 KSI, 0.048" THICK) 6063-T5 ALUMINUM (MIN. 1/8" THICK)	#10 TEK SCREW	1	3 THREADS PENETRATION	3/4"	16"	13-3/4"
				WOOD (MIN. S.G. = 0.55)	#8 WOOD SCREWS	2	1 1/2"	3/4"	16"	13-3/4"
			INSTALLATION CLIP	CONCRETE (MIN. F'C = 3000 PSI) CMU (ASTM C90)	3/16" ITW TAPCON	1	1 1/4"	1-3/4"	16"	13-3/4"
				STEEL STUD (MIN. Fy= 33 KSI, 0.048" THICK) 6063-T5 ALUMINUM (MIN. 1/8" THICK)	#8 TEK SCREWS	2	3 THREADS PENETRATION	3/4"	16"	13-3/4"
				WOOD (MIN. S.G. = 0.55)	#8 WOOD SCREWS	1	1 1/2"	3/4"	7"	7"
			NAIL FIN	STEEL STUD (MIN. Fy= 33 KSI, 0.048" THICK) 6063-T5 ALUMINUM (MIN. 1/8" THICK)	#8 TEK SCREWS	1	3 THREADS PENETRATION	3/4"	7"	7"
				WOOD (MIN. S.G. = 0.55)	#8 WOOD SCREWS	1	1 1/2"	3/4"	7"	7"
				STEEL STUD (MIN. Fy= 33 KSI, 0.048" THICK) 6063-T5 ALUMINUM (MIN. 1/8" THICK)	#8 TEK SCREWS	1	3 THREADS PENETRATION	3/4"	7"	7"
CIRCLE TOP NARROWLINE (CTN)	75-5/16" X 40"	+/- 50 PSF	THROUGH FRAME	WOOD (MIN. S.G. = 0.55)	#10 WOOD SCREW	1	1 1/2"	3/4"	12"	12"
				CONCRETE (MIN. F'C = 3000 PSI) CMU (ASTM C90)	3/16" ITW TAPCON	1	1 1/4"	1-3/4"	12"	12"
				STEEL STUD (MIN. Fy= 33 KSI, 0.048" THICK) 6063-T5 ALUMINUM (MIN. 1/8" THICK)	#10 TEK SCREW	1	3 THREADS PENETRATION	3/4"	12"	12"
			INSTALLATION CLIP	WOOD (MIN. S.G. = 0.55)	#8 WOOD SCREWS	2	1 1/2"	3/4"	12"	12"
				CONCRETE (MIN. F'C = 3000 PSI) CMU (ASTM C90)	3/16" ITW TAPCON	1	1 1/4"	1-3/4"	12"	12"
				STEEL STUD (MIN. Fy= 33 KSI, 0.048" THICK) 6063-T5 ALUMINUM (MIN. 1/8" THICK)	#8 TEK SCREWS	2	3 THREADS PENETRATION	3/4"	12"	12"
			NAIL FIN	WOOD (MIN. S.G. = 0.55)	#8 WOOD SCREWS	1	1 1/2"	3/4"	7"	7"
				STEEL STUD (MIN. Fy= 33 KSI, 0.048" THICK) 6063-T5 ALUMINUM (MIN. 1/8" THICK)	#8 TEK SCREWS	1	3 THREADS PENETRATION	3/4"	7"	7"
				WOOD (MIN. S.G. = 0.55)	#8 WOOD SCREWS	1	1 1/2"	3/4"	7"	7"

ANCHOR SCHEDULE NOTES:

- SIZES & DESIGN PRESSURES HEREIN ARE DEPENDENT UPON INSTALLATION METHOD.
- CORNER DISTANCE (DIST.) FOR ALL INSTALLATION CLIP AND THROUGH FRAME TYPE INSTALLATIONS SHALL BE MAXIMUM 6" FROM FRAME CORNERS.
- CORNER DISTANCE (DIST.) FOR ALL NAIL FIN TYPE INSTALLATIONS SHALL BE 2" FROM FIN CORNER, TYPICAL.



ANDERSEN
WINDOWS & DOORS

100 FOURTH AVE NORTH
BAYPORT, MN 55003-1096

PH: (651) 264-5150 FX: (651) 264-5485

TITLE: 400 SERIES TILT WASH
FIXED WINDOWS
(NON-HVHZ)(NON-IMPACT)

ANCHOR LAYOUTS &
ANCHOR SCHEDULE

PREPARED BY: BUILDING DROPS, INC.

1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132
PH: (954) 399-8478
FAX: (954) 744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
7TH FBC CODE CHANGE	SR	3.20.20
8TH FBC CODE CHANGE	SH	5.25.23
DP & GLAZING UPD.	SH	9.26.24
GLAZING UPDATE	SH	2.23.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #: **FL15905**

DATE: **08.15.17**

DWG. BY: **CL** CHK. BY: **HFN**

SCALE: **NTS**


DWG. #: **AWD140**

SHEET:


3

OF 11


c:\users\sebastianhereros\building drops, inc\building drops landing - common\projects\andersen corporation\fb-26-0227 - fl15905 400 series tilt wash fixed windows - triple ig qualification - awd140.dwg\$awd140.dwg
2/23/2026 10:05 AM




DHP GLAZING DETAIL 1




TWT GLAZING DETAIL 1




CTN GLAZING DETAIL 1



DHP GLAZING DETAIL 2



TWT GLAZING DETAIL 2



CTN GLAZING DETAIL 2

- GLAZING NOTES:
- GLASS TYPE & THICKNESS SHALL COMPLY WITH ASTM E1300 REQUIREMENTS AS WELL AS APPLICABLE SAFETY GLAZING REQUIREMENTS PER THE FBC. TEMPER AND SAFETY GLAZING REQUIREMENTS SHALL BE REVIEWED ON A SITE SPECIFIC BASIS.
 - SETTING BLOCK DUROMETER HARDNESS OF 70-90 (SHORE A) AS REFERENCED IN FBC CHAPTER 24.
 - SETTING BLOCKS TO BE LOCATED AT 1/4 SPAN LENGTH FOR GLASS WIDER THAN 36" AS PER FBC CHAPTER 24.
 - D.L.O. AND DESIGN PRESSURES MAY NOT EXCEED MAX VALUES SHOWN ON SHEET 2.



100 FOURTH AVE NORTH
BAYPORT, MN 55003-1096
PH: (651) 264-5150 FX: (651) 264-5485

TITLE: 400 SERIES TILT WASH
FIXED WINDOWS
(NON-HVHZ)(NON-IMPACT)

GLAZING DETAILS

PREPARED BY: BUILDING DROPS, INC.

1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132
PH: (954) 399-8478
FAX: (954) 744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
7TH FBC CODE CHANGE	SR	3.20.20
8TH FBC CODE CHANGE	SH	5.25.23
DP & GLAZING UPD.	SH	9.26.24
GLAZING UPDATE	SH	2.23.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #: FL15905

DATE: 08.15.17

DWG. BY: CL
CHK. BY: HFN

SCALE: NTS


DWG. #: AWD140

SHEET:


4

OF 11


c:\users\sebastianh\documents\building drops, inc\building drops landing - common\projects\andersen corporation\fb-26-0227 - fl15905 400 series tilt wash fixed windows - triple ig qualification - awd140.dwg 2/23/2026 10:05 AM



A
5 **VERTICAL SECTION**
HEAD - 2X WOOD BUCK
NAIL FIN



B
5 **VERTICAL SECTION**
SILL - 1X WOOD ON CONCRETE/MASONRY
INSTALLATION CLIP



C
5 **HORIZONTAL SECTION**
JAMB - METAL FRAME SUBSTRATE
THROUGH FRAME



ANDERSEN
WINDOWS & DOORS

100 FOURTH AVE NORTH
BAYPORT, MN 55003-1096

PH: (651) 264-5150 FX: (651) 264-5485

TITLE: 400 SERIES TILT WASH
FIXED WINDOWS
(NON-HVHZ)(NON-IMPACT)

DH VERTICAL SECTIONS &
HORIZONTAL SECTION

PREPARED BY:

BUILDING DROPS, INC.

1900 NE MIAMI COURT, STE. 2-15

MIAMI, FL 33132

PH: (954) 399-8478


FAX: (954) 744-4738

WEB: www.buildingdrops.com



REMARKS	BY	DATE
7TH FBC CODE CHANGE	SR	3.20.20
8TH FBC CODE CHANGE	SH	5.25.23
DP & GLAZING UPD.	SH	9.26.24
GLAZING UPDATE	SH	2.23.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #: **FL15905**

DATE: **08.15.17**

DWG. BY: **CL** CHK. BY: **HFN**

SCALE: **NTS**


DWG. #: **AWD140**

SHEET:


5

OF 11


c:\users\sebastianh\documents\building drops, inc\building drops, inc\projects\anderson corporation\fb-26-0227 - fl15905 400 series tilt wash fixed windows - triple ig qualification - awd140.dwg 2/23/2026 10:05 AM



A
6 **VERTICAL SECTION**
HEAD - 2X WOOD BUCK
TRIPLE IG - NAIL FIN



B
6 **VERTICAL SECTION**
SILL - 1X WOOD ON CONCRETE/MASONRY
TRIPLE IG - INSTALLATION CLIP



C
6 **HORIZONTAL SECTION**
JAMB - METAL FRAME SUBSTRATE
TRIPLE IG - THROUGH FRAME




100 FOURTH AVE NORTH
BAYPORT, MN 55003-1096
PH: (651) 264-5150 FX: (651) 264-5485

TITLE: 400 SERIES TILT WASH
FIXED WINDOWS
(NON-HVHZ)(NON-IMPACT)
DH VERTICAL SECTIONS &
HORIZONTAL SECTION

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132
PH: (954) 399-8478
FAX: (954) 744-4738
WEB: www.buildingdrops.com


REMARKS	BY	DATE
7TH FBC CODE CHANGE	SR	3.20.20
8TH FBC CODE CHANGE	SH	5.25.23
DP & GLAZING UPD.	SH	9.26.24
GLAZING UPDATE	SH	2.23.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.




FL #:	FL15905
DATE:	08.15.17
DWG. BY:	CL
CHK. BY:	HFN
SCALE:	NTS
DWG. #:	AWD140
SHEET:	6


c:\Users\sebastianhereros\building drops, inc\building drops, inc\common\projects\andersen corporation\fb-26-0227 - fl15905 400 series tilt wash fixed windows - triple ig qualification - awd140.dwg 2/23/2026 10:05 AM



A
7 **VERTICAL SECTION**
HEAD - METAL FRAME SUBSTRATE
NAIL FIN



B
7 **VERTICAL SECTION**
SILL - 2X WOOD BUCK
THROUGH FRAME



C
7 **HORIZONTAL SECTION**
JAMB - 1X WOOD ON CONCRETE/MASONRY
INSTALLATION CLIP



100 FOURTH AVE NORTH
BAYPORT, MN 55003-1096
PH: (651) 264-5150 FX: (651) 264-5485

TITLE:
400 SERIES TILT WASH
FIXED WINDOWS
(NON-HVHZ)/(NON-IMPACT)


TWT VERTICAL SECTIONS &
HORIZONTAL SECTION

PREPARED BY:
BUILDING DROPS, INC.
1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132
PH: (954) 399-8478
FAX: (954) 744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
7TH FBC CODE CHANGE	SR	3.20.20
8TH FBC CODE CHANGE	SH	5.25.23
DP & GLAZING UPD.	SH	9.26.24
GLAZING UPDATE	SH	2.23.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #:

FL15905

DATE: **08.15.17**

DWG. BY:
CL

CHK. BY:
HFN

SCALE: **NTS**


DWG. #: **AWD140**

SHEET:


7

OF 11


c:\users\sebastianh\documents\building drops, inc\building drops, inc\common\projects\andersen corporation\fb-26-0227 - fl15905 400 series tilt wash fixed windows - triple ig qualification - awd140.dwg 2/23/2026 10:05 AM



A
8 **VERTICAL SECTION**
HEAD - METAL FRAME SUBSTRATE
TRIPLE IG - NAIL FIN



B
8 **VERTICAL SECTION**
SILL - 2X WOOD BUCK
TRIPLE IG - THROUGH FRAME



C
8 **HORIZONTAL SECTION**
JAMB - 1X WOOD ON CONCRETE/MASONRY
TRIPLE IG - INSTALLATION CLIP



100 FOURTH AVE NORTH
BAYPORT, MN 55003-1096
PH: (651) 264-5150 FX: (651) 264-5485

TITLE: 400 SERIES TILT WASH
FIXED WINDOWS
(NON-HVHZ)/(NON-IMPACT)


TWT VERTICAL SECTIONS &
HORIZONTAL SECTION

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132
PH: (954) 399-8478
FAX: (954) 744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
7TH FBC CODE CHANGE	SR	3.20.20
8TH FBC CODE CHANGE	SH	5.25.23
DP & GLAZING UPD.	SH	9.26.24
GLAZING UPDATE	SH	2.23.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #:

FL15905

DATE: **08.15.17**

DWG. BY:
CL

CHK. BY:
HFN


SCALE: **NTS**

DWG. #: **AWD140**


SHEET:

8


OF 11




A
9 **VERTICAL SECTION**
HEAD - 2X WOOD BUCK
INSTALLATION CLIP



C
9 **VERTICAL SECTION**
HEAD/JAMB - METAL STUD
NAIL FIN



B
9 **VERTICAL SECTION**
SILL - 1X WOOD ON CONCRETE/MASONRY
THROUGH FRAME



D
9 **VERTICAL SECTION**
SILL - 2X WOOD BUCK
THROUGH FRAME



100 FOURTH AVE NORTH
BAYPORT, MN 55003-1096
PH: (651) 264-5150 FX: (651) 264-5485

TITLE: 400 SERIES TILT WASH
FIXED WINDOWS
(NON-HVHZ)(NON-IMPACT)

CTN VERTICAL SECTIONS

PREPARED BY: BUILDING DROPS, INC.

1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132
PH: (954) 399-8478
FAX: (954) 744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
7TH FBC CODE CHANGE	SR	3.20.20
8TH FBC CODE CHANGE	SH	5.25.23
DP & GLAZING UPD.	SH	9.26.24
GLAZING UPDATE	SH	2.23.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #: **FL15905**

DATE: **08.15.17**

DWG. BY: **CL** CHK. BY: **HFN**

SCALE: **NTS**

DWG. #: **AWD140**



SHEET:

9


OF 11

MAXIMUM DESIGN PRESSURE CAPACITY CHART (PSF): 400 SERIES TW/TWT/DHP/CTN WOOD MULLION WITH V-NOTCH GUSSET																	
L - Mull Length (in)	W - Tributary Width (in)																
	18.0	21.0	24.0	27.0	30.0	33.0	36.0	42.0	48.0	54.0	60.0	66.0	72.0	78.0	84.0	90.0	96.0
24.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0
30.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0
36.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0
42.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0
48.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0	80.0
54.0	80.0	80.0	80.0	80.0	77.0	71.7	67.6	61.8	58.6	57.6	57.6	57.6	57.6	57.6	57.6	57.6	57.6
60.0	80.0	80.0	73.9	66.7	61.0	56.6	53.0	47.8	44.5	42.6	42.0	42.0	42.0	42.0	42.0	42.0	42.0
66.0	79.1	68.4	60.5	54.4	49.7	45.9	42.8	38.2	35.1	33.1	31.9	31.5	31.5	31.5	31.5	31.5	31.5
72.0	66.2	57.2	50.5	45.3	41.3	38.0	35.3	31.3	28.5	26.6	25.3	24.5	24.3	24.3	24.3	24.3	24.3
78.0	56.2	48.5	42.8	38.3	34.8	32.0	29.7	26.2	23.7	21.9	20.6	19.8	19.3	19.1	19.1	19.1	19.1
84.0	45.3	39.1	34.5	30.9	28.1	25.8	24.0	21.1	19.1	17.6	16.5	15.8	15.3	-	-	-	-
90.0	36.7	31.7	27.9	25.0	22.7	20.8	19.3	16.9	15.2	-	-	-	-	-	-	-	-
96.0	30.2	26.0	22.9	20.5	18.6	17.0	15.8	-	-	-	-	-	-	-	-	-	-


- NOTE:
- MULLION CHART APPLIES TO NARROW WOOD MULLION ASSEMBLIES, SEE TYP. DETAIL A/10, WHEN USED TO MULL WINDOWS IN CONFIGURATIONS SHOWN IN ELEVATIONS A & B.
 - DESIGN PRESSURE VALUES ARE POSITIVE AND NEGATIVE IN PSF.
 - MAXIMUM DEFLECTION HAS BEEN LIMITED TO L/175.
 - DESIGN PRESSURE OF ASSEMBLY IS LIMITED TO THE LESSER DESIGN PRESSURE OF THE MULLION OR THE INDIVIDUAL WINDOW UNIT OF INSTALLATION.
 - MULLION CHART ABOVE APPLIES TO MULLED ASSEMBLIES CONSISTING OF 400 SERIES TW DOUBLE HUNG WINDOWS, CTN, PICTURE, AND TRANSOM WINDOWS. 400 SERIES TW DOUBLE HUNG WINDOWS UNDER SEPARATE APPROVAL.
 - ADJACENT WINDOWS SHALL BE FASTENED TO THE ROUGH OPENING WITH ADDITIONAL ANCHORS IN ACCORDANCE WITH DETAILS B/10 & C/10, SHEET 10.
 - FOR DOUBLE HUNG PICTURE AND DOUBLE HUNG WINDOWS, SILLS SHALL UTILIZE V-NOTCH GUSSET PLATES WITH FASTENERS THROUGH GUSSET & NAIL FIN. THROUGH FRAME & INSTALLATION CLIP INSTALLATIONS AT SILL ARE NOT APPLICABLE WHEN UNITS ARE MULLED.



A
10
HORIZONTAL SECTION
TW-TW OR TWT-DHP-TWT



B
10
FRONT VIEW
MULLION ANCHOR DETAIL
V-NOTCH GUSSET



C
10
FRONT VIEW
MULLION ANCHOR DETAIL
THRU FRAME/INSTALLATION CLIP

ANDERSEN
WINDOWS & DOORS
100 FOURTH AVE NORTH
BAYPORT, MN 55003-1096
PH: (651) 264-5150 FX: (651) 264-5485

TITLE: 400 SERIES TILT WASH FIXED WINDOWS (NON-HVHZ)/(NON-IMPACT) HORIZONTAL SECTIONS, ONE-WAY WOOD MULL DP TABLE & MULL DETAILS (W/ V-NOTCH GUSSET)

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132
PH: (954) 399-8478
FAX: (954) 744-4738
WEB: www.buildingdrops.com

REMARKS	BY	DATE
7TH FBC CODE CHANGE	SR	3.20.20
8TH FBC CODE CHANGE	SH	5.25.23
DP & GLAZING UPD.	SH	9.26.24
GLAZING UPDATE	SH	2.23.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.

HERMES F. NORERO
LICENSE
No. 73778
STATE OF FLORIDA
PROFESSIONAL ENGINEER
HERMES F. NORERO, P.E.
BUILDING DROPS, INC.
1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132
FBPE CERT. OF AUTHORIZATION No. 29578

FL #: **FL15905**

DATE: **08.15.17**

DWG. BY: CL	CHK. BY: HFN
--------------------	---------------------


SCALE: **NTS**

DWG. #: **AWD140**


SHEET: **10** OF 11

MAXIMUM DESIGN PRESSURE CAPACITY CHART (PSF): 400 SERIES TW/TWT/DHP/CTN STEEL MULLION WITH V-NOTCH GUSSET															
L - Mull Length (in)	W - Tributary Width (in)														
	12.0	18.0	24.0	30.0	36.0	42.0	48.0	54.0	60.0	66.0	72.0	78.0	84.0	90.0	96.0
24.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0
30.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0
36.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0
42.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0
48.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0
54.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0
60.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	48.9
66.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	49.8	46.2	43.1	40.4
72.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	49.4	45.3	41.8	38.8	36.2	34.0
78.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	50.0	46.3	42.1	38.6	35.6	33.1	30.9	29.0
84.0	50.0	50.0	50.0	50.0	50.0	50.0	49.9	44.4	39.9	36.3	33.3	30.7	28.5	26.6	25.0
90.0	50.0	50.0	50.0	50.0	50.0	49.7	43.5	38.7	34.8	31.6	29.0	26.8	24.9	23.2	21.7
96.0	50.0	50.0	50.0	50.0	48.0	41.7	37.0	33.3	30.3	27.8	25.5	23.5	21.8	20.4	19.1
102.0	50.0	50.0	50.0	47.2	39.8	34.6	30.7	27.6	25.1	23.0	21.3	19.7	18.4	17.3	16.3
108.0	50.0	50.0	49.0	39.6	33.4	29.0	25.7	23.1	21.0	19.3	17.8	16.6	15.5	-	-
114.0	50.0	50.0	41.5	33.6	28.3	24.5	21.7	19.5	17.8	16.3	15.1	-	-	-	-
120.0	50.0	46.9	35.5	28.7	24.2	21.0	18.5	16.7	15.2	-	-	-	-	-	-
126.0	50.0	40.4	30.6	24.7	20.8	18.0	15.9	-	-	-	-	-	-	-	-
132.0	50.0	35.1	26.6	21.5	18.1	15.6	-	-	-	-	-	-	-	-	-
138.0	45.6	30.7	23.2	18.8	15.8	-	-	-	-	-	-	-	-	-	-
144.0	40.1	27.0	20.4	16.5	-	-	-	-	-	-	-	-	-	-	-


- NOTE:
- MULLION CHART APPLIES TO STEEL MULLION ASSEMBLIES, SEE TYP. DETAIL A/11, WHEN USED TO MULL WINDOWS IN CONFIGURATIONS SHOWN IN ELEVATIONS C & D.
 - DESIGN PRESSURE VALUES ARE POSITIVE AND NEGATIVE IN PSF.
 - MAXIMUM DEFLECTION HAS BEEN LIMITED TO L/175.
 - DESIGN PRESSURE OF ASSEMBLY IS LIMITED TO THE LESSER DESIGN PRESSURE OF THE MULLION OR THE INDIVIDUAL WINDOW UNIT OF INSTALLATION.
 - MULLION CHART ABOVE APPLIES TO MULLED ASSEMBLIES CONSISTING OF 400 SERIES TW DOUBLE HUNG WINDOWS, CTN, PICTURE, AND TRANSOM WINDOWS. 400 SERIES DOUBLE HUGN WINDOWS UNDER SEPARATE APPROVAL.
 - ADJACENT WINDOWS SHALL BE FASTENED TO 2X WOOD BUCKS WITH ADDITIONAL ANCHORS IN ACCORDANCE WITH DETAILS B/11, SHEET 11.



A
11
HORIZONTAL SECTION
TW-TW OR TWT-DHP-TWT



B
11
FRONT VIEW
MULLION ANCHOR DETAIL
V-NOTCH GUSSET




100 FOURTH AVE NORTH
BAYPORT, MN 55003-1096
PH: (651) 264-5150 FX: (651) 264-5485

TITLE:
400 SERIES TILT WASH
FIXED WINDOWS
(NON-HVHZ)/(NON-IMPACT)
TWO-WAY STEEL MULL
DP TABLE & MULL DETAILS

PREPARED BY:
BUILDING DROPS, INC.
1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132
PH: (954) 399-8478
FAX: (954) 744-4738
WEB: www.buildingdrops.com

REMARKS	BY	DATE
7TH FBC CODE CHANGE	SR	3.20.20
8TH FBC CODE CHANGE	SH	5.25.23
DP & GLAZING UPD.	SH	9.26.24
GLAZING UPDATE	SH	2.23.26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #:
FL15905

DATE: **08.15.17**

DWG. BY: **CL**
CHK. BY: **HFN**

SCALE: **NTS**

DWG. #: **AWD140**

SHEET:

11

OF 11