

c:\users\sebastian\hereros\building drops, inc\building drops landing - common\projects\andersen corporation\fb-24-1153 - fbc submittal - fl15922 100 series reinforced mullion - awd246 revision\dwgs\awd246.dwg 1/22/2026 11:51 AM

ANDERSEN CORPORATION

100 SERIES REINFORCED MULLION JOINING

(NON-HVHZ) (NON-IMPACT)

INSTALLATION NOTES:

1. *ONE (1)* INSTALLATION ANCHOR IS REQUIRED AT EACH ANCHOR LOCATION SHOWN, UNLESS OTHERWISE STATED.
2. THE NUMBER OF INSTALLATION ANCHORS DEPICTED IS THE MINIMUM NUMBER OF ANCHORS TO BE USED FOR PRODUCT INSTALLATION.
3. INSTALL INDIVIDUAL INSTALLATION ANCHORS WITHIN A TOLERANCE OF ±1/2 INCH OF THE DEPICTED LOCATION IN THE ANCHOR LAYOUT DETAIL (I.E., WITHOUT CONSIDERATION OF TOLERANCES). TOLERANCES ARE NOT CUMULATIVE FROM ONE INSTALLATION ANCHOR TO THE NEXT.
4. MINIMUM EMBEDMENT AND EDGE DISTANCE EXCLUDE 1X BUCKING, SHEATHING, & WALL FINISHES, INCLUDING BUT NOT LIMITED TO STUCCO, FOAM, BRICK VENEER, AND SIDING.
5. INSTALLATION ANCHORS AND ASSOCIATED HARDWARE MUST BE MADE OF CORROSION RESISTANT MATERIAL OR HAVE A CORROSION RESISTANT COATING.
6. INSTALLATION ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH ANCHOR MANUFACTURER'S INSTALLATION INSTRUCTIONS, AND ANCHORS SHALL NOT BE USED IN SUBSTRATES WITH STRENGTHS LESS THAN THE MINIMUM STRENGTH SPECIFIED BY THE ANCHOR MANUFACTURER.
7. INSTALLATION ANCHOR CAPACITIES FOR PRODUCTS HEREIN ARE BASED ON SUBSTRATE MATERIALS WITH THE FOLLOWING PROPERTIES:

A. WOOD - MINIMUM SPECIFIC GRAVITY OF 0.55.

B. CONCRETE -MINIMUM COMPRESSIVE STRENGTH OF 3000 PSI.

C. GROUT-FILLED CMU- UNIT STRENGTH CONFORMS TO ASTM C-90 WITH MINIMUM COMPRESSIVE STRENGTH OF 2000 PSI AND GROUT CONFORMS TO ASTM C 476, MINIMUM GROUT COMPRESSIVE STRENGTH OF 2000 PSI.

D. HOLLOW BLOCK CMU - UNIT STRENGTH CONFORMS TO ASTM C-90 WITH MINIMUM COMPRESSIVE STRENGTH OF 2000 PSI.

E. STEEL - MINIMUM WALL THICKNESS OF 54 MILS (16 GA.) WHEN THROUGH GUSSET INSTALLATION.

F. ALUMINUM - 1/8" MINIMUM THICKNESS (6063-T5)

GENERAL NOTES:

1. THE PRODUCT SHOWN HEREIN IS DESIGNED AND MANUFACTURED TO COMPLY WITH THE CURRENT EDITION FLORIDA BUILDING CODE (FBC) **EXCLUDING** HVHZ. ALL PRODUCTS UNDER THE SCOPE OF THIS DOCUMENT HAVE BEEN EVALUATED ACCORDING TO THE FOLLOWING:

AAMA 450-10

CH. 17 OF THE CURRENT EDITION OF FBC.
2. ADEQUACY OF THE EXISTING STRUCTURAL CONCRETE/MASONRY, 2X AND METAL STUD FRAMING AS A MAIN WIND FORCE RESISTING SYSTEM CAPABLE OF WITHSTANDING AND TRANSFERRING APPLIED PRODUCT LOADS TO THE FOUNDATION IS THE RESPONSIBILITY OF THE ENGINEER OR ARCHITECT OF RECORD FOR THE PROJECT OF INSTALLATION.
3. 1X AND 2X BUCKS (WHEN USED) SHALL BE DESIGNED AND ANCHORED TO PROPERLY TRANSFER ALL LOADS TO THE STRUCTURE. BUCK DESIGN AND INSTALLATION IS THE RESPONSIBILITY OF THE ENGINEER OR ARCHITECT OF RECORD FOR THE PROJECT OF INSTALLATION.
4. THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT IN NON-HVHZ AREAS.
5. APPROVED IMPACT PROTECTIVE SYSTEM **IS REQUIRED** TO PROTECT THIS PRODUCT IN AREAS REQUIRING IMPACT RESISTANCE.
6. MULLION MATERIAL: PULTRUDED FIBERGLASS
7. IN ACCORDANCE WITH THE CURRENT FBC, DISSIMILAR METALS INCLUDING FASTENERS SHALL BE PROTECTED FROM GALVANIC CORROSION.
8. CUSTOM SIZES AVAILABLE UPON REQUEST. CUSTOM DESIGN PRESSURE WILL BE ASSIGNED EQUAL TO NEXT LARGER STANDARD SIZE.
9. INTERIOR TRIM OPTIONS MAY VARY IN ACCORDANCE WITH ANDERSEN'S RECOMMENDATIONS.
- 10.MULL ASSEMBLIES ARE QUALIFIED FOR TWO OR MORE UNITS PER OPENING IN THE FOLLOWING CONFIGURATION:

"ONE WAY" - RIBBON OR STACKED MULLIONS

"TWO WAY" - 'X' OR 'T' MULLIONS

SEE SHEETS 7-8 FOR TYPICAL ELEVATION TYPES
- 11.ONE WAY MULLIONS USE 5-1/8" REINFORCED MULLION JOINING AND TWO WAY MULLIONS USE 5-1/8" REINFORCED MULLION JOINING FOR CONTINUOUS SPANS AND 3-1/4" NON-REINFORCED MULLION JOINING FOR TRIBUTARY/NON-CONTINUOUS SPANS. 100S NON-REINFORCED MULLION JOINING UNDER SEPARATE APPROVAL, SEE FL15922. #AWD225 FOR REFERENCE.

TABLE OF CONTENTS	
SHEET	SHEET DESCRIPTION
1	GENERAL AND INSTALLATION NOTES
2	MULL ASSEMBLY SECTIONS - 5-1/8" REINFORCED JOINING
3	MULL ASSEMBLY SECTIONS - 5-1/8" REINFORCED JOINING CONT.
4	INSTALLATION DETAILS - 5 1/8" REINFORCED JOINING WITH FULL GUSSETS
5	INSTALLATION DETAILS - 5 1/8" REINFORCED JOINING WITH HALF GUSSETS
6	MULLION INTERSECTION DETAILS - TWO WAY JOINING
7	ONE - WAY MULLION TABLES AND INSTALLATION NOTES
8	TWO - WAY MULLION TABLES AND INSTALLATION NOTES

PRODUCT ABBREVIATION KEY	
ABBREVIATION	PRODUCT NAME
PW =	PICTURE WINDOW FRAME
CS =	CASEMENT WINDOW FRAME
AW =	AWNING WINDOW FRAME
SH =	SINGLE HUNG WINDOW FRAME
GL =	GLIDING WINDOW FRAME
DH =	DOUBLE HUNG WINDOW FRAME

MISSILE IMPACT RATING
NON-IMPACT

MULLING INSTRUCTIONS:

- STEP 1: ESTABLISH MULL ASSEMBLY FRAME TYPES AND MULL CONFIGURATION.
- STEP 2: VERIFY MULL ASSEMBLY CONSTRUCTION FROM SHEETS 2-6 (REFER TO ABBREVIATION TABLE ABOVE).
- STEP 3: DETERMINE ALLOWABLE LOAD OF MULL ASSEMBLY FROM APPLICABLE LOAD TABLE, REFER TO SHEETS 7-8.
- STEP 4: INSTALL MULLION BASED ON APPLICABLE SPECIFICATIONS & DETAILS SHOWN ON SHEETS 4-5.



100 FOURTH AVE NORTH
BAYPORT, MN 55003-1096
PH: (651) 264-5150 FX: (651) 264-5485

TITLE:
100 SERIES REINFORCED MULLION
JOINING (NON-HVHZ) (NON-IMPACT)

GENERAL AND INSTALLATION NOTES

PREPARED BY:

BUILDING DROPS, INC.

1900 NE MIAMI CT, SUITE 2-15

MIAMI, FL 33132

PH: (954)399-8478

FAX: (954)744-4738


WEB: www.buildingdrops.com



REMARKS	BY	DATE
7TH FBC CODE CHANGE	NUS	10.09.20
GUSSET PLATE UPDATE	MS	02/07/23
8TH FBC CODE CHANGE	MS	10/19/23
DH WINDOW ADDITION	JR	02/24/25


THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.

Digitally signed by Hermes F. Norero, P.E.
Reason: I am approving this document
Date: 2026.02.08 11:16:05 -0500'




FL #:	FL15922
DATE:	02.21.25
DWG. BY:	CHK. BY:
JR	HFN
SCALE:	NTS
DWG. #:	AWD246
SHEET:	1
	OF 8

c:\users\sebastianh\documents\building drops, inc\building drops landing - common\projects\andersen corporation\fb-24-1153 - fbc submittal - fl15922 100 series reinforced mullion - awd246 revision\dwgs\awd246.dwg 1/22/2026 11:51 AM




A
3

DH TO PW
VERTICAL OR HORIZONTAL MULL
5-1/8" REINFORCED JOINING




B
3

DH TO CS/AW
VERTICAL OR HORIZONTAL MULL
5-1/8" REINFORCED JOINING



C
3

DH TO SH/GL
VERTICAL OR HORIZONTAL MULL
5-1/8" REINFORCED JOINING



D
3

DH TO DH
VERTICAL OR HORIZONTAL MULL
5-1/8" REINFORCED JOINING

PRODUCT ABBREVIATION KEY	
ABBREVIATION	PRODUCT NAME
PW =	PICTURE WINDOW FRAME
CS =	CASEMENT WINDOW FRAME
AW =	AWNING WINDOW FRAME
SH =	SINGLE HUNG WINDOW FRAME
GL =	GLIDING WINDOW FRAME
DH =	DOUBLE HUNG WINDOW FRAME



100 FOURTH AVE NORTH
BAYPORT, MN 55003-1096
PH: (651) 264-5150 FX: (651) 264-5485

TITLE:
100 SERIES REINFORCED MULLION
JOINING (NON-HVHZ) (NON-IMPACT)

MULL ASSEMBLY SECTIONS -
5-1/8" REINFORCED JOINING CONT.


PREPARED BY:
BUILDING DROPS, INC.

1900 NE MIAMI CT. SUITE 2-15
MIAMI, FL 33132
PH: (954) 399-8478
FAX: (954) 744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
7TH FBC CODE CHANGE	NUS	10.09.20
GUSSET PLATE UPDATE	MS	02/07/23
8TH FBC CODE CHANGE	MS	10/19/23
DH WINDOW ADDITION	JR	02/24/25

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #:
FL15922

DATE: **02.21.25**

DWG. BY: **JR** CHK. BY: **HFN**

SCALE: **NTS**


DWG. #: **AWD246**

SHEET:


3

OF 8


c:\users\sebastianhereros\building drops, inc\building drops landing - common\projects\andersen corporation\fb-24-1153 - fbc submittal - fl15922 100 series reinforced mullion - awd246 revision\dwgs\awd246.dwg 1/22/2026 11:51 AM



A
4 **TYPICAL DETAIL**
FULL GUSSET TO WOOD/METAL STUD
5-1/8" REINFORCED MULLION INSTALLATION



C
4 **TYPICAL SECTION**
MULLION END-CLIPPING DETAIL - FULL GUSSET
5-1/8" REINFORCED MULLION INSTALLATION



B
4 **TYPICAL DETAIL**
MULLION END-CLIPPING DETAIL - FULL GUSSET
5-1/8" REINFORCED MULLION INSTALLATION

INSTALLATION NOTES:

1. EACH WINDOW FRAME SHALL BE ATTACHED TO GUSSET WITH (6) #8 FH X 3/4" SCREWS.
2. FOR INSTALLATION THROUGH 2X BUCK USE (8) #10 FH WOOD SCREWS. INSTALLATION SHALL CONFORM TO THE FOLLOWING REQUIREMENTS:
 - 2.1. MINIMUM EMBEDMENT OF 1-1/2" INTO WOOD
 - 2.2. MINIMUM EDGE DISTANCE OF 3/4"
3. FOR INSTALLATION THROUGH METAL FRAME USE (8) #10 FH SELF-DRILLING OR SELF-TAPPING, SAE GR. 5, TYPE SCREWS. INSTALLATION SHALL CONFORM TO THE FOLLOWING REQUIREMENTS.
 - 3.1. THREE (3) THREADS MINIMUM PENETRATION BEYOND METAL FRAME WALL.
 - 3.2. MINIMUM EDGE DISTANCE OF 1/2"
4. FOR INSTALLATION DIRECT TO CONCRETE/MASONRY SUBSTRATES OR THROUGH 1X BUCK TO CONCRETE/MASONRY SUBSTRATES, USE (8) 1/4" FH ITW TAPCON TYP ANCHORS. INSTALLATION SHALL CONFORM TO THE FOLLOWING REQUIREMENTS.
 - 4.1. MINIMUM EMBEDMENT OF 1-3/4" INTO SUBSTRATE
 - 4.2. MINIMUM EDGE DISTANCE OF 2"
5. "MASONRY" SUBSTRATES REFER TO GROUT FILLED OR HOLLOW BLOCK OPENINGS.
6. SEE SHEET 1, INSTALLATION NOTE 7 FOR SUBSTRATE MINIMUM PROPERTIES.



100 FOURTH AVE NORTH
BAYPORT, MN 55003-1096
PH: (651) 264-5150 FX: (651) 264-5485


TITLE:
100 SERIES REINFORCED MULLION
JOINING (NON-FVHZ) (NON-IMPACT)
INSTALLATION DETAILS - 5-1/8"
REINFORCED JOINING (W/FULL GUSSETS)

PREPARED BY:
BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954) 399-8478
FAX: (954) 744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
7TH FBC CODE CHANGE	NUS	10.09.20
GUSSET PLATE UPDATE	MS	02/07/23
8TH FBC CODE CHANGE	MS	10/19/23
DH WINDOW ADDITION	JR	02/24/25

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #:

FL15922

DATE: **02.21.25**

DWG. BY:
JR

CHK. BY:
HFN


SCALE: **NTS**

DWG. #: **AWD246**


SHEET:

4


OF 8



A
5 **TYPICAL DETAIL**
HALF GUSSET TO WOOD/METAL STUD
5-1/8" REINFORCED MULLION INSTALLATION



B
5 **TYPICAL DETAIL**
MULLION END-CLIPPING DETAIL - HALF GUSSET
5-1/8" REINFORCED MULLION INSTALLATION



C
5 **TYPICAL SECTION**
MULLION END-CLIPPING DETAIL - HALF GUSSET
5-1/8" REINFORCED MULLION INSTALLATION

- INSTALLATION NOTES:**
1. EACH WINDOW FRAME SHALL BE ATTACHED TO GUSSET WITH (6) #8 FH X 3/4" SCREWS.
 2. FOR INSTALLATION THROUGH 2X BUCK USE (8) #10 FH WOOD SCREWS. INSTALLATION SHALL CONFORM TO THE FOLLOWING REQUIREMENTS:
 - 2.1. MINIMUM EMBEDMENT OF 1-1/2" INTO WOOD
 - 2.2. MINIMUM EDGE DISTANCE OF 3/4"
 3. FOR INSTALLATION THROUGH METAL FRAME USE (8) #10 FH SELF-DRILLING OR SELF-TAPPING, SAE GR. 5, TYPE SCREWS. INSTALLATION SHALL CONFORM TO THE FOLLOWING REQUIREMENTS.
 - 3.1. THREE (3) THREADS MINIMUM PENETRATION BEYOND METAL FRAME WALL.
 - 3.2. MINIMUM EDGE DISTANCE OF 1/2"
 4. FOR INSTALLATION DIRECT TO CONCRETE/MASONRY SUBSTRATES OR THROUGH 1X BUCK TO CONCRETE/MASONRY SUBSTRATES, USE (8) 1/4" FH ITW TAPCON TYP ANCHORS. INSTALLATION SHALL CONFORM TO THE FOLLOWING REQUIREMENTS.
 - 4.1. MINIMUM EMBEDMENT OF 1-3/4" INTO SUBSTRATE
 - 4.2. MINIMUM EDGE DISTANCE OF 2"
 5. "MASONRY" SUBSTRATES REFER TO GROUT FILLED OR HOLLOW BLOCK OPENINGS.
 6. SEE SHEET 1, INSTALLATION NOTE 7 FOR SUBSTRATE MINIMUM PROPERTIES.



100 FOURTH AVE NORTH
BAYPORT, MN 55003-1096
PH: (651) 264-5150 FX: (651) 264-5485


TITLE:
100 SERIES REINFORCED MULLION
JOINING (NON-FVHZ) (NON-IMPACT)
INSTALLATION DETAILS - 5-1/8"
REINFORCED JOINING (W/HALF GUSSETS)

PREPARED BY:
BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954) 399-8478
FAX: (954) 744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
7TH FBC CODE CHANGE	NUS	10.09.20
GUSSET PLATE UPDATE	MS	02/07/23
8TH FBC CODE CHANGE	MS	10/19/23
DH WINDOW ADDITION	JR	02/24/25

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #:
FL15922

DATE: **02.21.25**

DWG. BY: **JR** CHK. BY: **HFN**

SCALE: **NTS**


DWG. #: **AWD246**

SHEET:

5

OF 8


c:\users\sebastianhereros\building drops, inc\building drops, inc\building drops, inc\projects\andersen corporation\fb-24-1153 - fbc submittal - fl15922 100 series reinforced mullion - awd246 revision\dwgs\awd246.dwg 1/22/2026 11:51 AM



A
6

TYPICAL DETAIL

JOINING DETAIL
'X' MULLION INTERSECTION JOINT



B
6

TYPICAL DETAIL

JOINING DETAIL
'T' MULLION INTERSECTION JOINT

INSTALLATION NOTES:

- INTERSECTION JOINTS SECURED VIA FASTENERS DRIVEN BETWEEN MULLION JOINING PLATES/STRIPS AND ADJACENT WINDOW FRAME MEMBERS, PER RESPECTIVE MULLION ASSEMBLY SECTION DETAILS FOR 100S 5-1/8" REINFORCED MULLION JOINING (REFERENCE THIS REPORT, SHEETS 2 & 3), AND 100S NON-REINFORCED MULLION JOINING (REFERENCE FL15922/DWG. #AWD225, SHEET 2.)



100 FOURTH AVE NORTH
BAYPORT, MN 55003-1096
PH: (651) 264-5150 FX: (651) 264-5485

TITLE:
100 SERIES REINFORCED MULLION
JOINING (NON-HVHZ) (NON-IMPACT)

MULLION INTERSECTION DETAILS -
TWO WAY JOINING

PREPARED BY:

BUILDING DROPS, INC.

1900 NE MIAMI CT. SUITE 2-15
MIAMI, FL 33132
PH: (954) 399-8478
FAX: (954) 744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
7TH FBC CODE CHANGE	NUS	10.09.20
GUSSET PLATE UPDATE	MS	02/07/23
8TH FBC CODE CHANGE	MS	10/19/23
DH WINDOW ADDITION	JR	02/24/25

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #:
FL15922

DATE: **02.21.25**

DWG. BY:
JR

CHK. BY:
HFN

SCALE: **NTS**

DWG. #: **AWD246**

SHEET:

6



OF 8

FIBERGLASS REINFORCED MULL TABLE: ONE-WAY

MAXIMUM DESIGN PRESSURE CAPACITY CHART (PSF): SERIES 100, 5-1/8" REINFORCED MULLION - ONE-WAY															
L - Mull Length (in)	W - Tributary Width (in)														
	18.0	24.0	30.0	36.0	42.0	45.0	48.0	54.0	60.0	66.0	72.0	78.0	84.0	90.0	96.0
24.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0
30.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0
36.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0
42.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0
48.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0
54.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0
60.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0
66.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0
72.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0
78.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0
84.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	56.9	50.0
90.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	-	-	-	-
96.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	-	-	-	-
102.0	65.0	65.0	65.0	65.0	65.0	64.4	61.5	-	-	-	-	-	-	-	-
108.0	65.0	65.0	65.0	65.0	63.1	59.9	57.1	-	-	-	-	-	-	-	-
114.0	65.0	65.0	65.0	65.0	59.0	56.0	53.3	-	-	-	-	-	-	-	-
120.0	65.0	65.0	65.0	62.7	55.4	52.5	50.0	-	-	-	-	-	-	-	-
126.0	65.0	65.0	59.2	50.7	44.7	42.3	37.5	-	-	-	-	-	-	-	-
132.0	65.0	65.0	56.2	48.0	42.3	40.0	35.4	-	-	-	-	-	-	-	-
138.0	65.0	54.2	42.0	36.6	32.1	30.4	28.9	-	-	-	-	-	-	-	-
144.0	65.0	51.7	40.0	34.8	30.6	28.9	27.4	-	-	-	-	-	-	-	-

NOTE:

1. HIGHLIGHTED SIZES IN THE TABLE ABOVE ARE TESTED PRESSURES AS PER AAMA 450-10, THE REST OF THE VALUES OBTAINED ARE BASED ON COMPARATIVE ANALYSIS (AAMA 2502-19).
2. MULLION CHART APPLIES TO REINFORCED MULLION ASSEMBLIES, WHEN MULLED IN ONE-WAY, STACK OR RIBBON, CONFIGURATIONS.
3. DESIGN PRESSURE VALUES ARE POSITIVE AND NEGATIVE IN PSF.
4. DESIGN PRESSURE OF ASSEMBLY IS LIMITED TO THE LESSER DESIGN PRESSURE OF THE MULLION ASSEMBLY OR THE INDIVIDUAL UNIT OF INSTALLATION. ADJACENT WINDOWS SHALL BE UNDER SEPARATE FL APPROVAL.
5. MULLION CHART APPLIES TO THE FOLLOWING INSTALLATION CONDITIONS:
FULL OR HALF GUSSET INSTALLATION TO 2X WOOD, METAL STUD, GROUT FILLED OR HOLLOW BLOCK, OR CONCRETE.
6. TRIBUTARY WIDTH = $W = (A+B)/2$
7. REFER TO SHEET 4-6 FOR INSTALLATION DETAILS.
8. WHEN WINDOWS ARE STACKED VERTICALLY, THE MANUFACTURER/INSTALLER SHALL ENSURE THAT THE WEIGHT OF UNITS ABOVE WILL NOT CAUSE DEFLECTIONS OR STRESSES WHICH WILL AFFECT OPERATION OR STRUCTURAL ADEQUACY OF UNITS BELOW.



100 FOURTH AVE NORTH
BAYPORT, MN 55003-1096
PH: (651) 264-5150 FX: (651) 264-5485

TITLE:
100 SERIES REINFORCED MULLION
JOINING (NON-HVHZ) (NON-IMPACT)
ONE-WAY MULLION TABLES AND
INSTALLATION NOTES

PREPARED BY:
BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954) 399-8478
FAX: (954) 744-4738
WEB: www.buildingdrops.com

REMARKS	BY	DATE
7TH FBC CODE CHANGE	NUS	10.09.20
GUSSET PLATE UPDATE	MS	02/07/23
8TH FBC CODE CHANGE	MS	10/19/23
DH WINDOW ADDITION	JR	02/24/25

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.




FL #:	FL15922
DATE:	02.21.25
DWG. BY:	CHK. BY:
JR	HFN
SCALE:	NTS
DWG. #:	AWD246
SHEET:	7

FIBERGLASS REINFORCED MULL TABLE: TWO-WAY

MAXIMUM DESIGN PRESSURE CAPACITY CHART (PSF): SERIES 100, 5-1/8" REINFORCED JOINING MULLION - TWO-WAY											
L - Mull Length (in)	W - Tributary Width (in)										
	18.0	24.0	30.0	36.0	42.0	45.0	48.0	54.0	60.0	66.0	72.0
24.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0
30.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0
36.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0
42.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0
48.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0
54.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0
60.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0
66.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0
72.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	58.7
78.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	50.0
84.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0
90.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0
96.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	62.5
102.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	65.0	60.4	55.4
108.0	65.0	65.0	65.0	65.0	65.0	65.0	61.7	65.0	59.3	53.9	49.4
114.0	65.0	65.0	65.0	65.0	63.3	59.1	55.4	59.1	53.2	48.4	44.3
120.0	65.0	65.0	65.0	65.0	57.1	53.3	50.0	53.3	48.0	43.6	40.0
126.0	65.0	65.0	65.0	54.9	47.0	43.9	41.2	36.6	32.9	28.5	26.1
132.0	65.0	65.0	60.0	50.0	42.9	40.0	37.5	33.3	30.0	26.0	23.8
138.0	65.0	65.0	43.6	40.8	35.0	32.7	30.6	27.2	26.1	23.8	21.8
144.0	65.0	65.0	40.0	37.5	32.1	30.0	28.1	25.0	24.0	21.8	20.0

NOTE:

1. HIGHLIGHTED SIZES IN THE TABLE ABOVE ARE TESTED PRESSURES AS PER AAMA 450-10, THE REST OF THE VALUES OBTAINED ARE BASED ON COMPARATIVE ANALYSIS (AAMA 2502-19).
2. MULLION CHART APPLIES TO REINFORCED MULLION ASSEMBLIES, WHEN MULLED IN TWO-WAY,'X' OR 'T' CONFIGURATIONS, WHERE 5-1/8" REINFORCED JOINING IS USED FOR CONTINUOUS MULL SPANS, AND 3-1/4" NON-REINFORCED JOINING IS USED FOR TRIBUTARY/NON-CONTINUOUS MULL SPANS. 100S NON-REINFORCED MULLION JOINING UNDER SEPARATE APPROVAL, SEE FL15922.1/DWG. #AWD225.
3. DESIGN PRESSURE VALUES ARE POSITIVE AND NEGATIVE IN PSF.
4. DESIGN PRESSURE OF ASSEMBLY IS LIMITED TO THE LESSER DESIGN PRESSURE OF THE MULLION ASSEMBLY OR THE INDIVIDUAL UNIT OF INSTALLATION. ADJACENT WINDOWS SHALL BE UNDER SEPARATE FL APPROVAL.
5. MULLION CHART APPLIES TO THE FOLLOWING INSTALLATION CONDITIONS:
FULL OR HALF GUSSET INSTALLATION TO 2X WOOD, METAL STUD, GROUT FILLED OR HOLLOW BLOCK, OR CONCRETE
6. TRIBUTARY WIDTH = $W = (A+B)/2$
7. REFER TO SHEET 4-6 FOR INSTALLATION DETAILS.
8. WHEN WINDOWS ARE STACKED VERTICALLY, THE MANUFACTURER/INSTALLER SHALL ENSURE THAT THE WEIGHT OF UNITS ABOVE WILL NOT CAUSE DEFLECTIONS OR STRESSES WHICH WILL AFFECT OPERATION OR STRUCTURAL ADEQUACY OF UNITS BELOW.



100 FOURTH AVE NORTH
BAYPORT, MN 55003-1096
PH: (651) 264-5150 FX: (651) 264-5485

TITLE:
100 SERIES REINFORCED MULLION
JOINING (NON-HVHZ) (NON-IMPACT)
TWO-WAY MULLION TABLES AND
INSTALLATION NOTES

PREPARED BY:
BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
PH: (954) 399-8478
FAX: (954) 744-4738
WEB: www.buildingdrops.com

REMARKS	BY	DATE
7TH FBC CODE CHANGE	NUS	10.09.20
GUSSET PLATE UPDATE	MS	02/07/23
8TH FBC CODE CHANGE	MS	10/19/23
DH WINDOW ADDITION	JR	02/24/25

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #:
FL15922

DATE: **02.21.25**

DWG. BY: JR	CHK. BY: HFN
-----------------------	------------------------

SCALE: **NTS**

DWG. #: **AWD246**

SHEET: