

c:\Users\lucianosanchez\building drops, inc\building drops, inc\documents\common\projects\2026 code change projects\caoba doors\116469-r6\cab040.dwg 7/30/2026 12:37 PM

INSTALLATION NOTES:

1. THE MINIMUM NUMBER OF INSTALLATION ANCHORS REQUIRED AT EACH ANCHOR LOCATION SHOWN SHALL BE AS SPECIFIED HEREIN.
2. SHIM AS REQUIRED AT EACH INSTALLATION ANCHOR WITH LOAD BEARING SHIM(S). MAXIMUM ALLOWABLE SHIM STACK TO BE 1/4 INCH. SHIM WHERE SPACE OF 1/16 INCH OR GREATER OCCURS. SHIM(S) SHALL BE CONSTRUCTED OF HIGH DENSITY PLASTIC OR BETTER.
3. MINIMUM EMBEDMENT AND EDGE DISTANCE EXCLUDE WALL FINISHES, INCLUDING BUT NOT LIMITED TO STUCCO, FOAM, BRICK VENEER, AND SIDING.
4. INSTALLATION ANCHORS AND ASSOCIATED HARDWARE MUST BE MADE OF CORROSION RESISTANT MATERIAL OR HAVE A CORROSION RESISTANT COATING:

• FASTENERS USED WITHIN 3,000 FEET OF A SALTWATER COASTLINE AND INSTALLED IN ENCLOSED SPACES SHALL BE GALVANIZED IN ACCORDANCE WITH SECTION 1711.1.1 (E.G., ASTM A153 CLASS D, ASTM A641 CLASS 3S, OR EQUIVALENT CORROSION RESISTANCE).

• CONNECTORS AND METAL PLATES USED WITHIN 3,000 FEET OF A SALTWATER COASTLINE SHALL BE STANDARD GALVANIZED IN ACCORDANCE WITH SECTION 1711.1.2 (E.G., ASTM A653 G90, ASTM A123, OR PROTECTIVE COATING PER TPI 1).
5. FOR GROUT FILLED BLOCK, DO NOT INSTALL INSTALLATION ANCHORS INTO MORTAR JOINTS. EDGE DISTANCE IS MEASURED FROM FREE EDGE OF BLOCK OR EDGE OF MORTAR JOINT INTO FACE SHELL OF BLOCK.
6. INSTALLATION ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH ANCHOR MANUFACTURER'S INSTALLATION INSTRUCTIONS, AND ANCHORS SHALL NOT BE USED IN SUBSTRATES WITH STRENGTHS LESS THAN THE MINIMUM STRENGTH SPECIFIED BY THE ANCHOR MANUFACTURER.
7. INSTALLATION ANCHOR CAPACITIES FOR PRODUCTS HEREIN ARE BASED ON SUBSTRATE MATERIALS WITH THE FOLLOWING PROPERTIES:

• WOOD - MINIMUM SPECIFIC GRAVITY OF 0.55.

• CONCRETE -MINIMUM COMPRESSIVE STRENGTH OF 3000 PSI.

• MASONRY - STRENGTH CONFORMANCE TO ASTM C-90. MINIMUM COMPRESSIVE STRENGTH OF 2000 PSI.

• GROUT-FILLED CMU- UNIT STRENGTH CONFORMS TO ASTM C-90 WITH MINIMUM COMPRESSIVE STRENGTH OF 2000 PSI AND GROUT CONFORMS TO ASTM C 476, MINIMUM GROUT COMPRESSIVE STRENGTH OF 2000 PSI.

GENERAL NOTES:

1. THE PRODUCT SHOWN HEREIN IS DESIGNED AND MANUFACTURED TO COMPLY WITH THE CURRENT FLORIDA BUILDING CODE (FBC), INCLUDING HVHZ AND HAS BEEN EVALUATED ACCORDING TO THE FOLLOWING:

• TAS 201-94

• TAS 202-94

• TAS 203-94
2. ADEQUACY OF THE EXISTING STRUCTURAL CONCRETE/MASONRY AND 2X FRAMING AS A MAIN WIND FORCE RESISTING SYSTEM CAPABLE OF WITHSTANDING AND TRANSFERRING APPLIED PRODUCT LOADS TO THE FOUNDATION IS THE RESPONSIBILITY OF THE ENGINEER OR ARCHITECT OF RECORD FOR THE PROJECT OF INSTALLATION.
3. 1X AND 2X BUCKS (WHEN USED) SHALL BE DESIGNED AND ANCHORED TO PROPERLY TRANSFER ALL LOADS TO THE STRUCTURE. BUCK DESIGN AND INSTALLATION IS THE RESPONSIBILITY OF THE ENGINEER OR ARCHITECT OF RECORD FOR THE PROJECT OF INSTALLATION.
4. THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.
5. APPROVED IMPACT PROTECTIVE SYSTEM **IS NOT REQUIRED** ON THIS PRODUCT IN AREAS REQUIRING IMPACT RESISTANCE.
6. DOOR MATERIAL: MAHOGANY OR EQUIVALENT (MIN. SG = 0.42)
7. IN ACCORDANCE WITH THE FBC, WOOD COMPONENTS SHALL HAVE BEEN PRESERVATIVE TREATED OR SHALL BE OF A DURABLE SPECIES.
8. STEEL COMPONENTS SHALL BE COATED OR PROVIDED WITH CORROSION RESISTANCE PROTECTION IN CONFORMANCE WITH THE MATERIAL PROTECTION PROVISIONS OF THE FBC.
9. IN ACCORDANCE WITH THE FBC, DISSIMILAR METALS INCLUDING FASTENERS THAT MAY COME INTO CONTACT WITH ALUMINUM COMPONENTS SHALL BE PROTECTED.
10. GLASS SHALL MEET THE REQUIREMENTS OF ASTM E1300 GLASS CHARTS. SEE SHEET 4 FOR GLAZING DETAIL.
11. QUALIFIED CONFIGURATIONS INCLUDE:

• 2-PANEL - 2L, 2R

• 3-PANEL - 2L-1R, 1L-2R, 3L, 3R

• 4-PANEL - 3L-1R, 1L-3R, 2L-2R, 4L, 4R

TABLE OF CONTENTS	
SHEET	SHEET DESCRIPTION
1	INSTALLATION & GENERAL NOTES
2	ELEVATIONS
3	ANCHOR LAYOUT
4	VERTICAL SECTIONS & GLAZING DETAILS
5	HORIZONTAL SECTIONS
6	COMPONENTS
7	COMPONENTS
8	B.O.M.

DESIGN PRESSURE RATING		
GLAZE TYPE	DESIGN PRESSURE	IMPACT RATING
1	+/- 55.0 PSF	LARGE AND SMALL IMPACT MISSILE RATING



4918 CEDAR AVENUE
PHILADELPHIA, PA 19143

PH: (215) 525-5048 FX: (215) 747-8908

TITLE:
ALUMINUM CLAD VISTA VIEW
OUT FOLDING WOOD DOORS
WITH E3 HARDWARE
(HVHZ) (IMPACT)
INSTALLATION & GENERAL NOTES


PREPARED BY:
BUILDING DROPS, INC.
1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
2026 FBC UPDATE	LS	07/26

THE INSTALLATION DETAILS DESCRIBED HERE IN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.

Digitally signed by Hermes F. Norero, P.E
Reason: I am approving this document
Date: 2026.09.10 10:02:00'



FL #:
FL16469

DATE: **11.09.20**

DWG. BY: **RV**CHK. BY: **HFN**

SCALE: **NTS**


DWG. #: **CAB040**

SHEET:
1


REV. **A**

OF 8

c:\users\lucianosanchez\building drops, inc\building drops landing - documents\common\projects\2026 code change projects\caoba doors\2026 code change - 1711\dwgs\116469-r6\cab040.dwg 7/30/2026 12:37 PM



EXTERIOR ELEVATION



INTERIOR ELEVATION

OUT FOLDING WOOD DOORS



4918 CEDAR AVENUE
PHILADELPHIA, PA 19143

PH: (215) 525-5048 FX: (215) 747-8908

TITLE: ALUMINUM CLAD VISTA VIEW
OUT FOLDING WOOD DOORS
WITH E3 HARDWARE
(HVHZ) (IMPACT)
ELEVATIONS

PREPARED BY:

BUILDING DROPS, INC.

1900 NE MIAMI COURT, STE. 2-15

MIAMI, FL 33132

PH: (954) 399-8478


FAX: (954) 744-4738

WEB: www.buildingdrops.com



REMARKS	BY	DATE
2026 FBC UPDATE	LS	07/26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #: **FL16469**

DATE: **11.09.20**

DWG. BY: **RV**

CHK. BY: **HFN**

SCALE: **NTS**

DWG. #: **CAB040**

SHEET:

2


REV.

A


OF 8

c:\users\lucianosanchez\building drops, inc\building drops landing - documents\common\projects\2026 code change projects\caoba doors\16469-r6\cab040.dwg 7/30/2026 12:37 PM

- -ANCHORS THROUGH INTERIOR WOOD
- -ANCHORS THROUGH EXTERIOR ALUMINUM TRACK



HEAD ANCHOR LAYOUT



ANCHOR LAYOUT

INSTALLATION NOTES:

1. FOR INSTALLATION INTO WOOD FRAMING, INSTALL (2) #12 X 3.0" WOOD SCREWS AT HEAD THROUGH ALUMINUM EXTERIOR AT 10.5" MAX. O.C. PER LOCATION AND INSTALL (1) #14 WOOD SCREW THROUGH WOOD INTERIOR PER LOCATION INDICATED IN ANCHOR LAYOUT. AT JAMBS, INSTALL (2) #8 WOOD SCREWS PER LOCATION AS INDICATED IN ANCHOR LAYOUT. AT SILL, INSTALL (1) #14 WOOD SCREW THROUGH SILL TRACK PER LOCATION. WOOD SCREWS SHALL BE OF SUFFICIENT LENGTH TO ACHIEVE A MINIMUM OF 1 1/2 INCH EMBEDMENT INTO FRAMING. ANCHORS SHALL BE STAGGERED IN ORDER TO ACHIEVE A 2 1/4" MIN. SPACING BETWEEN ANCHORS.
2. FOR INSTALLATION INTO CONCRETE/MASONRY, INSTALL (2) 3/16" ITW TAPCONS AT HEAD THROUGH ALUMINUM EXTERIOR AT 10.5" MAX. O.C. PER LOCATION AND INSTALL (1) 1/4" ITW TAPCON THROUGH WOOD INTERIOR PER LOCATION. AT JAMBS, INSTALL (2) 3/16" ITW TAPCONS PER LOCATION AS INDICATED IN ANCHOR LAYOUT. AT SILL, INSTALL (1) 1/4" ITW TAPCON THROUGH SILL TRACK. TAPCONS SHALL BE OF SUFFICIENT LENGTH TO ACHIEVE A MINIMUM OF 1 1/4 INCH EMBEDMENT INTO CONCRETE/MASONRY. ANCHORS SHALL BE STAGGERED IN ORDER TO ACHIEVE A 2 1/4" MIN. SPACING BETWEEN ANCHORS.

caoba®

DOORS

4918 CEDAR AVENUE
PHILADELPHIA, PA 19143

PH: (215) 525-5048 FX: (215) 747-8908

TITLE:
ALUMINUM CLAD VISTA VIEW
OUT FOLDING WOOD DOORS
WITH E3 HARDWARE
(HVHZ) (IMPACT)
ANCHOR LAYOUT

PREPARED BY:
BUILDING DROPS, INC.
1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132
PH: (954) 399-8478
FAX: (954) 744-4738
WEB: www.buildingdrops.com

REMARKS

BY

DATE

2026 FBC UPDATE

LS

07/26

THE INSTALLATION DETAILS DESCRIBED HERE IN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.

HERMES F. NORERO

LICENSE

No. 73778

STATE OF

FLORIDA

PROFESSIONAL ENGINEER

HERMES F. NORERO, P.E.
BUILDING DROPS, INC.
1900 NE MIAMI CT, SUITE 2-15
MIAMI, FL 33132
FBPE CERT. OF AUTHORIZATION No. 29578

FL #:

FL16469

DATE:

11.09.20

DWG. BY:

RV

CHK. BY:

HFN

SCALE:

NTS

DWG. #:

CAB040

SHEET:

3




REV.

A

OF 8

7/30/2026 12:37 PM

c:\users\lucianosanchez\building drops, inc\building drops\landing - documents\common\projects\2026 code change projects\caoba doors\116469-6\cab040.dwg



- NOTE:**
- GLASS CAPACITIES ON THIS SHEET ARE BASED ON ASTM E1300-04 (3 SEC. GUSTS) AND CHAPTER 17 OF THE CURRENT FBC FOR SIZES OTHER THAN TESTED.
 - SETTING BLOCK DUROMETER HARDNESS OF 70-90 (SHORE A) AS REFERENCED IN CHAPTER 24.
 - SETTING BLOCKS TO BE LOCATED AT 1/4 SPAN LENGTH FOR GLASS WIDER THAN 36" AS PER CHAPTER 24.
 - D.L.O. MAY NOT EXCEED MAX DIMENSIONS IN GLASS CHARTS FOR GLASS TYPE.

caoba®
DOORS

4918 CEDAR AVENUE
PHILADELPHIA, PA 19143

PH: (215) 525-5048 FX: (215) 747-8908


TITLE: ALUMINUM CLAD VISTA VIEW
OUT FOLDING WOOD DOORS
WITH E3 HARDWARE
(HVHZ) (IMPACT)
VERTICAL SECTIONS & GLAZING DETAIL

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132
PH: (954) 399-8478
FAX: (954) 744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
2026 FBC UPDATE	LS	07/26


THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.




FL #:	FL16469
DATE:	11.09.20
DWG. BY:	RV
CHK. BY:	HFN
SCALE:	NTS
DWG. #:	CAB040
SHEET:	4
REV.	A
	OF 8

c:\users\lucianosanchez\building drops, inc\building drops\landing - documents\common\projects\2026 code change projects\caoba doors\116469-r6\cab040.dwg 7/30/2026 12:37 PM


1 EXTERIOR TOP TRACK COVER WOOD




2 JAMB HEAD TRACK COVER WOOD




3 INTERIOR TOP TRACK COVER WOOD




4 SILL WOOD




5 SILL EXTERIOR WOOD




6 JAMB LEG WOOD



7 SASH STOP WOOD




8 TOP RAIL WOOD




9 BOTTOM RAIL WOOD




10 MOULDING WOOD




11 JAMB SIDE STILE WOOD




12 STILE "A" WOOD




13 STILE "B" WOOD




14 INACTIVE SIDE STILE WOOD



15 ACTIVE SIDE STILE WOOD



16 ASTRAGAL WOOD



caoba[®]
DOORS

4918 CEDAR AVENUE
PHILADELPHIA, PA 19143

PH: (215) 525-5048 FX: (215) 747-8908

TITLE: ALUMINUM CLAD VISTA VIEW
OUT FOLDING WOOD DOORS
WITH E3 HARDWARE
(HVHZ) (IMPACT)
COMPONENTS


PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132

PH: (954) 399-8478
FAX: (954) 744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
2026 FBC UPDATE	LS	07/26

THE INSTALLATION DETAILS DESCRIBED HERE IN ARE GENERIC
AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC
SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE
FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED
ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC
DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #:
FL16469

DATE: **11.09.20**

DWG. BY: **RV** CHK. BY: **HFN**

SCALE: **NTS**


DWG. #: **CAB040**

SHEET: **6** REV. **A**


OF 8

c:\users\lucianosanchez\building drops, inc\building drops\landing - documents\common\projects\2026 code change projects\caoba doors\2026 code change - 1711\dwgs\fl16469-r6\cab040.dwg 7/30/2026 12:37 PM


17 EXTERIOR COVER CLADDING ALUMINUM



18 JAMB LEG CLADDING ALUMINUM




19 J. LEG COVER CLADDING ALUMINUM




23 KJV MULTIPOINT LOCKING SYSTEM STAINLESS STEEL


20 ASTRAGAL CLADDING ALUMINUM




21 AST. COVER CLADDING 6063-T5 ALUMINUM




22 SASH FACE CLADDING ALUMINUM




23 TOP RAIL COVER CLADDING ALUMINUM




54 TOP RAIL SASH FACE CLADDING ALUMINUM




57 BOTTOM RAIL SASH FACE CLADDING ALUMINUM




24 BOTTOM RAIL EXT. CLADDING ALUMINUM




55 MOULDING WOOD




53 TOP RAIL SASH FACE CLADDING ALUMINUM





56 BOTTOM RAIL SASH FACE CLADDING ALUMINUM



58 SASH FACE CLADDIN ALUMINUM



59 SASH FACE CLADDIN ALUMINUM



caoba®
DOORS

4918 CEDAR AVENUE
PHILADELPHIA, PA 19143

PH: (215) 525-5048 FX: (215) 747-8908

TITLE:
ALUMINUM CLAD VISTA VIEW
OUT FOLDING WOOD DOORS
WITH E3 HARDWARE
(HVHZ) (IMPACT)
COMPONENTS

PREPARED BY:
BUILDING DROPS, INC.
1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132
PH: (954) 399-8478
FAX: (954) 744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
2026 FBC UPDATE	LS	07/26

THE INSTALLATION DETAILS DESCRIBED HERE IN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #:

FL16469

DATE: 11.09.20

DWG. BY:
RV

CHK. BY:
HFN

SCALE: NTS

DWG. #: CAB040

SHEET:

7

REV.
A

OF 8

c:\users\lucianosanchez\building drops, inc\building drops\landing - documents\common\projects\2026 code change projects\caoba doors\cc-26-0457 2 - 2026 code change projects\caoba doors\l16469-r6\cab040.dwg 7/30/2026 12:37 PM

BILL OF MATERIALS				
ITEM #	PART #	ITEM DESCRIPTION	MANUFACTURER	MATERIAL
1	---	EXTERIOR TOP TRACK COVER	CAOBA DOORS	WOOD
2	---	JAMB HEAD TRACK COVER	CAOBA DOORS	WOOD
3	---	INTERIOR TOP TRACK COVER	CAOBA DOORS	WOOD
4	E3CS21463	E3 SILL ALUMINUM	CENTOR A.	ALUMINUM
5	---	SILL EXTENSION	CAOBA DOORS	WOOD
6	---	JAMB LEG	CAOBA DOORS	WOOD
7	---	SASH STOP	CAOBA DOORS	WOOD
8	---	TOP RAIL	CAOBA DOORS	WOOD
9	---	BOTTOM RAIL	CAOBA DOORS	WOOD
10	---	MOULDING	CAOBA DOORS	WOOD
11	---	JAMB SIDE STILE	CAOBA DOORS	WOOD
12	---	STILE "A"	CAOBA DOORS	WOOD
13	---	STILE "B"	CAOBA DOORS	WOOD
14	---	INACTIVE SIDE STILE	CAOBA DOORS	WOOD
15	---	ACTIVE SIDE STILE	CAOBA DOORS	WOOD
16	---	ASTRAGAL	CAOBA DOORS	WOOD
17	A33118-6063	HEAD JAMB EXTERIOR COVER CLADDING	METALS DEPOT	ALUMINUM
18	JDE001	JAMB LEG CLADDING	EXTRALUM	ALUMINUM
19	F4181	JAMB LEG COVER CLADDING	METALS DEPOT	ALUMINUM
20	DA001	ASTRAGAL CLADDING	EXTRALUM	ALUMINUM
21	A31116-6063	ASTRAGAL COVER CLADDING	METALS DEPOT	ALUMINUM
22	SIM001	TOP RAIL, BOTTOM AND STILE SASH FACE CLADDING	EXTRALUM	ALUMINUM
23	F4181	TOP RAIL COVER CLADDING	METALS DEPOT	ALUMINUM
24	WS1000	BOTTOM RAIL EXTENSION SASH FACE CLADDING	EXTRALUM	ALUMINUM
25	---	CLAD CLIP	PLASTIKA S.A.	PLASTIC
28	AWT3	$\frac{1}{4}$ " X $\frac{1}{16}$ " GLAZING TAPE	ARLON	TAPE
29	SG-20	SILICON SEALANT	SIKAFLEX	SILICONE
30	WS-305	SILICON SEALANT	SIKAFLEX	SILICONE
31	E3TAM	TOP TRACK	CENTOR	ALUMINUM
32	E3CPS_	PIVOT SET	ARCHITECTURAL CENTOR	SST
33	E3WPS_	WALL PIVOT	ARCHITECTURAL CENTOR	SST
34	E3CICS_	INTERMEDIATE CARRIER SET	ARCHITECTURAL CENTOR	SST
35	E3HNNH_	SINGLE HINGE	ARCHITECTURAL CENTOR	SST
36	E3HHS_	HALF OFFSET HINGE SET	ARCHITECTURAL CENTOR	SST
37	E3HHNNH_	SINGLE HALF OFFSET HINGE	ARCHITECTURAL CENTOR	SST
38	DBSY1000NR_	DROP BOLT	ARCHITECTURAL CENTOR	SST
39	DBOC200NR_	CONCEALED DROP BOLT	ARCHITECTURAL CENTOR	SST
40	3478816	MUNTIPOINT MFD AS796	KFV	SST
41	3436707	STRIKE PLATE FOR LATCH & DEADBOLT	KFV	SST
42	2025199	TONGUE STRIKE RADIUS LIP	HOPPE	SST
43	3466526	EXTENSION 250mm.	KFV	SST
44	3394608	EXTENSION 500mm.	KFV	SST
45	3395903	EXTENSION 1000mm.	KFV	SST
46	QEBD-650	WEATHERSEAL	SCHLEGEL	URETHANE FOAM
47	KP-51	PILE WEATHERSEAL	SCHLEGEL	URETHANE FOAM
48	WS18	WEATHERSEAL	CONSERVATION	RUBBER
49	QEZD-375	WEATHERSEAL	SCHLEGEL	URETHANE FOAM
50	WS33	WEATHERSEAL	CONSERVATION	RUBBER
51	TRIPLEX 11	WEATHERSEAL	UNIFORM	RUBBER
52	K 2031	CLAD WEATHERSEAL	TRELLEBORG	TSP-FOAM
53		TOP RAIL SASH FACE CLADDING	EXTRALUM	ALUMINUM
54		TOP RAIL SASH FACE CLADDING	EXTRALUM	ALUMINUM
55	---	MOULDING	CAOBA DOORS	WOOD
56		BOTTOM RAIL SASH FACE CLADDING	EXTRALUM	ALUMINUM
57		BOTTOM RAIL SASH FACE CLADDING	EXTRALUM	ALUMINUM
58		STILE SASH FACE CLADDING	EXTRALUM	ALUMINUM
59		STILE SASH FACE CLADDING	EXTRALUM	ALUMINUM

NOTE: FOLDING DOOR HARDWARE IS CENTOR E3 HARDWARE SYSTEM



4918 CEDAR AVENUE
PHILADELPHIA, PA 19143

PH: (215) 525-5048 FX: (215) 747-8908

TITLE:
ALUMINUM CLAD VISTA VIEW
OUT FOLDING WOOD DOORS
WITH E3 HARDWARE
(HVHZ) (IMPACT)
B.O.M.

PREPARED BY:
BUILDING DROPS, INC.
1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132
PH: (954) 399-8478
FAX: (954) 744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
2026 FBC UPDATE	LS	07/26

THE INSTALLATION DETAILS DESCRIBED HERE IN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #:	
FL16469	
DATE: 11.09.20	
DWG. BY: RV	CHK. BY: HFN
SCALE: NTS	
DWG. #: CAB040	
SHEET: 8	REV. A
OF 8	