

REVISIONS			
REV	DESCRIPTION	DATE	APPROVED

NOTES:

1. THE PRODUCT SHOWN HEREIN IS DESIGNED AND MANUFACTURED TO COMPLY WITH REQUIREMENTS OF THE FLORIDA BUILDING CODE INCLUDING THE HVHZ.
2. WOOD FRAMING, METAL STRUCTURE AND MASONRY OPENING TO BE DESIGNED AND ANCHORED TO PROPERLY TRANSFER ALL LOADS TO STRUCTURE. FRAMING AND MASONRY OPENING IS THE RESPONSIBILITY OF THE ARCHITECT OR ENGINEER OF RECORD.
3. WHERE SHIM OR BUCK THICKNESS IS LESS THAN 1-1/2" UNITS MUST BE ANCHORED THROUGH THE FRAME IN ACCORDANCE WITH MANUFACTURER'S PUBLISHED INSTALLATION INSTRUCTIONS. ANCHORS SHALL BE SECURELY FASTENED DIRECTLY INTO MASONRY, CONCRETE OR OTHER STRUCTURAL SUBSTRATE MATERIAL.
4. WHERE WOOD BUCK THICKNESS IS 1-1/2" OR GREATER, BUCK SHALL BE SECURELY FASTENED TO MASONRY, CONCRETE OR OTHER STRUCTURAL SUBSTRATE. UNITS MAY BE ANCHORED THROUGH FRAME TO SECURED WOOD BUCK IN ACCORDANCE WITH MANUFACTURER'S PUBLISHED INSTALLATION INSTRUCTIONS.
5. WHERE 1X BUCK IS NOT USED DISSIMILAR MATERIALS MUST BE SEPARATED WITH APPROVED COATING OR MEMBRANE. SELECTION OF COATING OR MEMBRANE IS THE RESPONSIBILITY OF THE ARCHITECT OR ENGINEER OF RECORD.
6. BUCKS SHALL EXTEND BEYOND UNIT FRAME INTERIOR FACE SO THAT FULL FRAME SUPPORT IS PROVIDED.
7. SHIM AS NEEDED AT EACH ANCHOR LOCATION WITH LOAD BEARING SHIM. SHIM WHERE SPACE OF 1/16" OR GREATER OCCURS. MAXIMUM ALLOWABLE SHIM STACK TO BE 3/8".
8. SHIMS SHALL BE LOCATED, APPLIED AND MADE FROM MATERIALS AND THICKNESS CAPABLE OF SUSTAINING APPLICABLE LOADS.
9. WIND LOAD DURATION FACTOR Cd=1.6 WAS USED FOR WOOD ANCHOR CALCULATIONS.
10. FRAME MATERIAL: EXTRUDED ALUMINUM.
11. UNITS MUST BE GLAZED PER ASTM E1300 SEE SHEET 7 FOR GLASS OPTIONS.
12. APPROVED IMPACT PROTECTIVE SYSTEM IS NOT REQUIRED FOR THIS PRODUCT IN WIND BORNE DEBRIS REGIONS.

13. FOR ANCHORING DETAILS SEE SHEET 6
14. ALL FASTENERS TO BE CORROSION RESISTANT.
15. INSTALLATION ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH ANCHOR MANUFACTURER'S INSTALLATION INSTRUCTIONS AND ANCHORS SHALL NOT BE USED IN SUBSTRATES WITH STRENGTHS LESS THAN THE MINIMUM STRENGTH SPECIFIED BELOW:
 - 15.A. WOOD: MINIMUM SPECIFIC GRAVITY OF G=0.42
 - 15.B. CONCRETE: MINIMUM COMPRESSIVE STRENGTH OF 2,000 PSI.
 - 15.C. MASONRY: HOLLOW/FILLED BLOCK PER ASTM C90 WITH Fm=2,000PSI MINIMUM.
 - 15.D. METAL STRUCTURE: STEEL 18GA (.048") FY=33KSI/FU=52KSI WITH WOOD BACKING OR 1/4" THICK STRUCTURAL STEEL.

TABLE OF CONTENTS	
SHEET NO.	DESCRIPTION
1	NOTES
2 - 3	ELEVATION AND RATINGS
4	APPROVED CONFIGURATIONS
5	CROSS SECTIONS
6	INSTALLATION DETAILS
7	GLASS DETAILS
8	COMPONENTS

NANA WALL SYSTEMS, INC.
100 MEADOWCREEK DRIVE, SUITE 250
CORTE MADERA, CA 94925

SL 73 ALUMINUM OUTSWING BI-FOLD DOOR SYSTEM
IMPACT HVHZ
NOTES

DRAWN:
R.L.

DWG NO.
08-04188

REV
-


SCALE NTS

DATE 12/29/25


SHEET 1 OF 8

L. ROBERTO LOMAS P.E.
208 7th Ave, INDIALANTIC, FL 32903
434-688-0609 rllomas@lrlomaspe.com

SIGNED: 02/24/2026



Luis R. Lomas P.E.
FL No.: 62514



REVISIONS			
REV	DESCRIPTION	DATE	APPROVED

- NOTES:
- PANEL SIZE: 36" X 96 1/4"
 - D.L.O.: 31 3/8" X 91 3/8"

SL 73 OUTSWING BI-FOLD DOOR SYSTEM
INTERIOR VIEW
6 PANELS SHOWN, MULTIPLE PANELS IN MULTIPLE
CONFIGURATIONS ARE APPROVED AS LONG AS TOTAL
FRAME AREA DOES NOT EXCEED 237FT²

STANDARD SILL	
DESIGN PRESSURE RATING	IMPACT RATING
±70.0PSF	LARGE MISSILE IMPACT
MISSILE LEVEL D, WIND ZONE 4 & HVHZ FOR ADDITIONAL SIZES SEE CHART #1 SHEET 3	

SADDLE SILL WATER PENETRATION RESISTANCE IS NOT REQUIRED	
DESIGN PRESSURE RATING	IMPACT RATING
±70.0PSF	LARGE MISSILE IMPACT
MISSILE LEVEL D, WIND ZONE 4 & HVHZ FOR ADDITIONAL SIZES SEE CHART #2 SHEET 3	

SADDLE SILL WATER PENETRATION RESISTANCE IS REQUIRED	
DESIGN PRESSURE RATING	IMPACT RATING
+36.2/-70.0PSF	LARGE MISSILE IMPACT
MISSILE LEVEL D, WIND ZONE 4 & HVHZ FOR ADDITIONAL SIZES SEE CHART #3 SHEET 3	


NANA WALL SYSTEMS, INC.
100 MEADOWCREEK DRIVE, SUITE 250
CORTE MADERA, CA 94925

SL 73 ALUMINUM OUTSWING BI-FOLD DOOR SYSTEM
IMPACT HVHZ
ELEVATIONS

DRAWN: R.L.	DWG NO. 08-04188	REV -
SCALE NTS	DATE 12/29/25	SHEET 2 OF 8

L. ROBERTO LOMAS P.E.
208 7th Ave, INDIALANTIC, FL 32903
434-688-0609 rllomas@lrlomaspe.com

SIGNED: 02/24/2026



Luis R. Lomas P.E.
FL No.: 62514

Rating chart #1 (psf)
Systems with standard sill

Panel Height (in)	Single Panel Width (in)													
	24.00		27.00		30.00		33.00		36.00		39.00		42.00	
	Pos	Neg	Pos	Neg	Pos	Neg	Pos	Neg	Pos	Neg	Pos	Neg	Pos	Neg
80.00	80.0	90.0	80.0	90.0	80.0	90.0	80.0	90.0	80.0	84.2	77.7	77.7	72.2	72.2
84.00	80.0	90.0	80.0	90.0	80.0	90.0	80.0	87.5	80.0	80.2	74.0	74.0	68.8	68.8
87.00	80.0	90.0	80.0	90.0	80.0	90.0	80.0	84.5	77.4	77.4	71.5	71.5	66.4	66.4
90.00	80.0	90.0	80.0	90.0	80.0	87.6	80.0	81.3	74.9	74.9	69.1	69.1	64.2	64.2
93.00	80.0	90.0	80.0	90.0	80.0	84.3	78.1	78.1	72.4	72.4	66.9	66.9	62.1	62.1
96.00	80.0	90.0	80.0	88.5	80.0	81.1	75.2	75.2	70.2	70.2	64.8	64.8	60.2	60.2
96.25	80.0	90.0	80.0	88.3	80.0	80.9	74.9	74.9	70.0	70.0	64.6	64.6	60.0	60.0
99.00	80.0	90.0	80.0	83.5	75.7	75.7	69.4	69.4	64.1	64.1	59.8	59.8	56.1	56.1
102.00	80.0	85.2	76.2	76.2	69.1	69.1	63.2	63.2	58.4	58.4	54.4	54.4	51.0	51.0
105.00	78.0	78.0	69.8	69.8	63.2	63.2	57.8	57.8	53.4	53.4	49.7	49.7	46.6	46.6
108.00	71.6	71.6	64.0	64.0	58.0	58.0	53.0	53.0	49.0	49.0	45.6	45.6	42.7	42.7
111.00	65.9	65.9	58.9	58.9	53.3	53.3	48.7	48.7	45.0	45.0	41.8	41.8	39.2	39.2
114.00	60.8	60.8	54.3	54.3	49.1	49.1	44.9	44.9	41.4	41.4	38.5	38.5	36.0	36.0
117.00	56.2	56.2	50.2	50.2	45.4	45.4	41.5	41.5	38.3	38.3	35.6	35.6	33.3	33.3
120.00	52.0	52.0	46.4	46.4	42.0	42.0	38.4	38.4	35.4	35.4	32.9	32.9	30.7	30.7

MISSILE LEVEL D, WIND ZONE 4 AND HVHZ

Rating chart #2 (psf)
Systems with saddle sill
where water penetration resistance is not required

Panel Height (in)	Single Panel Width (in)													
	24.00		27.00		30.00		33.00		36.00		39.00		42.00	
	Pos	Neg	Pos	Neg	Pos	Neg	Pos	Neg	Pos	Neg	Pos	Neg	Pos	Neg
80.00	90.0	90.0	90.0	90.0	90.0	90.0	90.0	90.0	84.2	84.2	77.7	77.7	72.2	72.2
84.00	90.0	90.0	90.0	90.0	90.0	90.0	87.5	87.5	80.2	80.2	74.0	74.0	68.8	68.8
87.00	90.0	90.0	90.0	90.0	90.0	90.0	84.5	84.5	77.4	77.4	71.5	71.5	66.4	66.4
90.00	90.0	90.0	90.0	90.0	87.6	87.6	81.3	81.3	74.9	74.9	69.1	69.1	64.2	64.2
93.00	90.0	90.0	90.0	90.0	84.3	84.3	78.1	78.1	72.4	72.4	66.9	66.9	62.1	62.1
96.00	90.0	90.0	88.5	88.5	81.1	81.1	75.2	75.2	70.2	70.2	64.8	64.8	60.2	60.2
96.25	90.0	90.0	88.3	88.3	80.9	80.9	74.9	74.9	70.0	70.0	64.6	64.6	60.0	60.0
99.00	90.0	90.0	83.5	83.5	75.7	75.7	69.4	69.4	64.1	64.1	59.8	59.8	56.1	56.1
102.00	85.2	85.2	76.2	76.2	69.1	69.1	63.2	63.2	58.4	58.4	54.4	54.4	51.0	51.0
105.00	78.0	78.0	69.8	69.8	63.2	63.2	57.8	57.8	53.4	53.4	49.7	49.7	46.6	46.6
108.00	71.6	71.6	64.0	64.0	58.0	58.0	53.0	53.0	49.0	49.0	45.6	45.6	42.7	42.7
111.00	65.9	65.9	58.9	58.9	53.3	53.3	48.7	48.7	45.0	45.0	41.8	41.8	39.2	39.2
114.00	60.8	60.8	54.3	54.3	49.1	49.1	44.9	44.9	41.4	41.4	38.5	38.5	36.0	36.0
117.00	56.2	56.2	50.2	50.2	45.4	45.4	41.5	41.5	38.3	38.3	35.6	35.6	33.3	33.3
120.00	52.0	52.0	46.4	46.4	42.0	42.0	38.4	38.4	35.4	35.4	32.9	32.9	30.7	30.7

MISSILE LEVEL D, WIND ZONE 4 AND HVHZ

Rating chart #3 (psf)
Systems with saddle sill
where water penetration resistance is required

Panel Height (in)	Single Panel Width (in)													
	24.00		27.00		30.00		33.00		36.00		39.00		42.00	
	Pos	Neg	Pos	Neg	Pos	Neg	Pos	Neg	Pos	Neg	Pos	Neg	Pos	Neg
80.00	36.2	90.0	36.2	90.0	36.2	90.0	36.2	90.0	36.2	84.2	36.2	77.7	36.2	72.2
84.00	36.2	90.0	36.2	90.0	36.2	90.0	36.2	87.5	36.2	80.2	36.2	74.0	36.2	68.8
87.00	36.2	90.0	36.2	90.0	36.2	90.0	36.2	84.5	36.2	77.4	36.2	71.5	36.2	66.4
90.00	36.2	90.0	36.2	90.0	36.2	87.6	36.2	81.3	36.2	74.9	36.2	69.1	36.2	64.2
93.00	36.2	90.0	36.2	90.0	36.2	84.3	36.2	78.1	36.2	72.4	36.2	66.9	36.2	62.1
96.00	36.2	90.0	36.2	88.5	36.2	81.1	36.2	75.2	36.2	70.2	36.2	64.8	36.2	60.2
96.25	36.2	90.0	36.2	88.3	36.2	80.9	36.2	74.9	36.2	70.0	36.2	64.6	36.2	60.0
99.00	36.2	90.0	36.2	83.5	36.2	75.7	36.2	69.4	36.2	64.1	36.2	59.8	36.2	56.1
102.00	36.2	85.2	36.2	76.2	36.2	69.1	36.2	63.2	36.2	58.4	36.2	54.4	36.2	51.0
105.00	36.2	78.0	36.2	69.8	36.2	63.2	36.2	57.8	36.2	53.4	36.2	49.7	36.2	46.6
108.00	36.2	71.6	36.2	64.0	36.2	58.0	36.2	53.0	36.2	49.0	36.2	45.6	36.2	42.7
111.00	36.2	65.9	36.2	58.9	36.2	53.3	36.2	48.7	36.2	45.0	36.2	41.8	36.2	39.2
114.00	36.2	60.8	36.2	54.3	36.2	49.1	36.2	44.9	36.2	41.4	36.2	38.5	36.0	36.0
117.00	36.2	56.2	36.2	50.2	36.2	45.4	36.2	41.5	36.2	38.3	35.6	35.6	33.3	33.3
120.00	36.2	52.0	36.2	46.4	36.2	42.0	36.2	38.4	35.4	35.4	32.9	32.9	30.7	30.7

MISSILE LEVEL D, WIND ZONE 4 AND HVHZ

HARDWARE SCHEDULE	
A.	(1) CONCEALED 3-POINT LOCKING SYSTEM AT SWING PANEL. ALTERNATE: DEAD BOLT WITH FLUSH BOLT AT TOP AND BOTTOM
B.	(3) 2-POINT LOCKING SYSTEM WITH HANDLE BETWEEN BI-FOLD PANELS AT HEAD SILL AND SWING PANEL
C.	(2) TWO WHEEL SEALED BALL BEARING CARRIAGE SYSTEM AT BOTTOM OF ROLLER POSTS
D.	(2) UPPER GUIDE CARIAGE SYSTEM AT TOP OF EACH ROLLER POST

REVISIONS			
REV	DESCRIPTION	DATE	APPROVED

- NOTES:
- WATER PENETRATION RESISTANCE IS NOT REQUIRED WHEN UNITS ARE INSTALLED IN AREAS WHERE OVERHANG RATIO IS EQUAL OR GREATER THAN 1 OR IN NON-HABITABLE AREAS DESIGNED TO ACCEPT WATER INFILTRATION.
 - NUMBER OF HINGES REQUIRED IS ACCORDING TO PANEL HEIGHT AND VARIES FROM 3 TO 7 PER JOINT.

SIGNED: 02/24/2026

NANA WALL SYSTEMS, INC.
100 MEADOWCREEK DRIVE, SUITE 250
CORTE MADERA, CA 94925

SL 73 ALUMINUM OUTSWING BI-FOLD DOOR SYSTEM
IMPACT HVHZ
RATING CHARTS

DRAWN:
R.L.

DWG NO.
08-04188


REV
—

SCALE
NTS

DATE
12/29/25


SHEET
3 OF 8

L. ROBERTO LOMAS P.E.
208 7th Ave, INDIALANTIC, FL 32903
434-688-0609 rllomas@lrlomaspe.com



Luis R. Lomas P.E.
FL No.: 62514


REVISIONS			
REV	DESCRIPTION	DATE	APPROVED



APPROVED CONFIGURATIONS (REFERENCE ONLY)
CONFIGURATIONS ARE NOT LIMITED TO THE ONES SHOWN HEREIN,
MULTIPLE PANELS IN MULTIPLE CONFIGURATIONS ARE APPROVED.
REFER TO SHEET 2 FOR LIMITATIONS


NANA WALL SYSTEMS, INC. 100 MEADOWCREEK DRIVE, SUITE 250 CORTE MADERA, CA 94925		
SL 73 ALUMINUM OUTSWING BI-FOLD DOOR SYSTEM IMPACT HVHZ APPROVED CONFIGURATIONS		
DRAWN: R.L.	DWG NO. 08-04188	REV -
SCALE NTS	DATE 12/29/25	SHEET 4 OF 8
L. ROBERTO LOMAS P.E. 208 7th Ave, INDIALANTIC, FL 32903 434-688-0609 rllomas@lrlomaspe.com		

SIGNED: 02/24/2026




Luis R. Lomas P.E.
FL No.: 62514


REVISIONS			
REV	DESCRIPTION	DATE	APPROVED




running carriage left side jamb




with running carriage set




lock




hinge at right side jamb




locking left side jamb



lock left panel open first



folding to opposite sides



locking on left and runnig carriage on right

SIGNED: 02/24/2026

NANA WALL SYSTEMS, INC.

100 MEADOWCREEK DRIVE, SUITE 250

CORTE MADERA, CA 94925

SL 73 ALUMINUM OUTSWING BI-FOLD DOOR SYSTEM

IMPACT HVHZ

HORIZONTAL CROSS SECTIONS

DRAWN: R.L.

DWG NO. 08-04188

REV -

SCALE NTS


DATE 12/29/25

SHEET 5 OF 8

L. ROBERTO LOMAS P.E.

208 7th Ave, INDIALANTIC, FL 32903

434-688-0609 rllomas@lrlomaspe.com



MIN EDGE DISTANCE
SEE CHART #4

SUBSTRATE
BY OTHERS
SEE CHART #4

BACKER ROD
& APPROVED
SEALANT

MIN EMBEDMENT
SEE CHART #4

3/8" MAX
SHIM SPACE

1/4" ANCHOR
SEE CHART #4

3/4" DIAMETER
WASHER

EXTERIOR

INTERIOR

3/4" DIAMETER
WASHER

BACKER ROD
& APPROVED
SEALANT

SUBSTRATE
BY OTHERS
SEE CHART #4

1/4" ANCHOR
SEE CHART #4

SILL TO BE SET
IN A BED OF
APPROVED SEALANT

3/8" MAX SHIM
SPACE

MIN EMBEDMENT
SEE CHART #4

MIN EDGE DISTANCE
SEE CHART #4

VERTICAL CROSS SECTION

EXTERIOR

INTERIOR

1/4" ANCHOR
SEE CHART #4

SILL TO BE SET
IN A BED OF
APPROVED SEALANT

BACKER ROD
& APPROVED
SEALANT

SUBSTRATE
BY OTHERS
SEE CHART #4

MIN EDGE DISTANCE
SEE CHART #4

3/4" DIAMETER
WASHER

3/8" MAX
SHIM SPACE

MIN EMBEDMENT
SEE CHART #4

VERTICAL CROSS SECTION WITH SADDLE SILL

MIN EMBEDMENT
SEE CHART #4

3/8" MAX SHIM
SPACE

SUBSTRATE
BY OTHERS
SEE CHART #5

1/4" ANCHOR
SEE CHART #4

MIN EDGE
DISTANCE
SEE CHART #4

BACKER ROD
& APPROVED
SEALANT

3/4" DIAMETER
WASHER

INTERIOR

EXTERIOR

JAMB INSTALLATION DETAIL

ANCHOR CHART #4

SUBSTRATE	ANCHOR	MINIMUM EDGE DISTANCE	MINIMUM EMBEDMENT
WOOD FRAME OR 2X BUCK	1/4" WOOD SCREW	3/4"	1 1/4"
METAL FRAMING OR METAL STRUCTURE	1/4" SMS OR 1/4" SELF DRILLING SCREW	3/4"	THREE THREADS MINIMUM BEYOND INTERIOR WALL
CONCRETE	1/4" TAPCON	2"	1 3/4"
MASONRY BLOCK GROUT FILLED	1/4" TAPCON	2"	1 3/4"

ANCHORS SHOULD BE WASHER HEAD AND EMPLOY A 3/4" DIAMETER WASHER
REFER TO NOTES 14 AND 15, SHEET 1

NOTES:

- INTERIOR AND EXTERIOR FINISHES, BY OTHERS, NOT SHOWN FOR CLARITY.
- PERIMETER AND JOINT SEALANT BY OTHERS TO BE DESIGNED IN ACCORDANCE WITH ASTM E2112
- WEEPS NOT SHOWN FOR CLARITY

NANA WALL SYSTEMS, INC.

100 MEADOWCREEK DRIVE, SUITE 250
CORTE MADERA, CA 94925

SL 73 ALUMINUM OUTSWING BI-FOLD DOOR SYSTEM
IMPACT HVHZ
(1) ANCHOR INSTALLATION DETAILS

DRAWN:

R.L.

DWG NO.

08-04188

REV

-

SCALE NTS

DATE


12/29/25

SHEET 6 OF 8

L. ROBERTO LOMAS P.E.


208 7th Ave, INDIALANTIC, FL 32903
434-688-0609 rllomas@lrlomaspe.com

SIGNED: 02/24/2026




Luis R. Lomas P.E.
FL No.: 62514

REVISIONS			
REV	DESCRIPTION	DATE	APPROVED




GLASS CHART #5		
GLASS TYPE	OVERALL WIDTH (IN)	DESCRIPTION (FROM EXTERIOR TO INTERIOR)
A	7/16"	3/16" HS - .090" SG BY KURARAY - 3/16" HS
B	9/16"	1/4" HS - .090" SG BY KURARAY - 1/4" HS
C	7/16"	3/16" ANN - .090" SG BY KURARAY - 3/16" ANN
D	9/16"	1/4" ANN - .090" SG BY KURARAY - 1/4" ANN



GLASS CHART #6		
GLASS TYPE	OVERALL WIDTH (IN)	DESCRIPTION (FROM EXTERIOR TO INTERIOR)
E	1 1/8"	3/16" TEMP - AIR - 3/16" HS - .090" SG BY KURARAY - 3/16" HS
F	1 1/8"	1/4" TEMP - AIR - 3/16" HS - .090" SG BY KURARAY - 3/16" HS
G	1 1/8"	3/16" TEMP - AIR - 3/16" ANN - .090" SG BY KURARAY - 3/16" ANN
H	1 1/8"	1/4" TEMP - AIR - 3/16" ANN - .090" SG BY KURARAY - 3/16" ANN

PLASTIC HYBRID
SST SPACER SYSTEM
TECHNOFORM TIS0102




GLASS CHART #7		
GLASS TYPE	OVERALL WIDTH (IN)	DESCRIPTION (FROM EXTERIOR TO INTERIOR)
I	1 7/16"	3/16" TEMP - AIR - 1/32" ANN - AIR - 3/16" HS - .090" SG BY KURARAY - 3/16" HS
J	1 7/16"	3/16" TEMP - AIR - 1/32" ANN - AIR - 3/16" ANN - .090" SG BY KURARAY - 3/16" ANN
K	1 1/2"	1/4" TEMP - AIR - 1/32" ANN - AIR - 3/16" HS - .090" SG BY KURARAY - 3/16" HS
L	1 1/2"	1/4" TEMP - AIR - 1/32" ANN - AIR - 3/16" ANN - .090" SG BY KURARAY - 3/16" ANN
M	1 9/16"	3/16" TEMP - AIR - 1/32" ANN - AIR - 1/4" HS - .090" SG BY KURARAY - 1/4" HS
N	1 9/16"	3/16" TEMP - AIR - 1/32" ANN - AIR - 1/4" ANN - .090" SG BY KURARAY - 1/4" ANN


PLASTIC HYBRID
SST SPACER SYSTEM
TECHNOFORM TIS0102

SIGNED: 02/24/2026


NANA WALL SYSTEMS, INC. 100 MEADOWCREEK DRIVE, SUITE 250 CORTE MADERA, CA 94925		
SL 73 ALUMINUM OUTSWING BI-FOLD DOOR SYSTEM IMPACT HVHZ GLASS DETAILS		
DRAWN: R.L.	DWG NO. 08-04188	REV -
SCALE NTS	DATE 12/29/25	SHEET 7 OF 8
L. ROBERTO LOMAS P.E. 208 7th Ave, INDIALANTIC, FL 32903 434-688-0609 rllomas@lrlomaspe.com		




Luis R. Lomas P.E.
FL No.: 62514




FRAME STD SILL
ALUMINUM 6063-T5 .079" THICK




PANEL STILE/RAIL
ALUMINUM 6063-T5 .071" THICK




SADDLE SILL
ALUMINUM 6063-T5 .077" THICK




POST
ALUMINUM 6063-T5 .067" THICK




SLIDING POST
ALUMINUM 6063-T5 .067" THICK




GLAZING BEAD
ALUMINUM 6063-T5 .079" THICK



GLAZING BEAD
ALUMINUM 6063-T5 .079" THICK



GLAZING BEAD
ALUMINUM 6063-T5 .079" THICK



PANEL BOTTOM RAIL
W/KICK PLATE

REVISIONS			
REV	DESCRIPTION	DATE	APPROVED

SIGNED: 02/24/2026

NANA WALL SYSTEMS, INC. 100 MEADOWCREEK DRIVE, SUITE 250 CORTE MADERA, CA 94925		
SL 73 ALUMINUM OUTSWING BI-FOLD DOOR SYSTEM IMPACT HVHZ COMPONENTS		
DRAWN: R.L.	DWG NO. 08-04188	REV -
SCALE NTS	DATE 12/29/25	SHEET 8 OF 8
L. ROBERTO LOMAS P.E. 208 7th Ave, INDIALANTIC, FL 32903 434-688-0609 rllomas@lrlomaspe.com		

Luis R. Lomas P.E.
FL No.: 62514