






① TYPICAL ELEVATION
Scale: NTS



GLAZING DETAIL
Scale: 2:1
FRAME SECTION (TYP)
VERTICAL SECTION



③ HORIZONTAL JAMB SECTION
Scale: NTS


Custom Epic Clad OSW French 2 Panel Door		
MAX. FRAME SIZE (in)	D.P. (psf)	IMPACT
69.813 x 83.438	+ 50 / - 50	WZ 3 - LVL D

General Notes:


- The product shown herein is designed, tested and manufactured to comply with the wind load criteria of the adopted International Building Code (IBS), the International Residential Code (IRC), the current Florida Building Code (FBC) and the industry requirement for the stated conditions.
- All glazing shall conform to ASTM E1300.
- At minimum, glazing shall be 4.7 mm annealed - 8.3 mm airspace - 3.0 mm annealed - 2.3 mm SGP interlayer - 3.0 mm annealed insulating glass.
- Use structural or composite shims where required.
- This drawing only addresses the fasteners required to anchor the unit to achieve the rated design pressure and impact performance (where applicable) up to the size limitations noted. It is not intended as a guide to the installation process and does not address the sealing consideration that may arise in different wall conditions. For the complete installation procedure, see the instructions packaged with the unit or go to www.jeld-wen.com

Installation Notes:

- Seal flange/frame to substrate. Sill shall be set on a continuous serpentine bead of structural grade silicone caulk when no fastener is used to anchor the sill (typical).
- Use #10 PH or greater fastener through the frame with sufficient length to penetrate a minimum of 1-1/2" into the wood framing. For 2x wood frame substrate (min. S.G. = 0.42)
- Host Structure (wood buck, masonry, steel) to be designed and anchored to properly transfer all loads to the structure. The host structure is the responsibility of the architect or engineer of record for the project of installation.



This item has been digitally signed and sealed by Micah Swartz, P.E. on the date adjacent to the seal. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies



5134 Cambridge Ct.
Klamath Falls, OR 97603

Phone: (541) 363-8075

info@swartzeng.com
www.swartzeng.com

Owner / Client:
Jeld-Wen Windows &
Doors

3737 Lakeport Dr.
Klamath Falls, OR
97601

Drawing No:
SCE 2512002

REVISION SCHEDULE	DATE	DESCRIPTION	MARK

DRAWN BY: M.S.


DS. BY: M.S.

DATE: 12/19/2025

TITLE:
Elevations and
Details - Thru Frame
into Wood Framing

SHEET NO:

Sheet 1 of 2




① TYPICAL ELEVATION
Scale: NTS

General Notes:


1. The product shown herein is designed, tested and manufactured to comply with the wind load criteria of the adopted International Building Code (IBC), the International Residential Code (IRC), the current Florida Building Code (FBC) and the industry requirement for the stated conditions.
2. All glazing shall conform to ASTM E1300.
3. At minimum, glazing shall be 4.7 mm annealed - 8.3 mm airspace - 3.0 mm annealed - 2.3 mm SGP interlayer - 3.0 mm annealed insulating glass.
4. Use structural or composite shims where required.
5. This drawing only addresses the fasteners required to anchor the unit to achieve the rated design pressure and impact performance (where applicable) up to the size limitations noted. It is not intended as a guide to the installation process and does not address the sealing consideration that may arise in different wall conditions. For the complete installation procedure, see the instructions packaged with the unit or go to www.jeld-wen.com

Installation Notes:

1. Seal flange/frame to substrate. Sill shall be set on a continuous serpentine bead of structural grade silicone caulk when no fastener is used to anchor the sill (typical).
2. Use 1/4" tapcon or equivalent fastener through frame with sufficient length to penetrate a minimum of 1-1/4" into concrete or masonry at each location with a 2-1/2" min edge distance. For concrete (min f'c = 3,000 psi) or masonry substrate (CMU shall adhere to ASTM C90).
3. Host Structure (wood buck, masonry, steel) to be designed and anchored to properly transfer all loads to the structure. The host structure is the responsibility of the architect or engineer of record for the project of installation.




② VERTICAL FRAME SECTION
Scale: NTS



③ HORIZONTAL JAMB SECTION
Scale: NTS

Custom Epic Clad OSW French 2 Panel Door

MAX. FRAME SIZE (in)	D.P. (psf)	IMPACT
69.813 x 83.438	+ 50 / - 50	WZ 3 - LVL D



This item has been digitally signed and sealed by Micah Swartz, P.E. on the date adjacent to the seal. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies



5134 Cambridge Ct.
Klamath Falls, OR 97603

Phone: (541) 363-8075

info@swartzeng.com
www.swartzeng.com

Owner / Client:
Jeld-Wen Windows &
Doors

3737 Lakeport Dr.
Klamath Falls, OR
97601

Drawing No:
SCE 2512002

REVISION SCHEDULE	DATE	DESCRIPTION	MARK				

DRAWN BY: M.S.

DS. BY: M.S.

DATE: 12/19/2025

TITLE:
Elevations and
Details -
Concrete/Masonry
Installation

SHEET NO:

Sheet 2 of 2