



This evaluation report is provided for State of Florida product approval under Rule 61G20-3. The manufacturer shall notify CREEK Technical Services, LLC of any product changes or quality assurance changes throughout the duration for which this report is valid. This evaluation report does not express nor imply warranty, installation, recommended use, or other product attributes that are not specifically addressed herein.


PRODUCT APPLICATION

Deck Type: Minimum 15/32-inch APA span rated plywood sheathing for new and existing roof deck (Deck shall be designed by others in accordance with FBC requirements).

Attachment Method: Cut a 46" x 3-1/2" slot according to manufacturer's instructions through the deck and sheathing. For a single vent, install the vent as close to the center of the roof length as possible. Multiple vents should be evenly spaced along the roof length.

Attach the vent with minimum 12 ga. galvanized, ring shank roofing nails with minimum 3/8-inch diameter head and sufficient length to penetrate through the sheathing a minimum 3/8-inch. Nails shall be installed 4-inch o.c. in a staggered pattern along all four sides of the vent flange. The flange edge and all exposed fasteners shall be covered and sealed with ASTM D 1668 fabric embedded in ASTM D 4586 roof cement.

Maximum Design Pressures: **-67.5 psf**
Pressures calculated using 2:1 margin of safety per 1504.9




LIMITATIONS

- 1) This report is not for use in the HVHZ.
- 2) Fire Classification is outside the scope of this evaluation.
- 3) The roof deck and deck attachment shall be designed by others in accordance with the FBC.
- 4) Off ridge vents shall be installed in strict compliance with this evaluation report and the manufacturer's published installation instructions. In the event of conflict, the more restrictive installation shall be enforced.
- 5) Deck substrates shall be clean, dry, and free from any irregularities and debris. All fasteners in the deck shall be checked for protrusion prior to installation.
- 6) Installation of the roof assembly is outside the scope of this evaluation.
- 7) Off ridge vents are intended to provide passive ventilation for an enclosed attic in residential construction applications
- 8) All products listed in this report shall be manufactured under a quality assurance program in compliance with Rule 61G20-3.

COMPLIANCE STATEMENT

This report has been prepared in accordance with F.A.C. Rule 61G20-3.



This item has been
digitally signed and
sealed by Zachary R.
Priest, PE, on 12/13/2024.

Printed copies of this
document are not
considered signed and
sealed and the signature
must be verified on any
electronic copies.



Digitally signed by Zachary R. Priest
CREEK Technical Services, LLC

2024.12.1
3 11:51:56
-05'00'

Zachary R. Priest, P.E.
Florida Registration No. 74021
Organization No. ANE9641

CERTIFICATION OF INDEPENDENCE

CREEK Technical Services, LLC does not have, nor will it acquire, a financial interest in any company manufacturing or distributing products under this evaluation.

CREEK Technical Services, LLC is not owned, operated, or controlled by any company manufacturing or distributing products under this evaluation.

Zachary R. Priest, P.E. does not have, nor will acquire, a financial interest in any company manufacturing or distributing products under this evaluation.

Zachary R. Priest, P.E. does not have, nor will acquire, a financial interest in any other entity involved in the approval process of the product.

END OF REPORT