



H3 2.0 Double Hung Operating Window 3-Wide Unit 120" x 83 1/2" Integral Vinyl Nail Fin Installation / Non-Impact

CCL Listing# 436-H-671.50,53

ELEMENT TEST REPORT NUMBER: ESP022630P-1920

H3 2.0 Aluminum Clad/Wood Composite Double Hung Operating Window Integral Vinyl Nail Fin Installation / WDMA Instructions / Non-Impact

SHEET: 1 OF 3

DRAWN BY: B.K.

TEST REPORT SUMMARY:

3-WIDE OPERATING MAXIMUM BASIC UNIT

FRAME SIZE: 120"(3048mm) x 83 1/2"(2121mm)

- OVERALL DESIGN PRESSURE: (STD)±35.19 psf
(HP)+60.15/-55.14 psf
- STRUCTURAL TEST PRESSURE: (STD)±52.63 psf
(HP)±82.71 psf
- RATING: (STD)LC-PG35
(HP)LC-PG50


GENERAL INSTALLATION NOTES:

- Check rough opening for proper size, plumb, level and square.
- Make all necessary adjustments to ensure rough opening is plumb, level & square.
- Sill must be flat, level and capable of supporting the weight of the unit.
- Opening should allow a maximum of 1/4" shim space at head, sill and each jamb.
- Consult full installation instructions found on the Sierra Pacific web site, www.hurd.com, for all recommended installation procedures.
- Wood buck, framing, fasteners, sealant and all wall system materials are provided by others

FLASHING:


- For units that have to meet a specific DP (Design Pressure) rating, any kind of building wrap must be folded and taped away from each rough opening before the unit is installed. Unit must come in contact with the building's bare sheathing. A bead of silicone must be applied to the backside of the nail fin where it meets the unit, at head and jambs.
- Once unit is installed and flashed properly, untape the building wrap and trim flush with the unit's exterior. A bead of sealant must be placed along the seam joint of the building wrap and the unit. Tape the corner cuts in the building wrap. See full window installation brochure for complete flashing details.

COMMON MULL DETAIL AT SILL H3 2.0 CLAD DOUBLE HUNG WINDOW OPERATING SASH



The High Performance upgrade requires one installation clip placed at each mull post end location, head and sill, and secured to the buck with two #8 x 32mm (1-1/4") PPH screws.


JAMB DETAIL H3 2.0 OPERATING DOUBLE HUNG




INSTALLATION NOTES:

1. USE 2" x _ PINE FOR WOOD BUCK
 - PLACE WOOD SHIMS EVERY 6-10"
2. 1/4" MAXIMUM SHIM SPACE AT HEAD, SILL & EACH JAMB
3. APPLY A CONTINUOUS BEAD OF SEALANT BETWEEN THE INTEGRAL VINYL NAIL FIN AND THE BUCK AT THE HEAD, SILL AND SIDE JAMBS TO SECURE INTEGRAL VINYL NAIL FIN TO FRAMING MATERIAL
4. INSTALL #8 X 1-1/4" PPH SCREWS SPACED APPROXIMATELY 2"-4" FROM EACH CORNER AND 4"-6" ON CENTER THEREAFTER, THROUGH THE INTEGRAL VINYL NAIL FIN INTO THE FRAMING MATERIAL, AT HEAD, SILL AND SIDE JAMBS; 3/8" MIN EDGE DISTANCE
5. 1" MINIMUM FASTENER EMBEDMENT INTO FRAMING MATERIAL
SILICONE SEAL OVER SCREW HEADS
6. MAXIMUM OVERALL BASIC UNIT WINDOW SIZE:
120" (3048mm) x 83 1/2" (2121mm)

HEAD DETAIL H3 2.0 OPERATING DOUBLE HUNG



MEETING RAIL DETAIL H3 2.0 OPERATING DOUBLE HUNG



SILL DETAIL H3 2.0 OPERATING DOUBLE HUNG



H3 2.0 Double Hung Operating Window
3-Wide Unit 120" x 83 1/2"
Integral Vinyl Nail Fin Installation / Non-Impact

CCL Listing# 436-H-671.50,53

ELEMENT TEST REPORT NUMBER: ESP022630P-1920

H3 2.0 Aluminum Clad/Wood Composite Double Hung Operating Window
Integral Vinyl Nail Fin Installation / WDMA Instructions / Non-Impact

SHEET: 2 OF 3


DRAWN BY: B.K.

TEST REPORT SUMMARY:

3-WIDE OPERATING MAXIMUM BASIC UNIT
FRAME SIZE: 120"(3048mm) x 83 1/2"(2121mm)

- OVERALL DESIGN PRESSURE: (STD)±35.19 psf
(HP)+60.15/-55.14 psf
- STRUCTURAL TEST PRESSURE: (STD)±52.63 psf
(HP)±82.71 psf
- RATING: (STD)LC-PG35
(HP)LC-PG50

The High Performance upgrade requires one installation clip placed at each mull post end location, head and sill, and secured to the buck with two #8 x 32mm (1-1/4") PPH screws.



Installation requirements may vary in particular locations and in other types of construction. Proper installation is essential, and Sierra Pacific Windows, recommends consultation with an AAMA Certified Installer, or other qualified, registered building professional before installation of any Sierra Pacific product. Proper installation of Sierra Pacific products is the responsibility of the installer. Sierra Pacific is not responsible for proper installation. Sierra Pacific is not responsible for the design of, conditions in, or performance of building construction beyond the perimeters of the Sierra Pacific units. Sierra Pacific is not responsible for proper integration of the Sierra Pacific units with the weather-repellent systems of the building.



H3 2.0 Double Hung Operating Window
3-Wide Unit 120" x 83 1/2"
Integral Vinyl Nail Fin Installation / Non-Impact

CCL Listing# 436-H-671.50,53

ELEMENT TEST REPORT NUMBER: ESP022630P-1920

H3 2.0 Aluminum Clad/Wood Composite Double Hung Operating Window
Integral Vinyl Nail Fin Installation / WDMA Instructions / Non-Impact

SHEET: 3 OF 3

DRAWN BY: B.K.

TEST REPORT SUMMARY:

3-WIDE OPERATING MAXIMUM BASIC UNIT FRAME
SIZE: 120" (3048mm) x 83 1/2" (2121mm)

- OVERALL DESIGN PRESSURE: (STD) ± 35.19 psf
(HP) $+60.15/-55.14$ psf
- STRUCTURAL TEST PRESSURE: (STD) ± 52.63 psf
(HP) ± 82.71 psf
- RATING: (STD) LC-PG35
(HP) LC-PG50

ELEVATION VIEWED FROM EXTERIOR
SHOWING FASTENER LOCATION & SPACING (TYP.)

The High Performance upgrade requires one installation clip placed at each mull post end location, head and sill, and secured to the buck with two #8 x 32mm (1-1/4") PPH screws.

