



Monument Clad Wood
Double Hung Operating 2-Wide Window Tested Size
74 3/8" X 76 5/8"
Vinyl Fin Installation / Non-Impact

CCL Listing# 436-H-615.64

Architectural Testing Report #: D9790.01-602-44

Monument Clad Wood Double Hung Operating Mullered Window
Aluminum Nail Fin Installation / WDMA Instructions / Non-Impact

SHEET: 1 OF 2

UPDATED: 11/10/2017



DRAWN BY: A.E.

TEST REPORT SUMMARY:

- **2-WIDE UNIT SHOWN. More than 2 windows may be mulled together (Mullion may be Horizontal or Vertical)**
- **SINGLE UNIT BASIC UNIT FRAME SIZE:**
37.9375" (948mm) x 76.625" (1946mm)
- **OVERALL DESIGN PRESSURE: +65 / -65 psf**
- **STRUCTURAL TEST PRESSURE: +97.74 / -97.74 psf**
- **RATING: LC-PG65**

- Check rough opening for proper size, plumb, level and square.
- Make all necessary adjustments, if necessary, to ensure rough opening is plumb, level & square.
- Sill must be flat, level and capable of supporting the weight of the window unit.
- Opening should allow a maximum of 1/4" shim space at head, sill and jambs.
- Consult full installation instructions found on the Sierra Pacific web site, www.sierrapacificwindows.com, for all recommended installation procedures.
- Wood buck, framing, fasteners, sealant and all wall system materials are provided by others.


A 1 HEAD DETAIL
 MONUMENT CLAD DOUBLE HUNG WINDOW



E 1 MULL DETAIL
 MONUMENT CLAD DOUBLE HUNG WINDOW

D 1 JAMB DETAIL
 MONUMENT CLAD DOUBLE HUNG WINDOW

B 1 MEETING RAIL DETAIL
 MONUMENT CLAD DOUBLE HUNG WINDOW



INSTALLATION NOTES:

1. USE 2" x _ BUCK
2. 1/4" MAXIMUM SHIM SPACE AT HEAD, SILL, JAMB
 - PLACE WOOD SHIM EVERY 6-10"
3. APPLY A CONTINUOUS BEAD OF SEALANT BETWEEN THE VINYL NAIL FIN AT HEAD, SIDES & SILL AND THE BUCK
4. INSTALL #8 X 1-1/4" PPH SCREWS SPACED 1-3" FROM EACH CORNER AND 7" ON CENTER THEREAFTER INTO THE FRAMING MATERIAL, THROUGH MANUFACTURER APPLIED VINYL NAIL FIN AT HEAD, SILL & SIDE JAMBS.
 - CONTINUOUS BEAD OF SILICONE ACROSS ENTIRE LENGTH OF NAIL FIN
5. 1" MINIMUM FASTENER EMBEDMENT INTO FRAMING MATERIAL
 - SILICONE SEAL OVER SCREW HEADS
6. MAXIMUM **INDIVIDUAL** WINDOW FRAME SIZE: 37.3125" (948mm) x 76.625" (1946mm)

Note: Qualifies Multiple Wide OR Multiple High Window Configurations

Installation requirements may vary in particular locations and in other types of construction. Proper installation is essential, and Sierra Pacific Windows, recommends consultation with an AAMA Certified Installer, or other qualified, registered building professional before installation of any Sierra Pacific product. Proper installation of Sierra Pacific products is the responsibility of the installer. Sierra Pacific is not responsible for proper installation. Sierra Pacific is not responsible for the design of, conditions in, or performance of building construction beyond the perimeters of the Sierra Pacific units. Sierra Pacific is not responsible for proper integration of the Sierra Pacific units with the weather-repellent systems of the building.



Monument Clad Wood
Double Hung Operating 2-Wide Window
74 3/4" X 76 5/8"
Vinyl Fin Installation / Non-Impact

CCL Listing# 436-H-615.64

Architectural Testing Report #: D9790.01-602-44

Monument Clad Wood Double Hung Operating Mullied Window
Aluminum Nail Fin Installation / WDMA Instructions / Non-Impact

SHEET: 2 OF 2


UPDATED: 11/10/2017

DRAWN BY: A.E.

TEST REPORT SUMMARY:

- **2-WIDE UNIT SHOWN.** More than 2 windows may be mullied together (Mullion may be Horizontal or Vertical)
- **SINGLE UNIT BASIC UNIT FRAME SIZE:**
37.9375" (948mm) x 76.625" (1946mm)
- **OVERALL DESIGN PRESSURE:** +65 / -65 psf
- **STRUCTURAL TEST PRESSURE:** +97.74 / -97.74 psf
- **RATING:** LC-PG65

NAIL FIN ANCHOR REQUIREMENTS TABLE			
THROUGH NAIL FIN UTILIZING SCREWS			
OPENING TYPE (SUBSTRATE)	JAMB TO OPENING FASTENER TYPE, FASTENER SPACING	MINIMUM EMBED	MINIMUM EDGE DIST.
2X_ WOOD FRAME OR BUCK	#8 X 1-1/4" PPH SCREWS SPACED 1-3" FROM EACH CORNER & 7" ON CENTER THEREAFTER.	1"	3/4"
ANCHORS MUST BE INTO A MIN. 2X_ WOOD FRAME OR BUCK. IF SPACE BETWEEN WALL FRAME & WINDOW FRAME IS GREATER THAN THAT REQUIRED FOR A 2X_ WOOD FRAME OF BUCK AND A SPACE EXISTS, THE SPACE MUST BE FILLED WITH A WOOD MEMBER OF EQUAL DEPTH TO THE WINDOW FRAME MEMBER OR BUCK AND OF LENGTH = MIN. 20". THE FRAME ANCHOR MUST THEN BE RUN THROUGH THE FRAME & WOOD SHIM AND INTO THE OPENING.			



Installation requirements may vary in particular locations and in other types of construction. Proper installation is essential, and Sierra Pacific Windows, recommends consultation with an AAMA Certified Installer, or other qualified, registered building professional before installation of any Sierra Pacific product. Proper installation of Sierra Pacific products is the responsibility of the installer. Sierra Pacific is not responsible for proper installation. Sierra Pacific is not responsible for the design of, conditions in, or performance of building construction beyond the perimeters of the Sierra Pacific units. Sierra Pacific is not responsible for proper integration of the Sierra Pacific units with the weather-repellent systems of the building.