



Monument Clad Wood
Double Hung Operating 2-Wide Window
74 5/8" X 76 5/8"
Vinyl Fin Installation / Non-Impact

CCL Listing# 436-H-615.79

ELEMENT TEST REPORT NUMBER: ESP016205P-1530

Monumnet Clad Wood Double Hung Operating Mullled Window
Aluminum Nail Fin Installation / WDMA Instructions / Non-Impact

SHEET: 1 OF 2


Updated: 11/21/2017

DRAWN BY: A.E.


TEST REPORT SUMMARY:

- 2-WIDE UNIT SHOWN. More than 2 windows may be mulled together (Mullion may be Horizontal or Vertical)
- SINGLE UNIT BASIC UNIT FRAME SIZE:
37.31" (953mm) x 76.63" (1946mm)
- OVERALL DESIGN PRESSURE: +45 / -45 psf
- STRUCTURAL TEST PRESSURE: +67.67 / -67.67 psf
- RATING: R-PG45


- Check rough opening for proper size, plumb, level and square.
- Make all necessary adjustments, if necessary, to ensure rough opening is plumb, level & square.
- Sill must be flat, level and capable of supporting the weight of the window unit.
- Opening should allow a maximum of 1/4" shim space at head, sill and jambs.
- Consult full installation instructions found on the Sierra Pacific Window web site, www.sierrapacificwindows.com, for all recommended installation procedures.
- Wood buck, framing, fasteners, sealant and all wall system materials are provided by others.



MULL DETAIL
MONUMENT CLAD DOUBLE HUNG WINDOW




JAMB DETAIL
MONUMENT CLAD DOUBLE HUNG WINDOW



MEETING RAIL DETAIL
MONUMENT CLAD DOUBLE HUNG WINDOW

SILL DETAIL
MONUMENT CLAD DOUBLE HUNG WINDOW



INSTALLATION NOTES:

1. USE 2" x _ PINE WOOD BUCK
2. 1/4" MAXIMUM SHIM SPACE AT HEAD, SILL, JAMB
- PLACE WOOD SHIM EVERY 6-10"
3. APPLY A CONTINUOUS BEAD OF SEALANT BETWEEN THE VINYL NAIL FIN AT HEAD, SIDES & SILL AND THE BUCK
4. INSTALL #8 X 1-1/4" PPH SS SCREWS SPACED 1-3" FROM EACH CORNER AND 7" ON CENTER THEREAFTER INTO THE FRAMING MATERIAL, THROUGH MANUFACTURER APPLIED VINYL NAIL FIN AT HEAD, SILL & SIDE JAMBS. 3/8" MINIMUM EDGE DISTANCE.
5. 1" MINIMUM FASTENER EMBEDMENT INTO FRAMING MATERIAL
- SILICONE SEAL OVER SCREW HEADS
6. ONE #10 X 2-1/2" PFH SS SCREW PLACED THROUGH THE HEAD JAMB AT THE MULL LOCATION AND SPACED 3" ON EACH SIDE OF THE MULL SEAM. TWO #10 X 3" DRYWALL SCREWS TOE SCREWED THROUGH THE SILL END OF THE VERTICAL MULL AND INTO THE BUCK, WITH ONE SCREW PER SIDE JAMB END.
7. MAXIMUM **INDIVIDUAL** WINDOW BASIC UNIT SIZE:
37.31" (953mm) x 76.63" (1946mm)

Note: Qualifies Multiple Wide OR Multiple High Window Configurations

Installation requirements may vary in particular locations and in other types of construction. Proper installation is essential, and Sierra Pacific Windows, recommends consultation with an AAMA Certified Installer, or other qualified, registered building professional before installation of any SPW product. Proper installation of SPW products is the responsibility of the installer. SPW is not responsible for proper installation. SPW is not responsible for the design of, conditions in, or performance of building construction beyond the perimeters of the SPW units. SPW is not responsible for proper integration of the SPW units with the weather-repellent systems of the building.



Monument Clad Wood
Double Hung Operating 2-Wide Window
74 5/8" X 76 5/8"
Vinyl Fin Installation / Non-Impact

CCL Listing# 436-H-615.79

ELEMENT TEST REPORT NUMBER: ESP016205P-1530

Monumnet Clad Wood Double Hung Operating Mullied Window
Aluminum Nail Fin Installation / WDMA Instructions / Non-Impact

SHEET: 2 OF 2

Updated: 11/21/2017

DRAWN BY: A.E.

TEST REPORT SUMMARY:


- 2-WIDE UNIT SHOWN. More than 2 windows may be mulled together (Mullion may be Horizontal or Vertical)
- SINGLE UNIT BASIC UNIT FRAME SIZE:
37.31" (953mm) x 76.63" (1946mm)
- OVERALL DESIGN PRESSURE: +45 / -45 psf
- STRUCTURAL TEST PRESSURE: +67.67 / -67.67 psf
- RATING: R-PG45

ELEVATION SHOWING
FASTENER LOCATION & SPACING

NAIL FIN ANCHOR REQUIREMENTS TABLE			
THROUGH NAIL FIN UTILIZING SCREWS			
OPENING TYPE (SUBSTRATE)	JAMB TO OPENING FASTENER TYPE, FASTENER SPACING	MINIMUM EMBED	MINIMUM EDGE DIST.
2X WOOD FRAME OR BUCK	#8 X 1-1/4" PPH SCREWS SPACED 1-3" FROM EACH CORNER & 7" ON CENTER THEREAFTER.	1"	3/8"

ANCHORS MUST BE INTO A MIN. 2X WOOD MEMBER. IF SPACE BETWEEN WALL FRAME & WINDOW FRAME IS GREATER THAN THAT REQUIRED FOR A 2X WOOD MEMBER AND A SPACE EXISTS, THE SPACE MUST BE FILLED WITH A WOOD MEMBER OF EQUAL DEPTH TO THE WINDOW FRAME MEMBER OR BUCK AND OF LENGTH = MIN. 20". THE FRAME ANCHOR MUST THEN BE RUN THROUGH THE FRAME & WOOD SHIM AND INTO THE OPENING.

#8 X 1-1/4" PPH SS SCREWS
1-3" FROM CORNER (TYP.)



Installation requirements may vary in particular locations and in other types of construction. Proper installation is essential, and Sierra Pacific Windows, recommends consultation with an AAMA Certified Installer, or other qualified, registered building professional before installation of any SPW product. Proper installation of SPW products is the responsibility of the installer. SPW is not responsible for proper installation. SPW is not responsible for the design of, conditions in, or performance of building construction beyond the perimeters of the SPW units. SPW is not responsible for proper integration of the SPW units with the weather-repellent systems of the building.