

GENERAL NOTES:

1. BERTHA H.V. ACCORDION SHUTTER SYSTEM SHOWN ON THIS PRODUCT EVALUATION DOCUMENT (P.E.D.) HAS BEEN VERIFIED FOR COMPLIANCE IN ACCORDANCE WITH THE 2026 (9th EDITION) OF THE FLORIDA BUILDING CODE. THIS ACCORDION SHUTTER SYSTEM SHALL NOT BE INSTALLED AT HIGH VELOCITY HURRICANE ZONES.

DESIGN WIND LOADS SHALL BE DETERMINED AS PER SECTION 1609 OF THE ABOVE MENTIONED CODE, FOR A BASIC WIND SPEED REQUIRED BY THE JURISDICTION WHERE THE SHUTTER WILL BE INSTALLED WITH A DIRECTIONALITY FACTOR $K_d=0.85$, USING ASCE 7-22 FOR INSTALLATIONS UNDER 2026 (9th EDITION) FBC AND SHALL NOT EXCEED THE MAXIMUM (A.S.D.) DESIGN PRESSURE RATINGS INDICATED ON SHEETS 12 THRU 17, 25, 26, 28 & 28A.

IN ORDER TO VERIFY THE ABOVE CONDITION, ULTIMATE DESIGN WIND LOADS DETERMINED PER ASCE 7-22 SHALL FIRST BE REDUCED TO A.S.D. DESIGN WIND LOADS BY MULTIPLYING THEM BY 0.6 IN ORDER TO COMPARE THESE WITH MAX. (A.S.D) DESIGN PRESSURE RATINGS INDICATED ON SHEETS 12 THRU 17, 25, 26, 28 & 28A.

IN ORDER TO VERIFY THAT ANCHORS ON THIS P.E.D., AS TESTED, WERE NOT OVERSTRESSED, A 33 % INCREASE IN ALLOWABLE LOADS FOR WIND LOADS WAS NOT USED IN THEIR ANALYSIS. BERTHA H.V. ACCORDION SHUTTER SYSTEM'S ADEQUACY FOR WIND AND LARGE MISSILE IMPACT LOAD HAS BEEN VERIFIED IN ACCORDANCE WITH SECTION 1609.1.2 OF THE ABOVE MENTIONED CODE AS PER ATL REPORTS: IMPACT MISSILE IS 9Lb, 2"x4", 50 ft/Sec.

-HV BLADE 1 #0214.01-03, #0715.01-03, #1004.01-05, #1214.01-05, #0317.02-06, #0609.01-10 AND #0210.01-11 AS PER TAS 201, TAS 202 AND TAS 203 PROTOCOLS.

-HV WINDOW BLADE 1A #0505.01-08 AS TAS 201, 202 & 203 PROTOCOLS AND 0725.01-08 AS PER TAS 202 PROTOCOL.

-HV BLADE 2 #0422.01-05 AS PER TAS 201, TAS 202 AND TAS 203 PROTOCOLS.

2. HV BLADE 1 AND HV BLADE 2 ARE ENGINEERED TO WORK IN UNISON WITH EACH OTHER IN AREAS WHERE THE DESIGN PRESSURES TRANSITION FROM END ZONE 5 TO INTERIOR ZONE 4. EACH WIND ZONE MUST BE CLEARLY IDENTIFIED IN ACCORDANCE WITH CHAPTER 30, OF ASCE 7-22 STANDARD. ALL MOUNTING CONDITIONS AND FASTENER TYPES SCHEDULES MUST BE APPLIED TO THE CORRESPONDING WIND ZONE. THIS SHALL INCLUDE REQUIREMENTS FOR MIN. SEPARATION TO GLASS. DELIMITATION OF WIND ZONES 4 AND 5 AS WELL AS VALIDITY OF COMPONENTS FOR HV BLADE 1 & 2 ACCORDION SHUTTERS SYSTEMS FOR EITHER WIND ZONE SHALL BE PREPARED AND CERTIFIED BY A FLORIDA REGISTERED ENGINEER OR ARCHITECT BASED ON BUILDING CONFIGURATION AND ASCE 7-22 STANDARD, AND SHALL BE SUBMITTED TO THE BUILDING OFFICIAL AT THE TIME PERMIT IS APPLIED FOR.

HV BLADE 1 AND HV WINDOW BLADE 1A ARE ENGINEERED TO WORK IN UNISON WITH EACH OTHER UNDER THE GENERAL LIMITATIONS AND CONDITIONS OF USE INDICATED ON SHEET 28.

3. BERTHA H.V. ACCORDION PINS (HV SCREWS), USED AT BLADES KNUCKLE AND FOR DIRECT MOUNT CONNECTION TO TRACKS SHALL BE # 14X2.75 AND # 14X1.75 RESPECTIVELY, 410-HT MINIMUM SERIES STAINLESS STEEL SCREWS WITH 135.0 ksi YIELD STRENGTH AND 180 ksi TENSILE STRENGTH. PINS SHALL BE COATED WITH BERTHA HV DACROSHIELD COATING SYSTEM AS MANUFACTURED BY APPROVED COATING APPLICATORS, REGISTERED WITH AMERICAN SHUTTER SYSTEMS ASSOCIATION. PINS MUST BEAR THE HV MARKING ON THEIR HEAD.

4. ALL ALUMINUM EXTRUSIONS SHALL BE ALUMINUM ASSOCIATION ALLOY AND TEMPER AS INDICATED ON SHEETS 2 AND 3. MINIMUM YIELD STRENGTH FOR 6063-T6 ALLOY IS 31.7 ksi AND 35.7 ksi FOR 6005-T5 ALLOY. ALL ALUMINUM EXTRUSIONS IN CONTACT WITH DISSIMILAR MATERIALS SHALL COMPLY WITH SECTION III-6 OF THE 2020 ALUMINUM DESIGN MANUAL.

5. ALL SCREWS SHALL BE STAINLESS STEEL 304 OR 316 AISI SERIES OR CORROSION RESISTANT COATED CARBON STEEL AS PER DIN 50018 WITH 50 ksi MIN. YIELD STRENGTH AND 90 ksi MIN. TENSILE STRENGTH & SHALL COMPLY WITH FLORIDA BUILDING CODE SECTIONS 2411.3.3.4 & 1711.

6. BOLTS SHALL BE ASTM A-307 GALVANIZED STEEL, OR AISI 304 OR 316 SERIES STAINLESS STEEL WITH 35 ksi MINIMUM YIELD STRENGTH.

7. SEE THE FOLLOWING SHEETS FOR ANCHOR SPECIFICATIONS: HV BLADE 1: 13,14,15,16,17 & 28A

HV BLADE 2 : 26.

HV BLADE 3 & 1A WORKING IN UNISON: 13, 14 & 16

8. THIS BERTHA H.V. ACCORDION SHUTTER SYSTEM BEARS A U.S. PATENT #6'779,582. COMPONENTS OF THIS APPROVAL ARE COVERED, IN WHOLE OR IN PART BY U.S. PATENT #5'458,179 ISSUED TO EASTERN METAL SUPPLY, INC.

9. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE SOUNDNESS OF THE STRUCTURE WHERE THE SHUTTER IS TO BE ATTACHED TO ENSURE PROPER ANCHORAGE. THE CONTRACTOR IS TO SEAL/CAULK ALL SHUTTER COMPONENT EDGES WHICH REMAIN, THRU FASTENING IN CONTINUOUS CONTACT WITH THE BUILDING TO PREVENT WIND/RAIN INTRUSION.

10. EACH UNIT MUST BEAR A PERMANENT LABEL IN A VISIBLE PLACE WITH WARNING NOTE: DURING PERIODS OF HURRICANE WARNINGS HOME OWNER, TENANT, OR OTHERS, MUST PROPERLY CLOSE ALL HV AND HD CENTERMATES AND ENGAGE OR LOCK ALL HV AND HD LOCKS.

11. SHUTTER MANUFACTURER'S LABEL SHALL BE LOCATED AT A READILY VISIBLE LOCATION ON THE ACCORDION SHUTTER IN ACCORDANCE WITH SECTION 1709.9.2 OF FLORIDA BUILDING CODE. ONE LABEL SHALL BE PLACED FOR EVERY OPENING.

12. BERTHA H.V. ACCORDION SHUTTER SYSTEM'S INSTALLATION SHALL COMPLY WITH SPECS INDICATED IN THIS DRAWING PLUS ANY BUILDING AND ZONING REGULATIONS PROVIDED BY THE JURISDICTION WHERE A PERMIT IS APPLIED FOR.

13. (a) THIS P.E.D. PREPARED BY THIS ENGINEER IS GENERIC AND DOES NOT PROVIDE INFORMATION FOR A SITE SPECIFIC PROJECT; i.e. WHERE THE SITE CONDITIONS DEVIATE FROM THE P.E.D.

(b) THE CONTRACTOR IS TO BE RESPONSIBLE FOR THE SELECTION, PURCHASE AND INSTALLATION INCLUDING LIFE SAFETY OF THIS PRODUCT, BASED ON THIS P.E.D., PROVIDED HE/SHE DOES NOT DEVIATE FROM THE CONDITIONS DETAILED ON THIS DOCUMENT. CONSTRUCTION SAFETY AT SITE IS THE CONTRACTOR'S RESPONSIBILITY.

(c) THIS P.E.D. WILL BE CONSIDERED INVALID IF ALTERED BY ANY MEANS.

(d) SITE SPECIFIC PROJECTS SHALL BE PREPARED BY A FLORIDA REGISTERED ENGINEER OR ARCHITECT WHO WILL BECOME THE ENGINEER OF RECORD (E.O.R.) FOR THE PROJECT AND WHO WILL BE RESPONSIBLE FOR THE PROPER USE OF THE P.E.D. ENGINEER OF RECORD, ACTING AS A DELEGATED ENGINEER TO THE P.E.D. ENGINEER SHALL SUBMIT TO THE LATTER THE SITE SPECIFIC DRAWINGS FOR REVIEW.

(e) ORIGINAL P.E.D. SHALL BEAR THE DATE AND ORIGINAL SEAL AND SIGNATURE OF THE PROFESSIONAL ENGINEER OF RECORD WHO PREPARED IT.

TABLE OF CONTENTS

AREA 1: HV BLADES 1, 1A & 2

GENERAL NOTES		SHEET 1
SYSTEM COMPONENTS	1-20	SHEET 2
SYSTEM COMPONENTS	21-37	SHEET 3
TYPICAL SHUTTER ASSEMBLY	38-43	SHEET 4

AREA 2: HV BLADE 1 AND HV WINDOW BLADE 1A (WHERE APPLICABLE)

TYPICAL SHUTTER ELEVATION & NOTES ON LOCKS	SHEET 5
INSTALLATION DETAILS A-E, CONCRETE/BLOCK	SHEET 6
INSTALLATION DETAILS F-L, CONCRETE/BLOCK	SHEET 7
CENTERMATE DETAILS HV	SHEET 8
CENTERMATE ALTERNATING DETAILS HV	SHEET 9
CENTERMATE DETAILS HD	SHEET 10
END CONNECTION DETAILS 1-6, CONCRETE/BLOCK	SHEET 11
MAXIMUM SPAN TABLES	SHEET 12
ANCHOR SCHEDULE- CONCRETE & BLOCK	SHEET 13
ANCHOR SCHEDULE- CONCRETE & BLOCK	SHEET 14
ANCHOR SCHEDULE- CONCRETE & BLOCK	SHEET 15
ANCHOR SCHEDULE- WOOD	SHEET 16
ANCHOR SCHEDULE- WOOD	SHEET 17
INSTALLATION DETAILS M-R, WOOD	SHEET 18
INSTALLATION DETAILS S-X, WOOD	SHEET 19
END CONNECTION DETAILS 7-12 & X, WOOD	SHEET 20

AREA 3: HV BLADE 2 ONLY

TYPICAL SHUTTER ELEVATION & NOTES ON LOCKS	SHEET 21
INSTALLATION DETAILS AA-GG, CONCRETE	SHEET 22
CENTERMATE DETAILS HD	SHEET 23
END CONNECTION DETAILS 1-6 & X, CONCRETE/BLOCK	SHEET 24
MAXIMUM SPAN TABLES	SHEET 25
ANCHOR SCHEDULE, CONCRETE	SHEET 26

AREA 4: HV WINDOW BLADE 1A ONLY


TYPICAL WINDOW BLADE & WINDOW DETAIL	SHEET 27
TYPICAL SHUTTER ELEVATION	SHEET 28

AREA 5: HV WINDOW BLADE 1 ONLY

INSTALLATION DETAILS, METAL STUD WALLS	SHEET 28A
--	-----------

FLORIDA BUILDING CODE (Non High Velocity Hurricane Zone)

THIS DRAWING SHALL ONLY BE USED TO OBTAIN PERMITS IN THE STATE OF FLORIDA



P.E. SEAL/SIGNATURE/DATE

©2026 TILTECO, INC.



TILLIT TESTING & ENGINEERING COMPANY

6355 N.W. 36th. St., Ste. 305, VIRGINIA GARDENS, FLORIDA 33166

Phone : (305)871-1530 . Fax : (305)871-1531

e-mail: tilteco@aol.com

CA-0006719

WALTER A. TILLIT Jr. P.E.

FLORIDA Lic. # 44167

A.S.S.A.

American Shutter Systems Association, Inc.

4268 Westroads Drive
West Palm Beach, FL 33407

© 2026 EASTERN METAL SUPPLY, INC.


BERTHA HV™
Accordion Shutter System

H.V. BLADE #1 W/ OR W/O H.V. WINDOW BLADE & H.V. BLADE #2

REV. No	DESCRIPTION	DATE	DRAWN BY: W.H.
1	OLD 23-126	6/30/26	DATE: 06/30/2026
2			
3			
4			
5			
6			

DRAWING No
26-104

SHEET
1 OF 28




1 HV SOLID BLADE

COVERED UNDER US PATENT # 5458179


1A HV WINDOW BLADE*

*SEE LIMITATIONS OF USE OF BLADE 1A ON SHEET 28
6063-T6 ALLOY AND TEMPER




6 HV ADJ. FLOOR TRACK

QUALIFIED FOR USE W/ HV
BLADE 1 & 2
6063-T6 ALLOY AND TEMPER



11 HV CEILING HEADER


QUALIFIED FOR USE W/ HV BLADE 1 ONLY,
SEE SECTIONS FOR VALIDITY.
6063-T6 ALLOY AND TEMPER



16 SIDE ANGLES


QUALIFIED FOR USE W/ HV
BLADE 1 & 2
6063-T6 ALLOY AND TEMPER

MIN. X	MIN. Y	MIN. t
1"	1"	0.062"




2 HV BLADE

COVERED UNDER US PATENT # 5458179
6005-T5 ALLOY AND TEMPER




7 HV ADJ. ADAPTER W/LIP

QUALIFIED FOR USE W/ HV
BLADE 1 & 2
6063-T6 ALLOY AND TEMPER




12 HV HEADER/SILL

QUALIFIED FOR USE W/ HV BLADE 1 ONLY
6063-T6 ALLOY AND TEMPER




3 HV UNIVERSAL FLOATER

QUALIFIED FOR USE W/ HV BLADE 1 & 2
6005-T5 ALLOY AND TEMPER




8 HV WALK-OVER TRACK

QUALIFIED FOR USE W/ HV
BLADE 1 & 2
6063-T6 ALLOY AND TEMPER




13 HD CEILING HEADER/SILL

QUALIFIED FOR USE W/ HV BLADE 1
SEE SECTIONS FOR VALIDITY.
6063-T6 ALLOY AND TEMPER




4 HV DIRECT MOUNT

QUALIFIED FOR USE W/ HV
BLADE 1 & 2
6063-T6 ALLOY AND TEMPER




9 HV TRENCH TRACK

QUALIFIED FOR USE W/ HV
BLADE 1 & 2 ONLY.
6063-T6 ALLOY AND TEMPER




14 HD WALL HEADER/SILL

QUALIFIED FOR USE W/ HV
BLADE 1 ONLY.
6063-T6 ALLOY AND TEMPER




5 HV 90°/180° STARTER

QUALIFIED FOR USE W/
HV BLADE 1 & 2
6063-T6 ALLOY AND TEMPER




10 HV RAINGUARD

QUALIFIED FOR USE W/ HV
BLADE 1 & 2
6063-T6 ALLOY AND TEMPER



15 SHD CEILING HEADER/SILL

QUALIFIED FOR USE W/ HV BLADE 1 & 2
6063-T6 ALLOY AND TEMPER



20 CORNER POSTS


QUALIFIED FOR USE W/ HV
BLADE 1 & 2
6063-T6 ALLOY AND TEMPER

X	Y	t
2"	2"	0.125"
3"	3"	0.090"

ALUMINUM ANGLES

QUALIFIED FOR USE W/ HV
BLADE (SEE SCHEDULE)
6063-T6 ALLOY AND TEMPER

COMPONENT	A	B	T1	T2	BLADE QUALIFIED
17	2"	5" MAX.	1/8"	1/8"	HV 1
18	2"	5" MAX.	0.192"	0.192"	HV 2
19	2.5"	7" MAX.	0.190"	0.190"	HV 1



©2026 TILTECO, INC.



TILLIT TESTING & ENGINEERING COMPANY
6355 N.W. 36th. St., Ste. 305, VIRGINIA GARDENS, FLORIDA 33166
Phone : (305)871-1530 . Fax : (305)871-1531
e-mail: tilteco@aol.com
CA-0006719
WALTER A. TILLIT Jr. P.E.
FLORIDA Lic. # 44167

A.S.S.A.
American Shutter Systems
Association, Inc.
4268 Westroads Drive
West Palm Beach, FL 33407

FLORIDA BUILDING CODE (Non High Velocity Hurricane Zone)

© 2026 EASTERN METAL SUPPLY, INC.


BERTHA HV™ Accordion Shutter System

H.V. BLADE #1 W/ OR W/O H.V. WINDOW BLADE & H.V. BLADE #2

REV. No	DESCRIPTION	DATE	DRAWN BY: W.H.
1	OLD 23-126	6/30/26	DATE: 06/30/2026
2			
3			
4			
5			
6			

DRAWING No
26-104

SHEET
2 OF 28



22 HV FLOATING CENTERMATE

②③ HV CORNER CENTERMATE

24 HV LOCK

②⑤ HV EGRESS LOCK

27 LOCKER FOR "T" LOCK CENTERMATE

28 HV MALE "T" LOCK CENTERMATE

29 HV FEMALE "T" LOCK CENTERMATE

③③ HV "T" LOCK

1/4" ϕ -20 x 3/4"
S.S. THUMBSCREW

BEFORE RIVETING

26 HV ALTERNATIVE LOCK

31 HD CENTERMATE W/ NO LOCKING ROD

③② HD CENTERMATE W/ LOCKING ROD

③③ HD CENTERMATE'S INSERT

35 LOCKING ROD 

③⑥ HV 3/8"Ø-16 ACETAL
THUMBSCREWS

37 HV 1/4" ϕ -20 AISI 304
SERIES S.S. THUMBSCREWS

0.875" Min.
1.125" Max

THUMBTURN CYLINDER OR KEY CYLINDER

1.57" Min.

1.78" Max.


③4 HD LOCK

FLORIDA BUILDING CODE (Non High Velocity Hurricane Zone)

© 2026 EASTERN METAL SUPPLY, INC.

BERTHA HV™ Accordion Shutter System

H.V. BLADE #1 W/ OR W/O H.V. WINDOW BLADE & H.V. BLADE #2			
REV. No	DESCRIPTION	DATE	DRAWN BY: W.H.
1	OLD 23-126	6/30/26	DATE: 06/30/2026
2			DRAWING No 26-104
3			
4			
5			SHEET 3 OF 28
6			



©2026 TILTECO, INC.



TILECO INC.

TILLIT TESTING & ENGINEERING COMPANY
6355 N.W. 36th. St., Ste. 305, VIRGINIA GARDENS, FLORIDA 33166
Phone : (305)871-1530 . Fax : (305)871-1531
e-mail: tilteco@aol.com
CA-0006719
WALTER A. TILLIT Jr. P.E.
FLORIDA Lic. # 44167

A.S.S.A.
American Shutter Systems
Association, Inc.
4268 Westroads Drive
West Palm Beach, FL 33407


РЕРТА НУ-

SHUTTER ASSEMBLY SCHEDULE FOR HV ①, HV ①A AND HV ② BLADES.


①	HV BLADE 1
①A	HV BLADE 1A
②	HV BLADE 2
③8	HV LONG RECESSED NYLON BUSHING
③9	HV SHORT RECESSED NYLON BUSHING
④0	HV NYLON HAT WASHER
④1	HV WHEEL CARRIAGE AISI 302-303 SERIES ø.870"x3/16" THICK NYLON WHEEL. 0.188"ø AISI 302 SERIES S.S. RIVETS
④2	HV 1 3/4" ACCORDION PIN W/ #8 HEAD *
④3	HV 2 3/4" ACCORDION PIN W/ #8 HEAD *
④4	POLYCARBONATE IMPACT RESISTANT HV WINDOW (SEE SHEET 27)

* HV PIN REQUIREMENTS AT EXTERIOR BLADE KNUCKLE FOR HV ①, HV ①A & HV ② BLADES.

- HV PIN ④3 SHALL ALWAYS BE USED AT ALL EXTERIOR BOTTOM KNUCKLES OF HV ACCORDION SYSTEM W/ HV ① OR HV ①A BLADE.
- HV PIN ④2 MAY BE USED IN LIEU OF ④3 AND ONLY AT EXTERIOR BOTTOM KNUCKLES OF HV ACCORDION SYSTEM W/ HV ② BLADE WHEN CORRESPONDING TO INSTALLATIONS "CC" AND "DD", SHEET 22.
- HV PIN ④2 OR ④3 W/ 1/2" O.D. 1/16" THICK S.S. WASHER SHALL BE USED FOR DIRECT MOUNT INSTALLATION PER DETAIL X, SHEETS 11 & 24.




EXTERIOR




TYPICAL SHUTTER ASSEMBLY

SCALE: 3/8" = 1"



WHEEL CARRIAGE DETAIL

N.T.S.




EXTERIOR

HV PIN ④2 OR ④3 AT
EXTERIOR
BLADE'S KNUCKLE.
(SEE NOTE * FOR
REQUIREMENTS)

ASSEMBLY LAYOUT

N.T.S.

FLORIDA BUILDING CODE (Non High Velocity Hurricane Zone)



P.E. SEAL/SIGNATURE/DATE

©2026 TILTECO, INC.




TILLIT TESTING & ENGINEERING COMPANY
6355 N.W. 36th. St., Ste. 305, VIRGINIA GARDENS, FLORIDA 33166
Phone : (305)871-1530 . Fax : (305)871-1531
e-mail: tilteco@aol.com
CA-0006719
WALTER A. TILLIT Jr. P.E.
FLORIDA Lic. # 44167

A.S.S.A.
American Shutter Systems
Association, Inc.
4268 Westroads Drive
West Palm Beach, FL 33407

© 2026 EASTERN METAL SUPPLY, INC.

BERTHA HV™ Accordion Shutter System			
H.V. BLADE #1 W/ OR W/O H.V. WINDOW BLADE & H.V. BLADE #2			
REV. No	DESCRIPTION	DATE	DRAWN BY: W.H.
1	OLD 23-126	6/30/26	DATE: 06/30/2026
2			DRAWING No 26-104
3			
4			
5			SHEET 4 OF 28
6			



TYPICAL (1) HV BLADE SHUTTER ELEVATION
N.T.S.

*** NOTES ON HV LOCKS AND CENTERMATES:**


- MANDATORY CONDITION #1:** ONE HV LOCK (24) OR (25) SHALL BE USED AT 1/2 OF SHUTTER SPAN FOR ANY SPAN OR 12" ABOVE OR BELOW 1/2 OF SHUTTER SPAN FOR SPANS UP TO 105", AND FOR INSTALLATIONS AT ANY ELEVATION. HV LOCK (24) OR (25) MAY BE USED AS AN INSIDE OR OUTSIDE LOCK, ATTACHED TO (21) OR (22) CENTERMATES W/(2) 1/4"Ø-20 x 1/2" LONG FLAT HEAD S.S. M.S. LOCATION OF LOCK SHALL BE AS INDICATED ON TYPICAL SHUTTER ELEVATION.
- OPTIONAL CONDITION #1:** IF DESIRED, FOR BETTER PERFORMANCE OR FOR SECURITY PURPOSES, UP TO TWO HV LOCKS (24), (25) OR (26) MAY BE USED AS AN INSIDE OR OUTSIDE LOCK. CONNECTION OF LOCKS TO CENTERMATES (21) OR (22) SHALL BE AS INDICATED ON NOTE (1) ABOVE. LOCATION OF LOCKS SHALL BE AS INDICATED ON TYPICAL SHUTTER ELEVATION.
- OPTIONAL CONDITION #2 (VALID ONLY WHEN MANDATORY CONDITION #1 OR LIMITED MANDATORY CONDITION #2 IS USED W/TWO H.V. LOCKS):** LOCKING RODS (35) ARE NOT REQUIRED AT HURRICANE POSITION, BUT MAY BE USED IF DESIRED TO ENHANCE SHUTTER PERFORMANCE. LOCKING RODS (35) OR AN ALTERNATIVE DEVICE MAY ALSO BE USED AT STACKING POSITION (NON HURRICANE POSITION).
- MANDATORY CONDITION #2:** ONE HV LOCK (24) OR (25) SHALL BE USED AT CORNER CENTERMATES FOR ANY SPAN AND INSTALLATIONS AT ANY ELEVATION. HV LOCK (24) OR (25) SHALL BE USED AS AN OUTSIDE OR INSIDE LOCK, ATTACHED TO (23) CORNER CENTERMATE W/(2) 1/4"Ø-20 x 1/2" LONG FLAT HEAD S.S. M.S. TWO LOCKING RODS (35) AT TOP & BOTTOM SHALL BE USED. LOCATION OF LOCK SHALL BE AS INDICATED ON TYPICAL SHUTTER ELEVATION. MAXIMUM SHUTTER SPAN SHALL BE DETERMINED AS PER SCHEDULES SHOWN ON SHEET 12.
- FIRST ALTERNATE TO MANDATORY CONDITION #1 VALID ONLY FOR HV LOCK (26) W/ SYMMETRICAL CENTERMATES (21) OR (22):** ONE ALTERNATE HV LOCK (26) MAY BE USED IN LIEU OF HV LOCK (24) OR (25) FOR ANY SPAN AND INSTALLATIONS AT ANY ELEVATION. ALTERNATE LOCK (26) MAY BE USED AS AN INSIDE OR OUTSIDE LOCK. ATTACHMENT OF 1/4"Ø-20x3/4" S.S. THUMBSCREW TO (21) OR (22) CENTERMATES SHALL BE MADE W/ 1/4"Ø-20x3/4" ALUM. RIVNUT AS SHOWN ON SECTION HVE, SHEET 8. ONE LOCK SHALL BE USED AT 1/2 OF SHUTTER SPAN OR TWO LOCKS AT 1/3 OF SHUTTER SPAN.

***NOTES ON HV "T" LOCKS AND CENTERMATES:**

- SECOND ALTERNATE TO MANDATORY CONDITION #1 VALID ONLY FOR HV "T" LOCK (30) AND CENTERMATES (28) AND (29):** ONE ALTERNATE HV "T" LOCK (30) MAY BE INSTALLED IN LIEU OF HV LOCKS (24) OR (25) FOR ANY SPAN AND INSTALLATION AT ANY ELEVATION. ALTERNATE LOCK (30) MAY BE USED AS AN INSIDE OR OUTSIDE LOCK. ATTACHMENT OF LOCK (30) INCLUDES USING REINFORCING LOCKER (27), AS SHOWN ON SECTION HVG, SHEET 9, WHICH MUST BE CONNECTED TO CENTERMATES (28) AND (29) W/ 1/4"Ø-20 x 1 1/2" LONG S.S. THREADED BOLT W/ 7/8"Ø x 3/32" WINGNUT OR W/ 1/4"Ø-20x1" S.S.M.S. INTO A 1/4"Ø x 5/8" RIVNUT. LOCK MAY BE INSTALLED AT MIDSPAN OR 12" MAXIMUM ABOVE AND BELOW MIDSPAN. USE OF TWO LOCKING RODS (35) TOP AND BOTOM IS MANDATORY.

***NOTES ON HD LOCKS & CENTERMATES:**

- HD LOCK (34) W/ HD CENTERMATES (31) OR (32) W/ (33):** ONE ALTERNATE HD LOCK (34) MAYBE USED IN LIEU OF HV LOCKS (24) OR (25) FOR ANY SPAN AND INSTALLATIONS AT ANY ELEVATION. ALTERNATE HD LOCK (34) MAY BE USED AS AN INSIDE OR OUTSIDE LOCK. ATTACHMENT OF HD LOCK (34) TO (33) IS W/ 3 #8 x 3/8" F.H. S.S.M.S., AND INCLUDES REINFORCEMENT INSERT (33) AS SHOWN ON SECTIONS HDB-HVB AND HDC-HVC, SHEET 10. LOCK MAY BE INSTALLED AT MIDSPAN OR 12" MAXIMUM BELOW OR ABOVE MIDSPAN. USE OF LOCKING RODS (35) IS COMPLETELY OPTIONAL.



P.E. SEAL/SIGNATURE/DATE

©2026 TILTECO, INC.



TILLIT TESTING & ENGINEERING COMPANY
6355 N.W. 36th. St., Ste. 305, VIRGINIA GARDENS, FLORIDA 33166
Phone : (305)871-1530 . Fax : (305)871-1531
e-mail: tilteco@aol.com
CA-0006719
WALTER A. TILLIT Jr. P.E.
FLORIDA Lic. # 44167

A.S.S.A.
American Shutter Systems
Association, Inc.
4268 Westroads Drive
West Palm Beach, FL 33407

FLORIDA BUILDING CODE (Non High Velocity Hurricane Zone)

© 2026 EASTERN METAL SUPPLY, INC.


BERTHA HV™
Accordion Shutter System

H.V. BLADE #1 W/ OR W/O H.V. WINDOW BLADE & H.V. BLADE #2


REV. No	DESCRIPTION	DATE	DRAWN BY: W.H.
1	OLD 23-126	6/30/26	DATE: 06/30/2026
2			
3			
4			
5			
6			

DRAWING No
26-104


SHEET
5 OF 28




A HV WALL HEADER INSTALLATION




B HV WALL HEADER INSTALLATION




C HV WALL HEADER INSTALLATION



D HV WALL SILL INSTALLATION



E HV WALL SILL INSTALLATION



F HV WALL SILL INSTALLATION


INSTALLATION DETAILS W/ ① HV BLADE

FLORIDA BUILDING CODE (Non High Velocity Hurricane Zone)

NOTE FOR COMBINATION OF SECTIONS:
1- SEE SHEET 4 FOR TYPICAL SHUTTER ASSEMBLY
2- MOUNTING SECTIONS CAN BE COMBINED IN ANY WAY TO SUIT ANY INSTALLATION.

* E. D. = EDGE DISTANCE
(SEE SPECIFICATIONS ON SHEET 14)

◆ SEE LIMITATIONS OF USE FOR
BLADE ①A ON SHEET 28



©2026 TILTECO, INC.



TILLIT TESTING & ENGINEERING COMPANY
6355 N.W. 36th. St., Ste. 305, VIRGINIA GARDENS, FLORIDA 33166
Phone : (305)871-1530 . Fax : (305)871-1531
e-mail: tilteco@aol.com
CA-0006719
WALTER A. TILLIT Jr. P.E.
FLORIDA Lic. # 44167

A.S.S.A.
American Shutter Systems
Association, Inc.
4268 Westroads Drive
West Palm Beach, FL 33407


© 2026 EASTERN METAL SUPPLY, INC.

BERTHA HV™ Accordion Shutter System


H.V. BLADE #1 W/ OR W/O H.V. WINDOW BLADE & H.V. BLADE #2			
REV. No	DESCRIPTION	DATE	DRAWN BY: W.H.
1	OLD 23-126	6/30/26	DATE: 06/30/2026
2			
3			
4			
5			
6			

DRAWING No
26-104

SHEET
6 OF 28



G HV CEILING INSTALLATION




J HV RAINGUARD INSTALLATION †


NOTE FOR COMBINATION OF SECTIONS:

1- SEE SHEET 4 FOR TYPICAL SHUTTER ASSEMBLY.
2- MOUNTING SECTIONS CAN BE COMBINED IN ANY WAY TO SUIT ANY INSTALLATION.

* E. D. = EDGE DISTANCE
(SEE SPECIFICATIONS ON SHEET 14)



H HV FLOOR INSTALLATION †




K HV WALL FLOOR INSTALLATION


NOTE:

† THIS INSTALLATION SHALL BE REMOVABLE WHEN PERFORMED ADJACENT TO AN OPERABLE EXIT OR ENTRANCE

♦ SEE LIMITATIONS OF USE FOR BLADE 1A ON SHEET 28




I HV WALK-OVER INSTALLATION




I1 TRENCH INSTALLATION

VALID ONLY FOR UP TO +70, -75 PSF PRESSURE RATING & FOR SPANS PER SCHEDULE #3, SHEET 12



L HV WALL WALK-OVER INSTALLATION

**INSTALLATION DETAILS W/
1 HV BLADE**



P.E. SEAL/SIGNATURE/DATE

©2026 TILTECO, INC.



TILLIT TESTING & ENGINEERING COMPANY
6355 N.W. 36th. St., Ste. 305, VIRGINIA GARDENS, FLORIDA 33166
Phone : (305)871-1530 . Fax : (305)871-1531
e-mail: tilteco@aol.com
CA-0006719
WALTER A. TILLIT Jr. P.E.
FLORIDA Lic. # 44167

A.S.S.A.
American Shutter Systems
Association, Inc.
4268 Westroads Drive
West Palm Beach, FL 33407

FLORIDA BUILDING CODE (Non High Velocity Hurricane Zone)

© 2026 EASTERN METAL SUPPLY, INC.


BERTHA HV™
Accordion Shutter System

H.V. BLADE #1 W/ OR W/O H.V. WINDOW BLADE & H.V. BLADE #2

REV. No	DESCRIPTION	DATE	DRAWN BY: W.H.
1	OLD 23-126	6/30/26	DATE: 06/30/2026
2			
3			
4			
5			
6			

DRAWING No
26-104
SHEET
7 OF 28




SEE END WALL CONNECTION DETAILS ON SHEETS 11 & 20



INSTALLATIONS W/ ① HV
BLADE W/ HV CENTERMATES
②①, ②② OR ②③

* SEE NOTES ON LOCKING RODS ③⑨, HV LOCKS ②④ OR ②⑤
AND ALTERNATE HV LOCK ②⑥ ON SHEET 5.
** BLADE SLACK DETAIL HVF IS VALID FOR ALL
CENTERMATES APPLICATION WITH BLADE ①

SEE END WALL CONNECTION
DETAILS ON SHEETS 11 & 20



FLORIDA BUILDING CODE (Non High Velocity Hurricane Zone)


WALTER A. TILLIT JR.
LICENSE
No. 44167
STATE OF
FLORIDA
PROFESSIONAL ENGINEER
P.E. SEAL/SIGNATURE/DATE

©2026 TILTECO, INC.
TILTECO INC.
TILLIT TESTING & ENGINEERING COMPANY
6355 N.W. 36th. St., Ste. 305, VIRGINIA GARDENS, FLORIDA 33166
Phone : (305)871-1530 . Fax : (305)871-1531
e-mail: tilteco@aol.com
CA-0006719
WALTER A. TILLIT Jr. P.E.
FLORIDA Lic. # 44167

A.S.S.A.
American Shutter Systems
Association, Inc.
4268 Westroads Drive
West Palm Beach, FL 33407

© 2026 EASTERN METAL SUPPLY, INC.			
BERTHA HV™ Accordion Shutter System			
H.V. BLADE #1 W/ OR W/O H.V. WINDOW BLADE & H.V. BLADE #2			
REV. NO.	DESCRIPTION	DATE	DRAWN BY: W.H.
1	OLD 23-126	6/30/26	DATE: 06/30/2026
2			
3			
4			
5			
6			
			DRAWING No 26-104
			SHEET 8 OF 28

SEE END CONNECTION DETAILS ON SHEETS 11 & 20



† SERIES 9444 ALUMINUM
(2024-T3 ALLOY) LARGE FLANGE THIN
SHEET NUTSERT, PART # 0820,
AS MANUFACTURED BY AVDEL CHERRY
TEXTORN, PARSIPPENY, NEW JERSEY
07054 OR EQUAL.


HVG*

FLORIDA BUILDING CODE (Non High Velocity Hurricane Zone)

© 2026 EASTERN METAL SUPPLY, INC.

BERTHA HV™ Accordion Shutter System

H.V. BLADE #1 W/ OR W/O H.V. WINDOW BLADE & H.V. BLADE #2			
REV. No	DESCRIPTION	DATE	DRAWN BY: W.H.
1	OLD 23-126	6/30/26	DATE: 06/30/2026
2			DRAWING No 26-104
3			
4			
5			
6			SHEET 9 OF 28



P.E. SEAL/SIGNATURE/DATE


©2026 TILTECO, INC.



TILLIT TESTING & ENGINEERING COMPANY
6355 N.W. 36th. St., Ste. 305, VIRGINIA GARDENS, FLORIDA 33166
Phone : (305)871-1530 . Fax : (305)871-1531
e-mail: tilteco@aol.com
CA-0006719
WALTER A. TILLIT Jr. P.E.
FLORIDA Lic. # 44167


A.S.S.A.
American Shutter Systems
Association, Inc.
4268 Westroads Drive
West Palm Beach, FL 33407

SEE END WALL CONNECTION DETAILS ON SHEETS 11 & 20




INSTALLATION ① HV BLADE W/ HD CENTERMATES ③①, ③②, ③③

SEE END WALL CONNECTION
DETAILS ON SHEETS 11 & 20



- * SEE NOTES ON LOCKING RODS ③⑤ & HD ③④ LOCKS ON SHEET 5
- ** UNIVERSAL FLOATING BLADE ③ DETAIL HDD-HVD IS VALID FOR ALL CENTERMATES APPLICATIONS WITH BLADE ①



WALTER A. TILLIT JR.
LICENSE
No. 44167
STATE OF
FLORIDA
PROFESSIONAL ENGINEER
P.E. SEAL/SIGNATURE/DATE

©2026 TILTECO, INC.

TILTECO INC.


TILLIT TESTING & ENGINEERING COMPANY
6355 N.W. 36th. St., Ste. 305, VIRGINIA GARDENS, FLORIDA 33166
Phone : (305)871-1530 . Fax : (305)871-1531
e-mail: tilteco@aol.com
CA-0006719
WALTER A. TILLIT Jr. P.E.
FLORIDA Lic. # 44167

A.S.S.A.
American Shutter Systems
Association, Inc.
4268 Westroads Drive
West Palm Beach, FL 33407

FLORIDA BUILDING CODE (Non High Velocity Hurricane Zone)

© 2026 EASTERN METAL SUPPLY, INC.

BERTHA HV™ Accordion Shutter System			
H.V. BLADE #1 W/ OR W/O H.V. WINDOW BLADE & H.V. BLADE #2			
REV. No	DESCRIPTION	DATE	DRAWN BY: W.H.
1	OLD 23-126	6/30/26	DATE: 06/30/2026
2			
3			
4			
5			
6			
			DRAWING No 26-104
			SHEET 10 OF 28



FLORIDA BUILDING CODE (Non High Velocity Hurricane Zone)

WALTER A. TILLIT JR.
LICENSE
No. 44167
STATE OF FLORIDA
PROFESSIONAL ENGINEER
SEAL/SIGNATURE/DATE

©2026 TILTECO, INC.

TILTECO INC.

TILLIT TESTING & ENGINEERING COMPANY
6355 N.W. 36th. St., Ste. 305, VIRGINIA GARDENS, FLORIDA 33166
Phone : (305)871-1530 . Fax : (305)871-1531
e-mail: tilteco@aol.com
CA-0006719
WALTER A. TILLIT Jr. P.E.
FLORIDA Lic. # 44167

A.S.S.A.
American Shutter Systems
Association, Inc.
4268 Westroads Drive
West Palm Beach, FL 33407

© 2026 EASTERN METAL SUPPLY, INC.			
BERTHA HV™ Accordion Shutter System			
H.V. BLADE #1 W/ OR W/O H.V. WINDOW BLADE & H.V. BLADE #2			
REV. No	DESCRIPTION	DATE	DRAWN BY: W.H.
1	OLD 23-126	6/30/26	DATE: 06/30/2026
2			
3			
4			
5			
6			
			DRAWING No
			26-104
			SHEET
			11 OF 28

SCHEDULE #1

MAXIMUM SHUTTER SPAN* "L+" OR "L-" (ft.). FOR INSTALLATIONS W/ SYMMETRICAL CENTERMATES, 21 & 22 or 31 or 32 W/ ONE H.V. LOCK 24 or 25 or 26 or HD LOCK 34 W/ NO LOCKING RODS 35 or CENTERMATES 28 & 29 W/ ONE HV "T" LOCK 30 W/TWO LOCKING RODS 35 TOP & BOTTOM (SEE NOTE †)

MAX. A.S.D. DESIGN PRESSURE RATING (p.s.f.) (+ OR -)	CONCRETE & WOOD INSTALLATIONS 0			
	WALL MOUNTING		FLOOR/CEILING MOUNTING	
	L + (ft)	L - (ft)	L + (ft)	L - (ft)
30 OR LESS	16'-0"	16'-0"	16'-0"	16'-0"
35	14'-10"	14'-10"	15'-2"	16'-0"
40	13'-10"	13'-10"	14'-2"	15'-2"
45	13'-1"	13'-1"	13'-4"	14'-3"
50	12'-5"	12'-5"	12'-8"	13'-7"
55	11'-10"	11'-10"	12'-1"	12'-11"
60	11'-4"	11'-4"	11'-7"	12'-4"
65	10'-10"	10'-10"	11'-1"	11'-11"
70	10'-6"	10'-6"	10'-9"	11'-5"
75	10'-1"	10'-1"	10'-4"	11'-1"
80	9'-10"	9'-10"	10'-0"	10'-9"
85	9'-6"	9'-6"	9'-9"	10'-5"
90	9'-3"	9'-3"	9'-5"	10'-1"
95	9'-0"	8'-9"	9'-2"	9'-10"
100	8'-9"	8'-4"	9'-0"	9'-7"
105	8'-7"	7'-11"	8'-9"	9'-4"
110	8'-4"	7'-7"	8'-7"	9'-2"
115	8'-2"	7'-3"	8'-4"	8'-11"
120	8'-0"	6'-11"	8'-2"	8'-9"
125	7'-10"	6'-8"	8'-0"	8'-5"
130	7'-8"	6'-5"	7'-10"	8'-1"
135	7'-7"	6'-2"	7'-9"	7'-9"
140	7'-5"	5'-11"	7'-7"	7'-6"
145	7'-3"	5'-9"	7'-5"	7'-3"
150	7'-2"	5'-7"	7'-4"	7'-0"
155	7'-0"	5'-5"	7'-2"	6'-9"
160	6'-11"	5'-2"	7'-1"	6'-7"
165	6'-10"	5'-1"	7'-0"	6'-4"
170	6'-9"	4'-11"	6'-11"	6'-2"
175	6'-7"	4'-9"	6'-9"	6'-0"
180	6'-6"	4'-8"	6'-8"	5'-10"
185	6'-5"	4'-6"	6'-7"	5'-8"
190	6'-4"	4'-5"	6'-6"	5'-6"
195	6'-3"	4'-3"	6'-5"	5'-5"
200	6'-2"	4'-2"	6'-4"	5'-3"
205	6'-1"	4'-1"	6'-3"	5'-1"

SCHEDULE #2

MAXIMUM SHUTTER SPAN* "L+" OR "L-" (ft.) FOR INSTALLATIONS W/ OPPOSING CENTERMATES, 21 & 22 ONE HV LOCK 24 or 25 or 26 W/ NO LOCKING RODS 35 (SEE NOTE †)

MAX. A.S.D. DESIGN PRESSURE RATING (p.s.f.) (+ OR -)	CONCRETE & WOOD INSTALLATIONS 0	
	WALL MOUNTING & FLOOR/CEILING MOUNTING	
	L + (ft)	L - (ft)
30	16'-0"	16'-0"
35	14'-10"	14'-10"
40	13'-10"	13'-10"
45	13'-1"	13'-1"
50	12'-5"	12'-5"
55	11'-10"	11'-10"
60	11'-4"	11'-4"
65	10'-10"	10'-10"
70	10'-6"	10'-6"
75	10'-1"	10'-1"
80	9'-10"	9'-10"
85	9'-6"	9'-6"
90	9'-3"	9'-3"
95	9'-0"	8'-9"
100	8'-9"	8'-4"
105	8'-7"	7'-11"
110	8'-4"	7'-7"
115	8'-2"	7'-3"
120	8'-0"	6'-11"
125	7'-10"	6'-8"
130	7'-8"	6'-5"
135	7'-7"	6'-2"
140	7'-5"	5'-11"
145	7'-3"	5'-9"
150	7'-2"	5'-7"
155	7'-0"	5'-5"
160	6'-11"	5'-2"
165	6'-10"	5'-1"
170	6'-9"	4'-11"
175	6'-7"	4'-9"
180	6'-6"	4'-8"
185	6'-5"	4'-6"
190	6'-4"	4'-5"
195	6'-3"	4'-3"
200	6'-2"	4'-2"
205	6'-1"	4'-1"

SCHEDULE #3

MAXIMUM SHUTTER SPAN* "L+" OR "L-" (ft.) INSTALLATIONS W/ SYMMETRICAL CENTERMATES 21 & 22 W/ ONE HV LOCKS 24 OR 25 W/ NO LOCKING RODS 35

MAX. A.S.D. DESIGN PRESSURE RATING (p.s.f.) (+ OR -)	CONCRETE INSTALLATIONS	
	FLOOR/CEILING MOUNTING OR FLOOR/WALL MOUNTING	
	L + (ft)	L - (ft)
30	16'-0"	16'-0"
35	15'-2"	16'-10"
40	14'-2"	15'-2"
45	13'-4"	14'-3"
50	12'-3"	13'-1"
55	11'-1"	11'-11"
60	10'-2"	10'-11"
65	9'-5"	10'-1"
70	8'-9"	9'-4"
75	-	8'-9"

INSTALLATION LEGEND		
	CONCRETE & MANSORY	WOOD
WALL MOUNTING	A, B, C, D, E, F, K & L	M, N, O, P, Q, R, S, & V.
FLOOR/CEILING MOUNTING	G, H, I, J & J	T, U, W & X

0 MAXIMUM SHUTTER SPAN "L+" OR "L-" FOR INSTALLATIONS INTO WOOD SHALL BE LIMITED TO 105 psf. A.S.D. DESIGN PRESSURE RATING.

† HV CORNER CENTERMATE #3 MAY BE USED AT ALL MOUNTING INSTALLATIONS. LOCKING SPECIFICATIONS SHALL BE AS INDICATED ON MANDATORY CONDITION #2 NOTE #5, SHEET 5.

SEPARATION TO GLASS SCHEDULE

WIND ZONE ASTM E-1996	MINIMUM SEPARATION TO GLASS
1 THRU 3	1"

1 HV BLADE

* NOTES:

(1) L+: MAXIMUM ALLOWABLE SPAN FOR A GIVEN A.S.D. POSITIVE DESIGN PRESSURE RATING.
L-: MAX. ALLOWABLE SPAN FOR A GIVEN NEGATIVE A.S.D. DESIGN PRESSURE RATING.

(2) PROCEDURE TO DETERMINE MAXIMUM SPAN FOR WALL MOUNTINGS (TOP/BOTTOM) OR FLOOR/CEILING:

GIVEN A POSITIVE A.S.D. DESIGN PRESSURE RATING, DETERMINE MAXIMUM SPAN "L+" FROM SCHEDULE. GIVEN A NEGATIVE A.S.D. DESIGN PRESSURE RATING, DETERMINE MAXIMUM SPAN "L-" FROM SCHEDULE.

FINAL MAXIMUM ALLOWABLE SPAN IS EQUAL TO THE MINIMUM DETERMINED SPAN BETWEEN "L+" AND "L-".

(3) PROCEDURE TO DETERMINE MAXIMUM SPAN FOR COMBINATIONS IN BETWEEN WALL MOUNTINGS W/ FLOOR/CEILING MOUNTINGS:


FOR A GIVEN POSITIVE A.S.D. DESIGN PRESSURE RATING:
DETERMINE:
L1+= MAX. SPAN FOR WALL MOUNTING INSTALLATIONS.
L2+= MAX. SPAN FOR FLOOR/CEILING MOUNTING INSTALLATIONS.

FOR A GIVEN NEGATIVE A.S.D. DESIGN PRESSURE RATING:
DETERMINE:
L1-= MAX. SPAN FOR WALL MOUNTING INSTALLATIONS.
L2-= MAX. SPAN FOR FLOOR/CEILING MOUNTING INSTALLATIONS.

FINAL MAXIMUM ALLOWABLE SPAN IS EQUAL TO THE MINIMUM BETWEEN "L1+", "L2+", "L1-" AND "L2-"

(4) GO TO ANCHOR SCHEDULE WITH FINAL MAXIMUM ALLOWABLE SPAN AND NEGATIVE A.S.D. DESIGN PRESSURE RATING TO DETERMINE MAXIMUM ANCHOR SPACING.

FLORIDA BUILDING CODE (Non High Velocity Hurricane Zone)



©2026 TILTECO, INC.

TILTECO INC.

TILLIT TESTING & ENGINEERING COMPANY
6355 N.W. 36th. St., Ste. 305, VIRGINIA GARDENS, FLORIDA 33166
Phone : (305)871-1530 . Fax : (305)871-1531
e-mail: tilteco@aol.com
CA-0006719
WALTER A. TILLIT Jr. P.E.
FLORIDA Lic. # 44167

A.S.S.A.
American Shutter Systems
Association, Inc.
4268 Westroads Drive
West Palm Beach, FL 33407

© 2026 EASTERN METAL SUPPLY, INC.

BERTHA HV™
Accordion Shutter System

H.V. BLADE #1 W/ OR W/O H.V. WINDOW BLADE & H.V. BLADE #2

REV. No	DESCRIPTION	DATE	DRAWN BY: W.H.
1	OLD 23-126	6/30/26	DATE: 06/30/2026
2			
3			
4			
5			
6			

DRAWING No
26-104

SHEET
12 OF 28

MAXIMUM ANCHOR* SPACING (in.) SCHEDULE FOR A GIVEN MAX. SHUTTER SPAN.
DESIGN NEGATIVE LOAD AND A CORRESPONDING MOUNTING TYPE FOR CONCRETE OR CONCRETE BLOCK INSTALLATIONS
(SEE MOUNTINGS A, B, C, D AND F ON SHEET 6)

ANCHORS SPACING LEGEND

410 SS TAPCON OR
OR ULTRAACON+
OR ULTRAACON SS4
BLUE TAP

* SEE ANCHOR
SPECIFICATIONS
ON SHEET 14

◆ SEE LIMITATIONS OF USE FOR
BLADE ①A ON SHEET 28

① HV BLADE OR ① HV BLADE
W/ ①A HV WINDOW BLADE
WORKING IN UNISON ◆

MAXIMUM SPAN (ft)	POURED CONCRETE																		POURED CONCRETE/CONCRETE BLOCK																																			
	(A) WALL HEADER MOUNTING W/ (12)									(A) WALL HEADER MOUNTING W/ (14)									(B) WALL HEADER MOUNTING									(D) WALL SILL MOUNTING W/ (12)									(D) WALL SILL MOUNTING W/ (14)									(C) & (F) WALL HEADER/SILL MOUNTING								
	A.S.D. DESIGN NEGATIVE LOAD (psf)									A.S.D. DESIGN NEGATIVE LOAD (psf)									A.S.D. DESIGN NEGATIVE LOAD (psf)									A.S.D. DESIGN NEGATIVE LOAD (psf)									A.S.D. DESIGN NEGATIVE LOAD (psf)									A.S.D. DESIGN NEGATIVE LOAD (psf)								
	30	40	60	75	90	120	160	205		30	40	60	75	90	120	160	205	30	40	60	75	90	120	160	205	30	40	60	75	90	120	160	205	30	40	60	75	90	120	160	205	30	40	60	75	90	120	160	205					
3'-0" OR LESS	14	12	10	9	8	8	6	6		14	12	10	9	8	8	6	6		14	12	10	9	8	8	6	6		14	12	10	9	8	8	6	6		14	12	10	9	8	8	6	5.5		8	8	8	8	8	8	7	5.5	
	14	12	10	9	8	8	6	6		14	12	10	9	8	8	6	6		14	12	10	9	8	8	6	6		14	12	10	9	8	8	6	6		14	12	10	9	8	8	6	6		8	8	8	8	8	8	8	8	
	14	12	10	9	8	8	6	5		14	12	10	9	8	8	6	6		14	12	10	9	8	8	6	6		14	12	10	9	8	8	6	6		14	12	10	9	8	8	6	6		8	8	8	8	8	8	8	6.5	
	14	12	10	9	8	8	6	6		14	12	10	9	8	8	6	6		14	12	10	9	8	8	6	6		14	12	10	9	8	8	6	3		14	12	10	9	8	8	6	6		8	8	8	8	8	8	8	7	
4'-0"	14	12	10	9	8	8	6	4		14	12	10	9	8	8	6	6		14	12	10	9	8	8	6	6		14	12	10	9	8	7	-	-		14	12	10	9	8	7	5.5	-		8	8	8	8	8	7	5.5	4	
	14	12	10	9	8	8	6	4		14	12	10	9	8	8	6	6		14	12	10	9	8	8	6	6		14	12	10	9	8	8	5.5	-		14	12	10	9	8	8	6	6		8	8	8	8	8	8	8	8	
	14	12	10	9	8	8	4.5	-		14	12	10	9	8	8	6	4		14	12	10	9	8	8	6	6		14	12	10	9	8	8	8	-		14	12	10	9	8	8	6	6		8	8	8	8	8	8	6.5	5	
	14	12	10	9	8	8	6	4		14	12	10	9	8	8	6	6		14	12	10	9	8	8	6	6		14	12	10	9	8	8	8	-		14	12	10	9	8	8	6	6		8	8	8	8	8	8	7	5.5	
5'-0"	14	12	10	9	8	8	4.5	-		14	12	10	9	8	8	6	3.5		14	12	10	9	8	8	6	6		14	12	10	9	7.5	-	-		14	12	10	9	7.5	5.5	-		8	8	8	8	7.5	5.5	4	3			
	14	12	10	9	8	8	4.5	-		14	12	10	9	8	8	6	3.5		14	12	10	9	8	8	6	6		14	12	10	9	8	7	-	-		14	12	10	9	8	8	6	-		8	8	8	8	8	8	8	8	
	14	12	10	9	8	5.5	-	-		14	12	10	9	8	8	4.5	-		14	12	10	9	8	8	6	5		14	12	10	9	8	3	-	-		14	12	10	9	8	7	-	-		8	8	8	8	8	7	5	4	
	14	12	10	9	8	8	4	-		14	12	10	9	8	8	6	3.5		14	12	10	9	8	8	6	6		14	12	10	9	8	8	3	-	-	14	12	10	9	8	7.5	-	-		8	8	8	8	8	7.5	5.5	4	
6'-0"	14	12	10	9	8	5.5	3	-		14	12	10	9	8	8	4.5	-		14	12	10	9	8	8	6	6		14	12	10	9	8.5	7.5	4	-	-	14	12	9.5	7.5	6.5	3.5	-	-		8	8	8	7.5	6.5	4.5	3.5	-	
	14	12	10	9	8	5.5	-	-		14	12	10	9	8	8	4.5	-		14	12	10	9	8	8	6	6		14	12	10	9	8	4	-	-		14	12	10	9	8	8	4	-		8	8	8	8	8	8	7.5	7	
	14	12	10	9	8	3	-	-		14	12	10	9	8	8	-	-		14	12	10	9	8	8	5.5	3.5		14	12	10	9	8	4.5	-	-		14	12	10	9	7.5	4	-	-		8	8	8	8	7.5	5.5	4	3	
	14	12	10	9	8	5	-	-		14	12	10	9	8	8	4	-	-	14	12	10	9	8	8	6	5.5		14	12	10	9	8	5	-	-		14	12	10	9	8	4.5	-	-		8	8	8	8	6	4.5	-	-	
7'-0"	14	12	10	9	8	4	-	-		14	12	10	9	8	6.5	3	-		14	12	10	9	8	8	6	-		14	12	8	4.5	-	-	-		14	12	8	6.5	5.5	-	-		8	8	8	6.5	5.5	4	3	-			
	14	12	10	9	8	4	-	-		14	12	10	9	8	6.5	3	-		14	12	10	9	8	8	6	-		14	12	10	9	6	-	-		14	12	10	9	8	7	-	-		8	8	8	8	8	7.5	6			
	14	12	10	9	4.5	-	-		14	12	10	9	8	4	-	-		14	12	10	9	8	7	4	-		14	12	10	5.5	-	-	-		14	12	10	8	6.5	-	-		8	8	8	8	6.5	5	3.5	-				
	14	12	10	9	7.5	3.75	-	-		14	12	10	9	8	6	-	-		14	12	10	9	8	8	6	-		14	12	10	6	-	-	-		14	12	10	8.5	7	-	-		8	8	8	8	7	5	4	-			
8'-0"	14	12	10	9	5.5	3	-	-		14	12	10	9	8	4.5	-	-		14	12	10	9	8	8	-	-		14	11	7	-	-	-	-		14	11	7	5.5	3.5	-	-		8	8	7	5.5	4.5	3.5	-	-			
	14	12	10	9	5.5	-	-	-		14	12	10	9	8	4.5	-	-		14	12	10	9	8	8	-	-		14	12	10	7	4	-	-		14	12	10	9	8	3	-	-		8	8	8	8	7.5	7	4			
	14	12	10	5.5	3	-	-	-		14	12	10	9	8	-	-	-		14	12	10	9	8	5.5	-	-		14	12	8.5	3	-	-	-		14	12	8.5	7	4	-	-		8	8	8	7	5.5	4	3	-			
	14	12	10	9	5	-	-	-		14	12	10	9	8	4	-	-	-		14	12	10	9	8	8	-	-		14	12	9.5	-	-	-	-		14	12	9.5	7.5	4.5	-	-		8	8	8	7.5	6	4.5	-	-		
9'-0"	14	12	10	6.5	4.5	-	-	-		14	12	10	9	7.5	-	-	-		14	12	10	9	8	-	-	-		13	9.5	4	-	-	-	-		13	9.5	6.5	5	-	-	-		8	8	6.5	5	4	3	-	-			
	14	12	10	6.5	4	-	-	-		14	12	10	9	7.5	-	-	-		14	12	10	9	8	-	-	-		14	12	10	5	-	-	-		14	12	10	9	5.5	-	-	-		8	8	8	8	6.5	6	3	-		
	14	12	8.5	4	-	-	-	-		14	12	10	9	4.5	-	-	-		14	12	10	9	7.5	-	-	-		14	11.5	4.5	-	-	-	-		14	11.5	7.5	6	-	-	-		8	8	7.5	6	5	4	-	-			
	14	12	10	6	4	-	-	-		14	12	10	9	7	-	-	-		14	12	10	9	8	-	-	-		14	12	5	-	-	-	-		14	12	8	6.5	-	-	-		8	8	8	6.5	5.5	4	-	-			
10'-0"	14	12	9.5	5	3.5	-	-	-		14	12	10	9	5.5	-	-	-		14	12	10	9	8	-	-	-		11.5	8.5	-	-	-	-	-		11.5	8.5	5.5	-	-	-	-		8	8	5.5	4.5	3.5	-	-	-			
	14	12	9.5	5	3.5	-	-	-		14	12	10	9	5.5	-	-	-		14	12	10	9	8	-	-	-		14	12	7	-	-	-	-		14	12	10	7.5	5	-	-	-		8	8	8	8	7.5	4.5	-	-		
	14	12	5.5	3	-	-	-	-		14	12	10	6	3	-	-	-		14	12	10	9	6	-	-	-		14	10.5	3	-	-	-	-		14	10.5	7	3.5	-	-	-	-		8	8	7	5.5	4.5	3.5	-	-		
	14	12	9	4.5	3	-	-	-		14	12	10	9	5	-	-	-		14	12	10	9	8	-	-	-		14	11	-	-	-	-	-		14	11	7.5	-	-	-	-		8	8	7.5	6	5	-</					

MAXIMUM ANCHOR* SPACING (in.) SCHEDULE FOR A GIVEN MAX. SHUTTER SPAN, A.S.D.
DESIGN NEGATIVE PRESSURE RATING AND A CORRESPONDING MOUNTING TYPE FOR CONCRETE OR CONCRETE BLOCK INSTALLATIONS
(SEE MOUNTINGS E, G, & H ON SHEETS 6 & 7)

MAXIMUM SPAN (ft)	POURED CONCRETE/CONCRETE BLOCK								POURED CONCRETE															
	Ⓔ WALL SILL MOUNTING								Ⓖ CEILING MOUNTING								Ⓕ FLOOR MOUNTING							
	A.S.D. DESIGN NEGATIVE LOAD (psf)								A.S.D. DESIGN NEGATIVE LOAD (psf)								A.S.D. DESIGN NEGATIVE LOAD (psf)							
	30	40	60	75	90	120	160	205	30	40	60	75	90	120	160	205	30	40	60	75	90	120	160	205
3'-0" OR LESS	14	12	10	9	8	8	6	5.5	14	12	10	9	8	8	6	6	14	12	10	9	8	8	6	6
	14	12	10	9	8	8	6	6	14	12	10	9	8	8	6	6	14	12	10	9	8	8	6	6
	14	12	10	9	8	8	6	6	14	12	10	9	8	8	6	6	14	12	10	9	8	8	6	5
	14	12	10	9	8	8	6	7	14	12	10	9	8	8	6	6	14	12	10	9	8	8	6	6
4'-0"	14	12	10	9	8	7	5.5	3.5	14	12	10	9	8	8	6	6	14	12	10	9	8	8	6	5
	14	12	10	9	8	8	6	6	14	12	10	9	8	8	6	6	14	12	10	9	8	8	6	5.5
	14	12	10	9	8	8	6	4	14	12	10	9	8	8	6	4.5	14	12	10	9	8	8	6	4
	14	12	10	9	8	8	6	4.5	14	12	10	9	8	8	6	5.5	14	12	10	9	8	8	6	4.5
5'-0"	14	12	10	9	7.5	5.5	3.5	-	14	12	10	9	8	8	6	5	14	12	10	9	8	7	5.5	4
	14	12	10	9	8	8	6	6	14	12	10	9	8	8	6	5.5	14	12	10	9	8	8	6	4.5
	14	12	10	9	8	7	4	-	14	12	10	9	8	6.5	5	3.5	14	12	10	8	6.5	5	3.5	3
	14	12	10	9	8	7.5	4.5	-	14	12	10	9	8	8	6	4.5	14	12	10	9	8	6	4.5	3.75
6'-0"	14	12	9.5	7.5	6.5	4.5	-	-	14	12	10	9	8	7.5	5.5	4	14	12	10	9	8	6	4.5	3.5
	14	12	10	9	8	8	6	-	14	12	10	9	8	8	6	5	14	12	10	9	8	6.5	5	3.5
	14	12	10	9	7.5	5.5	3	-	14	12	10	8.5	7	5.5	4	3	14	12	8	6.5	5.5	4	3	-
	14	12	10	9	8	6	-	-	14	12	10	9	8	6.5	5	3.75	14	12	10	8.5	8	5	4	-
7'-0"	14	12	8	6.5	5.5	3	-	-	14	12	10	9	8	6.5	4.5	3.5	14	12	10	8	7	5	3.5	3
	14	12	10	9	8	8	-	-	14	12	10	9	8	7	5	4	14	12	10	9	7.5	5.5	4	3
	14	12	10	8	6.5	4	-	-	14	12	9	7.5	6	4.5	3.5	-	14	10.5	7	5.5	4.5	3.5	-	-
	14	12	10	8.5	7	4	-	-	14	12	10	9	7.5	5.5	4	-	14	12	9	7	7.5	4.5	-	-
8'-0"	14	11	7	5.5	4.5	-	-	-	14	12	10	9	7.5	5.5	4	-	14	12	9	7	6	4.5	3	-
	14	12	10	9	8	6.5	-	-	14	12	10	9	8	6	4	-	14	12	10	8	6.5	5	3.5	-
	14	12	8.5	7	5.5	3	-	-	14	12	8	6.5	5.5	4	3	-	12.5	9.5	6	5	4	3	-	-
	14	12	9.5	7.5	6	-	-	-	14	12	9.5	8	6.5	5	-	-	14	12	8	6	6.5	4	-	-
9'-0"	13	9.5	6.5	5	3.5	-	-	-	14	12	10	8	6.5	5	-	-	14	12	8	6.5	5	4	-	-
	14	12	10	9	8	-	-	-	14	12	10	9	7.5	4.5	-	-	14	12	8.5	7	5.5	4	-	-
	14	11.5	7.5	6	4	-	-	-	14	11	7	5.5	5	3.5	-	-	11	8	5.5	4.5	3.5	-	-	-
	14	12	8	6.5	4.5	-	-	-	14	12	8.5	7	5.5	4	-	-	14	10.5	7	5.5	6	4.5	-	-
10'-0"	11.5	8.5	5.5	4	-	-	-	-	14	12	9	7	6	4.5	-	-	14	11	7	5.5	4.5	3.5	-	-
	14	12	10	9	7.5	-	-	-	14	12	10	8	6.5	5	-	-	14	12	8	6	5	4	-	-
	14	10.5	7	5	3.5	-	-	-	13	9.5	6.5	5	4	3	-	-	10	7.5	5	4	3	-	-	-
	14	11	7.5	5.5	-	-	-	-	14	11.5	9	6	5	4	-	-	12.5	9.5	6	5	4	4	-	-
11'-0"	10.5	8	5	-	-	-	-	-	14	12	8	6.5	5.5	4	-	-	13	10	6.5	5	4	3	-	-
	14	12	10	-	-	-	-	-	14	12	9	7	6	4.5	-	-	14	10.5	7	5.5	4.5	3.5	-	-
	12.5	9.5	5	-	-	-	-	-	12	9	6	4.5	4	3	-	-	9	7	4.5	3.5	3	-	-	-
	14	10	7	-	-	-	-	-	14	10.5	7	5.5	4.5	-	-	-	11.5	8.5	5.5	4.5	3.75	-	-	-
12'-0"	9.5	7	4.5	-	-	-	-	-	14	11.5	7.5	6	5	-	-	-	12	9	6	4.5	4	-	-	-
	14	12	10	-	-	-	-	-	14	12	8	6.5	5.5	-	-	-	13	10	6.5	5	4	-	-	-
	11.5	8.5	4.5	-	-	-	-	-	11	8	5.5	4	3.5	-	-	-	8	6	4	3	-	-	-	-
	13.5	9.5	6	-	-	-	-	-	13	9.5	6.5	5	4	-	-	-	10.5	8	5	4	-	-	-	-
13'-0"	9	6.5	-	-	-	-	-	-	14	10.5	7	5.5	4.5	-	-	-	11	8.5	5.5	4.5	3.5	-	-	-
	14	12	-	-	-	-	-	-	14	11.5	7.5	6	5	-	-	-	12	9	6	4.5	4	-	-	-
	10.5	8	-	-	-	-	-	-	10	7.5	5	4	3	-	-	-	7.5	5.5	4	3	-	-	-	-
	12.5	8.5	-	-	-	-	-	-	12	9	6	4.5	4	-	-	-	9.5	7	5	4	-	-	-	-
14'-0"	8	6	-	-	-	-	-	-	13	9.5	6.5	5	-	-	-	-	10.5	7.5	5	4	-	-	-	-
	14	12	-	-	-	-	-	-	14	10.5	7	5.5	-	-	-	-	11	8.5	5.5	4.5	-	-	-	-
	10	7.5	-	-	-	-	-	-	9	7	4.5	3.5	-	-	-	-	7	5	3.5	3	-	-	-	-
	11.5	8	-	-	-	-	-	-	11	8	5.5	4.5	-	-	-	-	9	6.5	4.5	-	-	-	-	-
15'-0"	7.5	-	-	-	-	-	-	-	12	9	6	-	-	-	-	-	9.5	7	4.5	-	-	-	-	-
	14	-	-	-	-	-	-	-	13.5	10	6.5	-	-	-	-	-	10.5	8	5	-	-	-	-	-
	9	-	-	-	-	-	-	-	8.5	6.5	4	-	-	-	-	-	6.5	5	3	-	-	-	-	-
	10	-	-	-	-	-	-	-	10.5	8	5	-	-	-	-	-	8.5	6	4	-	-	-	-	-
16'-0"	7	-	-	-	-	-	-	-	11.5	8.5	5.5	-	-	-	-	-	9	6.5	4.5	-	-	-	-	-
	14	-	-	-	-	-	-	-	12.5	9.5	6	-	-	-	-	-	10	7.5	5	-	-	-	-	-
	8	-	-	-	-	-	-	-	8	6	4	-	-	-	-	-	6	4.5	3	-	-	-	-	-
	9.5	-	-	-	-	-	-	-	9.5	7	5	-	-	-	-	-	8	6	4	-	-	-	-	-

MAXIMUM ANCHOR* SPACING (in.) SCHEDULE FOR A GIVEN MAX. SHUTTER SPAN, A.S.D.
DESIGN NEGATIVE LOAD AND A CORRESPONDING MOUNTING TYPE FOR CONCRETE OR CONCRETE BLOCK INSTALLATIONS
(SEE MOUNTINGS I, J, K & L ON SHEET 7)

MAXIMUM SPAN (ft)	POURED CONCRETE																POURED CONCRETE/CONCRETE BLOCK																
	(I) WALK OVER & (11) TRENCH MOUNTINGS ⚡								(J) RAINGUARD MOUNTING								(K) WALL/FLOOR MOUNTING								(L) WALL/WALK OVER MOUNTING								
	A.S.D DESIGN NEGATIVE LOAD (psf)								A.S.D. DESIGN NEGATIVE LOAD (psf)								A.S.D. DESIGN NEGATIVE LOAD (psf)								A.S.D. DESIGN NEGATIVE LOAD (psf)								
	30	40	60	75	90	120	160	205	30	40	60	75	90	120	160	205	30	40	60	75	90	120	160	205	30	40	60	75	90	120	160	205	
3'-0" OR LESS	14	12	10	9	8	8	6	6	12	12	12	12	12	11.5	8.5	6.5	7	7	7	7	7	7	7	5.5	5	5	5	5	5	5	5	5	
	14	12	10	9	8	8	6	6	12	12	12	12	12	12	9.5	7	7	7	7	7	7	7	7	5	5	5	5	5	5	5	5	5	
	14	12	10	9	8	8	6	6	12	12	12	12	12	10.5	8	6	4.5	7	7	7	7	7	7	6.5	5	5	5	5	5	5	5	5	
	14	12	10	9	8	8	6	6	12	12	12	12	12	10	7.5	6	7	7	7	7	7	7	7	5	5	5	5	5	5	5	5	5	
4'-0"	14	12	10	9	8	8	6	6	12	12	12	12	12	11.5	8.5	6.5	5	7	7	7	7	7	7	5.5	4	5	5	5	5	5	5	4	
	14	12	10	9	8	8	6	6	12	12	12	12	12	9.5	7	5.5	7	5.5	7	7	7	7	7	4	5	5	5	5	5	5	5	5	
	14	12	10	9	8	8	6	6	12	12	12	9.5	8	6	4.5	3.5	7	7	7	7	7	7	6.5	5	5	5	5	5	5	5	5	5	
	14	12	10	9	8	8	6	6	12	12	12	12	10	7.5	5.5	4	7	7	7	7	7	7	7	5.5	5	5	5	5	5	5	5	5	
5'-0"	14	12	10	9	8	8	6	6	12	12	12	11	9	7	5	4	7	7	7	7	7	7	5.5	4	3	5	5	5	5	5	5	4	3
	14	12	10	9	8	8	6	6	12	12	12	12	10	7.5	5.5	4	7	7	7	7	7	7	7	5	5	5	5	5	5	5	5	5	
	14	12	10	9	8	8	6	6	12	12	12	9.5	7	6	4.5	3.5	7	7	7	7	7	7	5	5	5	5	5	5	5	5	5	5	
	14	12	10	9	8	8	6	6	12	12	12	9.5	8	6	4.5	—	7	7	7	7	7	7	5	5	5	5	5	5	5	5	5	4	
6'-0"	14	12	10	9	8	8	6	6	12	12	11.5	9	7.5	5.5	4	3	7	7	7	7	7	7	4.5	3.5	—	5	5	5	5	5	4.5	3.5	—
	14	12	10	9	8	8	6	6	12	12	12	10	8	6	4.5	3.5	7	7	7	7	7	7	7	7	5	5	5	5	5	5	5	5	
	14	12	10	9	8	8	6	6	12	12	12	8	6	5	4	3	7	7	7	7	7	7	5.5	4	5	5	5	5	5	5	4	3	
	14	12	10	9	8	8	6	6	12	12	10	8	6.5	5	3.75	—	7	7	7	7	7	7	6	4.5	—	5	5	5	5	5	5	4.5	—
7'-0"	14	12	10	9	8	8	6	6	12	12	10	8	6.5	5	3.5	—	7	7	7	6.5	5.5	4	—	—	5	5	5	5	5	4	3	—	
	14	12	10	9	8	8	6	6	12	12	12	8.5	7	5	4	3	7	7	7	7	7	7	7	6	5	5	5	5	5	5	5	5	
	14	12	10	9	8	8	6	6	12	10	6.5	5	4.5	3	—	—	7	7	7	7	6.5	5	3	—	5	5	5	5	5	5	3.5	3	
	14	12	10	9	8	8	6	6	12	12	8.5	7	5.5	4	—	—	7	7	7	7	7	5	—	—	5	5	5	5	5	5	4	—	
8'-0"	14	12	10	9	8	8	6	—	12	12	8.5	7	5.5	4	3	—	7	7	7	5.5	4.5	3	—	—	5	5	5	5	4.5	3.5	—	—	
	14	12	10	9	8	8	6	—	12	12	10.5	7.5	6	4.5	3.5	—	7	7	7	7	7	7	7	4	5	5	5	5	5	5	5	5	
	14	12	10	9	8	8	6	—	12	9	6	4.5	4	3	—	—	7	7	7	7	5.5	4	—	—	5	5	5	5	5	4	3	—	
	14	12	10	9	8	8	6	—	12	11	7.5	6	5	3.75	—	—	7	7	7	7.5	6	4.5	—	—	5	5	5	5	5	4.5	—	—	
9'-0"	14	12	10	9	8	8	—	—	12	11.5	7.5	6	5	3.5	—	—	7	7	6.5	5	4	—	—	—	5	5	5	5	4	3	—	—	
	14	12	10	9	8	8	—	—	12	12	9.5	6.5	5.5	4	3	—	7	7	7	7	7	7	6	3	5	5	5	5	5	5	5	5	
	14	12	10	9	8	8	—	—	10.5	8	5	4	3.5	—	—	—	7	7	7	6	5	3.5	—	—	5	5	5	5	5	4	3	—	
	14	12	10	9	8	8	—	—	12	10	6.5	5	4.5	—	—	—	7	7	7	6.5	5.5	—	—	—	5	5	5	5	5	4	—	—	
10'-0"	14	12	10	9	8	8	—	—	12	10.5	7	5.5	4.5	3.5	—	—	7	7	5.5	4.5	3.5	—	—	—	5	5	5	4.5	3.5	—	—	—	
	14	12	10	9	8	8	—	—	12	11	8.5	6	5	3.5	—	—	7	7	7	7	7	7	4.5	—	5	5	5	5	5	5	4.5	—	
	14	12	10	9	8	8	—	—	9.5	7	4.5	3.5	3	—	—	—	7	7	7	5.5	4.5	—	—	—	5	5	5	5	4.5	3.5	—	—	
	14	12	10	9	8	8	—	—	12	9	6	5	4	—	—	—	7	7	7	6	5	—	—	—	5	5	5	4.5	5	—	—	—	
11'-0"	14	12	10	9	8	8	—	—	12	9.5	6	5	4	3	—	—	7	7	5	4	3	—	—	—	5	5	5	4	3.5	—	—	—	
	14	12	10	9	8	8	—	—	12	10	7	5.5	4.5	3.5	—	—	7	7	7	7	7	7	3.5	—	5	5	5	5	5	5	4	—	
	14	12	10	9	8	8	—	—	8.5	6.5	4	3.5	3	—	—	—	7	7	6	5	4	—	—	—	5	5	5	5	4	3	—	—	
	14	12	10	9	8	8	—	—	11	8	5.5	4	—	—	—	—	7	7	7	5.5	4.5	—	—	—	5	5	5	5	4.5	—	—	—	
12'-0"	14	12	10	9	8	—	—	—	11.5	8.5	5.5	4.5	3.5	—	—	—	7	7	4.5	3.5	—	—	—	—	5	5	4.5	3.5	3	—	—	—	
	14	12	10	9	8	—	—	—	12	9.5	6.5	5	4	3	—	—	7	7	7	7	7	6	3	—	5	5	5	5	5	5	4.5	3.5	
	14	12	10	9	8	—	—	—	8	6	4	3	—	—	—	—	7	7	5.5	4.5	3.5	—	—	—	5	5	5	4.5	4	3	—	—	
	14	12	10	9	8	—	—	—	10	7.5	5	4	—	—	—	—	7	7	6	5	—	—	—	—	5	5	5	5	4	—	—	—	
13'-0"	14	12	10	9	8	—	—	—	10.5	8	5	4	3.5	—	—	—	7	6.5	4.5	3.5	—	—	—	—	5	5	4.5	3.5	3	—	—	—	
	14	12	10	9	8	—	—	—	11.5	8.5	6	4.5	3.5	3	—	—	7	7	7	7	7	4.5	—	—	5	5	5	5	5	5	4.5	3.5	
	14	12	10	9	8	—	—	—	7	5.5	3.5	3	—	—	—	—	7	7	5	4	3	—	—	—	5	5	5	4	3	—	—	—	
	14	12	10	9	8	—	—	—	9	7	4.5	3.75	—	—	—	—	7	7	5.5	4.5	—	—	—	—	5	5	5	4.5	4	—	—	—	
14'-0"	14	12	10	9	—	—	—	—	10	7.5	5	4	3	—	—	—	7	6	4	3	—	—	—	—	5	5	4	3	—	—	—	—	
	14	12	10	9	—	—	—	—	10.5	8	5.5	4	3.5	—	—	—	7	7	7	7	7	4	—	—	5	5	5	5	5	4	3	—	
	14	12	10	9	—	—	—	—	6.5	5	3	—	—	—	—	—	7	7	5	3.5	—	—	—	—	5	5	5	4	—	—	—	—	
	14	12	10	9	—	—	—	—	8.5	6.5	4	—	—	—	—	—	7	7	5	4	—	—	—	—	5	5	5	4	—	—	—	—	
15'-0"	14	12	10	—	—	—	—	—	9	7	4.5	3.5	3	—	—	—	7	5.5	3.5	—	—	—	—	—	5	5	3.5	3	—	—	—	—	
	14	12	10	—	—	—	—	—	10	7.5	5	4	3	—	—	—	7	7	7	7	7	3.5	—	—	5	5	5	5	5	5	4	3	
	14	12	10	—	—	—	—	—	6	4.5	3	—	—	—	—	—	7	7	4.5	3	—	—	—	—	5	5	4.5	3.5	—	—	—	—	
	14	12	10	—	—	—	—	—	8	6	4	—	—	—	—	—	7	7	5	—	—	—	—	—	5	5	5	4	—	—	—	—	
16'-0"	14	12	10	—	—	—	—	—	8.5	6.5	4	3.5	—	—	—	—	7	5.5	3.5	—	—	—	—	—	5	5	3.5	—	—	—	—	—	
	14	12	10	—	—	—	—	—	9.5	7	4.5	3.5	3	—	—	—	7	7	7	7	6	3	—	—	5	5	5	5	5	4.5	3.5	—	
	14	12	10	—	—	—	—	—	6	4.5	3	—	—	—	—	—	7	6.5	4	—	—	—	—	—	5	5	4	3.5	—	—	—	—	
	14	12	10	—	—	—	—	—	7.5	5.5	3.75	—	—	—	—	—	7	7	4.5	—	—	—	—	—	5	5	4.5	—	—	—	—	—	

ANCHORS SPACING LEGEND


410 SS TAPCON OR 1/4"Ø ULTRACON+ OR ULTRACON SS4
FEMALE PANEL MATE
BLUE TAP

* SEE ANCHOR
SPECIFICATIONS
ON SHEET 14

◇ VALID ONLY FOR UP TO +70, -75
PSF A.S.D. DESIGN PRESSURE
RATING & FOR SPANS PER
SCHEDULE #3, SHEET 12

① HV BLADE ONLY

FLORIDA BUILDING CODE (Non High Velocity Hurricane Zone)



©2026 TILTECO, INC.

TILTECO INC.

TILLIT TESTING & ENGINEERING COMPANY
6355 N.W. 36th. St., Ste. 305, VIRGINIA GARDENS, FLORIDA 33166
Phone : (305)871-1530 . Fax : (305)871-1531
e-mail: tilteco@aol.com
CA-0006719
WALTER A. TILLIT Jr. P.E.
FLORIDA Lic. # 44167

A.S.S.A.
American Shutter Systems
Association, Inc.
4268 Westroads Drive
West Palm Beach, FL 33407

© 2026 EASTERN METAL SUPPLY, INC.

BERTHA HV™
Accordion Shutter System

H.V. BLADE #1 W/ OR W/O H.V. WINDOW BLADE & H.V. BLADE #2

REV. No	DESCRIPTION	DATE	DRAWN BY: W.H.
1	OLD 23-126	6/30/26	DATE: 06/30/2026
2			
3			
4			
5			
6			

DRAWING No
26-104

SHEET
15 OF 28

MAXIMUM ANCHOR⁺ SPACING (in.) SCHEDULE FOR A GIVEN MAX. SHUTTER SPAN,
NEGATIVE A.S.D. DESIGN PRESSURE RATING AND A CORRESPONDING MOUNTING TYPE
(SEE MOUNTINGS ON SHEETS 18 & 19)

MAXIMUM SPAN (ft)	SUBSTRATE																																									
	SOUTHERN PINE No. 2 W/ MIN. G=0.55, DOUGLAS FIR W/ MIN. G=0.50												SPRUCE PINE FIR NORTH W/ MIN. G=0.43												SPRUCE PINE FIR SOUTH W/ MIN. G=0.36												1/2" MIN. CDX PLYWOOD					
	WALL MOUNTINGS M, N, O & R						CEILING MOUNT T FLOOR MOUNTINGS W & X						WALL MOUNTINGS M, N, O & R						CEILING MOUNT T FLOOR MOUNTINGS W & X						WALL MOUNTINGS M, N, O & R						CEILING MOUNT T FLOOR MOUNTINGS W & X						WALL MOUNTINGS P & Q					
	A.S.D. NEGATIVE DESIGN LOAD (psf)						A.S.D. NEGATIVE DESIGN LOAD (psf)						A.S.D. NEGATIVE DESIGN LOAD (psf)						A.S.D. NEGATIVE DESIGN LOAD (psf)						A.S.D. NEGATIVE DESIGN LOAD (psf)						A.S.D. NEGATIVE DESIGN LOAD (psf)						A.S.D. NEGATIVE DESIGN LOAD (psf)					
	30	40	60	75	90	105	30	40	60	75	90	105	30	40	60	75	90	105	30	40	60	75	90	105	30	40	60	75	90	105	30	40	60	75	90	105	30	40	60	75	90	105
3'-0" OR LESS	12	10	10	9	8	8	6	6	6	6	6	5	12	10	10	9	8	8	6	6	6	6	5	4	12	10	10	9	8	8	6	6	6	4.5	4	3	6	5	4	4	4	3
4'-0"	12	10	10	9	8	8	6	6	6	5	4.5	4	12	10	10	9	8	8	6	6	5.5	4.5	3.5	3	12	10	10	9	8	8	6	6	4.5	3.5	3	2.5	6	5	4	4	4	3
5'-0"	12	10	10	9	8	8	6	6	5	4	3.5	3	12	10	10	9	8	8	6	6	4.5	3.5	3	2.5	12	10	10	9	8	7	6	5.5	3.5	3	2	2	6	5	4	4	4	3
6'-0"	12	10	10	9	8	6.5	6	6	4.5	3.5	3	2.5	12	10	10	9	8	4.5	6	5.5	3.5	3	2.5	2	12	10	10	9	6	3	6	4.5	3	2	2	-	6	5	4	4	3.5	-
7'-0"	12	10	10	9	6.5	4	6	5.5	4	3	2.5	2	12	10	10	9	4.5	3	6	5	3	2.5	2	-	12	10	10	7	3	-	5	4	2.5	2	-	-	6	5	4	4	-	-
8'-0"	12	10	10	7.5	4.5	3	6	5	3	2.5	2	2	12	10	10	5.5	3	-	5.5	4	2.5	2	2	-	12	10	10	4	-	-	4.5	3	2	-	-	-	6	5	4	-	-	-
9'-0"	12	10	10	5	3.5	-	6	4.5	3	2	2	-	12	10	8.5	4	-	-	5	3.5	2.5	2	-	-	12	10	4	2.5	-	-	4	3	2	-	-	-	6	5	3.5	-	-	-
10'-0"	12	10	7.5	4	-	-	5	4	2.5	2	-	-	12	10	5.5	3	-	-	4.5	3	2	-	-	-	12	10	3	-	-	-	3.5	2.5	-	-	-	-	6	5	-	-	-	-
11'-0"	12	10	5.5	-	-	-	5	3.5	2	-	-	-	12	10	4	-	-	-	4	3	2	-	-	-	12	10	-	-	-	-	3	2.5	-	-	-	-	6	5	-	-	-	-
12'-0"	12	10	4.5	-	-	-	4.5	3	2	-	-	-	12	10	3	-	-	-	3.5	2.5	-	-	-	-	12	10	-	-	-	-	3	2	-	-	-	-	6	5	-	-	-	-
13'-0"	12	10	-	-	-	-	4	3	-	-	-	-	12	10	-	-	-	-	3.5	2.5	-	-	-	-	12	7	-	-	-	-	2.5	2	-	-	-	-	6	4	-	-	-	-
14'-0"	12	10	-	-	-	-	4	3	-	-	-	-	12	7	-	-	-	-	3	2	-	-	-	-	12	5	-	-	-	-	2.5	2	-	-	-	-	6	3	-	-	-	-
15'-0"	12	-	-	-	-	-	3.5	-	-	-	-	-	12	-	-	-	-	-	3	-	-	-	-	-	11.5	-	-	-	-	-	2	-	-	-	-	-	6	-	-	-	-	-
16'-0"	12	-	-	-	-	-	3	-	-	-	-	-	12	-	-	-	-	-	2.5	-	-	-	-	-	11	-	-	-	-	-	2	-	-	-	-	-	6	-	-	-	-	-

+ NOTES ON ANCHORS REQUIREMENTS: WOOD SUBSTRATES.

1. ANCHORS TO WALL, FLOOR OR SOLID WOOD SOFFIT SHALL BE AS FOLLOWS:
- 1/4"Ø 410 SS TAPCON ANCHORS, OR 1/4"Ø ULTRACON+ OR ULTRACON SS4 ANCHORS AS MANUFACTURED BY I.T.W. BUILDDEX OR DEWALT RESPECTIVELY, W/ MINIMUM THREADED PENETRATION AS INDICATED AT EACH SECTION ON SHEETS 18 & 19. EXCEPTION: SEE NOTE 2 BELOW.
2. ANCHORS TO HOLLOW CEILING SHALL BE AS PER MOUNTING TYPE U, SHEET 19 AND SHALL CONSIST OF LAG SCREWS AS PER ANSI/AWC NDS-24 SPECIFICATIONS, OR 1/4"Ø ULTRACON SS4 OR 5/16"Ø SS LAG SCREWS.
3. SUBSTRATE SHALL CONSIST OF THE FOLLOWING:
- SOUTHERN PINE No. 2 W/ G=0.55 (N.D.S)
 - DOUGLAS FIR W/ G=0.50 (N.D.S.)
 - SPRUCE PINE FIR NORTH W/ G=0.43 (N.D.S.)
 - SPRUCE PINE FIR SOUTH W/ G=0.36 (N.D.S.)
 - MIN. 1/2" CDX PLYWOOD (1986 APA)
4. ANCHORS SHALL BE INSTALLED FOLLOWING ALL OF THE RECOMMENDATIONS AND SPECIFICATIONS OF THE ANCHOR'S MANUFACTURER. ONLY STAINLESS STEEL ANCHORS ARE ALLOWED AT INSTALLATIONS WITHIN 300 ft FROM COASTAL SHORELINE.

① HV BLADE OR ① HV BLADE W/
①A HV WINDOW BLADE WORKING IN UNISON ♦

♦ SEE LIMITATIONS OF USE OF
BLADE ①A ON SHEET 28

FLORIDA BUILDING CODE (Non High Velocity Hurricane Zone)

WALTER A. TILLIT JR.
LICENSE
No. 44167
STATE OF
FLORIDA
PROFESSIONAL ENGINEER
P.E. SEAL/SIGNATURE/DATE

©2026 TILTECO, INC.
TILTECO INC.
TILLIT TESTING & ENGINEERING COMPANY
6355 N.W. 36th. St., Ste. 305, VIRGINIA GARDENS, FLORIDA 33166
Phone : (305)871-1530 . Fax : (305)871-1531
e-mail: tilteco@aol.com
CA-0006719
WALTER A. TILLIT Jr. P.E.
FLORIDA Lic. # 44167

A.S.S.A.
American Shutter Systems
Association, Inc.
4268 Westroads Drive
West Palm Beach, FL 33407

© 2026 EASTERN METAL SUPPLY, INC.			
BERTHA HV™ Accordion Shutter System			
H.V. BLADE #1 W/ OR W/O H.V. WINDOW BLADE & H.V. BLADE #2			
REV. No	DESCRIPTION	DATE	DRAWN BY: W.H.
1	OLD 23-126	6/30/26	DATE: 06/30/2026
2			
3			
4			
5			
6			
			DRAWING No
			26-104
			SHEET
			16 OF 28


MAXIMUM ANCHOR+ SPACING (in.) SCHEDULE FOR A GIVEN MAX. SHUTTER SPAN, NEGATIVE A.S.D DESIGN PRESSURE RATING AND A CORRESPONDING MOUNTING TYPE
(SEE MOUNTINGS ON SHEET 19)

MAXIMUM SPAN (ft)	SUBSTRATE																	
	SOUTHERN PINE No. 2 W/ MIN. G=0.55, DOUGLAS FIR W/ MIN. G=0.50						SPRUCE PINE FIR NORTH W/ MIN. G=0.43						SPRUCE PINE FIR SOUTH W/ MIN. G=0.36					
	B.O. WALL MOUNTINGS S & V						B.O. WALL MOUNTINGS S & V						B.O. WALL MOUNTINGS S & V					
	A.S.D NEGATIVE DESIGN LOAD (psf)						A.S.D NEGATIVE DESIGN LOAD (psf)						A.S.D NEGATIVE DESIGN LOAD (psf)					
	30	40	60	75	90	105	30	40	60	75	90	105	30	40	60	75	90	105
3'-0" OR LESS	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12
4'-0"	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12
5'-0"	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	11.5	10	
6'-0"	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	11.5	9.5	8
7'-0"	12	12	12	12	12	12	12	12	12	12	12	10	12	12	12	10	8	8
8'-0"	12	12	12	12	12	12	12	12	12	12	10.5	9	12	12	11	8.5	7	7
9'-0"	12	12	12	12	12	10.5	12	12	12	11	9	8	12	12	9.5	7.5	6.5	6
10'-0"	12	12	12	12	11.5	9.5	12	12	12	10	8	7	12	12	8.5	7	6	5.5
11'-0"	12	12	12	12	10	8.5	12	12	11.5	9	7.5	6.5	12	12	8	6	5	5
12'-0"	12	12	12	11.5	9.5	8	12	12	10.5	8	7	6	12	11	7	6	5	4.5
13'-0"	12	12	12	10.5	8.5	7.5	12	12	9.5	7.5	6	5.5	12	10	6.5	5	4.5	4
14'-0"	12	12	12	9.5	8	6	12	12	9	7	6	4.5	12	9.5	6	5	4	3.5
15'-0"	12	12	11	9	7.5	5	12	12	8	6.5	5.5	3.5	11.5	8.5	6	4.5	4	3
16'-0"	12	12	10.5	8.5	6.5	4	11.5	12	8	6	4.5	3	11	8	5.5	4	3	-

- + NOTES ON ANCHORS REQUIREMENTS: WOOD SUBSTRATES.
- ANCHORS TO WALL, FLOOR OR SOLID WOOD SOFFIT SHALL BE AS FOLLOWS:
 - 1/4"Ø 410 SS TAPCON ANCHORS, OR 1/4"Ø ULTRACON+ OR ULTRACON SS4 ANCHORS AS MANUFACTURED BY I.T.W. BUILDDEX OR DEWALT RESPECTIVELY, W/ MINIMUM THREADED PENETRATION AS INDICATED AT EACH SECTION ON SHEETS 18 & 19. EXCEPTION: SEE NOTE 2 BELOW.
 - ANCHORS TO HOLLOW CEILING SHALL BE AS PER MOUNTING TYPE U, SHEET 19 AND SHALL CONSIST OF LAG SCREWS AS PER NDS 2024 SPECIFICATIONS, OR 1/4"Ø ULTRACON SS4 OR 5/16"Ø SS LAG SCREWS.
 - SUBSTRATE SHALL CONSIST OF THE FOLLOWING:
 - SOUTHERN PINE No. 2 W/ G=0.55 (N.D.S)
 - DOUGLAS FIR W/ G=0.50 (N.D.S.)
 - SPRUCE PINE FIR NORTH W/ G=0.43 (N.D.S.)
 - SPRUCE PINE FIR SOUTH W/ G=0.36 (N.D.S.)
 - MIN. 1/2" CDX PLYWOOD (1986 APA)
 - ANCHORS SHALL BE INSTALLED FOLLOWING ALL OF THE RECOMMENDATIONS AND SPECIFICATIONS OF THE ANCHOR'S MANUFACTURER. ONLY STAINLESS STEEL ANCHORS ARE ALLOWED AT INSTALLATIONS WITHIN 300 ft FROM COASTAL SHORELINE.

① HV BLADE ONLY

FLORIDA BUILDING CODE (Non High Velocity Hurricane Zone)



©2026 TILTECO, INC.

TILTECO INC.

TILLIT TESTING & ENGINEERING COMPANY
6355 N.W. 36th. St., Ste. 305, VIRGINIA GARDENS, FLORIDA 33166
Phone : (305)871-1530 . Fax : (305)871-1531
e-mail: tilteco@aol.com
CA-0006719
WALTER A. TILLIT Jr. P.E.
FLORIDA Lic. # 44167

A.S.S.A.
American Shutter Systems
Association, Inc.
4268 Westroads Drive
West Palm Beach, FL 33407

© 2026 EASTERN METAL SUPPLY, INC.

BERTHA HV™
Accordion Shutter System


H.V. BLADE #1 W/ OR W/O H.V. WINDOW BLADE & H.V. BLADE #2

REV. No	DESCRIPTION	DATE	DRAWN BY: W.H.
1	OLD 23-126	6/30/26	DATE: 06/30/2026
2			
3			
4			
5			
6			


DRAWING No
26-104
SHEET
17 OF 28

INSTALLATION DETAILS ON EXISTING WOOD BUILDINGS FOR ① HV & ①A HV♦ BLADES (AS APPLICABLE)


MAX. SHUTTER SPAN L+ OR L- FOR INSTALLATIONS INTO WOOD WITH HV BLADE ① ONLY SHALL BE LIMITED TO 105.0 psf. A.S.D. DESIGN PRESSURE RATING, SEE SHEET 28 FOR MAX SPAN & A.S.D. DESIGN PRESSURE RATING FOR INSTALLATION WITH BLADE ① & ①A WORKING IN UNISON




M HV WALL HEADER INSTALLATION




N HV WALL HEADER INSTALLATION




O HV WALL SILL INSTALLATION



P HV WALL SILL INSTALLATION



Q HV WALL SILL INSTALLATION




R HV WALL SILL INSTALLATION

NOTE:
1-SEE SHEET 4 FOR TYPICAL SHUTTER ASSEMBLY.
2-MOUNTING SECTIONS CAN BE COMBINED IN ANY WAY TO SUIT ANY INSTALLATION.

♦ SEE LIMITATIONS OF USE OF BLADE 1A ON SHEET 28

FLORIDA BUILDING CODE (Non High Velocity Hurricane Zone)



P.E. SEAL/SIGNATURE/DATE

©2026 TILTECO, INC.



TILLIT TESTING & ENGINEERING COMPANY
6355 N.W. 36th. St., Ste. 305, VIRGINIA GARDENS, FLORIDA 33166
Phone : (305)871-1530 Fax : (305)871-1531
e-mail: tilteco@aol.com
CA-0006719
WALTER A. TILLIT Jr. P.E.
FLORIDA Lic. # 44167

A.S.S.A.
American Shutter Systems
Association, Inc.
4268 Westroads Drive
West Palm Beach, FL 33407

© 2026 EASTERN METAL SUPPLY, INC.

BERTHA HV™
Accordion Shutter System


H.V. BLADE #1 W/ OR W/O H.V. WINDOW BLADE & H.V. BLADE #2			
REV. No	DESCRIPTION	DATE	DRAWN BY: W.H.
1	OLD 23-126	6/30/26	DATE: 06/30/2026
2			
3			
4			
5			
6			

DRAWING No
26-104

SHEET
18 OF 28


INSTALLATION DETAILS ON EXISTING WOOD BUILDINGS FOR ① HV & ①A HV ♦ BLADES (AS APPLICABLE)

MAX. SHUTTER SPAN L+ OR L- FOR INSTALLATIONS INTO WOOD WITH HV BLADE ① ONLY SHALL BE LIMITED TO 105.0 psf. A.S.D DESIGN PRESSURE RATING, SEE SHEET 28 FOR MAX SPAN & A.S.D DESIGN PRESSURE RATING FOR INSTALLATION WITH BLADE ① & ①A WORKING IN UNISON




⑤ HV WALL HEADER INSTALLATION


NOTES:
1-SEE SHEET 4 FOR TYPICAL SHUTTER ASSEMBLY,
2-MOUNTING SECTIONS CAN BE COMBINED
IN ANY WAY TO SUIT ANY INSTALLATION.




⑥ HV WALL SILL INSTALLATION




⑦ HV CEILING INSTALLATION



⑧ HV CEILING INSTALLATION




⑨ HV FLOOR INSTALLATION



⑩ HV WALK-OVER INSTALLATION

♦ SEE LIMITATIONS OF USE OF
BLADE ①A ON SHEET 28

FLORIDA BUILDING CODE (Non High Velocity Hurricane Zone)



©2026 TILTECO, INC.

TILTECO INC.

TILLIT TESTING & ENGINEERING COMPANY
6355 N.W. 36th. St., Ste. 305, VIRGINIA GARDENS, FLORIDA 33166
Phone : (305)871-1530 . Fax : (305)871-1531
e-mail: tilteco@aol.com
CA-0006719
WALTER A. TILLIT Jr. P.E.
FLORIDA Lic. # 44167

A.S.S.A.
American Shutter Systems
Association, Inc.
4268 Westroads Drive
West Palm Beach, FL 33407

© 2026 EASTERN METAL SUPPLY, INC.

BERTHA HV™
Accordion Shutter System


H.V. BLADE #1 W/ OR W/O H.V. WINDOW BLADE & H.V. BLADE #2

REV. No	DESCRIPTION	DATE	DRAWN BY:	W.H.
1	OLD 23-126	6/30/26		DATE: 06/30/2026
2				
3				
4				
5				
6				


DRAWING No
26-104

SHEET
19 OF 28


END INSTALLATIONS ① HV & ①A HV ♦ BLADES INTO 2"x4" MIN. WOOD STUDS.




END CONNECTION DETAIL ⑦




END CONNECTION DETAIL ⑪




END CONNECTION DETAIL ⑧



END CONNECTION DETAIL ⑫



END CONNECTION DETAIL ⑨




END CONNECTION DETAIL ⑩

★ REQUIRED ONLY FOR SPANS GREATER THAN 12'-0"

♦ SEE LIMITATIONS OF USE OF BLADE ①A ON SHEET 28

FLORIDA BUILDING CODE (Non High Velocity Hurricane Zone)



©2026 TILTECO, INC.




TILLIT TESTING & ENGINEERING COMPANY
6355 N.W. 36th. St., Ste. 305, VIRGINIA GARDENS, FLORIDA 33166
Phone : (305)871-1530 . Fax : (305)871-1531
e-mail: tilteco@aol.com
CA-0006719
WALTER A. TILLIT Jr. P.E.
FLORIDA Lic. # 44167

A.S.S.A.
American Shutter Systems
Association, Inc.
4268 Westroads Drive
West Palm Beach, FL 33407

© 2026 EASTERN METAL SUPPLY, INC.

BERTHA HV™
Accordion Shutter System

H.V. BLADE #1 W/ OR W/O H.V. WINDOW BLADE & H.V. BLADE #2			
REV. No	DESCRIPTION	DATE	DRAWN BY: W.H.
1	OLD 23-126	6/30/26	DATE: 06/30/2026
2			
3			
4			
5			
6			
			DRAWING No
			26-104
			SHEET
			20 OF 28



*** NOTES ON HD LOCKS AND CENTERMATES:**

- MANDATORY CONDITION # 1:** ONE (34) H.D. LOCK SHALL BE USED FOR ANY SPAN AND INSTALLATION AT HEAVY DUTY SYMMETRICAL CENTERMATES, (31) OR (32) + (33) AND AT ANY ELEVATION. (34) H.D. LOCK MAY BE USED AS AN INSIDE OR OUTSIDE LOCK, ATTACHED TO (33) HEAVY DUTY SYMMETRICAL CENTERMATES WITH (3) #8 x 3/8" LONG FLAT HEAD S.S. M.S. LOCKING RODS (35) ARE NOT MANDATORY, i.e. THEY ARE COMPLETELY OPTIONAL.
- MANDATORY CONDITION # 2:** LOCATION OF (34) H.D. LOCK SHALL BE AS INDICATED ON SHUTTER ELEVATION, i.e., FOR SHUTTER SPANS UP TO 105". (34) H.D. LOCK MAY BE INSTALLED AT MID HEIGHT OF SHUTTER OR AT 12" ABOVE OR BELOW MID HEIGHT OF SHUTTER. FOR SHUTTER SPANS GREATER THAN 105", (34) H.D. LOCK SHALL BE INSTALLED AT MID HEIGHT OF SHUTTER.

TYPICAL ② HV BLADE SHUTTER ELEVATION
N.T.S.

WALTER A. TILLIT JR.
LICENSE
No. 44167
STATE OF FLORIDA
PROFESSIONAL ENGINEER
P.E. SEAL/SIGNATURE/DATE

©2026 TILTECO, INC.
TILTECO INC.
TILLIT TESTING & ENGINEERING COMPANY
6355 N.W. 36th. St., Ste. 305, VIRGINIA GARDENS, FLORIDA 33166
Phone : (305)871-1530 . Fax : (305)871-1531
e-mail: tilteco@aol.com
CA-0006719
WALTER A. TILLIT Jr. P.E.
FLORIDA Lic. # 44167

A.S.S.A.
American Shutter Systems
Association, Inc.
4268 Westroads Drive
West Palm Beach, FL 33407

FLORIDA BUILDING CODE (Non High Velocity Hurricane Zone)


© 2026 EASTERN METAL SUPPLY, INC.

BERTHA HV™
Accordion Shutter System


H.V. BLADE #1 W/ OR W/O H.V. WINDOW BLADE & H.V. BLADE #2			
REV. No	DESCRIPTION	DATE	DRAWN BY: W.H.
1	OLD 23-126	6/30/26	DATE: 06/30/2026
2			
3			
4			
5			
6			

DRAWING No
26-104


SHEET
21 OF 28




AA HD WALL HEADER INSTALLATION




BB HD CEILING INSTALLATION




CC HD TRENCH INSTALLATION




DD HD WALK-OVER INSTALLATION



EE HD WALL SILL INSTALLATION



FF HD RAINGUARD INSTALLATION



GG HD FLOOR INSTALLATION

NOTE FOR COMBINATION OF SECTIONS:


1- SEE SHEET 21 FOR TYPICAL SHUTTER ASSEMBLY
2- MOUNTING SECTIONS CAN BE COMBINED IN ANY WAY TO SUIT ANY INSTALLATION.

* E. D. = EDGE DISTANCE
(SEE SPECIFICATIONS ON SHEET 26)

INSTALLATION DETAILS W/ ② HV BLADE

SCALE: 3/8"=1"

FLORIDA BUILDING CODE (Non High Velocity Hurricane Zone)



P.E. SEAL/SIGNATURE/DATE

©2026 TILTECO, INC.



TILLIT TESTING & ENGINEERING COMPANY
6355 N.W. 36th. St., Ste. 305, VIRGINIA GARDENS, FLORIDA 33166
Phone : (305)871-1530 . Fax : (305)871-1531
e-mail: tilteco@aol.com
CA-0006719
WALTER A. TILLIT Jr. P.E.
FLORIDA Lic. # 44167

A.S.S.A.
American Shutter Systems
Association, Inc.
4268 Westroads Drive
West Palm Beach, FL 33407


© 2026 EASTERN METAL SUPPLY, INC.

BERTHA HV™
Accordion Shutter System


H.V. BLADE #1 W/ OR W/O H.V. WINDOW BLADE & H.V. BLADE #2

REV. No	DESCRIPTION	DATE	DRAWN BY: W.H.
1	OLD 23-126	6/30/26	DATE: 06/30/2026
2			
3			
4			
5			
6			

DRAWING No
26-104
SHEET
22 OF 28




END CONNECTION DETAIL 1 **END CONNECTION DETAIL 2** **END CONNECTION DETAIL 3** **END CONNECTION DETAIL 4**
 ♦ REQUIRED ONLY FOR SPANS GREATER THAN 12'-0"



END CONNECTION DETAIL 5 **END CONNECTION DETAIL 6** **PLAN** **VIEW Y**

END INSTALLATION
2 HV BLADE INTO CONCRETE OR CONCRETE BLOCK WALL.

FLORIDA BUILDING CODE (Non High Velocity Hurricane Zone)



©2026 TILTECO, INC.

TILTECO INC.

TILLIT TESTING & ENGINEERING COMPANY
 6355 N.W. 36th. St., Ste. 305, VIRGINIA GARDENS, FLORIDA 33166
 Phone : (305)871-1530 . Fax : (305)871-1531
 e-mail: tilteco@aol.com
 CA-0006719
 WALTER A. TILLIT Jr. P.E.
 FLORIDA Lic. # 44167

A.S.S.A.
 American Shutter Systems
 Association, Inc.
 4268 Westroads Drive
 West Palm Beach, FL 33407

© 2026 EASTERN METAL SUPPLY, INC.

BERTHA HV™
 Accordion Shutter System

H.V. BLADE #1 W/ OR W/O H.V. WINDOW BLADE & H.V. BLADE #2

REV. No	DESCRIPTION	DATE	DRAWN BY: W.H.
1	OLD 23-126	6/30/26	DATE: 06/30/2026
2			
3			
4			
5			
6			

DRAWING No
26-104

SHEET
24 OF 28

MAXIMUM SHUTTER SPAN* "L+" OR "L-" (ft.) INSTALLATIONS W/ <u>SYMMETRICAL</u> <u>HD CENTERMATES</u> . ③① OR ③② , W/ ONE H.D. ③④ LOCK & NO LOCKING RODS ③⑤ ♦		
MAXIMUM A.S.D. DESIGN PRESSURE RATING (p.s.f.) (+ OR -)	CONCRETE & CONCRETE BLOCK INSTALLATIONS	
	ALL MOUNTING CONDITIONS	
	L + (ft)	L - (ft)
30 OR LESS	18'-0"	18'-0"
35	18'-0"	18'-0"
40	17'-4"	17'-10"
45	16'-4"	17'-6"
50	15'-6"	17'-0"
55	14'-10"	16'-10"
60	14'-2"	16'-2"
65	13'-8"	15'-6"
70	13'-2"	14'-11"
75	12'-8"	14'-5"
80	12'-3"	14'-0"
85	11'-11"	13'-7"
90	11'-6"	13'-2"
95	11'-3"	12'-10"
100	10'-6"	12'-6"
105	10'-0"	12'-2"
110	9'-6"	11'-11"
115	9'-1"	11'-8"
120	8'-9"	11'-5"
125	-	11'-2"
130	-	10'-11"
135	-	10'-9"
140	-	10'-6"
145	-	10'-4"
150	-	10'-2"
155	-	10'-0"
160	-	9'-10"
165	-	9'-9"
170	-	9'-7"
175	-	9'-5"
180	-	9'-4"
185	-	9'-2"
190	-	9'-0"
195	-	8'-9"

* NOTES:

(1) L+: MAXIMUM ALLOWABLE SPAN FOR A GIVEN POSITIVE A.S.D. DESIGN PRESSURE RATING.
L-: MAX. ALLOWABLE SPAN FOR A GIVEN NEGATIVE A.S.D. DESIGN PRESSURE RATING.

(2) PROCEDURE TO DETERMINE MAXIMUM SPAN FOR WALL MOUNTINGS OR FLOOR/CEILING:

GIVEN A POSITIVE A.S.D. DESIGN PRESSURE RATING, DETERMINE MAXIMUM SPAN "L+" FROM SCHEDULE.
GIVEN A NEGATIVE A.S.D. DESIGN PRESSURE RATING, DETERMINE MAXIMUM SPAN "L-" FROM SCHEDULE.

FINAL MAXIMUM ALLOWABLE SPAN IS EQUAL TO THE MINIMUM DETERMINED SPAN BETWEEN "L+" AND "L-".

(3) PROCEDURE TO DETERMINE MAXIMUM SPAN FOR COMBINATIONS IN BETWEEN WALL W/ FLOOR/CEILING MOUNTINGS:

FOR A GIVEN POSITIVE A.S.D. DESIGN PRESSURE RATING:
DETERMINE:
L1+= MAX. SPAN FOR WALL MOUNTING INSTALLATIONS.
L2+= MAX. SPAN FOR FLOOR/CEILING MOUNTING INSTALLATIONS.

FOR A GIVEN NEGATIVE A.S.D. DESIGN PRESSURE RATING:
DETERMINE:
L1-= MAX. SPAN FOR WALL MOUNTING INSTALLATIONS.
L2-= MAX. SPAN FOR FLOOR/CEILING MOUNTING INSTALLATIONS.

FINAL MAXIMUM ALLOWABLE SPAN IS EQUAL TO THE MINIMUM BETWEEN "L1+", "L2+", "L1-" AND "L2-"


(4) GO TO ANCHOR SCHEDULE WITH FINAL MAXIMUM ALLOWABLE SPAN AND MAXIMUM A.S.D. DESIGN PRESSURE RATING TO DETERMINE MAXIMUM ANCHOR SPACING.

INSTALLATION LEGEND	
SUBSTRATE MOUNTINGS	POURED CONCRETE (SHEET 22)
WALL MOUNTING	AA & EE
FLOOR/CEILING MOUNTING	BB, CC, DD, FF & GG

WIND ZONE ASTM E-1996	MINIMUM SEPARATION TO GLASS
1 THRU 3	1"
4	3"

② HV BLADE

FLORIDA BUILDING CODE (Non High Velocity Hurricane Zone)



©2026 TILTECO, INC.

TILLIT TESTING & ENGINEERING COMPANY
6355 N.W. 36th. St., Ste. 305, VIRGINIA GARDENS, FLORIDA 33166
Phone : (305)871-1530 . Fax : (305)871-1531
e-mail: tilteco@aol.com
CA-0006719
WALTER A. TILLIT Jr. P.E.
FLORIDA Lic. # 44167

A.S.S.A.
American Shutter Systems
Association, Inc.
4268 Westroads Drive
West Palm Beach, FL 33407

© 2026 EASTERN METAL SUPPLY, INC.

BERTHA HV™
Accordion Shutter System
H.V. BLADE #1 W/ OR W/O H.V. WINDOW BLADE & H.V. BLADE #2

REV. No	DESCRIPTION	DATE	DRAWN BY: W.H.
1	OLD 23-126	6/30/26	DATE: 06/30/2026
2			
3			
4			
5			
6			

DRAWING No
26-104
SHEET
25 OF 28

ANCHORS SPACING LEGEND

1/4"Ø 410 SS TAPCON
5/16"Ø TAPCON XL OR
3/8"Ø SS KWIK BOLT 3

MAXIMUM ANCHOR* SPACING (in.) SCHEDULE FOR A GIVEN
MAX. SHUTTER SPAN, MAXIMUM A.S.D. DESIGN PRESSURE
RATING AND A CORRESPONDING MOUNTING TYPE
FOR CONCRETE INSTALLATIONS

MAXIMUM SPAN (ft)	POURED CONCRETE				
	ALL MOUNTINGS AA THRU GG (SHEET 22)				
	USE MAXIMUM VALUES BETWEEN POSITIVE AND NEGATIVE A.S.D. DESIGN LOADS				
	50 OR LESS	>50 TO 90	>90 TO 120	>120 TO 160	>160 TO 195
8'-9" OR LESS	8"	4 1/2"	3 1/2"	—	—
	12"	8"	6"	4"	3 3/4"
>8'-9" UP TO 12'-1"	6"	3 1/2"	3" ‡	—	—
	10"	6"	4"	4"	—
>12'-1" UP TO 18'-0"	4"	3 1/2"	—	—	—
	7 1/2"	5 1/2"	4"	—	—

NOTE:

‡ VALID ONLY FOR UP TO 10'-0" SPAN

*SPECIFICATIONS ON ANCHOR REQUIREMENTS: POURED CONCRETE SUBSTRATE


- (A) ANCHORS TO WALL SHALL BE AS FOLLOWS:
- A.1) TO EXISTING POURED CONCRETE: (Min. f'c = 3192 psi)
– 1/4"Ø 410 SS TAPCON ANCHORS, OR 1/4"Ø ULTRACON+ OR ULTRACON SS4 AS MANUFACTURED BY I.T.W. BUILDDEX & DEWALT RESPECTIVELY.
MINIMUM EMBEDMENT INTO POURED CONCRETE OF TAPCON IS 1 3/4".
- A.2) TO EXISTING POURED CONCRETE: (Min. f'c = 2899 psi)
– 5/16"Ø TAPCON XL ANCHORS, AS MANUFACTURED BY I.T.W. BUILDDEX. OR 3/8"Ø KWIK BOLT 3 BY HILTI W/ 3" OF EMBEDMENT.
MINIMUM EMBEDMENT INTO POURED CONCRETE OF 5/16" TAPCON XL ANCHORS IS 2 1/4".
- A.3) IN CASE THAT PRECAST STONE, PRECAST CONCRETE PANELS, PAVERS OR ANY VENEER BE FOUND ON THE EXISTING WALL OR FLOOR, ANCHORS SHALL BE LONG ENOUGH TO REACH THE MAIN STRUCTURE BEHIND SAID WALL FINISHES. ANCHORAGE SHALL BE AS INDICATED ON NOTE A.1) ABOVE. FOR INSTALLATIONS ON VINYL SIDING OR EIFS CONSULT THIS ENGINEER.
- (B) ANCHORS SHALL BE INSTALLED FOLLOWING ALL OF THE RECOMMENDATIONS AND SPECIFICATIONS OF THE ANCHOR'S MANUFACTURER.
- (C) SEE BELOW FOR MINIMUM REQUIRED EDGE DISTANCE FOR ANCHORS.
- (D) ONLY STAINLESS STEEL ANCHORS ARE ALLOWED AT INSTALLATIONS WITHIN 300 ft FROM COASTAL SHORELINE.

MINIMUM REQUIRED EDGE DISTANCE FOR ANCHORS

MAXIMUM ANCHOR SPACINGS ARE VALID FOR
3" EDGE DISTANCE FOR 1/4"Ø TAPCON AND
3 5/8" EDGE DISTANCE FOR 5/16"Ø TAPCON XL, OR
3/8"Ø KWIK BOLT 3.

② HV BLADE ONLY

FLORIDA BUILDING CODE (Non High Velocity Hurricane Zone)




©2026 TILTECO, INC.

TILTECO INC.

TILLIT TESTING & ENGINEERING COMPANY
6355 N.W. 36th. St., Ste. 305, VIRGINIA GARDENS, FLORIDA 33166
Phone : (305)871-1530 . Fax : (305)871-1531
e-mail: tilteco@aol.com
CA-0006719
WALTER A. TILLIT Jr. P.E.
FLORIDA Lic. # 44167

A.S.S.A.
American Shutter Systems
Association, Inc.
4268 Westroads Drive
West Palm Beach, FL 33407

© 2026 EASTERN METAL SUPPLY, INC.			
BERTHA HV™ Accordion Shutter System			
H.V. BLADE #1 W/ OR W/O H.V. WINDOW BLADE & H.V. BLADE #2			
REV. No	DESCRIPTION	DATE	DRAWN BY: W.H.
1	OLD 23-126	6/30/26	DATE: 06/30/2026
2			DRAWING No 26-104
3			
4			SHEET 26 OF 28
5			
6			



44 POLYCARBONATE IMPACT RESISTANT HV WINDOW
BAYER MAKROLON 3103 POLYCARBONATE
RESINS, UV-STABILIZED GRADE OR SABIC
INNOVATIVE PLASTIC LEXAN 103 RESIN
(SEE NOTE "F" ON SHEET 28).

POLYCARBONATE SOURCES FOR 44			
TYPICAL PROPERTIES	APPLICABLE STANDARD REFERENCE	RESULT	
		BAYER MATERIAL / SCIENCE LLC.MAKROLON 3103	SABIC INNOVATIVE PLASTIC LEXAN 103 RESIN
PHYSICAL:			
SPECIFIC GRAVITY	ASTM D792	0.043 lb/in ³	0.043 lb/in ³
MECHANICAL:			
TENSILE YIELD STRENGTH	ASTM D638	9,400 p.s.i.	9,500 p.s.i.
FLEXURAL STRENGTH AT YIELD	ASTM D790	12,500 p.s.i.	13,400 p.s.i.
FLEXURAL MODULUS	ASTM D790	340,000 p.s.i.	345,000 p.s.i.
IMPACT:			
NOTCHED IZOD	ASTM D256	18 FT-lb/in	17 FT-lb/in
FIRE BURNING CHARACTERISTICS:			
SMOKE DENSITY	ASTM D2843	47.2 %	64.5 % MAX
RATE OF BURNING	ASTM D635	C-1 CLASS	C-1 CLASS
SELF IGNITION	ASTM D1929	1040 °F	980 °F
WEATHERING:	ASTM G155		
TENSILE STRENGTH AFTER WEATHERING	ASTM 638	9302 p.s.i.	8840 p.s.i.
TENSILE STRESS BEFORE WEATHERING	ASTM 638	8461 p.s.i.	8880 p.s.i.

TYPICAL HV WINDOW BLADE 1A AND
POLYCARBONATE HV WINDOW DETAIL


FLORIDA BUILDING CODE (Non High Velocity Hurricane Zone)

WALTER A. TILLIT JR.
LICENSE
No. 44167
STATE OF FLORIDA
PROFESSIONAL ENGINEER
P.E. SEAL/SIGNATURE/DATE

©2026 TILTECO, INC.
TILTECO INC.
TILLIT TESTING & ENGINEERING COMPANY
6355 N.W. 36th. St., Ste. 305, VIRGINIA GARDENS, FLORIDA 33166
Phone : (305)871-1530 . Fax : (305)871-1531
e-mail: tilteco@aol.com
CA-0006719
WALTER A. TILLIT Jr. P.E.
FLORIDA Lic. # 44167

A.S.S.A.
American Shutter Systems
Association, Inc.
4268 Westroads Drive
West Palm Beach, FL 33407

© 2026 EASTERN METAL SUPPLY, INC.
BERTHA HV™
Accordian Shutter System
H.V. BLADE #1 W/ OR W/O H.V. WINDOW BLADE & H.V. BLADE #2
REV. No. DESCRIPTION DATE DRAWN BY: W.H.
1 OLD 23-126 6/30/26 DATE: 06/30/2026
2
3
4
5
6
DRAWING No
26-104
SHEET
27 OF 28




5 OR 4 OR
16 OR 20
TYP. EA. END

44
MAX. 5 WINDOWS
ALLOWED AT HV
WINDOW BLADE 1A

SEE END
CONNECTION
DETAILS ON
SHEET 11 TYP.
FULL HEIGHT.

35 (SEE PLAN FOR REQUIREMENTS)
TYP TOP & BOTTOM

ELEVATION



SYMMETRICAL CENTERMATES 21, 22
W/ 24 OR 25 AND
W/O 35 (SEE NOTE 4 ABOVE)

PLAN

TYPICAL 1 HV BLADE WORKING IN UNISON WITH HV WINDOW BLADE 1A SHUTTER*

N.T.S.


* GENERAL LIMITATIONS AND CONDITIONS OF USE FOR BERTHA

1 HV BLADE ACCORDION SHUTTER SYSTEM WORKING IN UNISON WITH HV WINDOW BLADE 1A


1. MAX. A.S.D. DESIGN PRESSURE RATING: +110, - 110 p.s.f.
2. MAX. SHUTTER SPAN: 96"
3. ALLOWED MOUNTINGS: A, D, G & H ON SHEETS 6, 7; AS WELL AS MOUNTINGS M, O, T, U & W ON SHEETS 18 & 19.
4. ONLY CENTERMATES 21, 22 (BOTH W/ 24 OR 25) ARE ALLOWED WITH 21, 22 ARRANGED IN A SYMMETRICAL OR OPPOSING LAYOUT. IN CASE OF OPPOSING LAYOUT, 35 MUST BE INCLUDED ONLY AT EXTERIOR ACCESS SIDE OF CENTERMATE.
5. (A) HV WINDOW BLADE 1A SHALL ONLY ALLOW A MAXIMUM OF 5 OPENINGS (3"Ø HOLES) FOR 44 PER BLADE AT SPACINGS SHOWN ON SHEET 27.
(B) MIN. CLEARANCE FROM TOP OR BOTTOM EDGE OF HV WINDOW BLADE 1A OF ANY 3"Ø HOLE FOR 44 SHALL BE 12".
(C) FIRST OR LAST BLADE COMING OUT FROM STARTERS AT ENDS MAY BE HV WINDOW BLADE 1A
(D) HV WINDOW BLADE 1A MUST BE USED ALTERNATE TO A SOLID HV BLADE 1 THROUGHOUT SHUTTER'S WIDTH.
(E) CENTERMATES SHALL ALWAYS BE INSTALLED ADJACENT TO A SOLID HV BLADE 1 AT EITHER SIDE OF THEM.
(F) POLYCARBONATE HV WINDOW 44 SHALL BE INSTALLED SO THAT TABS FACE THE INTERIOR OF THE OPENING BEING PROTECTED. HV WINDOW 44 MUST BE ONLY INSTALLED AND LOCKED USING A HV SETTING TOOL PROVIDED BY ASSA, INC.
6. SEE ANCHOR SPACING SCHEDULE FOR INSTALLATIONS INTO WOOD FRAME BUILDINGS ON SHEET 16, AS LIMITED BY SPAN AND A.S.D DESIGN LOAD (SEE NOTES 1 & 2 ABOVE).
7. SEE ANCHOR SPACING SCHEDULE FOR INSTALLATIONS INTO POURED CONCRETE OR CONCRETE BLOCK WALL ON SHEETS 13 & 14 AS LIMITED BY SPAN AND A.S.D DESIGN LOAD (SEE NOTES 1 & 2 ABOVE).
8. MINIMUM SEPARATION TO GLASS SCHEDULE, PER ASTM E-1996:

WIND ZONE	MINIMUM SEPARATION TO GLASS
1 THRU 3	1"
4	6.25"

ALTERNATE OPPOSING CENTERMATES 21, 22 W/ 35 (EXTERIOR ONLY) AND W/ 24 OR 25 (SEE NOTE 4 ABOVE)



FLORIDA BUILDING CODE (Non High Velocity Hurricane Zone)



©2026 TILTECO, INC.



TILLIT TESTING & ENGINEERING COMPANY
6355 N.W. 36th. St., Ste. 305, VIRGINIA GARDENS, FLORIDA 33166
Phone : (305)871-1530 . Fax : (305)871-1531
e-mail: tilteco@aol.com
CA-0006719
WALTER A. TILLIT Jr. P.E.
FLORIDA Lic. # 44167

A.S.S.A.
American Shutter Systems
Association, Inc.
4268 Westroads Drive
West Palm Beach, FL 33407

© 2026 EASTERN METAL SUPPLY, INC.

BERTHA HV™ Accordion Shutter System

REV. No	DESCRIPTION	DATE	DRAWN BY: W.H.
1	OLD 23-126	6/30/26	DATE: 06/30/2026
2			
3			
4			
5			
6			

DRAWING No
26-104
SHEET
28 OF 28

INSTALLATIONS W/ ① HV BLADE & HV CENTERMATES ②①
INTO METAL STUD WALLS *

* GENERAL LIMITATIONS AND CONDITIONS OF USE
FOR BERTHA ① HV BLADE ACCORDION SHUTTER
SYSTEM INSTALLATION TO METAL STUD WALLS


1. MAX. A.S.D. DESIGN PRESSURE RATING: +75, - 75 p.s.f.
2. MAX. SHUTTER SPAN: 84"
3. ALLOWED MOUNTING: (MS) ON THIS SHEET.
4. ONLY CENTERMATE ②① W/ ②④ HV LOCK ARE ALLOWED WITH ②① ARRANGED IN A SYMMETRICAL LAYOUT. USE OF (2) ③⑤ (6" LONG, MINIMUM) MUST ALWAYS BE INCLUDED AT EXTERIOR OR INTERIOR ACCESS SIDE OF CENTERMATE.

** BLADE SLACK DETAIL HVF IS VALID FOR
CENTERMATE ②① APPLICATION WITH BLADE ①


SEPARATION TO GLASS SCHEDULE

WIND ZONE ASTM E-1996	MINIMUM SEPARATION TO GLASS
1 THRU 3	1"
4	4"

④③① 1/4"Ø NOMINAL
ALUMINUM SLEEVE
6063-T5 ALLOY





④③② 1/4"Ø-20X3"
304 SS BOLT
MUST PENETRATE ④③① 1"




④③③ 1/4"Ø 304 SS ELCO
CONSTRUCTION PRODUCTS
FAB-LOK HD

COMPONENTS

SCALE: 3/8"= 1"



1 3/4"x 6 1/4"x 0.035" THICK Min.
CONT. GALV. STEEL TRACK CHANNEL,
ASTM A-653 GRADE 40 Min. G-60
GALVANIZED FASTENED TO STUDS
W/ (2) #6x1/2" TEK SCREWS ON
INTERIOR & EXTERIOR FACE



VIEW Y
SIDE CONNECTION TO TRACK

FLORIDA BUILDING CODE (Non High Velocity Hurricane Zone)

WALTER A. TILLIT JR.
LICENSE
No. 44167
STATE OF
FLORIDA
PROFESSIONAL ENGINEER
P.E. SEAL/SIGNATURE/DATE

©2026 TILTECO, INC.
TILTECO INC.
TILLIT TESTING & ENGINEERING COMPANY
6355 N.W. 36th. St., Ste. 305, VIRGINIA GARDENS, FLORIDA 33166
Phone : (305)871-1530 . Fax : (305)871-1531
e-mail: tilteco@aol.com
CA-0006719
WALTER A. TILLIT Jr. P.E.
FLORIDA Lic. # 44167

A.S.S.A.
American Shutter Systems
Association, Inc.
4268 Westroads Drive
West Palm Beach, FL 33407

© 2026 EASTERN METAL SUPPLY, INC.			
BERTHA HV™ Accordion Shutter System			
H.V. BLADE #1 W/ OR W/O H.V. WINDOW BLADE & H.V. BLADE #2			
REV. No	DESCRIPTION	DATE	DRAWN BY: W.H.
1	OLD 23-126	6/30/26	DATE: 06/30/2026
2			
3			
4			
5			
6			
			DRAWING No 26-104
			SHEET 28A OF 28