




Wind loaded sectional doors are designed, tested, and sold by PSF.
The AHJ of a given jobsite is responsible for determining the appropriate PSF.

Doors tested per
ANSI/DASMA 108
for static air pressure

Complies with the Wind Load
requirements of the IBC/IRC 2021

Legacy & Carriage Collection									
Max. Door Width	Short Panel			Long Panel			Carriage Panel		
	Ctr. Hngs. per Sect.	Design Loads		Ctr. Hngs. per Sect.	Design Loads		Ctr. Hngs. per Sect.	Design Loads	
8'-0"	1	12.2	-13.7	1	12.2	-13.7	1	12.2	-13.7
9'-0"	1	10.8	-12.2	1	10.8	-12.2	1	10.8	-12.2

Scott A. Brown, P.E. Lic. No. 65940
Willett, Hofmann & Associates, Inc.
809 E. 2nd Street, Dixon, IL 61021
FBPE CA Lic. No. 35415
Structural Adequacy for Wind Load

Digitally signed by Scott A Brown
Date: 2024.02.19 17:44:41-06'00'

Printed copies of this document are not considered signed and sealed and the SHA authentication code must be verified on any electronic copies.


Rev.	A	New drawing.	9019.01	01/10/24	Date: 01/10/24	ECO: 9019.01
		Description	ECO	Date		

Scale: None
Drawn by: J. Poitras
Checked by: G. Wedekind
Date: 01/10/24
ECO: 9019.01


PRODOOR
MFG CO

6030 Gateway Drive
Plainfield, IN 46168


Title: Spec, Wind Load Legacy & Carriage Collection			
No.	P-6000	Sheet 1 of 3	Rev A



Typical Track Installation
Normal headroom track shown
Low headroom and lift clearance available




- Jamb Attachment Notes:
1. Maximum Positive Load per Jamb = (9'-0" x 10.8 PSF) / 2 = 49 lbs. per foot.
 2. Maximum Negative Load per Jamb = (9'-0" x -12.2 PSF) / 2 = 55 lbs. per foot.
 3. Design of the supporting structure shall be the sole responsibility of the building designer and shall be designed for the jamb loads listed in notes 1 and 2.
 4. Alternate jamb attachments may be used if approved by a registered Professional Engineer.
 5. DASMA Technical Data Sheet TDS-161 may be used for alternate jamb attachments.
 6. 3/8" diameter lag screws required 1/16" pilot hole and 1-1/2" minimum required distance.



Scott A. Brown, P.E. Lic. No. 65940
Willett, Hofmann & Associates, Inc.
809 E. 2nd Street, Dixon, IL 61021
FBPE CA Lic. No. 35415
Structural Adequacy for Wind Load

Scott A. Brown
Digitally signed by Scott A Brown
Date: 2024.02.19 17:45:06-06'00'




Window Styles

Short panel windows


Long panel windows

2x6 Attachment to Structure						
Structure Type	Fastener Type	Minimum Embedment	Minimum Edge Distance	Minimum on Center Spacing	Maximum on Center Spacing	Allowable Tension Load
2500 PSI Min. Concrete	1/4" Tapcon+ (Plus) with 1-1/8" OD Washer	2"	2.5	6"	24"	526
Southern Pine	3/8" x 3" Lag with 1-1/8" OD Washer	1.50"	1.50"	1.50"	24"	655
Spruce Pine Fir	3/8" x 3" LAG with 1-1/8" OD Washer	1.50"	1.50"	1.50"	24"	482


Scale: None	 6030 Gateway Drive Plainfield, IN 46168	Title: Spec, Wind Load Legacy & Carriage Collection	
Drawn by: J. Poitras		No. P-6000	Sheet 2
Checked by: G. Wedekind			
Date: 01/10/24			
ECO: 9019.01			Rev A




Corner Bracket
.085 min. Galv. Steel




Track Bracket
.099 min. Galv. Steel




Center Hinge
.045 min. Galv. Steel




Edge Hinge
.069 min. Galv. Steel




2" Track
.055 min. Galv. Steel




Jamb Angle
.071 min. Galv. Steel




Top Fixture
.085 min. Galv. Steel




Roller Carrier
.085 min. Galv. Steel
Attached to Top Fixture
w/(2) Track Bolts and Whiz Nuts




2" Roller
Nylon 11-ball (Std.)
Steel 10-ball (Opt.)




Slide Lock




Serrated Hex Flange Nut




Track Bolt



Self-Drilling Screw



Hex Head Lag Screw



Scott A. Brown, P.E. Lic. No. 65940
Willett, Hofmann & Associates, Inc.
809 E. 2nd Street, Dixon, IL 61021
FBPE CA Lic. No. 35415
Structural Adequacy for Wind Load

Scott A. Brown
Digitally signed by Scott A Brown
Date: 2024.02.19 17:45:26-06'00'

Printed copies of this document are not considered signed and sealed and the SHA authentication code must be verified on any electronic copies.

All parts shown are for illustration purposes only. The actual product may include equivalent parts due to availability.

Scale: None	 6030 Gateway Drive Plainfield, IN 46168	Title: Spec, Wind Load Legacy & Carriage Collection	
Drawn by: J. Poitras		No. P-6000	Sheet 3
Checked by: G. Wedekind			
Date: 01/10/24			
ECO: 9019.01			Rev A