





Legacy & Carriage Collection								
Max. Door Width	Short Panel		Long Panel		Carriage Panel		Ctr. Hngs. per Sect.	Design Loads
	Ctr. Hngs. per Sect.	Design Loads	Ctr. Hngs. per Sect.	Design Loads	Ctr. Hngs. per Sect.	Design Loads		
8'-0"	1	57.5 -66.7	1	57.5 -66.7	1	57.5 -66.7	1	57.5 -66.7
9'-0"	1	51.1 -59.3	1	51.1 -59.3	1	51.1 -59.3	1	51.1 -59.3
10'-0"	2	49.3 -55.7	1	41.4 -48.0	1	41.4 -48.0	1	41.4 -48.0
12'-0"	2	41.1 -46.4	2	41.1 -46.4	2	36.7 -41.5	2	36.7 -41.5
14'-0"	2	31.4 -35.5	2	31.4 -35.5	2	31.4 -35.5	2	31.4 -35.5
16'-0"	3	27.8 -33.1	3	27.8 -33.1	3	27.8 -33.1	3	27.8 -33.1
18'-0"	3	22.0 -26.2	3	22.0 -26.2	3	20.2 -25.3	3	20.2 -25.3
20'-2"	4	16.8 -18.7	4	16.8 -18.7	4	16.8 -18.7	4	16.8 -18.7



Scott A. Brown, P.E. Lic. No. 65940
Willett, Hofmann & Associates, Inc.
809 E. 2nd Street, Dixon, IL 61021
FBPE CA Lic. No. 35415
Structural Adequacy for Wind Load

Digitally signed by Scott A Brown
Date: 2024.02.19 17:52:33-06'00'

Printed copies of this document are not considered signed and sealed and the SHA authentication code must be verified on any electronic copies.


Wind loaded sectional doors are designed, tested, and sold by PSF. The AHJ of a given jobsite is responsible for determining the appropriate PSF.

Rev.	Description	ECO	Date
A	New drawing.	9019.01	01/10/24


Scale: None
Drawn by: J. Poitras
Checked by: G. Wedekind
Date: 01/10/24
ECO: 9019.01




Title: Spec, Wind Load Legacy & Carriage Collection	
No. P-6004	Sheet 1 of 3
Rev A	



Typical Track Installation
Normal headroom track shown
Low headroom and lift clearance available




- Jamb Attachment Notes:
1. Maximum Positive Load per Jamb = (12'-0" x 41.1 PSF) / 2 = 247 lbs. per foot.
 2. Maximum Negative Load per Jamb = (12'-0" x -46.4 PSF) / 2 = 279 lbs. per foot.
 3. Design of the supporting structure shall be the sole responsibility of the building designer and shall be designed for the jamb loads listed in notes 1 and 2.
 4. Alternate jamb attachments may be used if approved by a registered Professional Engineer.
 5. DASMA Technical Data Sheet TDS-161 may be used for alternate jamb attachments.
 6. 3/8" diameter lag screws required 1/16" pilot hole and 1-1/2" minimum required distance.



Scott A. Brown, P.E. Lic. No. 65940
Willett, Hofmann & Associates, Inc.
809 E. 2nd Street, Dixon, IL 61021
FBPE CA Lic. No. 35415
Structural Adequacy for Wind Load

Scott Brown
Digitally signed by Scott A Brown
Date: 2024.02.19 17:53:11-06'00'




Window Styles

Short Panel windows


Long Panel windows

2x6 Attachment to Structure						
Structure Type	Fastener Type	Minimum Embedment	Minimum Edge Distance	Minimum on Center Spacing	Maximum on Center Spacing	Allowable Tension Load
2500 PSI Min. Concrete	1/4" Tapcon+ (Plus) with 1-1/8" OD Washer	2"	2.5	6"	24"	526
Southern Pine	3/8" x 3" Lag with 1-1/8" OD Washer	1.50"	1.50"	1.50"	24"	655
Spruce Pine Fir	3/8" x 3" LAG with 1-1/8" OD Washer	1.50"	1.50"	1.50"	23"	482


Scale: None	 6030 Gateway Drive Plainfield, IN 46168	Title: Spec, Wind Load Legacy & Carriage Collection		
Drawn by: J. Poitras		No. P-6004	Sheet 2	Rev A
Checked by: G. Wedekind				
Date: 01/10/24				
ECO: 9019.01				




Corner Bracket
.085 min. Galv. Steel
Max. Door Weight = 325 Lbs.




Corner Bracket
.109 min. Galv. Steel
Max. Door Weight = 2000 Lbs.




Track Bracket
.099 min. Galv. Steel




Center Hinge
.045 min. Galv. Steel




Edge Hinge
.069 min. Galv. Steel




2" Track
.055 min. Galv. Steel




Jamb Angle
.071 min. Galv. Steel




Top Fixture
.085 min. Galv. Steel




Roller Carrier
.085 min. Galv. Steel
Attached to Top Fixture
w/(2) Track Bolts and Whiz Nuts




2" Roller
Nylon 11-ball (Std.)
Steel 10-ball (Opt.)




Steel Box Strut
20 Ga. (.035" min.) Galvanized
High Tensile Steel
80 KSI Minimum Yield




Slide Lock




Steel U-bar
18 Ga. (.049 min.) Galvanized
High Tensile Steel
80 KSI Minimum Yield




Retaining Nut




Serrated Hex Flange Nut




Track Bolt



Self-Drilling Screw



Hex Head Lag Screw



Scott A. Brown, P.E. Lic. No. 65940
Willett, Hofmann & Associates, Inc.
809 E. 2nd Street, Dixon, IL 61021
FBPE CA Lic. No. 35415
Structural Adequacy for Wind Load

Digitally signed by Scott A Brown
Date: 2024.02.19 17:53:50-06'00'

Printed copies of this document are not considered signed and sealed and the SHA authentication code must be verified on any electronic copies.

All parts shown are for illustration purposes only. The actual product may include equivalent parts due to availability.

Scale: None	 PRODOOR MFG CO 6030 Gateway Drive Plainfield, IN 46168	Title: Spec, Wind Load Legacy & Carriage Collection		
Drawn by: J. Poitras		No. P-6004	Sheet 3	Rev A
Checked by: G. Wedekind				
Date: 01/10/24				
ECO: 9019.01				