






ISOMETRIC VIEW

Sealant required for Option 2 fastening and in the HVHZ when slope is $< 2^{\circ}/12^{\circ}$.



Panels are seamed 90 degrees, Single Lock

2" long clip, 4" from ends of panels, 13" o.c. max. = -67.25psf
10" o.c. max. = -101psf
2 screws per clip

21" nom. max. coverage

1/2" (15/32" min.) 4-Ply CDX Plywood or 3/4" min. thick wood plank (See min. substrate notes in Eval. Report)

2" Clip, spaced 4" from ends, 13" o.c. max. = -67.25psf uplift resistance, or 10" o.c. max. = -101psf uplift resistance

(2) #10 Pancake Screws per clip

Approved underlayment. Comply with FBC 1507.1.1 (non-HVHZ) or 1518.2 (HVHZ), Residential Code 905.1, 905.1.1, 905.1.1.1


MAX. DESIGN PRESSURE
26ga Galvalume Tested FLPA# 47604.7-R1
APPROVED FOR USE INSIDE HVHZ

Option #1 Clips spaced 13" o.c. max. = -67.25psf

Option #2, Clips spaced 10" o.c. max. = -101 psf with continuous bead of Bostic 915 sealant concealed at top corner of 90° seam.

GENERAL NOTES:


1. Roof slope is limited per the requirements of FBC Section 1507.4.2 or 1515.2. Residential Code 905.10.2
2. Design of substrate is by others and not a part of this approval. Perimeters and woodblocking should comply with (RAS 111 where applicable).
3. All panel system perimeters, penetrations, and transitions to be flashed and sealed per the requirements of DYME Metals' Installation Instructions and (RAS 133 where applicable).



FLPA# 47604.7-R1
DM CLASS 1150 Panel Profile

SCOTT WOLTERS
FL PE# 62354

WOLTERS ENGINEERING
(COA# 27194)
15211 97TH ROAD N
WEST PALM BEACH, FL 33412
PH/FAX: (561) 225-1982



Digitally signed
by Scott Wolters
Date: 2025.09.08
21:54:46 -04'00'



DRAWN
RWM
CHECKED

DATE
9-8-25

SCALE
NTS