


SOSOARES CAIXILHARIAS E VIDROS S.A.

OS-D+ SLIDING GLASS DOOR (HVHZ)(NON-IMPACT)

GENERAL NOTES:

- THE PRODUCT SHOWN HEREIN IS DESIGNED AND MANUFACTURED TO COMPLY WITH THE CURRENT EDITION FLORIDA BUILDING CODE (FBC), **INCLUDING** HVHZ AND HAS BEEN EVALUATED ACCORDING TO THE FOLLOWING:
 - TAS 202-94
- ADEQUACY OF THE EXISTING STRUCTURAL CONCRETE/MASONRY, 2X FRAMING, AND METAL FRAMING AS A MAIN WIND FORCE RESISTING SYSTEM CAPABLE OF WITHSTANDING AND TRANSFERRING APPLIED PRODUCT LOADS TO THE FOUNDATION IS THE RESPONSIBILITY OF THE ENGINEER OR ARCHITECT OF RECORD FOR THE PROJECT OF INSTALLATION.
- 1X AND 2X BUCKS (WHEN USED) SHALL BE DESIGNED AND ANCHORED TO PROPERLY TRANSFER ALL LOADS TO THE STRUCTURE. BUCK DESIGN AND INSTALLATION IS THE RESPONSIBILITY OF THE ENGINEER OR ARCHITECT OF RECORD FOR THE PROJECT OF INSTALLATION.
- INSTALL INDIVIDUAL INSTALLATION ANCHORS WITHIN A TOLERANCE OF ±1/2 INCH OF THE DEPICTED LOCATION IN THE ANCHOR LAYOUT DETAIL (I.E., WITHOUT CONSIDERATION OF TOLERANCES). TOLERANCES ARE NOT CUMULATIVE FROM ONE INSTALLATION ANCHOR TO THE NEXT.
- THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.
- APPROVED IMPACT PROTECTIVE SYSTEM **IS REQUIRED** ON THIS PRODUCT IN AREAS REQUIRING IMPACT RESISTANCE.
- DOOR FRAME MATERIAL: ALUMINUM 6060-T5
- GLASS MEETS THE REQUIREMENTS OF ASTM E1300 GLASS CHARTS. SEE SHEET 1 FOR GLAZING DETAIL.
- DESIGNATIONS "X" AND "O" STAND FOR THE FOLLOWING:
 - X: OPERABLE PANEL
 - O: FIXED PANEL
- APPROVED CONFIGURATIONS INCLUDE:
 - 2 TRACK - XX



GLAZING NOTES:

- GLASS TYPE SHALL COMPLY WITH ASTM E1300 REQUIREMENTS. PER THE FBC TEMPER AND SAFETY GLAZING REQUIREMENTS SHALL BE REVIEWED ON A SITE SPECIFIC BASIS.
- SETTING BLOCK DUROMETER HARDNESS OF 70-90 (SHORE A) AS REFERENCED IN FBC CHAPTER 24.
- SETTING BLOCKS TO BE LOCATED AT 1/4 SPAN LENGTH FOR GLASS WIDER THAN 36" AS PER FBC CHAPTER 24.
- D.L.O. AND DESIGN PRESSURES MAY NOT EXCEED MAX VALUES SHOWN HEREIN.

TABLE OF CONTENTS	
SHEET	SHEET DESCRIPTION
1	GENERAL NOTES & GLAZING DETAIL
2	DESIGN PRESSURE TABLES
3	ELEVATION
4	ANCHOR LAYOUT
5	VERTICAL SECTIONS
6	HORIZONTAL SECTIONS
7	INSTALLATION NOTES & ANCHOR DETAILS

DESIGN PRESSURE RATING (PSF)				
CONFIGURATION	WIDTH (IN.)	HEIGHT (IN.)	DESIGN PRESSURE	MISSILE IMPACT RATING
SEE SHEETS 2 & 3				NON-IMPACT



SOSOARES CAIXILHARIAS E VIDROS S.A.
ZONA INDUSTRIAL DE COIMBRÕES 101, 3500-618
SÃO JOÃO DA LOUROSA – VISEU, PORTUGAL
PH: +351 232 458 567

TITLE:
OS-D+ SLIDING
GLASS DOOR
(HVHZ)(NON-IMPACT)

GENERAL NOTES & GLAZING DETAIL

PREPARED BY:


BUILDING DROPS, INC.

1900 NE MIAMI CT. SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

REMARKS	BY	DATE
2026 CODE CHANGE	HJ	08/26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.

Digitally signed by Hermes F. Norero, P.E.
Reason: I am approving this document
Date: 2026.10.11 16:54:49 -0400'



FL #:
FL47923

DATE: **11.19.2025**

DWG. BY: **HJ** CHK. BY: **HFN**

SCALE: **NTS**

DWG. #: **SOS002**

SHEET: **1** REV. **A**

OF 7

c:\users\harley\desktop\projects\2026 code change\dwgs\sos002-a.dwg 9/17/2026 4:43 PM

DESIGN PRESSURE TABLE (PSF)			
NOMINAL DIMS.		POS. (+)	NEG. (-)
PANEL WIDTH (IN.)	FRAME HEIGHT (IN.)		
36	84	40.0	40.0
42		40.0	40.0
48		40.0	40.0
54		40.0	40.0
60		40.0	40.0
66		40.0	40.0
72		40.0	40.0
78		40.0	40.0
84		40.0	40.0
90		40.0	40.0
96		40.0	40.0
102		40.0	40.0
108	90	40.0	40.0
114		40.0	40.0
120		40.0	40.0
36		40.0	40.0
42		40.0	40.0
48		40.0	40.0
54		40.0	40.0
60		40.0	40.0
66		40.0	40.0
72		40.0	40.0
78		40.0	40.0
84		40.0	40.0
90		40.0	40.0
96	96	40.0	40.0
102		40.0	40.0
108		40.0	40.0
114		40.0	40.0
120		40.0	40.0
36		40.0	40.0
42		40.0	40.0
48		40.0	40.0
54		40.0	40.0
60		40.0	40.0
66		40.0	40.0
72		40.0	40.0
78	102	40.0	40.0
84		40.0	40.0
90		40.0	40.0
96		40.0	40.0
102		40.0	40.0
108		40.0	40.0
114		40.0	40.0
120		40.0	40.0
36		40.0	40.0
42		40.0	40.0
48		40.0	40.0
54		40.0	40.0

DESIGN PRESSURE TABLE (PSF)			
NOMINAL DIMS.		POS. (+)	NEG. (-)
PANEL WIDTH (IN.)	FRAME HEIGHT (IN.)		
36	108	40.0	40.0
42		40.0	40.0
48		40.0	40.0
54		40.0	40.0
60		40.0	40.0
66		40.0	40.0
72		40.0	40.0
78		40.0	40.0
84		40.0	40.0
90		40.0	40.0
96		40.0	40.0
102		40.0	40.0
108	114	40.0	40.0
114		40.0	40.0
120		40.0	40.0
36		40.0	40.0
42		40.0	40.0
48		40.0	40.0
54		40.0	40.0
60		40.0	40.0
66		40.0	40.0
72		40.0	40.0
78		40.0	40.0
84	120	40.0	40.0
90		40.0	40.0
96		40.0	40.0
102		40.0	40.0
108		40.0	40.0
114		40.0	40.0
120		40.0	40.0
36		40.0	40.0
42		40.0	40.0
48		40.0	40.0
54		40.0	40.0
60	126	40.0	40.0
66		40.0	40.0
72		40.0	40.0
78		40.0	40.0
84		40.0	40.0
90		40.0	40.0
96		40.0	40.0
102		40.0	40.0
108		40.0	40.0
114		40.0	40.0
120		40.0	40.0

DESIGN PRESSURE TABLE (PSF)			
NOMINAL DIMS.		POS. (+)	NEG. (-)
PANEL WIDTH (IN.)	FRAME HEIGHT (IN.)		
36	132	40.0	40.0
42		40.0	40.0
48		40.0	40.0
54		40.0	40.0
60		40.0	40.0
66		40.0	40.0
72		40.0	40.0
78		40.0	40.0
84		40.0	40.0
90		40.0	40.0
96		40.0	40.0
102		40.0	40.0
108	138	40.0	40.0
36		40.0	40.0
42		40.0	40.0
48		40.0	40.0
54		40.0	40.0
60		40.0	40.0
66		40.0	40.0
72		40.0	40.0
78		40.0	40.0
84		40.0	40.0
90		40.0	40.0
96		40.0	40.0
102	144	40.0	40.0
36		40.0	40.0
42		40.0	40.0
48		40.0	40.0
54		40.0	40.0
60		40.0	40.0
66		40.0	40.0
72		40.0	40.0
78		40.0	40.0
84		40.0	40.0
90		40.0	40.0
96		40.0	40.0
36	151.25	40.0	40.0
42		40.0	40.0
48		40.0	40.0
54		40.0	40.0
60		40.0	40.0
66		40.0	40.0
72		40.0	40.0
78		40.0	40.0
84		40.0	40.0
90		40.0	40.0
96		40.0	40.0
102		40.0	40.0

DESIGN PRESSURE TABLE (PSF)			
NOMINAL DIMS.		POS. (+)	NEG. (-)
PANEL WIDTH (IN.)	FRAME HEIGHT (IN.)		
36	156	40.0	40.0
42		40.0	40.0
48		40.0	40.0
54		40.0	40.0
60		40.0	40.0
66		40.0	40.0
72		40.0	40.0
78		40.0	40.0
84		39.7	39.7
90		37.7	37.7
36	162	40.0	40.0
42		40.0	40.0
48		40.0	40.0
54		40.0	40.0
60		40.0	40.0
66		40.0	40.0
72		39.8	39.8
78		37.2	37.2
84		35.1	35.1
36	168	40.0	40.0
42		40.0	40.0
48		40.0	40.0
54		40.0	40.0
60		40.0	40.0
66		38.2	38.2
72		35.5	35.5
78		33.2	33.2
84		31.2	31.2
36	174	40.0	40.0
42		40.0	40.0
48		40.0	40.0
54		40.0	40.0
60		37.3	37.3
66		34.2	34.2
72		31.7	31.7
78		29.7	29.7



SOSOARES CAIXILHARIAS E VIDROS S.A.
ZONA INDUSTRIAL DE COIMBRÕES 101, 3500-618
SÃO JOÃO DA LOUROSA – VISEU, PORTUGAL
PH: +351 232 458 567

TITLE:
OS-D+ SLIDING
GLASS DOOR
(HVHZ)/(NON-IMPACT)


DESIGN PRESSURE TABLES

PREPARED BY:
BUILDING DROPS, INC.
1900 NE MIAMI CT., SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

BUILDING DROPS

REMARKS	BY	DATE
2026 CODE CHANGE	HJ	08/26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #:
FL47923

DATE: **11.19.2025**

DWG. BY: **HJ** CHK. BY: **HFN**

SCALE: **NTS**

DWG. #: **SOS002**


SHEET:
2

REV.
A

OF 7



D.L.O. HEIGHT = FRAME HEIGHT - 8.625"
D.L.O. WIDTH = PANEL WIDTH - 2.875"
PANEL HEIGHT = FRAME HEIGHT - 5.187"
FRAME WIDTH = PANEL WIDTH*2 + 1.375"



ELEVATION


PREPARED BY:

900 NE MIAMI CT. SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744.4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
2026 CODE CHANGE	HJ	08/26/2025

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERAL AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #:

FL47923

DATE: 11.19.2025

DWG. BY:
HJ

CHK. BY:	HFN
----------	-----

SCALE: NTS

DWG. #: **SOS002**

SHEET:


REV.

(3)

A

OF 7

c:\users\harley\desktop\building drops, inc\building drops, inc\common\projects\2026 code change projects\sos002-2a.dwg 9/17/2026 4:43 PM



ANCHOR LAYOUT
LIFT & SLIDE DOOR
THROUGH FRAME: HEAD & JAMB
CLIP: SILL



SOSOARES CAIXILHARIAS E VIDROS S.A.
ZONA INDUSTRIAL DE COIMBRÕES 101, 3500-618
SÃO JOÃO DA LOUROSA – VISEU, PORTUGAL
PH: +351 232 458 567


OS-D+ SLIDING
GLASS DOOR
(HVHZ)/(NON-IMPACT)
ANCHOR LAYOUT

PREPARED BY:
BUILDING DROPS, INC.
1900 NE MIAMI CT. SUITE 2-15
MIAMI, FL 33132
PH: (954)599-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
2026 CODE CHANGE	HJ	08/26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #: **FL47923**

DATE: **11.19.2025**


DWG. BY: HJ	CHK. BY: HFN
-----------------------	------------------------

SCALE: **NTS**


DWG. #: **SOS002**

SHEET: 4	REV. A
--------------------	------------------

c:\users\harley\desktop\building drops, inc\building drops landing - common\projects\2026 code change projects\sos002-26-6135 - 2026 code change\dwgs\sos002-a.dwg 9/17/2026 4:43 PM



A
5 VERTICAL SECTION
HEAD - 2 TRACK



B
5 VERTICAL SECTION
FLUSH SILL - 2 TRACK



SOSOARES CAIXILHARIAS E VIDROS S.A.
ZONA INDUSTRIAL DE COIMBRÕES 101, 3500-618
SÃO JOÃO DA LOUROSA – VISEU, PORTUGAL
PH: +351 232 458 567

TITLE:
OS-D+ SLIDING
GLASS DOOR
(HVHZ)/(NON-IMPACT)

VERTICAL SECTIONS


PREPARED BY:
BUILDING DROPS, INC.

1900 NE MIAMI CT. SUITE 2-15
MIAMI, FL 33132
PH: (954)599-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com




REMARKS	BY	DATE
2026 CODE CHANGE	HJ	08/26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #:	FL47923
DATE:	11.19.2025
DWG. BY:	CHK. BY:
HJ	HFN
SCALE:	NTS
DWG. #:	SOS002
SHEET:	REV.
5	A
OF 7	

c:\users\harley\desktop\projects\2026 code change\projects\sos002\2026 code change\dwgs\sos002-a.dwg 9/17/2026 4:43 PM



SOSOARES CAIXILHARIAS E VIDROS S.A.
ZONA INDUSTRIAL DE COIMBRÕES 101, 3500-618
SÃO JOÃO DA LOUROSA – VISEU, PORTUGAL
PH: +351 232 458 567


TITLE:
OS-D+ SLIDING
GLASS DOOR
(HVHZ)(NON-IMPACT)
HORIZONTAL SECTIONS

PREPARED BY:
BUILDING DROPS, INC.
1900 NE MIAMI CT. SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

**BUILDING DROPS**


REMARKS	BY	DATE
2026 CODE CHANGE	HJ	08/26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #:		FL47923
DATE:		11.19.2025
DWG. BY:	CHK. BY:	
HJ	HFN	
SCALE:		NTS
DWG. #:		SOS002
SHEET:		6
REV.		A
		OF 7

c:\users\harley\desktop\building drops, inc\building drops, inc\common\projects\sos002-2a.dwg 9/17/2026 4:43 PM




A
7 **VERTICAL SECTION**
THROUGH FRAME INSTALLATION - HEAD

JAMB SIMILAR

INSTALLATION NOTES:

- ONE (1) INSTALLATION ANCHOR IS REQUIRED AT EACH ANCHOR LOCATION SHOWN, UNLESS OTHERWISE STATED ON SHEET 4.
- THE NUMBER OF INSTALLATION ANCHORS DEPICTED IS THE MINIMUM NUMBER OF ANCHORS TO BE USED FOR PRODUCT INSTALLATION OF THE MAXIMUM SIZE LISTED.
- INSTALL INDIVIDUAL INSTALLATION ANCHORS WITHIN A TOLERANCE OF $\pm 1/2$ INCH THE DEPICTED LOCATION & SPACING IN THE ANCHOR LAYOUT DETAILS (I.E., WITHOUT CONSIDERATION OF TOLERANCES). TOLERANCES ARE NOT CUMULATIVE FROM ONE INSTALLATION ANCHOR TO THE NEXT.
- SHIM AS REQUIRED AT EACH INSTALLATION ANCHOR WITH LOAD BEARING SHIM(S). MAXIMUM ALLOWABLE SHIM STACK TO BE 1/4 INCH. SHIM WHERE SPACE OF 1/16 INCH OR GREATER OCCURS. SHIM(S) SHALL BE CONSTRUCTED OF HIGH DENSITY PLASTIC OR BETTER.
- FOR MASONRY OR CONCRETE OPENINGS, A 1X WOOD BUCK MAY BE USED (OPTIONAL) AS LONG AS THE MINIMUM EMBEDMENT AND EDGE DISTANCE REQUIREMENTS ARE STILL MET WITHIN THE CORRESPONDING HOST SUBSTRATE. SEE GENERAL NOTE #3 ON SHEET 1 FOR MORE INFORMATION.
- MINIMUM EMBEDMENT AND EDGE DISTANCE EXCLUDE WALL FINISHES, INCLUDING BUT NOT LIMITED TO STUCCO, FOAM, BRICK VENEER, AND SIDING.
- INSTALLATION ANCHORS AND ASSOCIATED HARDWARE MUST BE MADE OF CORROSION RESISTANT MATERIAL OR HAVE A CORROSION RESISTANT COATING.
 - FASTENERS USED WITHIN 3,000 FEET OF A SALTWATER COASTLINE AND INSTALLED IN ENCLOSED SPACES SHALL BE GALVANIZED IN ACCORDANCE WITH SECTION 1711.1.1 (E.G., ASTM A153 CLASS D, ASTM A641 CLASS 3S, OR EQUIVALENT CORROSION RESISTANCE).
 - CONNECTORS AND METAL PLATES USED WITHIN 3,000 FEET OF A SALTWATER COASTLINE SHALL BE STANDARD GALVANIZED IN ACCORDANCE WITH SECTION 1711.1.2 (E.G., ASTM A653 G90, ASTM A123, OR PROTECTIVE COATING PER TPI 1).
- FOR HOLLOW BLOCK AND GROUT FILLED BLOCK, DO NOT INSTALL INSTALLATION ANCHORS INTO MORTAR JOINTS. EDGE DISTANCE IS MEASURED FROM FREE EDGE OF BLOCK OR EDGE OF MORTAR JOINT INTO FACE SHELL OF BLOCK.
- INSTALLATION ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH ANCHOR MANUFACTURER'S INSTALLATION INSTRUCTIONS, AND ANCHORS SHALL NOT BE USED IN SUBSTRATES WITH STRENGTHS LESS THAN THE MINIMUM STRENGTH SPECIFIED BY THE ANCHOR MANUFACTURER.



B
7 **VERTICAL SECTION**
CLIP INSTALLATION - SILL

ANCHOR SCHEDULE				
METHOD	SUBSTRATE	ANCHOR TYPE	MIN. EMBEDMENT	MIN. EDGE DISTANCE
CLIP & THROUGH FRAME	WOOD: MIN. SG = 0.55	#14 WOOD SCREW	1.50"	0.75"
	METAL: 18 GAUGE STEEL, MIN. Fy = 33KSI ALUMINUM: 1/8" MIN., 6063-T5	#14 SELF-DRILLING SCREW	3 THREADS MIN PENETRATION BEYOND STRUCTURE	0.50"
	CONCRETE: f'c=3000PSI	1/4" ITW TAPCON	1.25"	2.00"
	MASONRY: CMU per ASTM C90 MIN. 2000 PSI	1/4" ITW TAPCON	1.00"	2.00"



SOSOARES CAIXILHARIAS E VIDROS S.A.
ZONA INDUSTRIAL DE COIMBRÕES 101, 3500-618
SÃO JOÃO DA LOUROSA – VISEU, PORTUGAL
PH: +351 232 458 567


TITLE:
OS-D+ SLIDING
GLASS DOOR
(HVHZ)(NON-IMPACT)
INSTALLATION NOTES
& ANCHOR DETAILS

PREPARED BY:
BUILDING DROPS, INC.
1900 NE MIAMI CT., SUITE 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

**BUILDING DROPS**

REMARKS	BY	DATE
2026 CODE CHANGE	HJ	08/26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #:
FL47923

DATE: **11.19.2025**

DWG. BY: **HJ**CHK. BY: **HFN**

SCALE: **NTS**

DWG. #: **SOS002**

SHEET:
7

REV.
A

OF 7