

REILLY ARCHITECTURAL

SERIES 3170 OUTSWING CASEMENT WINDOW

(HVHZ)(IMPACT)

GENERAL NOTES:

1. THE PRODUCT SHOWN HEREIN IS DESIGNED AND MANUFACTURED TO COMPLY WITH THE CURRENT EDITION OF THE FLORIDA BUILDING CODE (FBC), **INCLUDING** HVHZ AND HAS BEEN EVALUATED ACCORDING TO THE FOLLOWING:
- TAS 201-94

TAS 202-94

TAS 203-94
2. ADEQUACY OF THE EXISTING STRUCTURAL CONCRETE/MASONRY, 2X FRAMING, AND METAL FRAMING AS A MAIN WIND FORCE RESISTING SYSTEM CAPABLE OF WITHSTANDING AND TRANSFERRING APPLIED PRODUCT LOADS TO THE FOUNDATION IS THE RESPONSIBILITY OF THE ENGINEER OR ARCHITECT OF RECORD FOR THE PROJECT OF INSTALLATION.
3. 1X AND 2X BUCKS (WHEN USED) SHALL BE DESIGNED AND ANCHORED TO PROPERLY TRANSFER ALL LOADS TO THE STRUCTURE. BUCK DESIGN AND INSTALLATION IS THE RESPONSIBILITY OF THE ENGINEER OR ARCHITECT OF RECORD FOR THE PROJECT OF INSTALLATION.
4. THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.
5. APPROVED IMPACT PROTECTIVE SYSTEM **IS NOT REQUIRED** ON THIS PRODUCT IN AREAS REQUIRING IMPACT RESISTANCE.
6. WINDOW FRAME MATERIAL: MAHOGANY
7. GLASS MEETS THE REQUIREMENTS OF ASTM E1300 GLASS CHARTS. SEE SHEET 2 FOR GLAZING DETAILS.

INSTALLATION NOTES:

1. ONE (1) INSTALLATION ANCHOR IS REQUIRED AT EACH ANCHOR LOCATION SHOWN, UNLESS OTHERWISE STATED ON SHEET 5.
2. INSTALL INDIVIDUAL INSTALLATION ANCHORS WITHIN A TOLERANCE OF ±1/2 INCH THE DEPICTED LOCATION & SPACING IN THE ANCHOR LAYOUT DETAILS (I.E., WITHOUT CONSIDERATION OF TOLERANCES). TOLERANCES ARE NOT CUMULATIVE FROM ONE INSTALLATION ANCHOR TO THE NEXT.
3. SHIM AS REQUIRED AT EACH INSTALLATION ANCHOR WITH LOAD BEARING SHIM(S). MAXIMUM ALLOWABLE SHIM STACK TO BE 1/2 INCH. SHIM WHERE SPACE OF 1/16 INCH OR GREATER OCCURS. SHIM(S) SHALL BE CONSTRUCTED OF HIGH DENSITY PLASTIC OR BETTER.
4. MINIMUM EMBEDMENT AND EDGE DISTANCE EXCLUDE WALL FINISHES, INCLUDING BUT NOT LIMITED TO STUCCO, FOAM, BRICK VENEER, AND SIDING.
5. INSTALLATION ANCHORS AND ASSOCIATED HARDWARE MUST BE MADE OF CORROSION RESISTANT MATERIAL OR HAVE A CORROSION RESISTANT COATING:

FASTENERS USED WITHIN 3,000 FEET OF A SALTWATER COASTLINE AND INSTALLED IN ENCLOSED SPACES SHALL BE GALVANIZED IN ACCORDANCE WITH SECTION 1711.1.1 (E.G., ASTM A153 CLASS D, ASTM A641 CLASS 3S, OR EQUIVALENT CORROSION RESISTANCE).

CONNECTORS AND METAL PLATES USED WITHIN 3,000 FEET OF A SALTWATER COASTLINE SHALL BE STANDARD GALVANIZED IN ACCORDANCE WITH SECTION 1711.1.2 (E.G., ASTM A653 G90, ASTM A123, OR PROTECTIVE COATING PER TPI 1).

6. FOR MASONRY OR CONCRETE OPENINGS, A 1X WOOD BUCK MAY BE USED (OPTIONAL) AS LONG AS THE MINIMUM EMBEDMENT AND EDGE DISTANCE REQUIREMENTS ARE STILL MET WITHIN THE CORRESPONDING HOST SUBSTRATE. SEE GENERAL NOTE #3 ON SHEET 1 FOR MORE INFORMATION.

7. FOR HOLLOW BLOCK AND GROUT FILLED BLOCK, DO NOT INSTALL INSTALLATION ANCHORS INTO MORTAR JOINTS. EDGE DISTANCE IS MEASURED FROM FREE EDGE OF BLOCK OR EDGE OF MORTAR JOINT INTO FACE SHELL OF BLOCK.

8. INSTALLATION ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH ANCHOR MANUFACTURER'S INSTALLATION INSTRUCTIONS, AND ANCHORS SHALL NOT BE USED IN SUBSTRATES WITH STRENGTHS LESS THAN THE MINIMUM STRENGTH SPECIFIED BY THE ANCHOR MANUFACTURER.
- | TABLE OF CONTENTS | |
|-------------------|--------------------------------------|
| SHEET | SHEET DESCRIPTION |
| 1 | GENERAL NOTES AND INSTALLATION NOTES |
| 2 | GLAZING DETAILS |
| 3 | ELEVATIONS |
| 4 | ELEVATION & QUALIFIED CONFIGURATIONS |
| 5 | ANCHOR LAYOUTS |
| 6 | ANCHOR LAYOUTS & LOCK QUANTITY TABLE |
| 7 | VERTICAL SECTIONS |
| 8 | HORIZONTAL SECTIONS |
| 9 | ANCHOR DETAILS & ANCHOR SCHEDULE |
| 10 | BILL OF MATERIALS & COMPONENTS |
| 11 | COMPONENTS |
- | DESIGN PRESSURE RATING (PSF) | | | | |
|------------------------------|--------------|---------------|-----------------|------------------------------|
| WIDTH (IN.) | HEIGHT (IN.) | CONFIGURATION | DESIGN PRESSURE | MISSILE IMPACT RATING |
| 79-1/4" | 96" | XX | +70/-75 | LARGE & SMALL MISSILE IMPACT |
| 41-1/4" | 96" | X | +70/-75 | |
| 79-1/4" | 133-1/4" | O/XX | +70/-75 | |
-
- 901 BURMAN BLVD, BUILDING 701
CALVERTON, NY 11933
PH: 631-208-0710 FAX: 631-208-0711
EMAIL: WWW.REILLYARCH.COM
- SERIES 3170 OUTSWING
CASEMENT WINDOW
(HVHZ)(IMPACT)
GENERAL NOTES &
INSTALLATION NOTES
- PREPARED BY:


BUILDING DROPS, INC.

1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132
PH: (954) 399-8478
FAX: (954) 744-4738
WEB: www.buildingdrops.com


B.D.

BUILDING DROPS
- | REMARKS | BY | DATE |
|-----------------|----|-------|
| 2026 FBC UPDATE | LS | 06/26 |
| | | |
| | | |
| | | |
- THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.
- Digitally signed by Hermes F. Norero, P.E.
Reason: I am approving this document
Date: 2026.08.15 14:42:27 -03'00'
-
- FL #:
FL48048
- DATE: **03.05.2026**
- | | |
|-----------------------|------------------------|
| DWG. BY:
DB | CHK. BY:
HFN |
|-----------------------|------------------------|
- SCALE: **NTS**
- DWG. #: **RWD031**
- | | |
|----------|----------|
| SHEET: | REV. |
| 1 | A |
- OF 11


c:\users\lucianosanchez\building drops, inc\building drops landing - documents\common\projects\2026 code change projects\reilly architectural\cc-26-0587.1 - 2026 code change\dwgs\148048-r1\rvwd031.dwg 7/9/2026 3:17 PM



GLAZING DETAIL 1




GLAZING DETAIL 2



GLAZING DETAIL 3

GLAZING NOTES:

1. GLASS TYPE COMPLIES WITH ASTM E1300 REQUIREMENTS. PER THE FBC, TEMPER AND SAFETY GLAZING REQUIREMENTS SHALL BE REVIEWED ON A SITE SPECIFIC BASIS.
2. SETTING BLOCK DUROMETER HARDNESS OF 70-90 (SHORE A) AS REFERENCED IN FBC CHAPTER 24.
3. SETTING BLOCKS TO BE LOCATED AT 1/4 SPAN LENGTH FOR GLASS WIDER THAN 36" AS PER FBC CHAPTER 24.
4. D.L.O. AND DESIGN PRESSURES MAY NOT EXCEED MAX VALUES SHOWN HEREIN.
5. ALTERNATE GLAZING BEADS QUALIFIED AS LONG AS THE MOMENT OF INERTIA VALUE OF THE DESIRED BEAD IS EQUAL TO OR GREATER THAN THE TESTED BEAD SHOWN ON THE RIGHT.



MOMENT OF INERTIA ABOUT THE Y-AXIS = 0.0076 IN⁴

REILLY

ARCHITECTURAL


901 BURMAN BLVD, BUILDING 701
CALVERTON, NY 11933
PH: 631-208-0710 FAX: 631-208-0711
EMAIL: WWW.REILLYARCH.COM

TITLE: SERIES 3170 OUTSWING
CASEMENT WINDOW
(HVHZ)(IMPACT)
GLAZING DETAILS

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132
PH: (954) 399-8478
FAX: (954) 744-4738
WEB: www.buildingdrops.com


REMARKS	BY	DATE
2026 FBC UPDATE	LS	06/26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.




FL #:	FL48048
DATE:	03.05.2026
DWG. BY:	CHK. BY:
DB	HFN
SCALE:	NTS
DWG. #:	RWD031
SHEET:	REV.
2	A
OF 11	

c:\users\lucianosanchez\building drops, inc\building drops landing - documents\common\projects\2026 code change projects\reilly architectural\cc-26-0587.1 - 2026 code change\dwgs\148048-r1\rvd031.dwg 7/9/2026 3:17 PM



ELEVATION
FRENCH CASEMENT



ELEVATION
SINGLE CASEMENT

NOTE:
• HARDWARE - FOURTEEN (14) CAM LOCKS TOTAL FOR FRENCH CASEMENTS AND TEN (10) CAM LOCKS TOTAL FOR SINGLE CASEMENTS.

REILLY ARCHITECTURAL

901 BURMAN BLVD, BUILDING 701
CALVERTON, NY 11933
PH: 631-208-0710 FAX: 631-208-0711
EMAIL: WWW.REILLYARCH.COM

TITLE: SERIES 3170 OUTSWING
CASEMENT WINDOW
(HVHZ)(IMPACT)

ELEVATIONS

PREPARED BY: BUILDING DROPS, INC.

1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
2026 FBC UPDATE	LS	06/26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #: FL48048


DATE: 03.05.2026

DWG. BY: DB
CHK. BY: HFN

SCALE: NTS

DWG. #: RWD031

SHEET: 3
REV. A




ELEVATION

FRENCH CASEMENT WITH TRANSOM

HARDWARE NOTES:

- 1) EACH CASEMENT SASH SHALL UTILIZE BRASS OR STAINLESS STEEL BUTT HINGES ACCORDING TO MAX O.C. SPACING DESIGNATED ABOVE
- 2) CASEMENT SASHES SHALL UTILIZE SIEGENIA MULTIPOINT LOCKING HARDWARE
- 3) SEE SHEET 6 FOR LOCK QUANTITY REQUIREMENTS

HINGE QUANTITY REQUIREMENTS	
FRAME HEIGHT	QTY.
FH > 75 $\frac{9}{32}$ "	5
75 $\frac{9}{32}$ " $\geq$ FH > 54 $\frac{9}{16}$ "	4
54 $\frac{9}{16}$ " $\geq$ FH > 33 $\frac{27}{32}$ "	3
33 $\frac{27}{32}$ " $\geq$ FH	2



QUALIFIED CONFIGURATIONS

QUALIFIED CONFIGURATIONS NOTES:

1. SHOWN CONFIGURATIONS ARE QUALIFIED BASED ON TESTING SUCH THAT THEY DO NOT EXCEED THE MAXIMUM D.L.O. OR SASH DIMENSIONS SHOWN ON ELEVATION.
2. SEE DETAILS "D" AND "E" ON SHEET 8 FOR VERTICAL MULLION DETAILS APPLICABLE TO QUALIFIED CONFIGURATIONS.
3. OPERABLE WINDOWS IN THE MULLED CONFIGURATIONS SHOWN ABOVE MAY BE REPLACED WITH FIXED WINDOWS.

901 BURMAN BLVD, BUILDING 701
CALVERTON, NY 11933
PH: 631-208-0710 FAX: 631-208-0711
EMAIL: WWW.REILLYARCH.COM

**SERIES 3170 OUTSWING
CASEMENT WINDOW
(HVHZ)(IMPACT)
ELEVATION & QUALIFIED
CONFIGURATIONS**

PREPARED BY:

 **BUILDING DROPS**

BUILDING DROPS, INC.
1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744,4738
WEB: www.buildingdrops.com

REMARKS	BY	DATE
2026 FBC UPDATE	LS	06/26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERAL AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #:

FL48048

DATE: 03.05.2026

DWG. BY: DB	CHK. BY: HFN
-----------------------	------------------------


SCALE: NTS

DWG. #: RWD031


SHEET: 4

7/9/2026 3:17 PM


c:\users\lucianosanchez\building drops, inc\building drops landing - documents\common\projects\2026 code change projects\reilly architectural\cc-26-0587.1 - 2026 code change\dwgs\148048-r1.rwd031.dwg




ANCHOR LAYOUT
THROUGH FRAME - HEAD & JAMBS
ANGLE CLIP - SILL




ANCHOR LAYOUT
FLAT CLIP - HEAD & JAMBS
ANGLE CLIP - SILL




ANCHOR LAYOUT
ANGLE CLIP - HEAD & JAMBS
ANGLE CLIP - SILL



ANCHOR LAYOUT
THROUGH FRAME - HEAD & JAMBS
ANGLE CLIP - SILL



ANCHOR LAYOUT
FLAT CLIP - HEAD & JAMBS
ANGLE CLIP - SILL



ANCHOR LAYOUT
ANGLE CLIP - HEAD & JAMBS
ANGLE CLIP - SILL

REILLY
ARCHITECTURAL

901 BURMAN BLVD, BUILDING 701
CALVERTON, NY 11933
PH: 631-208-0710 FAX: 631-208-0711
EMAIL: WWW.REILLYARCH.COM

TITLE:
SERIES 3170 OUTSWING
CASEMENT WINDOW
(HVHZ)(IMPACT)


ANCHOR LAYOUTS

PREPARED BY:
BUILDING DROPS, INC.
1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
2026 FBC UPDATE	LS	06/26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC
AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC
SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE
FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED
ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC
DOCUMENTS FOR USE WITH THIS DOCUMENT.




FL #:	FL48048
DATE:	03.05.2026
DWG. BY:	DB
CHK. BY:	HFN
SCALE:	NTS
DWG. #:	RWD031
SHEET:	5
REV.	A
OF 11	

c:\users\lucianosanchez\building drops, inc\building drops landing - documents\common\projects\2026 code change projects\reilly architectural\cc-26-0587.1 - 2026 code change projects\dwgs\148048-r1.rwd031.dwg 7/9/2026 3:17 PM


LOCK REQUIREMENTS:

- 1) SPACING OF PRIMARY SASH LOCK LOCATIONS AT THE LOCK STILE SHALL NOT EXCEED THE MAXIMUM TESTED SPACING OF 23"
- 2) QUANTITY REQUIRED AT HEAD AND SILL STILES APPLIES TO BOTH PRIMARY AND SECONDARY SASHES ON TWIN UNITS



ANCHOR LAYOUT

FLAT CLIP OR ANGLE CLIP - HEAD
THROUGH FRAME - JAMBS
ANGLE CLIP - SILL



ANCHOR LAYOUT

FLAT CLIP OR ANGLE CLIP - HEAD & JAMBS
ANGLE CLIP - SILL

MINIMUM REQUIRED LOCK LOCATIONS

SASH SIZE		QUANTITY AT LOCK JAMB	QUANTITY AT HEAD/SILL
HEIGHT	WIDTH		
96.125	39.75	5	2
96.125	35	5	2
96.125	30	4	2
96.125	25	4	2
96.125	20	3	2
90.00	39.75	5	2
90.00	35	5	2
90.00	30	4	2
90.00	25	3	2
90.00	20	3	1
85.00	39.75	5	2
85.00	35	4	2
85.00	30	4	2
85.00	25	3	2
85.00	20	3	1
80.00	39.75	5	2
80.00	35	4	2
80.00	30	4	2
80.00	25	3	2
80.00	20	3	1
75.00	39.75	4	2
75.00	35	4	2
75.00	30	3	2
75.00	25	3	1
75.00	20	2	1
70.00	39.75	4	2
70.00	35	4	2
70.00	30	3	2
70.00	25	3	1
70.00	20	2	1
65.00	39.75	4	2
65.00	35	3	2
65.00	30	3	2
65.00	25	3	1
65.00	20	2	1
60.00	39.75	4	2
60.00	35	3	2
60.00	30	3	1
60.00	25	2	1
60.00	20	2	1
55.00	39.75	3	2
55.00	35	3	2
55.00	30	3	1
55.00	25	2	1
55.00	20	2	1

REILLY
ARCHITECTURAL


901 BURMAN BLVD, BUILDING 701
CALVERTON, NY 11933
PH: 631-208-0710 FAX: 631-208-0711
EMAIL: WWW.REILLYARCH.COM

TITLE: SERIES 3170 OUTSWING
CASEMENT WINDOW
(HVHZ)(IMPACT)
ANCHOR LAYOUTS &
LOCK QUANTITY TABLE

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com


REMARKS	BY	DATE
2026 FBC UPDATE	LS	06/26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.




FL #:	FL48048
DATE:	03.05.2026
DWG. BY:	CHK. BY:
DB	HFN
SCALE:	NTS
DWG. #:	RWD031
SHEET:	REV.
6	A
OF 11	


c:\users\lucianosanchez\building drops, inc\building drops landing - documents\common\projects\2026 code change projects\reilly architectural\cc-26-c0587.1 - 2026 code change\dwgs\148048-r1\rvd031.dwg 7/9/2026 3:17 PM




A
7 VERTICAL SECTION
CASEMENT HEAD




B
7 VERTICAL SECTION
TRANSOM HEAD



C
7 VERTICAL SECTION
CASEMENT SILL



D
7 VERTICAL SECTION
HORIZONTAL MULLION (WOOD)



E
7 VERTICAL SECTION
HORIZONTAL MULLION (WOOD W/ STEEL)

REILLY

ARCHITECTURAL

901 BURMAN BLVD, BUILDING 701
CALVERTON, NY 11933
PH: 631-208-0710 FAX: 631-208-0711
EMAIL: WWW.REILLYARCH.COM

TITLE:
SERIES 3170 OUTSWING
CASEMENT WINDOW
(HVHZ)(IMPACT)

VERTICAL SECTIONS

PREPARED BY:

BUILDING DROPS, INC.

1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132


PH: (954)399-8478
FAX: (954)744-4738

WEB: www.buildingdrops.com



REMARKS	BY	DATE
2026 FBC UPDATE	LS	06/26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #:
FL48048

DATE: **03.05.2026**

DWG. BY:
DB

CHK. BY:
HFN

SCALE: **NTS**

DWG. #: **RWD031**


SHEET:

7


REV.

A


c:\users\lucianosanchez\building drops, inc\building drops, inc\documents\common\projects\2026 code change, projects\reilly architectural\cc-26-cd87.1 - 2026 code change.dwg (148048-r1) rwd031.dwg 7/9/2026 3:17 PM




A
8 HORIZONTAL SECTION
CASEMENT
JAMB




B
8 HORIZONTAL SECTION
FRENCH CASEMENT
MEETING STILE



C
8 HORIZONTAL SECTION
TRANSOM
JAMB



D
8 HORIZONTAL SECTION
VERTICAL MULLION (WOOD)



E
8 HORIZONTAL SECTION
VERTICAL MULLION (WOOD W/ STEEL)

REILLY
ARCHITECTURAL

901 BURMAN BLVD, BUILDING 701
CALVERTON, NY 11933
PH: 631-208-0710 FAX: 631-208-0711
EMAIL: WWW.REILLYARCH.COM

TITLE:
SERIES 3170 OUTSWING
CASEMENT WINDOW
(HVHZ)(IMPACT)

HORIZONTAL SECTIONS

PREPARED BY:

BUILDING DROPS, INC.

1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132

PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com




REMARKS	BY	DATE
2026 FBC UPDATE	LS	06/26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #:	FL48048
DATE:	03.05.2026
DWG. BY:	DB
CHK. BY:	HFN
SCALE:	NTS
DWG. #:	RWD031
SHEET:	8
REV.	A

c:\users\lucianosanchez\building drops, inc\building drops landing - documents\common\projects\2026 code change projects\reilly architectural\cc-26-0587.1 - 2026 code change\dwgs\148048-r1\rvd031.dwg 7/9/2026 3:17 PM




EXTERIOR

INTERIOR

A
9

ANCHOR DETAIL

HEAD - THROUGH FRAME
JAMB SIMILAR




EXTERIOR

INTERIOR

B
9

ANCHOR DETAIL

HEAD - FLAT CLIP
JAMB SIMILAR



EXTERIOR

INTERIOR


C
9

ANCHOR DETAIL

HEAD - ANGLE CLIP
JAMB SIMILAR

NOTE: TRANSOM CAN ONLY BE INSTALLED USING FLAT CLIP
INSTALLATION OR ANGLE CLIP INSTALLATION.

ANCHOR SCHEDULE					
METHOD	QUANTITY PER LOCATION	SUBSTRATE	ANCHOR TYPE	MIN. EMBEDMENT	MIN. EDGE DISTANCE
THROUGH FRAME	1	WOOD: MIN. SG = 0.55	#12 WOOD SCREW	1.50"	0.75"
		METAL: 18 GAUGE STEEL, MIN. Fy = 33KSI ALUMINUM: 1/8" MIN., 6063-T5	#12 SELF-DRILLING SCREW	3 THREADS MIN PENETRATION BEYOND STRUCTURE	0.50"
		CONCRETE: f'c=3000PSI	1/4" ITW TAPCON	1.25"	2.50"
		MASONRY: CMU per ASTM C90 MIN. 2000 PSI	1/4" ITW TAPCON	1.00"	2.50"
FLAT CLIP/ SILL ANGLE CLIP	2	WOOD: MIN. SG = 0.55	#10 WOOD SCREW	1.50"	0.75"
		METAL: 18 GAUGE STEEL, MIN. Fy = 33KSI ALUMINUM: 1/8" MIN., 6063-T5	#10 SELF-DRILLING SCREW	3 THREADS MIN PENETRATION BEYOND STRUCTURE	0.50"
		CONCRETE: f'c=3000PSI	3/16" ITW TAPCON	1.00"	2.00"
		MASONRY: CMU per ASTM C90 MIN. 2000 PSI	3/16" ITW TAPCON	1.00"	2.00"
ANGLE CLIP	2	WOOD: MIN. SG = 0.55	#10 WOOD SCREW	1.50"	0.75"
		METAL: 18 GAUGE STEEL, MIN. Fy = 33KSI ALUMINUM: 1/8" MIN., 6063-T5	#10 SELF-DRILLING SCREW	3 THREADS MIN PENETRATION BEYOND STRUCTURE	0.50"



D
9

ANCHOR DETAIL

SILL - ANGLE CLIP

NOTE: SILL USES ITS OWN ANGLE CLIP REGARDLESS OF
INSTALLATION METHOD AT THE HEAD/JAMBS.

REILLY
ARCHITECTURAL

901 BURMAN BLVD, BUILDING 701
CALVERTON, NY 11933
PH: 631-208-0710 FAX: 631-208-0711
EMAIL: WWW.REILLYARCH.COM


TITLE: SERIES 3170 OUTSWING
CASEMENT WINDOW
(HVHZ)(IMPACT)
ANCHOR DETAILS &
ANCHOR SCHEDULE

PREPARED BY: BUILDING DROPS, INC.
1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132
PH: (954) 399-8478
FAX: (954) 744-4738
WEB: www.buildingdrops.com




REMARKS	BY	DATE
2026 FBC UPDATE	LS	06/26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC
AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC
SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE
FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED
ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC
DOCUMENTS FOR USE WITH THIS DOCUMENT.




FL #:	FL48048	
DATE:	03.05.2026	
DWG. BY:	DB	CHK. BY: HFN
SCALE:	NTS	
DWG. #:	RWD031	
SHEET:	9	REV. A
OF 11		


BILL OF MATERIALS			
ITEM	DESCRIPTION	MATERIAL	MANUFACTURER
1	STILE/TOP RAIL	MAHOGANY	REILLY
2	BOTTOM RAIL	MAHOGANY	REILLY
3	MEETING STILE	MAHOGANY	REILLY
4	MEETING STILE	MAHOGANY	REILLY
5	ASTRAGAL	MAHOGANY	REILLY
6	JAMB/HEAD	MAHOGANY	REILLY
7	SILL	MAHOGANY	REILLY
8	JAMB/HEAD EXTENSION	MAHOGANY	REILLY
9	SILL EXTENSION	MAHOGANY	REILLY
10	MULTI-POINT LOCK	STEEL	VARIES
11	WEATHERSTRIP	SILICONE	DEVENTER
12	WEATHERSTRIP	SILICONE	DEVENTER
13	WEATHERSTRIP	SILICONE	DEVENTER
14	FLAT CLIP	ALUMINUM	VARIES
15	ANGLE CLIP	304 S.S.	VARIES
16	SILL ANGLE CLIP	304 S.S.	VARIES
17	HINGE	BRASS	REILLY
18	HORIZONTAL MULLION	MAHOGANY	REILLY
19	HORIZONTAL MULLION	MAHOGANY	REILLY
20	HORIZONTAL MULLION STIFFENER	MAHOGANY	REILLY
21	HORIZONTAL MULLION STIFFENER	STEEL	VARIES
22	VERTICAL MULLION	MAHOGANY	REILLY
23	VERTICAL MULLION STIFFENER	MAHOGANY	REILLY
24	VERTICAL MULLION STIFFENER	STEEL	VARIES
25	TRANSOM STILE/RAIL	MAHOGANY	REILLY




1 STILE/TOP RAIL
MAHOGANY




2 BOTTOM RAIL
MAHOGANY




3 MEETING STILE
MAHOGANY




4 MEETING STILE
MAHOGANY




5 ASTRAGAL
MAHOGANY




6 JAMB/HEAD
MAHOGANY




7 SILL
MAHOGANY




8 JAMB/HEAD EXTENSION
MAHOGANY



9 SILL EXTENSION
MAHOGANY



14 FLAT CLIP
ALUMINUM



15 ANGLE CLIP
304 STAINLESS STEEL

REILLY
ARCHITECTURAL

901 BURMAN BLVD, BUILDING 701
CALVERTON, NY 11933
PH: 631-208-0710 FAX: 631-208-0711
EMAIL: WWW.REILLYARCH.COM

TITLE:
SERIES 3170 OUTSWING
CASEMENT WINDOW
(HVHZ)(IMPACT)
BILL OF MATERIALS &
COMPONENTS

PREPARED BY:
BUILDING DROPS, INC.
1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132
PH: (954) 399-8478
FAX: (954) 744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
2026 FBC UPDATE	LS	06/26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC
AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC
SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE
FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED
ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC
DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #:
FL48048


DATE: **03.05.2026**

DWG. BY: **DB** CHK. BY: **HFN**


SCALE: **NTS**

DWG. #: **RWD031**


SHEET: **10** REV. **A**




16 SILL ANGLE CLIP
304 STAINLESS STEEL




18 HORIZONTAL MULLION
MAHOGANY




19 HORIZONTAL MULLION
MAHOGANY




20 HORIZONTAL MULLION STIFFENER
MAHOGANY




21 HORIZONTAL MULLION STIFFENER
STEEL




22 VERTICAL MULLION
MAHOGANY



23 VERTICAL MULLION STIFFENER
MAHOGANY



24 VERTICAL MULLION STIFFENER
STEEL



25 TRANSOM STILE/RAIL
MAHOGANY

REILLY
ARCHITECTURAL

901 BURMAN BLVD, BUILDING 701
CALVERTON, NY 11933
PH: 631-208-0710 FAX: 631-208-0711
EMAIL: WWW.REILLYARCH.COM

TITLE:
SERIES 3170 OUTSWING
CASEMENT WINDOW
(HVHZ)(IMPACT)

COMPONENTS

PREPARED BY:

BUILDING DROPS, INC.

1900 NE MIAMI COURT, STE. 2-15
MIAMI, FL 33132
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
2026 FBC UPDATE	LS	06/26

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC
AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC
SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE
FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED
ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC
DOCUMENTS FOR USE WITH THIS DOCUMENT.



FL #:
FL48048

DATE: **03.05.2026**

DWG. BY: **DB** CHK. BY: **HFN**

SCALE: **NTS**

DWG. #: **RWD031**

SHEET: **11** REV. **A**