

Product Evaluation Report

Report No.: **FL-16185.5**

Date: **July 2, 2026**

Product Category	Sub Category	Manufacturer	Product Name
Exterior Doors	Swinging Exterior Door Assemblies	Dallas Millwork, Inc 119 Sunnyland Drive Hiram, GA 30141 (770) 943-3909	Wood Entry Door Double w/ or w/out Sidelites Inswing/Outswing "Non-Impact"

Scope: This is a Product Evaluation report issued by R W Building Consultants, Inc. and Lyndon F. Schmidt, P.E. (System ID # 1998) for Dallas Millwork, Inc based on Rule Chapter No. 61G20-3, Method 1D of the State of Florida Product Approval, Department of Business & Professional Regulation.

RW Building Consultants and Lyndon F. Schmidt, P.E. do not have nor will acquire financial interest in the company manufacturing or distributing the product or in any other entity involved in the approval process of the product named herein.

Limitations:

1. This product has been evaluated and is in compliance with the 9th Edition (2026) Florida Building Code (FBC) structural requirements excluding the "High Velocity Hurricane Zone" (HVHZ).
2. Product anchors shall be as listed and spaced as shown on details. Anchor embedment to base material shall be beyond wall dressing or stucco.
3. When used in areas requiring wind borne debris protection this product is required to be protected with an impact resistant covering that complies with FBC Sections 1609.1.2 & R301.2.1.2.
4. For 2x stud framing construction, anchoring of these units shall be the same as that shown for 2x buck masonry construction.
5. Site conditions that deviate from the details of drawing FL 16185.5 require further engineering analysis by a licensed engineer or registered architect.

Supporting Documents:

- | | | | |
|---|---|--|--|
| 1. Test Report No.
TEL 02950559
TEL 02950560
TEL 02950561
TEL 02950562
TEL 02950563 | Test Standard
ASTM E330-02, E331-00
ASTM E330-02, E331-00
ASTM E330-02, E331-00
ASTM E330-02, E331-00
ASTM E330-02, E331-00 | Testing Laboratory
Testing Evaluation Laboratory, Inc.
Testing Evaluation Laboratory, Inc.
Testing Evaluation Laboratory, Inc.
Testing Evaluation Laboratory, Inc.
Testing Evaluation Laboratory, Inc. | Signed by
Jarrett Wright
Jarrett Wright
Jarrett Wright
Jarrett Wright
Jarrett Wright |
| 2. Drawing No.
No. FL-16185.5 | Prepared by
RW Building Consultants, Inc. (#9813) | Signed & Sealed by
Lyndon F. Schmidt, P.E. | |
| 3. Calculations
Anchoring
ASTM E 1300 Glass Load | Prepared by
RW Building Consultants, Inc. (#9813)
RW Building Consultants, Inc. (#9813) | Signed & Sealed by
Lyndon F. Schmidt, P.E. | |
| 4. Quality Assurance
Certificate of Participation issued by National Accreditation and Management Institute, certifying that Dallas Millwork, Inc is manufacturing products within a quality assurance program that complies with ISO/IEC 17020 and Guide 53. | | | |

Digitally signed by
Lyndon F Schmidt
Date: 2026.07.02
08:52:42 -04'00'

LYNDON F. SCHMIDT, State of Florida, Professional Engineer, License No. 43409
This item has been digitally signed and sealed by L. F. Schmidt on 7-02-26.
Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.
THIS PRODUCT APPROVAL IS VALID ONLY FOR THE STATE OF FLORIDA