



R W Building Consultants, Inc.

Consulting and Engineering Services for the Building Industry

P.O. Box 230 Valrico, FL 33595 Phone 813.659.9197

Florida Board of Professional Engineers Registry License No. 9813

Product Evaluation Report

Report No.: FL-17038.12

Date: September 14, 2023

Product Category	Sub Category	Manufacturer	Product Name
Windows	Double Hung	Millwork Artisans, LLC 145 King Street Charleston, SC 29401 PH 843.577.3348	Arch Double Hung Window w/ Weight and Chain "Impact"

Scope: Product Evaluation report issued by R W Building Consultants, Inc. & Lyndon F. Schmidt, P.E. (System ID # 1998) for Millwork Artisans, LLC, based on Rule Chapter No. 61G20-3, Method 1D of the State of Florida Product Approval, Dept. of Business & Professional Regulation.

RW Building Consultants and Lyndon F. Schmidt, P.E. do not have nor will acquire financial interest in the company manufacturing or distributing the product or in any other entity involved in the approval process of the product named herein.

Limitations:

1. This product has been evaluated and is in compliance with the 8th Edition (2023) Florida Building Code (FBC) structural requirements including the "High Velocity Hurricane Zone" (HVHZ).
2. Product anchors shall be as listed and spaced as shown on details. Anchor embedment to base material shall be beyond wall dressing or stucco.
3. When used in the "HVHZ" this product complies with Section 1626 of the FBC and does not require an impact resistant covering.
4. For 2x stud framing construction, anchoring of these units shall be the same as that shown for 2x buck masonry construction.
5. All window frame wood to be Sapele (Specific Gravity = 0.55).
6. Site conditions that deviate from the details of drawing FL-17038.12 require further engineering analysis by a licensed engineer or registered architect.
7. This product meets water infiltration requirements for "HVHZ".
8. See drawing FL-17038.12 for size and design pressure limitations.

Supporting Documents:

- | | | | |
|---|---|---|--|
| 1. Test Report No.
TEL 01931039
TEL 01931158 | Test Standard
TAS 201, 202 and 203-94
TAS 201, 202 and 203-94 | Testing Laboratory
Testing Evaluation Lab., Inc.
Testing Evaluation Lab., Inc. | Signed by
William Shelton, P.E.
William Shelton, P.E. |
| 2. Miami Dade NOA
23-0717.30
23-0717.20 | Materials Testing
SentryGlas® Interlayer (Kuraray)
Saflex® PVB Interlayer (Eastman Chemical Company) | | |
| 3. Drawing No.
No. FL-17038.12 | Prepared by
RW Building Consultants, Inc. (#9813) | | Signed & Sealed by
Lyndon F. Schmidt, P.E. |
| 4. Calculations
Anchoring
ASTM E1300 Glass Load | Prepared by
RW Building Consultants, Inc. (#9813)
RW Building Consultants, Inc. (#9813) | | Signed & Sealed by
Lyndon F. Schmidt, P.E. |
| 5. Quality Assurance
Certificate of Participation issued by National Accreditation and Management Institute, certifying that Millwork Artisans, LLC is manufacturing products within a quality assurance program that complies with ISO/IEC 17020 and Guide 53. | | | |

Digitally signed by
Lyndon F Schmidt
Date: 2023.09.14
16:36:20 -04'00'

LYNDON F. SCHMIDT, State of Florida, Professional Engineer, License No. 43409
This item has been digitally signed and sealed by L. F. Schmidt on 9-14-23.
Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.
THIS PRODUCT APPROVAL IS VALID ONLY FOR THE STATE OF FLORIDA