

STRUCTURAL SOLUTIONS, P.A.*

Structural Engineering ■ Investigations ■ Consulting

GARAGE DOOR EVALUATION REPORT

Garage Door No.:	IRC-1516-120-15		Test Date:	5/7/2014		Project No.:	14-022			
Design Pressures:	+21.8 psf, -24.8 psf		Report Date:	11/2/2020		Model #	1500			
Test Pressures:	+32.7 psf, -37.2 psf		Test Location:	Entrematic, Winston-Salem, NC						
ASCE 7-16 Criteria:	Up to 5 Feet of Door Width in Zone 5; Any Roof Slope; Enclosed Building									
	Exp. B, 30' MRH		Exp. C, 15' MRH		Exp. C, 25' MRH		Exp. D, 15' MRH		Exp. D, 25' MRH	
	155 mph		141 mph		134 mph		128 mph		122 mph	

Reference Test Report and Drawing:

- Structural Solutions, P.A.* Garage Door Static Pressure Test Report for IRC-1516-120-15 dated 11/02/2020
- Entrematic Drawing number IRC-1516-120-15 dated 5/7/2014

Description of Test Specimen:

16'-0"x7'-0" Model 1500, 27 ga steel garage door as shown in drawing IRC-1516-120-15.

Test Standards and Report Conclusion:

The above referenced Test Report states the following:

- The tests were conducted in accordance with ASTM E330 and DASMA 108.
- The test was witnessed and certified by Thomas L. Shelmerdine, PE (FL PE# 48579)
- The test facility at Entrematic is accredited by the American Association for Laboratory Accreditation, Certificate #2595.01.


Summary:

The 16'-0"x7'-0" Model 1500 as described on drawing IRC-1516-120-15 meets or exceeds the testing criteria as described above. By comparison to the construction of the 16'-0"x7'-0" Model 1500, the following doors also meet or exceed the above testing criteria, when constructed in accordance with drawing IRC-1516-120-15:

- 16' x 7' Model 1200 doors (which are constructed of thicker 24 gauge exterior steel in lieu of 27 gauge steel)
- 16' x 7' Model 1550 doors (which have alternate embossment patterns in the skin)
- Model 1500, 1200 and 1550 doors with widths up to 16'-0" and heights up to 14'-0"
- Heritage 3000, Stratford 3000, and Oak Summit 3000 doors (which are Models 1200, 1500 and 1550 respectively)
- Short, Long, Flush, and Oak Summit Panels, which are alternate embossment patterns in the skin
- 8 short panel (18-1/8" x 10-5/8") or 4 long panel (38-1/8" x 10-5/8") windows (3/32" annealed glass minimum - meets ASTM E1300-04) may be installed in 1 section

To the best of my knowledge, the above garage door conforms to the requirements of the Florida Building Code 7th Edition (2020).

Submitted By:



STRUCTURAL SOLUTIONS, P.A.* (*Florida: dba Structural Solutions of North Carolina, Inc., Firm #29412)

Thomas L. Shelmerdine, PE (NC PE #14654; Florida PE #0048579)

5921-G West Friendly Avenue ■ Greensboro, North Carolina 27410 ■ (336) 856-2686 ■ www.sspa.biz ■ NC Firm #C-1096