

Evaluation Report 1073C
September 16, 2026

Product Description: Series 6150 PVC Picture Window, Large Missile Impact Wind Zone 3, with Design Pressure +/-50 psf

Manufacturer: Custom Window Systems, Inc. 1900 SW 44th Ave, Ocala, FL 34474

Statement of Compliance: This report evaluates the above-listed product per the requirements of FAC Product Approval Rule Chapter 61G20-3.005 (4). This product complies with the requirements of the 9th Edition (2026) Florida Building Code, not including the High Velocity Hurricane Zone or Wind Zone 4. The product testing standards performed are outlined below.

Technical Documentation:

- 1) This report, prepared by Lucas A. Turner, PE, at 2428 Old Natchez Trc Trl, Camden, TN
- 2) Approval drawing CWS-1073C, signed and sealed by Lucas A. Turner, P.E.
- 3) Test Reports NCTL-210-3988-01/02/03/04/05/06 and NCTL-210-3976-03/04, by National Certified Testing Laboratories, Orlando, FL, with testing performed with equivalency to: ASTM E 1886-13a/19, ASTM E 1996-17/20 (large missile impacts in accordance with Wind Zone 3), and AAMA/WDMA/CSA 101/I.S.2/A440-11/17
- 4) Supplemental Calculations to support CWS-1073C, signed and sealed by Lucas A. Turner, P.E.


Installation: Units must be installed according to approval document CWS-1073C.

Limitations of Use: This product:

- May be used up to the sizes and daylight openings with glazing and design pressures as indicated in CWS-1073C
- Is Large Missile impact resistant and does not require the use of shutters
- May not be used in the High Velocity Hurricane Zone or Wind Zone 4 areas
- Requires Kuraray Butacite PVB Interlayer, 0.090" thick in 36"x76" unit size and 0.105" thick in 48"x76" size. Requires 0.090" Kuraray SentryGlas Interlayer in unit sizes 68"x76" and 54"x96". Width and height may be transposed.
- Requires ATN PVC frames with current listing as AAMA 303 Certified Profile Licensee

Coastal Compliance:

- Fastener criteria other than described below shall be in accordance with CWS-1073C.
- Fasteners used in locations less than or equal to 300 ft from a saltwater coastline, where



Lucas Turner
2026.09.16
17:02:14 -05'00'

9/16/2026
Lucas A. Turner, P.E.
FL PE #58201

any portion of the fastener is located to the exterior of the Water-Resistive Barrier (WRB) of the wall construction, or is a Weather-Exposed Surface, or as otherwise required by the Authority Having Jurisdiction (AHJ), shall meet the criteria of FBC Sect. 1711.1.1.1 or RBC Section R332.1.1.1 as applicable.

- For wood and metal installation substrates, requires stainless steel, 100 ksi min. ult. (cold worked).
- For concrete/masonry substrates requires 1/4" Simpson Strong-Tie Type 316 Stainless-Steel Titen Turbo or 1/4" Dewalt Aggre-Gator 300 Series SS fasteners.
 - In solid concrete, 2.67 ksi min., requires 1-1/2" min. embedment and 1-1/2" min. edge distance.
 - In hollow or grout-filled CMU applications, ASTM C-90. requires 1-1/4" min. embedment and 2" min. edge distance.
- Fasteners used in locations less than or equal to 300 ft from a saltwater coastline, where the entire fastener is located to the interior of the WRB of the wall construction, or determined by the Registered Design Professional or AHJ for the project to be located within the Unconditioned Interior of the wall construction, or as otherwise required by the AHJ, shall meet the criteria of FBC Sect. 1711.1.1.2 or RBC Section R332.1.1.2 as applicable^{††}.
- Fasteners used in locations greater than 300 ft and up to 3000 ft from a saltwater coastline, in any Exterior/Interior location of the wall construction, or as otherwise required by the AHJ, shall meet the criteria of FBC Sect. 1711.1.1.2 or RBC Section R332.1.1.2 as applicable^{††}

^{††} ITW Tapcon and Dewalt Ultracon+ carbon steel fasteners as listed in Table 1 meet these criteria with coatings provided by the manufacturer. Kwik-Cote on Hilti Kwik-Flex and Climaseal on ITW TEKS fasteners also meet these corrosion resistance criteria. Other fasteners must be galvanized or otherwise coated in accordance with one of the standards provided in FBC Sect. 1711.1.1.2 or RBC Sect. R332.1.1.2.

Certification of Independence: I do not have, nor do I intend to acquire, nor will I acquire, a financial interest in Custom Window Systems or in any company manufacturing or distributing products for which this report is being issued. I do not have, nor do I intend to acquire, nor will I acquire, a financial interest in any other entity involved in the testing or approval process of this product.

