



EVALUATION REPORT

FLORIDA BUILDING CODE, 9TH EDITION (2026)

Manufacturer: ARCHITECTURAL METAL FLASHINGS, LLC *Issued October 16, 2026*
2659 NE 9th Avenue
Cape Coral, FL 33909
(239) 980-0730

Manufacturing Plant: Cape Coral, FL

Quality Assurance: PRI Construction Materials Technologies
(QUA9110)

SCOPE

Category: Roofing
Subcategory: Roofing Accessories that are an Integral Part of the Roofing System
Code Edition: Florida Building Code, 9th Edition (2026) Non-HVHZ
Code Sections: 1503.5
Properties: Roof Ventilation

REFERENCES

<u>Entity</u>	<u>Report No.</u>	<u>Standard</u>	<u>Year</u>
PRI Construction Materials Technologies (TST5878)	1897T0008	ASTM E 330	2014(2021)

LIMITATIONS


1. This report is not for use inside the HVHZ.
2. Fire Classification is outside the scope of this evaluation.
3. The roof deck and deck attachment shall be designed by others in accordance with the FBC.
4. Vents shall be installed in strict compliance with this evaluation report and the manufacturer's published installation instructions. In the event of conflict, the more restrictive installation shall be enforced.
5. Deck substrates shall be clean, dry, and free from any irregularities and debris. All fasteners in the deck shall be checked for protrusion prior to installation.
6. All materials shall conform to FBC Section 1506.
7. Installation of the roof assembly is outside the scope of this evaluation.
8. Vents are intended to provide passive ventilation for an enclosed attic in residential construction applications.
9. Materials shall conform to FBC Sections 1506 and 1711.
10. All products listed in this report shall be manufactured under a quality assurance program in compliance with Rule 61G20-3.




PRODUCT DESCRIPTION AND APPLICATION

Tile Off-Ridge Vent


Minimum 0.032-inch 3003-H14 aluminum (min. 22 ksi YS) off-ridge static roof ventilator. Material shall conform with FBC Section 1507.4.3.



Side View



Front View




Vent Opening

Deck Type: Minimum 15/32-inch APA span rated plywood sheathing for new and existing roof deck.
(Deck shall be designed by others in accordance with FBC requirements)

Roof slope: Minimum 4:12

Attachment Method: Cut a 46" x 3-1/2" slot according to manufacturer's instructions through the deck and sheathing. For a single vent, install the vent as close to the center of the roof length as possible. Multiple vents should be evenly spaced along the roof length.


The vent shall be attached with minimum 12 ga. galvanized, ring shank roofing nails with minimum 3/8-inch diameter head and sufficient length to penetrate through the sheathing a minimum 3/8-inch. Nails shall be installed 4-inch o.c. in a staggered pattern along all four sides of the vent flange.



Limitations: -60 psf maximum design pressure

COMPLIANCE STATEMENT

This report has been prepared in accordance with F.A.C. Rule 61G20-3.



This item has been
digitally signed and
sealed by Zachary R.
Priest, PE, on 10/16/2026.

Printed copies of this
document are not
considered signed and
sealed and the signature
must be verified on any
electronic copies.


2026.10.16
14:01:52
-04'00'

Zachary R. Priest, P.E.
Florida Registration No. 74021
Organization No. ANE9641

CERTIFICATION OF INDEPENDENCE

CREEK Technical Services, LLC does not have, nor will it acquire, a financial interest in any company manufacturing or distributing products under this evaluation.

CREEK Technical Services, LLC is not owned, operated, or controlled by any company manufacturing or distributing products under this evaluation.

Zachary R. Priest, P.E. does not have, nor will acquire, a financial interest in any company manufacturing or distributing products under this evaluation.

Zachary R. Priest, P.E. does not have, nor will acquire, a financial interest in any other entity involved in the approval process of the product.

END OF REPORT