



NEMO EVALUATIONS REPORT

Report No.: NER-CTR-001.R1
Revision 1: 2025-04-17
Page 1 of 80

CertainTeed, LLC
FL2533-R33

Nemo|cert.

353 Christian Street, Unit 12b
Oxford, CT 06478
(475) 888-CERT (2378)
www.nemocert.com

INSPECT

CERTIFY

EVALUATE

VALIDATE

QUALIFY

NEMO EVALUATION REPORT (NER)



[CertainTeed, LLC](#)
20 Moores Road
Malvern, PA 19355
(610) 893-5400

SUBJECT: Flintlastic® Modified Bitumen Roof Systems

SCOPE: This NEMO Evaluation Report (henceforth 'NER') is issued under F.A.C. [Rule 61G20-3](#) and the applicable rules and regulations governing Product Approval of construction materials in the State of Florida and ISO/IEC 17065 via [NEMO|cert.](#) NEMO Evaluations has evaluated the product described herein for compliance with the [Code sections noted herein](#).

CODES: 2018 International Building Code TDI [Third-Party Evaluation Report](#) acceptance
2018 International Residential Code
2021 International Building Code
2021 International Residential Code
2023 Florida Building Code, 8th Edition
2023 Florida Building Code, Residential, 8th Edition

JURISDICTION: Non-HVHZ and HVHZ

CATEGORY: **FBC:** Roofing **NEMO:** Modified Bitumen

SUB-CATEGORY: **FBC:** Modified Bitumen Roof Systems

CSI DIVISION: 07 00 00 Thermal and Moisture Protection
07 52 00 Modified Bituminous Sheet Roofing

FBC METHOD: Method 1, Option C – Codified Material, Evaluation by Evaluation Entity

COMPLIANCE STATEMENT: Flintlastic® Modified Bitumen Roof Systems, as produced by CertainTeed, LLC, have demonstrated compliance with the [Code sections noted herein](#) through testing in accordance with the referenced Standards, rational analysis and an ongoing quality assurance program. Compliance is subject to the [Installation Requirements](#) and [Limitations of Use](#) set forth herein.

QUALITY ASSURANCE: Evidence of current quality assurance shall be listing and labeling in accordance with the requirements of [NEMO|cert.](#)

CONTINUED COMPLIANCE: This NER is valid until such time the named product(s) change, the referenced Quality Assurance changes, or the evaluated Code provisions change. NEMO Evaluations requires, at minimum, a complete review of this NER with each 3-year Code Cycle.

BUILDING PERMIT REQUIREMENTS: As required by the Building Official or Authority Having Jurisdiction to evaluate the installation of this product.

ADVERTISEMENT: "NEMO Evaluated" may be displayed in advertising literature. If any portion of the NER is displayed, it shall be displayed in its entirety.

CERTIFICATION OF INDEPENDENCE: ✓ NEMO CERT, LLC has not, nor does it intend to acquire or will it acquire, a financial interest in any company manufacturing or distributing products it evaluates.
✓ NEMO CERT, LLC is not owned, operated or controlled by any company manufacturing or distributing products it evaluates.
✓ This is a building code evaluation. NEMO CERT, LLC is not, in any way, the Designer of Record for any project on which this NER, or previous versions thereof, is/was used for permitting or design guidance.

NEMO CERT, LLC
www.nemocert.com

©NEMO. All rights reserved.

[LINK TO TOP OF ATTACHMENT REQUIREMENTS](#)



ISO/IEC 17065



ACCREDITED
Product Certification
Agency
PCA-145



ISO/IEC 17020



ACCREDITED
Inspection Agency
AA-779



NEMO EVALUATIONS REPORT

Report No.: NER-CTR-001.R1
Revision 1: 2025-04-17
Page 2 of 80

CertainTeed, LLC
FL2533-R33



1. CODES, PROPERTIES AND STANDARDS:

<u>CODE</u>	<u>SECTION</u>	<u>PROPERTY</u>	<u>STANDARD</u>
2018 International Building Code	1504.3.1	Wind resistance	FM 4474 or UL1897
	1504.6	Physical properties	ASTM G155
	1504.7	Impact resistance	FM 4470
	1505.1	Fire classification	UL 790
	1507.10.2, 1507.11.2.1	Material standard	ASTM D2178, D4601, D4897
	1507.11.2	Material standard	ASTM D6163, D6164
2018 International Residential Code	R902.1	Fire classification	UL 790
	R905.9.2, R905.11.2.1	Material standard	ASTM D2178, D4601, D4897
	R905.11.2	Material standard	ASTM D6163, D6164
2021 International Building Code	1504.4.1	Wind resistance	FM 4474 or UL1897
	1504.7	Physical properties	ASTM G155
	1504.8	Impact resistance	FM 4470
	1505.1	Fire classification	UL 790
	1507.10.2, 1507.11.2.1	Material standard	ASTM D2178, D4601, D4897
	1507.11.2	Material standard	ASTM D6163, D6164
2021 International Residential Code	R902.1	Fire classification	UL 790
	R905.9.2, R905.11.2.1	Material standard	ASTM D2178, D4601, D4897
	R905.11.2	Material standard	ASTM D6163, D6164
2023 Florida Building Code, 8 th Edition	1504.3.1	Wind resistance	FM 4474 or UL1897
	1504.6	Physical properties	ASTM G155
	1504.7	Impact resistance	FM 4470
	1505.1, 1516.1	Fire Classification	UL 790
	1507.10.2, TAS 110	Material Standard	ASTM D2178, D4601, D4897
	1507.11.2, TAS 110	Material standard	ASTM D6163, D6164
	TAS 110	Resistance to Foot Traffic	TAS 114, Section 8.9
	TAS 110	Wind resistance	TAS 114, Appendix C, D or J
	TAS 110	Susceptibility to Hail Damage	TAS 114, Appendix F
2023 Florida Building Code, Residential, 8 th Edition	R902.1	Fire Classification	UL 790
	R905.9.2	Material standard	ASTM D2178, D4601, D4897
	R905.11.2	Material standard	ASTM D6163, D6164



NEMO EVALUATIONS REPORT

Report No.: NER-CTR-001.R1
Revision 1: 2025-04-17
Page 3 of 80

CertainTeed, LLC
FL2533-R33



2. PRODUCTS:

TABLE 1A: EVALUATED CERTAINTIED COMPONENTS (NEMO Certified. Consult Directory of Certified Products for production location(s))				
TYPE	PRODUCT	MATERIAL STANDARD		
	NAME	REFERENCE	TYPE	GRADE
BASE SHEETS	Flintlastic® SA NailBase	ASTM D4601	II	N/A
	Glasbase™ Base Sheet	ASTM D4601	II	N/A
	All Weather/Empire™ Base Sheet	ASTM D4601	II	N/A
	Flintlastic® Base 20	ASTM D4601	II	N/A
	Flintlastic® Poly SMS Base Sheet	ASTM D4601 (except glass mat is N/A)	II	N/A
	Flintglas® MS Cap (inverted)	ASTM D4897	II	N/A
PLY SHEETS	Flintglas® Ply 4	ASTM D2178	IV	N/A
BASE PLY OR PLY MEMBRANES (APP)	Flintlastic® APP Base T	ASTM D6509	N/A	N/A
	Flintlastic® STA	ASTM D6222	I	S
CAP PLY MEMBRANES (APP)	Flintlastic® STA	ASTM D6222	I	S
	Flintlastic® GTA	ASTM D6222	I	G
	Flintlastic® GTA CoolStar®	ASTM D6222	I	G
	Flintlastic® GTA CoolStar® Ultra	ASTM D6222	I	G
	Flintlastic® GTA-FR	ASTM D6222	I	G
	Flintlastic® GTA-FR CoolStar®	ASTM D6222	I	G
BASE PLY OR PLY MEMBRANES (SBS)	Black Diamond® Base Sheet	ASTM D1970	N/A	N/A
	Flintlastic® SA PlyBase	ASTM D1970	N/A	N/A
	Flintlastic® SA MidPly	ASTM D6163	I	S
	Flintlastic® Ultra Glass SA	ASTM D6163	I	S
	Flintlastic® Base 20	ASTM D6163	I	S
	Flintlastic® Base 20 T	ASTM D6163	I	S
CAP MEMBRANES (SBS)	Flintlastic® SA Cap FR	ASTM D6163	I	G
	Flintlastic® SA Cap	ASTM D6164	I	G
	Flintlastic® FR-P	ASTM D6164	I	G
	Flintlastic® GMS	ASTM D6164	I	G

TABLE 1B: EVALUATED CERTAINTIED COMPONENTS (Contact contact@nemocert.com for production location(s) of non-Certified products)				
TYPE	PRODUCT	MATERIAL STANDARD		
	NAME	REFERENCE	TYPE	GRADE
BASE PLY OR PLY MEMBRANES (SBS)	Flintlastic® Ultra Poly SMS Base Sheet	ASTM D6164	I	S
CAP MEMBRANES (SBS)	Flintlastic® SA Cap FR CoolStar®	ASTM D6163	I	G
	Flintlastic® SA Cap CoolStar®	ASTM D6164	I	G
	Flintlastic® FR-P CoolStar®	ASTM D6164	I	G
	Flintlastic® GTS-FR	ASTM D6164	II	G
	Flintlastic® GTS-FR CoolStar®	ASTM D6164	II	G
	Flintlastic® Premium FR-P	ASTM D6164	II	G
	Flintlastic® Premium FR-P CoolStar®	ASTM D6164	II	G



NEMO EVALUATIONS REPORT

Report No.: NER-CTR-001.R1
Revision 1: 2025-04-17
Page 4 of 80

CertainTeed, LLC
FL2533-R33



TABLE 2: COMPONENTS BY OTHERS (4.1.3) (Refer to NOA if listed version was superseded to ensure use of latest version)				
TYPE	CERTAINTEED	ACCEPTABLE ALTERNATE	FBC	NOA
ADHESIVES:	FlintBond® Brush	Tropical #216 AF Modified Bitumen Adhesive	FL39113	21-0511.12
	N/A	Millennium One Step Foamable Adhesive	FL1800	21-1018.06
	N/A	Millennium PG-1 Pump Grade Adhesive	FL1800	21-1018.06
	N/A	Millennium PG-1 EF ECO	FL1800	21-1018.06
	N/A	Millennium Hurricane Force Membrane Adhesive HS	N/A	21-1018.06
	N/A	Millennium Hurricane Force Lap and Flashing Adhesive	N/A	N/A
	N/A	Polyset Board-Max	FL22256	22-0614.11
	N/A	Polyset Commercial Roofing Adhesive	FL1365	21-1115.05
	N/A	OlyBond 500 Adhesive Fastener	FL1608	22-0519.04
	N/A	Karnak 81AF Modified Bitumen Adhesive (Brush Grade)	FL1026	21-0706.03
	N/A	Henry 903 Modified Bitumen Membrane Adhesive	N/A	N/A
INSULATIONS:	N/A	Multi-Max FA3	FL11207	22-0815.03
	N/A	Ultra-Max	FL11207	22-0815.03
	FlintBoard _H ISO	H-Shield	FL5968	19-0521.04
	FlintBoard _H ISO Cold	H-Shield CG	FL5968	19-0521.04
	N/A	H-Shield HD	FL5968	19-0521.04
	N/A	H-Shield HD Composite CG	FL5968	19-0521.04
	N/A	ENRGY 3	FL4205	23-0509.05
	N/A	FescoBoard	FL4205	23-0509.05
	FlintBoard ISO	ACFoam II	FL17989	24-0215.03
	FlintBoard ISO Cold	ACFoam III	FL17989	24-0215.03
	N/A	ACFoam-HD CoverBoard	FL17989	24-0215.03
	N/A	DensDeck	FL1250	22-1223.04
	N/A	DensDeck Prime	FL1250	22-1223.04
	N/A	SECUROCK Gypsum-Fiber Roof Board	FL4264	21-0923.05
	N/A	Structodek High Density Fiberboard Roof Insulation	FL39113	23-0623.03
	N/A	STURDY-DEK Asphaltic Cover Board	N/A	23-0623.03
	N/A	Insulfoam II and IX	FL29563	22-0628.10
	N/A	Styrofoam Brand Roofmate	FL38732	23-1121.01
	N/A	Celcore Cellular Concrete	FL2037	23-0718.06
	N/A	Concrecel Lightweight Insulating Concrete	FL5584	21-1229.06
	N/A	Elastizell Lightweight Insulating Concrete	N/A	23-0817.05
	N/A	Mearlcrete	FL13492	19-0729.03



NEMO EVALUATIONS REPORT

Report No.: NER-CTR-001.R1
Revision 1: 2025-04-17
Page 5 of 80

CertainTeed, LLC
FL2533-R33



TABLE 2: COMPONENTS BY OTHERS (4.1.3) (Refer to NOA if listed version was superseded to ensure use of latest version)				
TYPE	CERTAINTEED	ACCEPTABLE ALTERNATE	FBC	NOA
MECHANICAL FASTENERS:	FlintFast #12 Fastener	Trufast #12 DP	FL4500	24-0227.06
	FlintFast #14 Fastener	Trufast #14 HD	FL4500	24-0227.06
	FlintFast #15 EHD Fastener	Trufast #15 EHD	FL4500	24-0227.06
	FlintFast 2" Barbed Metal Seam Plate	Trufast 2" Barbed Metal Seam Plate	FL4500	24-0227.06
	FlintFast 2.4" Barbed Metal Seam Plate	Trufast 2.4" Barbed Metal Seam Plate	FL4500	24-0227.06
	FlintFast 3" Insulation Plate	Trufast 3" Metal Insulation Plate	FL4500	24-0227.06
	N/A	Trufast FM-75 Base Sheet Fastener	FL4500	24-0227.06
	N/A	Trufast FM-90 Base Sheet Fastener	FL4500	24-0227.06
	N/A	Trufast Twin Loc-Nail Assembled Fastener	FL4500	24-0227.06
	N/A	Trufast Versa Fastener	FL4500	24-0227.06
	N/A	Trufast Versa Plate	FL4500	24-0227.06
	N/A	OMG #12 Standard Roofgrip	FL699	23-0718.03
	N/A	OMG #14 Heavy Duty	FL699	23-0718.03
	N/A	OMG 3 in. Galvalume Steel Plate	FL699	23-0718.03
	N/A	OMG AccuTrac Plate	FL699	23-0718.03
	N/A	OMG AccuTrac Flat Bottom	FL699	23-0718.03
	N/A	OMG Polymer GypTec Fastener	FL699	23-0718.03
	N/A	OMG 3" GypTec Plate	FL699	23-0718.03
	N/A	Dekfast DF-#14-PH3	FL20311	22-0913.02
	N/A	Dekfast PLT-H-2-7/8	FL20311	22-0913.02
	N/A	Dekfast PLT-R-3	FL20311	22-0913.02
PRIMERS:	FlintPrime QD	N/A	FL39113	21-0511.12

3. INSTALLATION:

3.1 **Flintlastic® Modified Bitumen Roof Systems** shall be installed in accordance with **CertainTeed, LLC** published installation instructions, subject to the [Limitations of Use](#) noted herein.

3.1.1 **Fasteners:** Unless otherwise noted, fasteners and stress plates shall be as follows. Recessed plates are not for use with hardboard (e.g., gypsum-based or cement) insulations. Fasteners shall be of sufficient length for the following engagements.

TABLE 3: FASTENER REFERENCES		
ROOF DECK	PARTS	FASTENER ENGAGEMENT
WOOD, ENGINEERED SHEATHING OR PLANK	Trufast #14 HD with Trufast 3" Metal Insulation Plate	Min. 0.75-inch penetration (engineered sheathing) or min. 1-inch embedment (plank)
	OMG #12 Standard Roofgrip with AccuTrac Plate or OMG #14 Heavy Duty with OMG 3 in. Galvalume Steel Plate	
	Dekfast DF-#14-PH3 with Dekfast PLT-H-2-7/8 or Dekfast PLT-R-3	
STEEL	Trufast #12 DP or Trufast #14 HD with Trufast 3" Metal Insulation Plate	Min. 0.75-inch penetration
	OMG #12 Standard Roofgrip or OMG #14 Heavy Duty with AccuTrac Plate or OMG 3 in. Galvalume Steel Plate	
	Dekfast DF-#12-PH3 or Dekfast DF-#14-PH3 with Dekfast PLT-H-2-7/8 or Dekfast PLT-R-3.	
STRUCTURAL CONCRETE	Trufast #14 HD or Trufast ¾" Concrete Spike with Trufast 3" Metal Insulation Plate	Non-HVHZ: Min. 1-inch embedment HVHZ: Min. 1.25-inch embedment
	OMG #12 Standard Roofgrip with AccuTrac Plate or OMG #14 Heavy Duty or CD-10 with OMG 3 in. Galvalume Steel Plate	
	Dekfast DF-#14-PH3 with Dekfast PLT-H-2-7/8 or Dekfast PLT-R-3.	



NEMO EVALUATIONS REPORT

Report No.: NER-CTR-001.R1
Revision 1: 2025-04-17
Page 6 of 80

CertainTeed, LLC
FL2533-R33



3.1.2 Insulation:

- (a) Unless otherwise noted, insulation may be any one layer or combination of Approved board(s) that meet IBC 1505, IRC R902, FBC 1505, FBC R902 or FBC HVHZ 1516 and, for foam plastic, IBC/FBC Chapter 26, when installed with the roof cover.
- (b) For Structural Concrete Deck or Recover Applications using System Type C-1 the base insulation layer is optional, and using System Type C-2, D-1 or D-2, the insulation is optional. Alternatively, an Approved insulation board or coverboard may be used as a separation layer. Board products shall be preliminarily attached prior to roof cover installation. The separator component shall be documented as meeting IBC 1505, IRC R902, FBC 1505, FBC R902 or FBC HVHZ 1516 and, for foam plastic, IBC/FBC Chapter 26, when installed with the roof cover in Recover applications.
- (c) Minimum 200 psi, minimum 2-inch thick Approved lightweight insulating concrete may be substituted for, or installed below, rigid insulation board for System Types B-1, C-1, C-2, D-1 or D-2, whereby fasteners are installed through the lightweight insulating concrete to engage the structural deck. The structural deck shall be of equal or greater type, thickness and strength to the steel and structural concrete deck listings. Roof decks and structural members shall be in accordance with applicable Code requirements to the satisfaction of the Authority Having Jurisdiction. This is a wind uplift resistance allowance and does not purport to address non-wind-uplift-related issues, such as deck venting or moisture levels within the LWIC and the potential effect on overlying components.
- (d) Florida Specific: Lightweight insulating concrete (LWIC) shall be cast in accordance with FBC 1917 to the satisfaction of the Authority Having Jurisdiction. For systems where specific LWIC is referenced, refer to current LWIC [Florida Product Approval](#) or [NOA](#) for specific deck construction and limitations. Unless otherwise noted, for systems where specific LWIC is not referenced, the minimum design mix shall be 300 psi. In all cases, the minimum top-coat thickness is 2-inches. For LWIC over structural concrete, reference is made to FBC 1917.4.1, Point 1. For “pre-existent” LWIC references, listings were established through testing over lightweight concrete cast using only foaming agent (ASTM C896), water and Portland cement (ASTM C150), with no proprietary additives, in accordance with procedures adopted by Miami-Dade BCCO (FBC CER1592). Use of these listings in new construction or re-roof (tear-off) applications is at the discretion of the Designer or Record and Authority Having Jurisdiction.
- (e) Unless otherwise noted, rigid board insulation or coverboard attachment patterns for Type B-1, B-2 and C-1 systems are as outlined below.

TABLE 4A: INSULATION ATTACHMENT PATTERNS – 4x4 FT BOARDS

1 per 4.0 ft ² (4 per board)	1 per 3.2 ft ² (5 per board)	1 per 2.7 ft ² (6 per board)



NEMO EVALUATIONS REPORT

Report No.: NER-CTR-001.R1
Revision 1: 2025-04-17
Page 7 of 80

CertainTeed, LLC
FL2533-R33



TABLE 4A: INSULATION ATTACHMENT PATTERNS – 4x4 FT BOARDS

1 per 2.0 ft ² (8 per board)	1 per 1.8 ft ² (9 per board)	1 per 1.6 ft ² (10 per board)
1 per 1.45 ft ² (11 per board)	1 per 1.3 ft ² (12 per board)	1 per 1.0 ft ² (16 per board)

TABLE 4B: INSULATION ATTACHMENT PATTERNS – 4x8 FT BOARDS

1 per 4.0 ft ² (8 per board)	1 per 3.2 ft ² (10 per board)	1 per 2.7 ft ² (12 per board)



NEMO EVALUATIONS REPORT

Report No.: NER-CTR-001.R1
Revision 1: 2025-04-17
Page 8 of 80

CertainTeed, LLC
FL2533-R33



TABLE 4B: INSULATION ATTACHMENT PATTERNS – 4x8 FT BOARDS

1 per 2.0 ft ² (16 per board)	1 per 1.8 ft ² (18 per board)	1 per 1.6 ft ² (20 per board)
1 per 1.45 ft ² (22 per board)	1 per 1.3 ft ² (24 per board)	1 per 1.0 ft ² (32 per board)

(f) Preliminary insulation attachment for Type D-1 or D-2 systems:

- IBC or FBC Non-HVHZ: Unless otherwise noted, use Approved roofing fasteners and plates and refer to Section 2.2.10.1.3 of [FM Loss Prevention Data Sheet 1-29](#).
- FBC HVHZ: Unless otherwise noted, use FBC HVHZ Approved roofing fasteners and plates; minimum four fasteners per 4 x 8 ft board or minimum two fasteners per 4 x 4 ft board.

(g) The following products are interchangeable within the scope of this NER:

TABLE 5: ACCEPTABLE ALTERNATES		
TYPE	LISTED PRODUCT	ALTERNATE PRODUCT
INSULATIONS:	DensDeck Prime	DensDeck StormX Prime Roof Board



NEMO EVALUATIONS REPORT

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 9 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065



ACCREDITED
Product Certification
Agency
PCA-145

3.1.3 Insulation Adhesives:

- (a) Unless otherwise noted, insulation adhesive application rate is continuous ribbons, maximum 12-inch o.c. Ribbons shall be applied and insulation boards shall be set in accordance with the manufacturer's published instructions. When multiple layers(s) of insulation and/or coverboard are installed in ribbon-applied adhesive, boards shall be staggered from layer-to-layer. The maximum edge distance from the adhesive ribbon to the edge of the insulation board shall be not less than one-half the specified ribbons spacing. Concrete deck shall be primed with ASTM D41 primer prior to asphalt-application.

TABLE 6A: INSULATION ADHESIVE REFERENCES			
ADHESIVE	REFERENCE	MINIMUM RATE	NOTE
Millennium One Step Foamable Adhesive	M-OSFA	Continuous 0.25 to 0.5-inch wide ribbons, 12-inch o.c.	
Millennium PG-1 Pump Grade Adhesive	M-PG-1	Continuous 0.5 to 0.75-inch wide ribbons, 12-inch o.c.	
Millennium PG-1 EF ECO	M-PG1-EF-ECO	Continuous 1 to 1.5-inch wide ribbons, 12-inch o.c.	
Polyset Board-Max	Polyset BM	Continuous 3-inch wide ribbons, 12-inch o.c.	
Polyset Commercial Roofing Adhesive	Polyset CRA	Continuous 2.5 to 3-inch wide ribbons, 12-inch o.c.	Formerly Polyset CR-20
Olybond 500 Adhesive Fastener	OB500	Continuous 0.75-inch wide ribbons, 12-inch o.c.	PaceCart, SpotShot, or Canister dispensing
ASTM D312, Type IV hot asphalt	N/A	Full coverage at 25-30 lbs/square	If applying hot asphalt to concrete deck, deck shall be primed with ASTM D41 primer

- (b) Unless otherwise noted, all adhered insulations are flat-stock or taper board of the minimum thickness noted. Tapered polyisocyanurate at the following thickness limitations may be substituted with the following Maximum Design Pressure (MDP) limitations. In no case shall these values be used to 'increase' the MDP listings in the tables; rather if MDP listing below meets or exceeds that listed for a particular system in the tables, then the thinner board listed below may be used as a drop-in for the equivalent thicker material listed in the selected assembly.

TABLE 6B: MDP LIMITATIONS FOR TAPERED POLYISOCYANURATE INSULATIONS			
ADHESIVE	INSULATION	MIN. TAPERED THICKNESS (IN)	MDP (psf)
M-OSFA	Any polyisocyanurate listed with adhesive herein	1.0	-157.5
M-PG-1	Any polyisocyanurate listed with adhesive herein	1.0	-157.5
Polyset CRA	Any polyisocyanurate listed with adhesive herein	1.0	-117.5
OB500	Multi-Max FA3	0.5	-45.0
OB500	H-Shield	0.5	-315.0
OB500	ENRGY 3	0.5	-315.0
OB500	ACFoam II	0.5	-487.5

- (c) Adhered Insulation, Board Size:

- IBC and FBC non-HVHZ: Unless otherwise noted, refer to Section 2.2.10.6.2 of [FM Loss Prevention Data Sheet 1-29](#).
- FBC HVHZ: Bonded polyisocyanurate insulation boards shall be maximum 4 x 4 ft.



NEMO EVALUATIONS REPORT

Report No.: NER-CTR-001.R1
Revision 1: 2025-04-17
Page 10 of 80

CertainTeed, LLC
FL2533-R33



3.1.4 Roof Covers:

(a) For bonded membrane applications, unless otherwise noted, refer to the following.

TABLE 7: MEMBRANE / ADHESIVE COMBINATIONS			
REFERENCE	LAYER	MATERIAL	APPLICATION
SBS-CA1	Base Ply:	Flintlastic Base 20, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base	Karnak 81AF Modified Bitumen Adhesive (Brush Grade), 1 gal/square
	Ply:	Flintlastic Base 20, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base	
	Cap Ply:	Flintlastic FR-P, Flintlastic FR-P CoolStar, Flintlastic Premium FR-P, Flintlastic Premium FR-P CoolStar, Flintlastic GMS	
	Note: Base ply cures overnight prior to application of the Ply or Cap Ply when using Karnak 81AF.		
BP-CA2	Base Ply:	Glasbase Base Sheet, All Weather/Empire Base Sheet, Flintlastic Base 20	Henry 903 Modified Bitumen Membrane Adhesive, 1.5 gal/square
SBS-CA2	Base Ply:	Flintlastic Base 20, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base	
	Ply:	Flintlastic Base 20, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base	
	Cap Ply:	Flintlastic FR-P, Flintlastic FR-P CoolStar, Flintlastic Premium FR-P, Flintlastic Premium FR-P CoolStar, Flintlastic GMS	
BP-CA3	Base Ply:	Glasbase Base Sheet, All Weather/Empire Base Sheet, Flintlastic Base 20	Millennium Hurricane Force Membrane Adhesive HS, beads spaced 6-inch o.c.
SBS-CA3	Base Ply:	Flintlastic Base 20, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base	
	Ply:	Flintlastic Base 20, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base	
	Cap Ply:	Flintlastic FR-P, Flintlastic FR-P CoolStar, Flintlastic Premium FR-P, Flintlastic Premium FR-P CoolStar, Flintlastic GMS	
SBS-CA4	Base Ply:	Flintlastic Base 20, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base	FlintBond Brush or Tropical #216 AF Modified Bitumen Adhesive, 1 to 1.5 gal/square
	Ply:	Flintlastic Base 20, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base	
	Cap Ply:	Flintlastic FR-P, Flintlastic FR-P CoolStar, Flintlastic Premium FR-P, Flintlastic Premium FR-P CoolStar, Flintlastic GMS	
	Note: Base ply cures overnight prior to application of the Ply or Cap Ply when using FlintBond Brush.		
BP-AA	Base Ply:	Glasbase Base Sheet, All Weather/Empire Base Sheet, Flintlastic Base 20	Hot asphalt, 20-40 lbs/square
	Ply:	One or more Flintglas Ply 4	
BP-AA2	Base Ply:	Flintglas MS Cap (inverted)	Hot asphalt, 24-inch diameter spots in 30-inch grid pattern
BP-AA3	Base Ply:	Flintglas MS Cap (inverted)	Hot asphalt, 9-inch diameter spots in grid pattern as noted
BP-AA4	Base Ply:	Flintglas MS Cap (inverted)	Hot asphalt, 9-inch wide ribbons spaced as noted
SBS-AA	Base Ply:	Flintlastic Base 20, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base	Hot asphalt, 20-40 lbs/square
	Ply:	One or more Flintlastic Base 20, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base	
	Cap Ply:	Flintlastic FR-P, Flintlastic FR-P CoolStar, Flintlastic Premium FR-P, Flintlastic Premium FR-P CoolStar, Flintlastic GMS	
SBS-TA	Base Ply:	Flintlastic Ultra Poly SMS Base Sheet, Flintlastic Base 20 T	Torch-applied, Full Bond
	Ply:	One or more Flintlastic Ultra Poly SMS Base Sheet, Flintlastic Base 20 T	
	Cap Ply:	Flintlastic GTS-FR, Flintlastic GTS-FR CoolStar	
APP-TA	Base Ply:	One or more Flintlastic APP Base T, Flintlastic STA	Torch-applied, Full Bond
	Cap Ply:	Flintlastic STA, Flintlastic GTA, Flintlastic GTA CoolStar, Flintlastic GTA CoolStar Ultra, Flintlastic GTA-FR, Flintlastic GTA-FR CoolStar	
SBS-SA-H	Base Ply:	Black Diamond Base Sheet, Flintlastic Ultra Glass SA, Flintlastic SA PlyBase	Self-adhering (activated by overlying membrane), Full Bond
	Note: Use of Flintlastic SA PlyBase in an SBS-SA-H application is limited to use of a torch-applied Cap Ply membrane overtop.		
SBS-SA	Base Ply:	Flintlastic SA PlyBase, Flintlastic SA MidPly	Self-adhering, Full Bond
	Ply:	Flintlastic SA PlyBase, Flintlastic SA MidPly	
	Cap Ply:	Flintlastic SA Cap, Flintlastic SA Cap CoolStar, Flintlastic SA Cap FR, Flintlastic SA Cap FR CoolStar	



NEMO EVALUATIONS REPORT

Report No.: NER-CTR-001.R1
Revision 1: 2025-04-17
Page 11 of 80

CertainTeed, LLC
FL2533-R33



3.1.5 Vapor Barriers:

- (a) For System Types B-1, B-2, C-1, C-2, D-1 or D-2, an optional thermal barrier and/or vapor barrier membrane may be installed atop the roof deck prior to installation of the insulation and roof cover. Refer to [FM Loss Prevention Data Sheet](#) 1-29 for design and installation recommendations and limitations.
- (b) Refer to [Section 4.3](#) herein for options where the vapor barrier forms part of the load path.

4. LIMITATIONS OF USE:

4.1 General:

4.1.1 This is a building code evaluation. NEMO CERT, LLC is not, in any way, the Designer of Record for any project on which this NER, or previous versions thereof, is/was used for permitting or design guidance. NERs are not to be construed as representing any attributes not specifically listed, nor are NERs to be construed as an endorsement of the subject of the report or a recommendation for its use. There is no warranty by NEMO CERT, LLC, express or implied, as to any finding or other matter in this report, or as to any product covered by the report.

4.1.2 Roof Decks:

- (a) This NER pertains to above-deck roof components. Roof decks and structural members shall be in accordance with applicable Code requirements to the satisfaction of the Authority Having Jurisdiction.
- (b) OSB sheathing is not permitted in FBC HVHZ jurisdictions.
- (d) Unless otherwise noted, reference to 'structural concrete' pertains to min. 2,500 psi structural concrete, and excludes 'structural lightweight concrete'.
- (e) **FBC HVHZ Specific:** The table below lists various 'as-tested' deck conditions in accordance with [Testing Application Standard](#) TAS 114(J). Steel deck stress analysis is the responsibility of others to the satisfaction of the Authority Having Jurisdiction.

TABLE 8: AS-TESTED DECK ATTACHMENT DETAILS (TAS 114, APPENDIX J)				
TYPE	AS TESTED SUB-ASSEMBLY			
	SPAN (INCH O.C.)	FASTENER	SPACING (INCH O.C.)	MDP (PSF)
15/32-inch APA rated CDX plywood	24	#8 wood screws	6	-75.0
	24	8d ring shank nails	6	-90.0
	24	#10 wood screws	6	-90.0
	24	#8 wood screws	8	-97.5
	24	#10 wood screws	4	-127.5
19/32-inch APA rated CDX plywood	24	8d ring shank nails	4	-60.0
	24	8d ring shank nails	6	-90.0
	24	#10 wood screws	6	-90.0
	24	#8 wood screws	6	-105.0
	24	#10 wood screws	4	-127.5
23/32-inch APA rated CDX plywood	24	8d ring shank nails	6	-45.0
22 ga., Type B, Grade 33 steel	72	#12 HWH Tek 5	6	-82.5
	72	#12 HWH Tek 5 with 3/4" steel washers	6	-97.5
	72	Two (2) #12 HWH Tek 5 with 3/4" steel washers	6	-172.5
22 ga., Type B, Grade 40 steel	72	#12 HWH Tek 5	6	-75.0
	72	5/8" puddle welds	6	-82.5
	72	#12 HWH Tek 5 with 3/4" steel washers	6	-97.5
22 ga., Type B, Grade 80 steel	72	#12 HWH Tek 5	6	-82.5
	72	#12 HWH Tek 5 with 3/4" steel washers	6	-112.5
	72	Two (2) #12 HWH Tek 5 with 3/4" steel washers	6	-120.0

4.1.3 Fire Classification:

- (a) Refer to **IBC/FBC 1505**, **FBC HVHZ 1516**, **UL TGFU.R11656** and the fire classification certificate for the roof cover manufacturer for requirements and limitations regarding roof assembly fire classification.
- (b) Refer to **FBC 2603** for requirements and limitations concerning the use of foam plastic insulation.



NEMO EVALUATIONS REPORT

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

CertainTeed, LLC

FL2533-R33

NEMO|cert.® Page 12 of 80



ISO/IEC 17065

PCA-145

4.1.4 Quality Assurance:

All components in the roof assembly shall have quality assurance surveillance in accordance with **F.A.C. Rule 61G20-3**. For components listed herein that are produced by a manufacturer other than the report holder on [Page 1](#) of this NER, refer to the supporting evidence held by the component manufacturer.

4.2 Jurisdiction Specific:

IBC and FBC Non-HVHZ	FBC HVHZ
4.2.1 This NER does not include evaluation of roof edge termination. Refer to IBC 1504.6 or FBC 1504.5 for requirements and limitations regarding edge securement for low-slope roofs. 4.2.2 Refer to IBC 1512 or FBC 1511 for requirements and limitations regarding recover installations. (a) For mechanical attachment to existing roof decks, fasteners shall be tested for withdrawal resistance. A qualified design professional shall review the data for comparison to the minimum requirements for the system. Testing shall be in accordance with ANSI/SPRI FX-1 or TAS 105. (b) For adhered re-roof (tear off) installation, the existing substrate shall be examined for compatibility with the adhesive. If any surface conditions exist that bring system performance into question, field uplift testing in accordance with ANSI/SPRI IA-1, FM Loss Prevention Data Sheet 1-52 or TAS 124 shall be conducted on mock-ups of the proposed interface. (c) For adhered recover installation, the existing roof system shall meet project design pressure requirements on its own merit to the satisfaction of the Authority Having Jurisdiction, as documented through field uplift testing in accordance with FM Loss Prevention Data Sheet 1-52 or TAS 124.	This NER does not include evaluation of roof edge termination. Refer to RAS 111 for requirements and limitations regarding edge securement for low-slope roofs. Refer to FBC HVHZ 1521 for requirements and limitations regarding recover installations. For mechanical attachment to existing roof decks, fasteners shall be tested for withdrawal resistance. A qualified design professional shall review the data for comparison to the minimum requirements for the system. Testing shall be in accordance with TAS 105. For adhered re-roof (tear off) installation, the existing substrate shall be examined for compatibility with the adhesive to be installed. If any surface conditions exist that bring system performance into question, field uplift testing in accordance with TAS 124 shall be conducted on mock-ups of the proposed interface. For adhered recover installation, the existing roof system shall meet project design pressure requirements on its own merit to the satisfaction of the Authority Having Jurisdiction, as documented through field uplift testing in accordance with TAS 124.
4.2.3 <u>Wind Load Resistance:</u> (a) Refer to Section 4.3 for a tabulated summary of assembly listings and maximum allowable design pressures. (b) “MDP” = Maximum Design Pressure is the result of testing for wind load resistance based on allowable wind loads, and reflects the ultimate passing pressure divided by 2 (the 2 to 1 margin of safety per FBC 1504.9 has already been applied). Refer to IBC, FBC 1609 for determination of design wind loads. (c) The MDP for the selected assembly shall meet or exceed at least the Zone 1 PRIME design pressure determined in accordance with IBC, FBC Chapter 16. Elevated pressure zones shall employ an attachment density designed by a qualified design professional to resist the elevated pressure criteria. Commonly used methods are ANSI/SPRI WD1, FM Loss Prevention Data Sheet 1-29, RAS 117 and RAS 137. Assemblies marked with an asterisk* carry the limitations set forth in Section 2.2.10.1 of FM Loss Prevention Data Sheet 1-29 for Zone 2/3 enhancements. (d) For fully-adhered installations, the maximum design pressure for the selected assembly shall meet or exceed the critical design pressure. Rational analysis is not permitted.	“MDP” = Maximum Design Pressure is the result of testing for wind load resistance based on allowable wind loads, and reflects the ultimate passing pressure divided by 2 (the 2 to 1 margin of safety per TAS 114 has already been applied). Refer to FBC HVHZ 1620 or RAS 128 for determination of design wind loads. Assemblies having a MDP < 45.0 psf are not permitted in FBC HVHZ jurisdictions. The MDP for the selected assembly shall meet or exceed at least the Zone 1 PRIME design pressure determined in accordance with FBC HVHZ 1620 or RAS 128. Elevated pressure zones shall employ an attachment density designed by a qualified design professional to resist the elevated pressure criteria. Analysis shall be in accordance with RAS 117 or RAS 137. For assemblies marked with an asterisk*, the maximum design pressure (MDP) limitation shall be applicable to all roof pressure zones. Rational analysis is not permitted.



4.3 **System Listings and Allowable Design Pressures:** See [Section 4.2.3](#)

4.3.1 **Thermal Barriers / Vapor Barriers:** The lesser of the MDP listings below vs. that for the selected roof assembly from [Section 4.3.2](#) applies.

(a) **Structural Concrete Decks:**

TABLE VB-1: STRUCTURAL CONCRETE DECK VAPOR BARRIER FOLLOWED BY ADHERED INSULATION					
OPTION #	PRIMER	VAPOR BARRIER		INSULATION ADHESIVE PER TABLE 3A (3.1.3)	MDP (psf)
		TYPE	ATTACH		
C-VB-1.	FlintPrime QD	Flintlastic SA PlyBase	Self-adhering	OB500, 12-inch o.c.	-82.5
C-VB-2.	None	All Weather/Empire Base Sheet, 3-inch wide side laps and 6-inch wide end laps are sealed with Millennium Hurricane Force Lap and Flashing Adhesive	Millennium Hurricane Force Membrane Adhesive HS, max. 6-inch o.c.	M-OSFA or M-PG-1, 12-inch o.c.	-82.5
C-VB-3.	None	Flintlastic Ultra Poly SMS Base Sheet, 3-inch wide side laps and 6-inch wide end laps are hot-air-welded, torch-welded or sealed with Millennium Hurricane Force Lap and Flashing Adhesive	Millennium Hurricane Force Membrane Adhesive HS, max. 6-inch o.c.	M-OSFA or M-PG-1, 12-inch o.c.	-82.5
C-VB-4.	FlintPrime QD	Black Diamond Base Sheet, Flintlastic Ultra Glass SA, or Flintlastic SA Cap	Self-adhering	M-OSFA or M-PG-1, 12-inch o.c.	-97.5
C-VB-5.	FlintPrime QD	Black Diamond Base Sheet, Flintlastic Ultra Glass SA, or Flintlastic SA Cap	Self-adhering	M-OSFA or M-PG-1, 6-inch o.c.	-315.0
C-VB-6.	FlintPrime QD	Flintlastic GTA	Torch-applied	M-OSFA or M-PG-1, 12-inch o.c.	-420.0
C-VB-7.	FlintPrime QD	Flintlastic Base 20 T	Torch-applied	M-OSFA or M-PG-1, 12-inch o.c.	-495.0

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 14 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065



PCA-145

4.3.2 Roof Assemblies:

TABLE	DECK	APPLICATION	TYPE	DESCRIPTION	PAGE
9A	Wood	New or Reroof (Tear-Off)	A-1	Bonded Insulation(s), Bonded Roof Cover	15
9B	Wood	New or Reroof (Tear-Off)	B-1	Mechanically Attached Base Insulation, Bonded Top Insulation(s), Bonded Roof Cover	16
9C	Wood	New or Reroof (Tear-Off)	B-3	Mechanically Attached Anchor Sheet, Bonded Insulation(s), Bonded Roof Cover	17
9D	Wood	New or Reroof (Tear-Off)	C-1	Mechanically Attached Insulation, Bonded Roof Cover	19
9E	Wood	New or Reroof (Tear-Off)	D-2	Insulated, Mechanically Attached Anchor Sheet, Bonded Roof Cover	21
9F	Wood	New or Reroof (Tear-Off)	E-2	Non-Insulated, Mechanically Attached Anchor Sheet, Bonded Roof Cover	23
9G	Wood	New, Reroof (Tear-Off), or Recover	E-2	Non-Insulated, Mechanically Attached Anchor Sheet, Bonded Roof Cover	24
9H	Wood	New, Reroof (Tear-Off), or Recover	F	Non-Insulated, Bonded Roof Cover	26
10A	Steel or Structural Concrete	New, Reroof (Tear-Off), or Recover	B-1	Mechanically Attached Base Insulation, Bonded Top Insulation(s), Bonded Roof Cover	27
10B	Steel or Structural Concrete	New, Reroof (Tear-Off), or Recover	C-1	Mechanically Attached Insulation, Bonded Roof Cover	30
10C	Steel or Structural Concrete	New, Reroof (Tear-Off), or Recover	D-2	Insulated, Mechanically Attached Anchor Sheet, Bonded Roof Cover	34
11A	Structural Concrete	New or Reroof (Tear-Off)	A-1	Bonded Insulation(s), Bonded Roof Cover	36
11B	Structural Concrete	New or Reroof (Tear-Off)	F	Non-Insulated, Bonded Roof Cover	44
12A	Deck with Lightweight Concrete	New or Reroof (Tear-Off)	A-1	Bonded Insulation(s), Bonded Roof Cover	44
12B	Deck with Lightweight Concrete	New or Reroof (Tear-Off)	A-1	Bonded Insulation(s), Bonded Roof Cover	46
12C	Deck with Lightweight Concrete	New or Reroof (Tear-Off)	A-2	Bonded Vapor Barrier, Bonded Insulation(s), Bonded Roof Cover	53
12D	Deck with Lightweight Concrete	New or Reroof (Tear-Off)	B-3	Mechanically Attached Anchor Sheet, Bonded Insulation(s), Bonded Roof Cover	56
12E	Deck with Lightweight Concrete	New or Reroof (Tear-Off)	E-2	Non-Insulated, Mechanically Attached Anchor Sheet, Bonded Roof Cover	59
12F	Deck with Lightweight Concrete	Reroof (Tear-Off) or Recover	E-2	Non-Insulated, Mechanically Attached Anchor Sheet, Bonded Roof Cover	64
12G	Deck with Lightweight Concrete	Reroof (Tear-Off)	F	Non-Insulated, Bonded Roof Cover	64
13A	Cementitious Wood Fiber	New or Reroof (Tear-Off)	A-1	Bonded Insulation(s), Bonded Roof Cover	65
13B	Cementitious Wood Fiber	New, Reroof (Tear-Off), or Recover	B-3	Mechanically Attached Anchor Sheet, Bonded Insulation(s), Bonded Roof Cover	66
13C	Cementitious Wood Fiber	Reroof (Tear-Off) or Recover	C-1	Mechanically Attached Insulation, Bonded Roof Cover	67
13D	Cementitious Wood Fiber	New, Reroof (Tear-Off), or Recover	E-2	Non-Insulated, Mechanically Attached Anchor Sheet, Bonded Roof Cover	68
14A	Existing Gypsum	Reroof (Tear-Off)	A-1	Bonded Insulation(s), Bonded Roof Cover	68
14B	Existing Gypsum	Reroof (Tear-Off)	B-3	Mechanically Attached Anchor Sheet, Bonded Insulation(s), Bonded Roof Cover	70
14C	Existing Gypsum	Reroof (Tear-Off)	C-1	Mechanically Attached Insulation, Bonded Roof Cover	71
14D	Existing Gypsum	Reroof (Tear-Off)	E-2	Non-Insulated, Mechanically Attached Anchor Sheet, Bonded Roof Cover	72
15A	Various	Recover	A-1	Bonded Insulation(s), Bonded Roof Cover	72
15B	Various	New, Reroof (Tear-Off)	F	Non-Insulated, Bonded Roof Cover	80



TABLE 9A: WOOD DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER

SYSTEM No.	DECK (4.1.2)	BASE INSULATION LAYER		TOP INSULATION LAYER(S)		PRIMER	ROOF COVER (3.1.4)			MDP (psf)
		TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
SELF-ADHERING SYSTEMS:										
W-1.	Min. 15/32-inch APA rated CDX plywood, 24-inch span	Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG1	(Optional) Additional layer(s) of base insulation and/or min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG1	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-60.0
W-2.	Min. 15/32-inch APA rated CDX plywood, 24-inch span	Min. 1.5-inch ACFoam II or H-Shield	OB500	(Optional) Additional layer(s) of base insulation and/or min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-60.0
W-3.	Min. 15/32-inch APA rated CDX plywood, 24-inch span, blocked 48-inch o.c.	Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG1, 6-inch o.c.	(Optional) Additional layer(s) of base insulation and/or min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG1, 6-inch o.c.	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-97.5
W-4.	Min. 15/32-inch APA rated CDX plywood, 24-inch span, blocked 48-inch o.c.	Min. 1.5-inch ACFoam II or H-Shield	OB500, 6-inch o.c.	(Optional) Additional layer(s) of base insulation and/or min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500, 6-inch o.c.	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-97.5
HYBRID SYSTEMS:										
W-5.	Min. 15/32-inch APA rated CDX plywood, 24-inch span	Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG1	(Optional) Additional layer(s) of base insulation and/or min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG1	None	SBS-SA-H	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-60.0
W-6.	Min. 15/32-inch APA rated CDX plywood, 24-inch span	Min. 1.5-inch ACFoam II or H-Shield	OB500	(Optional) Additional layer(s) of base insulation and/or min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	None	SBS-SA-H	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-60.0
W-7.	Min. 15/32-inch APA rated CDX plywood, 24-inch span, blocked 48-inch o.c.	Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG1, 6-inch o.c.	(Optional) Additional layer(s) of base insulation and/or min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG1, 6-inch o.c.	None	SBS-SA-H	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-97.5
W-8.	Min. 15/32-inch APA rated CDX plywood, 24-inch span, blocked 48-inch o.c.	Min. 1.5-inch ACFoam II or H-Shield	OB500, 6-inch o.c.	(Optional) Additional layer(s) of base insulation and/or min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500, 6-inch o.c.	None	SBS-SA-H	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-97.5
CONVENTIONAL SYSTEMS:										
W-9.	Min. 15/32-inch APA rated CDX plywood, 24-inch span	Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG1	Optional additional layers of base insulation, followed by min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG1	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-60.0



TABLE 9A: WOOD DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER

SYSTEM No.	DECK (4.1.2)	BASE INSULATION LAYER		TOP INSULATION LAYER(S)		PRIMER	ROOF COVER (3.1.4)			MDP (PSF)
		TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
W-10.	Min. 15/32-inch APA rated CDX plywood, 24-inch span	Min. 1.5-inch ACFoam II or H-Shield	OB500	(Optional) Additional layer(s) of base insulation and/or min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-60.0
W-11.	Min. 15/32-inch APA rated CDX plywood, 24-inch span, blocked 48-inch o.c.	Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG1, 6-inch o.c.	Optional additional layers of base insulation, followed by min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG1, 6-inch o.c.	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-97.5
W-12.	Min. 15/32-inch APA rated CDX plywood, 24-inch span, blocked 48-inch o.c.	Min. 1.5-inch ACFoam II or H-Shield	OB500, 6-inch o.c.	(Optional) Additional layer(s) of base insulation and/or min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500, 6-inch o.c.	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-97.5

TABLE 9B: WOOD DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER
SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER

SYSTEM NO.	DECK (4.1.2)	BASE INSULATION LAYER			TOP INSULATION LAYER		ROOF COVER (3.1.4)			MDP (PSF)
		TYPE	FASTENER (3.1.1, 4.2.2)	ATTACH (3.1.2e)	TYPE	ATTACH (3.1.3)	BASE	PLY	CAP	
SELF-ADHERING SYSTEMS:										
W-13.	Min. 15/32-inch plywood, 24-inch span	Min. 2-inch AC Foam II or H-Shield	3.1.1	1 per 2.7 ft²	Min. 2-inch H-Shield HD Composite CG	M-OSFA or M-PG1	SBS-SA	(Optional) SBS-SA	SBS-SA	-30.0
W-14.	Min. 15/32-inch plywood, 24-inch span	Min. 2-inch AC Foam II or H-Shield	Dekfast DF-#14-PH3 with Dekfast PLT-R-3	1 per 2.0 ft²	Min. 2-inch H-Shield HD Composite CG	M-OSFA or M-PG1	SBS-SA	(Optional) SBS-SA	SBS-SA	-52.5
HYBRID SYSTEMS:										
W-15.	Min. 15/32-inch plywood, 24-inch span	Min. 2-inch AC Foam II or H-Shield	3.1.1	1 per 2.7 ft²	Min. 2-inch H-Shield HD Composite CG	M-OSFA or M-PG1	SBS-SA-H	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-30.0
W-16.	Min. 15/32-inch plywood, 24-inch span	Min. 2-inch AC Foam II or H-Shield	Dekfast DF-#14-PH3 with Dekfast PLT-R-3	1 per 2.0 ft²	Min. 2-inch H-Shield HD Composite CG	M-OSFA or M-PG1	SBS-SA-H	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-52.5
W-17.	Min. 15/32-inch plywood, 24-inch span	Min. 1.5-inch AC Foam II or H-Shield	Trufast #12 DP or #14 HD with Trufast 3" Metal Insulation Plates	1 per 1.3 ft²	Min. 1.5-inch AC Foam II or H-Shield	Hot asphalt, M-OSFA, M-PG1, or OB500	SBS-SA-H	(Optional) APP-TA	APP-TA	-67.5
CONVENTIONAL SYSTEMS:										
W-18.	Min. 23/32-inch plywood, 24-inch span	Min. 1.5-inch AC Foam II, ENRGY 3, or H-Shield	3.1.1	1 per 2.0 ft²	Min. 0.5-inch Structodek High Density Fiberboard Roof Insulation, min. 0.75-inch FescoBoard (homogeneous)	Hot asphalt	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*



TABLE 9b: WOOD DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER
SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER

SYSTEM No.	DECK (4.1.2)	BASE INSULATION LAYER			TOP INSULATION LAYER		ROOF COVER (3.1.4)			MDP (PSF)
		TYPE	FASTENER (3.1.1, 4.2.2)	ATTACH (3.1.2E)	TYPE	ATTACH (3.1.3)	BASE	PLY	CAP	
W-19.	Min. 23/32-inch plywood, 24-inch span	Min. 1.5-inch ACFoam II, ENRGY 3, or H-Shield	3.1.1	1 per 2.0 ft ²	Min. 0.25-inch DensDeck, DensDeck Prime, or SECUROCK Gypsum-Fiber Roof Board	Hot asphalt	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
W-20.	Min. 15/32-inch plywood, 24-inch span	Min. 1.5-inch ACFoam II or H-Shield	Trufast #12 DP or #14 HD with Trufast 3" Metal Insulation Plates	1 per 1.3 ft ²	Optional additional layer(s) of base insulation followed by min. 0.25-inch SECUROCK Gypsum-Fiber Roof board	Hot asphalt, M-OSFA, M-PG1, or OB500	APP-TA	(Optional) APP-TA	APP-TA	-90.0
COLD-APPLIED SYSTEMS:										
W-21.	Min. 15/32-inch plywood, 24-inch span	Min. 2-inch ACFoam II or H-Shield	3.1.1	1 per 2.7 ft ²	Min. 2-inch H-Shield HD Composite CG	M-OSFA or M-PG1	SBS-CA4	None	SBS-CA4	-30.0
W-22.	Min. 15/32-inch plywood, 24-inch span	Min. 2-inch ACFoam II or H-Shield	Dekfast DF-#14-PH3 with Dekfast PLT-R-3	1 per 2.0 ft ²	Min. 2-inch H-Shield HD Composite CG	M-OSFA or M-PG1	SBS-CA4	None	SBS-CA4	-45.0

TABLE 9c: WOOD DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE B-3: MECHANICALLY ATTACHED ANCHOR SHEET, BONDED INSULATION, BONDED ROOF COVER

Sys. No.	Deck (4.1.2)	Anchor Sheet			Base Insulation Layer(s)		Top Insulation Layer		Primer	Roof Cover (3.1.4)			MDP (PSF)
		Type	Fastener (3.1.1, 4.2.2)	Attach (3.1.3)	Type	Attach (3.1.3)	Type	Attach (3.1.3)		Base	Ply	Cap	
Self-Adhering Systems:													
W-23.	Min. 19/32-inch plywood, 24-inch span	Glasbase Base Sheet, All Weather/Empire Base Sheet, Flintlastic Base 20, Poly SMS, Ultra Poly SMS, or Flintglas MS Cap (inverted)	32 ga., 1-5/8-inch dia. tin caps with 11 ga. annular ring shank nails	9-inch o.c. in 4-inch lap and 12-inch o.c. in two (2), equally spaced, staggered center rows	Min. 1.5-inch ACFoam II, ENRGY 3, H-Shield, or Multi-Max FA3	Hot asphalt	Min. 0.25-inch DensDeck	Hot asphalt	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-45.0*
W-24.	Min. 19/32-inch plywood, 24-inch span	Glasbase Base Sheet, All Weather/Empire Base Sheet, Poly SMS, or Ultra Poly SMS	32 ga., 1-5/8-inch dia. tin caps with 11 ga. annular ring shank nails	8-inch o.c. in 3-inch lap and 8-inch o.c. in three (3), equally spaced, staggered center rows	Min. 1.5-inch ACFoam II, ENRGY 3, H-Shield, or Multi-Max FA3	Hot asphalt full coverage or M-OSFA, OB500, Polyset BM, or Polyset CRA, 4-inch o.c.	Min. 0.25-inch DensDeck	Hot asphalt full coverage or M-OSFA, OB500, Polyset BM, or Polyset CRA, 6-inch o.c.	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-52.5
W-25.	Min. 19/32-inch plywood, 24-inch span	Flintglas MS Cap (inverted)	32 ga., 1-5/8-inch dia. Tin caps with 11 ga. annular ring shank nails	8-inch o.c. in 3-inch lap and 8-inch o.c. in three (3), equally spaced, staggered center rows	Min. 1.5-inch ACFoam II, ENRGY 3, H-Shield, or Multi-Max FA3	Hot asphalt	Min. 0.25-inch DensDeck	Hot asphalt	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-52.5



TABLE 9c: WOOD DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)

SYSTEM TYPE B-3: MECHANICALLY ATTACHED ANCHOR SHEET, BONDED INSULATION, BONDED ROOF COVER

SYS. NO.	DECK (4.1.2)	ANCHOR SHEET			BASE INSULATION LAYER(S)		TOP INSULATION LAYER		PRIMER	ROOF COVER (3.1.4)			MDP (PSF)
		TYPE	FASTENER (3.1.1, 4.2.2)	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
W-26.	Min. 19/32-inch plywood, 24-inch span	Glasbase Base Sheet, All Weather/Empire Base Sheet, Poly SMS, or Ultra Poly SMS	32 ga., 1-5/8-inch dia. tin caps with 11 ga. annular ring shank nails	8-inch o.c. in 3-inch lap and 8-inch o.c. in three (3), equally spaced, staggered center rows	(Optional) Min. 1.5-inch ACFoam II, ENRGY 3, H-Shield, or Multi-Max FA3	Hot asphalt full coverage or M-OSFA, OB500, Polyset BM, or Polyset CRA, 4-inch o.c.	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Hot asphalt full coverage or M-OSFA, OB500, Polyset BM, or Polyset CRA, 6-inch o.c.	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-60.0
W-27.	Min. 19/32-inch plywood, 24-inch span	Flintglas MS Cap (inverted)	32 ga., 1-5/8-inch dia. tin caps with 11 ga. annular ring shank nails	8-inch o.c. in 3-inch lap and 8-inch o.c. in three (3), equally spaced, staggered center rows	(Optional) Min. 1.5-inch ACFoam II, ENRGY 3, H-Shield, or Multi-Max FA3	Hot asphalt	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Hot asphalt	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-60.0
HYBRID SYSTEMS:													
W-28.	Min. 19/32-inch plywood, 24-inch span	Glasbase Base Sheet, All Weather/Empire Base Sheet, Flintlastic Base 20, Poly SMS, Ultra Poly SMS, or Flintglas MS Cap (inverted)	32 ga., 1-5/8-inch dia. tin caps with 11 ga. annular ring shank nails	9-inch o.c. in 4-inch lap and 12-inch o.c. in two (2), equally spaced, staggered center rows	Min. 1.5-inch ACFoam II, ENRGY 3, H-Shield, or Multi-Max FA3	Hot asphalt	None	N/A	None	SBS-SA-H	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
W-29.	Min. 19/32-inch plywood at max. 24-inch	Glasbase Base Sheet or Flintglas MS Cap (inverted)	32 ga., 1-5/8-inch dia. tin caps with 11 ga. annular ring shank nails	8-inch o.c. in 3-inch lap and 8-inch o.c. in three (3), equally spaced, staggered center rows	Min. 1.5-inch ACFoam II, ENRGY 3, H-Shield, or Multi-Max FA3	Hot asphalt	None	N/A	None	SBS-SA-H	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-60.0
CONVENTIONAL SYSTEMS:													
W-30.	Min. 19/32-inch plywood, 24-inch span	Glasbase Base Sheet, All Weather/Empire Base Sheet, Flintlastic Base 20, Poly SMS, Ultra Poly SMS, or Flintglas MS Cap (inverted)	32 ga., 1-5/8-inch dia. tin caps with 11 ga. annular ring shank nails	9-inch o.c. in 4-inch lap and 12-inch o.c. in two (2), equally spaced, staggered center rows	Min. 1.5-inch ACFoam II, ENRGY 3, H-Shield, or Multi-Max FA3	Hot asphalt	Min. 0.25-inch DensDeck	Hot asphalt	FlintPrime QD	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
W-31.	Min. 19/32-inch plywood, 24-inch span	Glasbase Base Sheet, All Weather/Empire Base Sheet, Poly SMS, or Ultra Poly SMS	32 ga., 1-5/8-inch dia. tin caps with 11 ga. annular ring shank nails	8-inch o.c. in 3-inch lap and 8-inch o.c. in three (3), equally spaced, staggered center rows	Min. 1.5-inch ACFoam II, ENRGY 3, H-Shield, or Multi-Max FA3	Hot asphalt full coverage or M-OSFA, OB500, Polyset BM, or Polyset CRA, 4-inch o.c.	Min. 0.25-inch DensDeck	Hot asphalt full coverage or M-OSFA, OB500, Polyset BM, or Polyset CRA, 6-inch o.c.	FlintPrime QD	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-52.5

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 19 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

TABLE 9c: WOOD DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)**SYSTEM TYPE B-3: MECHANICALLY ATTACHED ANCHOR SHEET, BONDED INSULATION, BONDED ROOF COVER**

SYS. NO.	DECK (4.1.2)	ANCHOR SHEET			BASE INSULATION LAYER(S)		TOP INSULATION LAYER		PRIMER	ROOF COVER (3.1.4)			MDP (PSF)
		TYPE	FASTENER (3.1.1, 4.2.2)	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
W-32.	Min. 19/32-inch plywood, 24-inch span	Glasbase Base Sheet, All Weather/Empire Base Sheet, Poly SMS, or Ultra Poly SMS	32 ga., 1-5/8-inch dia. tin caps with 11 ga. annular ring shank nails	8-inch o.c. in 3-inch lap and 8-inch o.c. in three (3), equally spaced, staggered center rows	(Optional) Min. 1.5-inch ACFoam II, ENRGY 3, H-Shield, or Multi-Max FA3	Hot asphalt full coverage or M-OSFA, OB500, Polyset BM, or Polyset CRA, 4-inch o.c.	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Hot asphalt full coverage or M-OSFA, OB500, Polyset BM, or Polyset CRA, 6-inch o.c.	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-60.0

TABLE 9D: WOOD DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER

SYSTEM NO.	DECK (4.1.2)	BASE INSULATION LAYER (3.1.2)	TOP INSULATION LAYER			PRIMER	ROOF COVER (3.1.4)			MDP (PSF)
			TYPE	FASTENER (3.1.1, 4.2.2)	ATTACH (3.1.3)		BASE	PLY	CAP	
SELF-ADHERING SYSTEMS:										
W-33.	Min. 15/32-inch plywood, 24-inch span	(Optional) One or more layers, any combination, loose laid	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Trufast #12 DP or #14 HD with Trufast 3" Metal Insulation Plates	1 per 3.2 ft²	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-30.0*
W-34.	Min. 19/32-inch plywood, 24-inch span	(Optional) One or more layers, any combination, loose laid	Min. 0.25-inch DensDeck	3.1.1	1 per 1.3 ft²	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-45.0
W-35.	Min. 19/32-inch plywood, 24-inch span	(Optional) One or more layers, any combination, loose laid	Min. 3/8-inch SECUROCK Gypsum-Fiber Roof Board	Trufast #12 DP or #14 HD with Trufast 3" Metal Insulation Plates	1 per 2.7 ft²	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-45.0*
W-36.	Min. 19/32-inch plywood, 24-inch span	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch ACFoam II, ENRGY 3, H-Shield, or Multi-Max FA3	Trufast #12 DP or #14 HD with Trufast 3" Metal Insulation Plates	1 per 2.0 ft²	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-45.0*
W-37.	Min. 19/32-inch plywood, 24-inch span	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch ACFoam II	Trufast #14 HD with Trufast 3" Metal Insulation Plates	1 per 1.6 ft²	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-52.5
W-38.	Min. 19/32-inch plywood, 24-inch span	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch ACFoam II, ENRGY 3, H-Shield, or Multi-Max FA3	3.1.1	1 per 1.45 ft²	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-60.0
HYBRID SYSTEMS:										
W-39.	Min. 15/32-inch plywood, 24-inch span	(Optional) One or more layers, any combination, loose laid	Min. 0.25-inch DensDeck, DensDeck Prime	Trufast #12 DP or #14 HD with Trufast 3" Metal Insulation Plates	1 per 2.0 ft²	None	SBS-SA-H	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-30.0*
W-40.	Min. 15/32-inch plywood, 24-inch span	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch ACFoam II	Trufast #14 HD with Trufast 3" Metal Insulation Plates	1 per 1.6 ft²	None	SBS-SA-H	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-52.5



TABLE 9D: WOOD DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER

SYSTEM NO.	DECK (4.1.2)	BASE INSULATION LAYER (3.1.2)	TOP INSULATION LAYER			PRIMER	ROOF COVER (3.1.4)			MDP (PSE)
			TYPE	FASTENER (3.1.1, 4.2.2)	ATTACH (3.1.3)		BASE	PLY	CAP	
W-41.	Min. 15/32-inch plywood, 24-inch span	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch ACFoam II, ENRGY 3, or Multi-Max FA3	3.1.1	1 per 1.3 ft ²	None	SBS-SA-H	(Optional) BP-AA or SBS-AA	SBS-AA	-52.5
W-42.	Min. 19/32-inch plywood, 24-inch span	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch ACFoam II or H-Shield	3.1.1	1 per 1.45 ft ²	None	SBS-SA-H	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-60.0
W-43.	Min. 15/32-inch plywood, 24-inch span	(Optional) Min. 1.5-inch, one or more layers, any combination, loose laid	Min. 1.5-inch ACFoam II or H-Shield	Trufast #12 DP or #14 HD with Trufast 3" Metal Insulation Plates	1 per 1.3 ft ²	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-75.0
W-44.	Min. 19/32-inch plywood, 24-inch span	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch ACFoam II, ENRGY 3, or Multi-Max FA3	3.1.1	1 per 1.3 ft ²	None	SBS-SA-H	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-82.5
W-45.	Min. 19/32-inch plywood, 24-inch span, #8 wood screws, 6" o.c.	One or more layers, min. 1.5-inch thick, any combination, loose laid	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Trufast #14 HD with Trufast 3" Metal Insulation Plate	1 per 1.3 ft ²	None	SBS-SA-H	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-82.5 (HVHZ)
CONVENTIONAL SYSTEMS:										
W-46.	Min. 23/32-inch plywood, 24-inch span	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch Structodek High Density Fiberboard Roof Insulation, min. 0.75-inch FescoBoard (homogeneous)	3.1.1	1 per 2.0 ft ²	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
W-47.	Min. 15/32-inch plywood, 24-inch span	(Optional) One or more layers, any combination, loose laid	Min. 0.25-inch DensDeck, DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board	Trufast #12 DP or #14 HD with Trufast 3" Metal Insulation Plates	1 per 2.0 ft ²	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
W-48.	Min. 15/32-inch plywood, 24-inch span	(Optional for Recover) Min. 1.5-inch, one or more layers, any combination, loose laid	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Trufast #12 DP or #14 HD with Trufast 3" Metal Insulation Plates	1 per 1.45 ft ²	None	APP-TA	(Optional) APP-TA	APP-TA	-60.0
W-49.	Min. 19/32-inch plywood, 24-inch span	Min. 2-inch ACFoam II, ENRGY 3, or H-Shield, loose laid	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Trufast #12 DP or #14 HD with Trufast 3" Metal Insulation Plates	1 per 1.8 ft ²	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-60.0
W-50.	Min. 15/32-inch plywood, 24-inch span	(Optional for Recover) Min. 1.5-inch, one or more layers, any combination, loose laid	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Trufast #12 DP or #14 HD with Trufast 3" Metal Insulation Plates	1 per 1.3 ft ²	None	APP-TA	(Optional) APP-TA	APP-TA	-67.5



TABLE 9E: WOOD DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE D-2: INSULATED, MECHANICALLY ATTACHED ANCHOR SHEET, BONDED ROOF COVER

SYSTEM NO.	DECK (4.1.2)	INSULATION LAYER(S) (3.1.2)		ANCHOR SHEET			PRIMER	ROOF COVER (3.1.4)		MDP (PSF)
		TYPE	ATTACH (3.1.3)	TYPE	FASTENER (3.1.1, 4.2.2)	SPACING		BASE	CAP	
SELF-ADHERING SYSTEMS:										
W-51.	Min. 19/32-inch plywood, 24-inch span	Min. 1.5-inch, one or more layers, any combination	Prelim. Attach	Flintlastic SA NailBase	3.1.1	8-inch o.c. at min. 3-inch lap and 8-inch o.c. in two (2), equally spaced, staggered center rows	FlintPrime QD at stress plates	(Optional) SBS-SA	SBS-SA	-82.5*
W-52.	Min. 15/32-inch plywood, 24-inch span	Min. 1.5-inch, one or more layers, any combination	Prelim. Attach	Flintlastic SA NailBase	OMG #14 HD with OMG 3 in. Round Metal Plate or Trufast #12 DP or #14 HD with Trufast 3" Metal Insulation Plate	6-inch o.c. at min. 2-inch lap and 6-inch o.c. in three (3), equally spaced, staggered center rows	FlintPrime QD at stress plates	(Optional) SBS-SA	SBS-SA	-97.5*
W-53.	Min. 15/32-inch plywood, 24-inch span	Min. 1.5-inch, one or more layers, any combination	Prelim. Attach	Flintlastic SA NailBase	OMG #14 HD with OMG 3 in. Round Metal Plate or Trufast #12 DP or #14 HD with Trufast 3" Metal Insulation Plate	6-inch o.c. at min. 2-inch lap and 6-inch o.c. in four (4), equally spaced, staggered center rows	FlintPrime QD at stress plates	(Optional) SBS-SA	SBS-SA	-127.5*
HYBRID SYSTEMS:										
W-54.	Min. 15/32-inch plywood, 24-inch span	Min. 1.5-inch, one or more layers, any combination	Prelim. Attach	Glasbase Base Sheet, Flintlastic Base 20, Flintlastic Poly SMS Base Sheet, or Flintlastic Ultra Poly SMS Base Sheet	OMG #14 HD with OMG 3 in. Round Metal Plate or Trufast #12 DP or #14 HD with Trufast 3" Metal Insulation Plate	6-inch o.c. at 4-inch lap and 6-inch o.c. in three (3), equally spaced, staggered center rows	FlintPrime QD at stress plates	SBS-SA-H	SBS-AA, SBS-TA or APP-TA	-97.5
W-55.	Min. 19/32-inch plywood, 24-inch span	Min. 1.5-inch, one or more layers, any combination	Prelim. Attach	Glasbase Base Sheet, Flintlastic Base 20, Flintlastic Poly SMS Base Sheet, or Flintlastic Ultra Poly SMS Base Sheet	3.1.1	7-inch o.c. at 3-inch lap and 7-inch o.c. in three (3), equally spaced, staggered center rows	None	SBS-SA-H	SBS-AA, SBS-TA or APP-TA	-105.0
W-56.	Min. 15/32-inch plywood, 24-inch span	Min. 1.5-inch, one or more layers, any combination	Prelim. Attach	Glasbase Base Sheet, Flintlastic Base 20, Flintlastic Poly SMS Base Sheet, or Flintlastic Ultra Poly SMS Base Sheet	OMG #14 HD with OMG 3 in. Round Metal Plate or Trufast #12 DP or #14 HD with Trufast 3" Metal Insulation Plate	6-inch o.c. at 4-inch lap and 6-inch o.c. in four (4), equally spaced, staggered center rows	FlintPrime QD at stress plates	SBS-SA-H	SBS-AA, SBS-TA or APP-TA	-127.5
CONVENTIONAL SYSTEMS:										
W-57.	Min. 23/32-inch plywood, 24-inch span	Min. 1.5-inch, one or more layers, any combination	Prelim. Attach	Glasbase Base Sheet, All Weather/Empire Base Sheet, Flintlastic Base 20, or Flintglas MS Cap (inverted)	3.1.1	12-inch o.c. at 4-inch lap and 36-inch o.c. in two (2), equally spaced, staggered center rows	None	BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-30.0*
W-58.	Min. 23/32-inch plywood, 24-inch span	Min. 1.5-inch, one or more layers, any combination	Prelim. Attach	Glasbase Base Sheet, All Weather/Empire Base Sheet, Flintlastic Base 20, or Flintglas MS Cap (inverted)	3.1.1	12-inch o.c. at 4-inch lap and 24-inch o.c. in two (2), equally spaced, staggered center rows	None	BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
W-59.	Min. 23/32-inch plywood, 24-inch span	Min. 1.5-inch, one or more layers, any combination	Prelim. Attach	Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base Sheet	3.1.1	12-inch o.c. at 4-inch lap and 36-inch o.c. in two (2), equally spaced, staggered center rows	None	BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*



TABLE 9E: WOOD DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE D-2: INSULATED, MECHANICALLY ATTACHED ANCHOR SHEET, BONDED ROOF COVER

SYSTEM NO.	DECK (4.1.2)	INSULATION LAYER(S) (3.1.2)		ANCHOR SHEET			PRIMER	ROOF COVER (3.1.4)		MDP (PSF)
		TYPE	ATTACH (3.1.3)	TYPE	FASTENER (3.1.1, 4.2.2)	SPACING		BASE	CAP	
W-60.	Min. 15/32-inch plywood, 24-inch span	Min. 1.5-inch, one or more layers, any combination	Prelim. Attach	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base Sheet, or Flintglas MS Cap (inverted)	OMG #14 HD with OMG 3 in. Round Metal Plate or Trufast #12 DP or #14 HD with Trufast 3" Metal Insulation Plate	6-inch o.c. at 4-inch lap and 6-inch o.c. in three (3), equally spaced, staggered center rows	None	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-97.5
W-61.	Min. 15/32-inch plywood, 24-inch span, plywood, 24-inch span	Min. 1.5-inch, one or more layers, any combination	Prelim. Attach	Flintlastic APP Base T	OMG #14 HD with OMG 3 in. Round Metal Plates	6-inch o.c. at 4-inch lap and 6-inch o.c. in three (3), equally spaced, staggered center rows	None	APP-TA	APP-TA	-97.5
W-62.	Min. 15/32-inch plywood, 24-inch span	One or more layers, any thickness or combination	Prelim. Attach	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base Sheet, or Flintglas MS Cap (inverted)	Trufast #14 HD with Trufast 3" Metal Insulation Plate	8-inch o.c. at 4-inch lap and 8-inch o.c. at three (3) equally spaced, staggered center rows	None	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-97.5
W-63.	Min. 19/32-inch plywood, 24-inch span	Min. 1.5-inch, one or more layers, any combination	Prelim. Attach	Glasbase Base Sheet, Flintlastic Base 20, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base Sheet, or Flintglas MS Cap (inverted)	3.1.1	7-inch o.c. at 3-inch lap and 7-inch o.c. in three (3), equally spaced, staggered center rows	None	BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-105.0
W-64.	Min. 19/32-inch plywood, 24-inch span	Min. 1.5-inch, one or more layers, any combination	Prelim. Attach	Flintlastic APP Base T	Dekfast DF-#14-PH3 with PLT-H-2-7/8 or OMG #14 HD with OMG 3 in. Round Metal Plate	7-inch o.c. at 3-inch lap and 7-inch o.c. in three (3), equally spaced, staggered center rows	None	APP-TA	APP-TA	-105.0
W-65.	Min. 15/32-inch plywood, 24-inch span	Min. 1.5-inch, one or more layers, any combination	Prelim. Attach	Glasbase Base Sheet, Flintlastic Base 20, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base Sheet, or Flintglas MS Cap (inverted)	OMG #14 HD with OMG 3 in. Round Metal Plate or Trufast #12 DP or #14 HD with Trufast 3" Metal Insulation Plate	6-inch o.c. at 4-inch lap and 6-inch o.c. in four (4), equally spaced, staggered center rows	None	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-127.5
W-66.	Min. 15/32-inch plywood, 24-inch span	Min. 1.5-inch, one or more layers, any combination	Prelim. Attach	Flintlastic APP Base T	OMG #14 HD with OMG 3 in. Round Metal Plates	6-inch o.c. at 4-inch lap and 6-inch o.c. in four (4), equally spaced, staggered center rows	None	APP-TA	APP-TA	-127.5
COLD-APPLIED SYSTEMS:										
W-67.	Min. 15/32-inch plywood, 24-inch span	Min. 1.5-inch, one or more layers, any combination	Loose laid	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base Sheet, or Flintglas MS Cap (inverted)	Trufast #12 DP or #14 HD with Trufast 3" Metal Insulation Plate	8-inch o.c. at 4-inch lap and 8-inch o.c. in three (3), equally spaced, staggered center rows	None	(Optional) SBS-CA1	SBS-CA1	-52.5



TABLE 9F: WOOD DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE E-2: NON-INSULATED, MECHANICALLY ATTACHED ANCHOR SHEET, BONDED ROOF COVER

SYSTEM No.	DECK (4.1.2)	BASE SHEET			PRIMER	ROOF COVER (3.1.4)		MDP (PSF)
		BASE	FASTENER (3.1.1, 4.2.2)	SPACING		BASE	CAP	
SELF-ADHERING SYSTEMS:								
W-68.	Min. 15/32-inch plywood, 24-inch span,	Flintlastic SA NailBase	Min. 1-inch long, 12 ga. Simplex Metal Cap Nails	6-inch o.c. at min. 2-inch lap and 6-inch o.c. in four (4), equally spaced, staggered center rows	None	(Optional) SBS-SA	SBS-SA	-52.5
W-69.	Min. 19/32-inch plywood, 24-inch span	Flintlastic SA NailBase	32 ga., 1-5/8-inch dia. tin caps with 11 ga. annular ring shank nails	8-inch o.c. at min. 2-inch lap and 8-inch o.c. in three (3), equally spaced, staggered center rows	None	(Optional) SBS-SA	SBS-SA	-52.5
W-70.	Min. 19/32-inch plywood, 24-inch span	Flintlastic SA NailBase	32 ga., 1-5/8-inch dia. tin caps with 11 ga. annular ring shank nails	8-inch o.c. at min. 2-inch lap and 8-inch o.c. in three (3), equally spaced, staggered center rows	None	(Optional) SBS-SA	SBS-SA	-60.0
W-71.	Min. 19/32-inch plywood, 24-inch span	Flintlastic SA NailBase	32 ga., 1-5/8-inch dia. tin caps with 11 ga. annular ring shank nails	6-inch o.c. at min. 2-inch lap and 6-inch o.c. in four (4), equally spaced, staggered center rows	None	(Optional) SBS-SA	SBS-SA	-75.0
W-72.	Min. 15/32-inch plywood, 24-inch span	Flintlastic SA NailBase	Cap nails: 1-inch diameter, 0.032-inch metal cap with 0.120" shank diameter, annular ring shank nails	7-inch o.c. at min. 4-inch laps and 7-inch o.c. in five (5), equally spaced, staggered center rows	None	(Optional) SBS-SA	SBS-SA	-75.0 (NO HVHZ)
W-73.	Min. 19/32-inch plywood, 24-inch span	Flintlastic SA NailBase	32 ga., 1-5/8-inch dia. tin caps with 11 ga. annular ring shank nails	4-inch o.c. at min. 2-inch lap and 4-inch o.c. in four (4), equally spaced, staggered center rows	None	(Optional) SBS-SA	SBS-SA	-105.0
HYBRID SYSTEMS:								
W-74.	Min. 19/32-inch plywood, 24-inch span	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, Flintlastic Poly SMS Base Sheet, or Flintlastic Ultra Poly SMS Base Sheet	32 ga., 1-5/8-inch dia. tin caps with 11 ga. annular ring shank nails	9-inch o.c. at 4-inch lap and 12-inch o.c. in two (2), equally spaced, staggered center rows	None	SBS-SA-H	SBS-AA, SBS-TA or APP-TA	-45.0*
W-75.	Min. 15/32-inch plywood, 24-inch span	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, Flintlastic Poly SMS Base Sheet, or Flintlastic Ultra Poly SMS Base Sheet	Min. 1-inch long, 12 ga. Simplex Metal Cap Nails	6-inch o.c. at 3-inch lap and 6-inch o.c. in four (4), equally spaced, staggered center rows	None	SBS-SA-H	SBS-AA, SBS-TA or APP-TA	-52.5
W-76.	Min. 19/32-inch plywood, 24-inch span	Glasbase Base Sheet, Flintlastic Base 20, Flintlastic Poly SMS Base Sheet, or Flintlastic Ultra Poly SMS Base Sheet	32 ga., 1-5/8-inch dia. tin caps with 11 ga. annular ring shank nails	8-inch o.c. at 4-inch lap and 8-inch o.c. in three (3), equally spaced, staggered center rows	None	SBS-SA-H	SBS-AA, SBS-TA or APP-TA	-52.5
W-77.	Min. 19/32-inch plywood, 24-inch span	Glasbase Base Sheet, Flintlastic Base 20, Flintlastic Poly SMS Base Sheet, or Flintlastic Ultra Poly SMS Base Sheet	32 ga., 1-5/8-inch dia. tin caps with 11 ga. annular ring shank nails	8-inch o.c. at 4-inch lap and 8-inch o.c. in three (3), equally spaced, staggered center rows	None	SBS-SA-H	SBS-AA, SBS-TA or APP-TA	-60.0
W-78.	Min. 19/32-inch plywood, 24-inch span	Glasbase Base Sheet, Flintlastic Base 20, Flintlastic Poly SMS Base Sheet, or Flintlastic Ultra Poly SMS Base Sheet	32 ga., 1-5/8-inch dia. tin caps with 11 ga. annular ring shank nails	6-inch o.c. at 4-inch lap and 6-inch o.c. in four (4), equally spaced, staggered center rows	None	SBS-SA-H	SBS-AA, SBS-TA or APP-TA	-82.5
W-79.	Min. 19/32-inch plywood, 24-inch span	Glasbase Base Sheet, Flintlastic Base 20, Flintlastic Poly SMS Base Sheet, or Flintlastic Ultra Poly SMS Base Sheet	32 ga., 1-5/8-inch dia. tin caps with 11 ga. annular ring shank nails	4-inch o.c. at 3-inch lap and 4-inch o.c. in four (4), equally spaced, staggered center rows	None	SBS-SA-H	SBS-AA, SBS-TA or APP-TA	-105.0
CONVENTIONAL SYSTEMS:								



TABLE 9F: WOOD DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE E-2: NON-INSULATED, MECHANICALLY ATTACHED ANCHOR SHEET, BONDED ROOF COVER

SYSTEM No.	DECK (4.1.2)	BASE SHEET			PRIMER	ROOF COVER (3.1.4)		MDP (PSE)
		BASE	FASTENER (3.1.1, 4.2.2)	SPACING		BASE	CAP	
W-80.	Min. 19/32-inch plywood, 24-inch span	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base Sheet, or Flintglas MS Cap (inverted)	32 ga., 1-5/8-inch dia. tin caps with 11 ga. annular ring shank nails	9-inch o.c. at 4-inch lap and 12-inch o.c. in two (2), equally spaced, staggered center rows	None	BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
W-81.	Min. 15/32-inch plywood, 24-inch span	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base Sheet, or Flintglas MS Cap (inverted)	Min. 1-inch long, 12 ga. Simplex Metal Cap Nails	6-inch o.c. at 3-inch lap and 6-inch o.c. in four (4), equally spaced, staggered center rows	None	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-52.5
W-82.	Min. 19/32-inch plywood, 24-inch span	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base Sheet, or Flintglas MS Cap (inverted)	32 ga., 1-5/8-inch dia. tin caps with 11 ga. annular ring shank nails	8-inch o.c. at 4-inch lap and 8-inch o.c. in three (3), equally spaced, staggered center rows	None	BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-52.5
W-83.	Min. 19/32-inch plywood, 24-inch span	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base Sheet, or Flintglas MS Cap (inverted)	32 ga., 1-5/8-inch dia. tin caps with 11 ga. annular ring shank nails	8-inch o.c. at 4-inch lap and 8-inch o.c. in three (3), equally spaced, staggered center rows	None	BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-60.0
W-84.	Min. 15/32-inch plywood, 24-inch span	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base Sheet, or Flintglas MS Cap (inverted)	Cap nails: 1-inch diameter, 0.032-inch metal cap with 0.120-inch shank diameter, annular ring shank nails.	6-inch o.c. at 4-inch lap and 6-inch o.c. at five (5) equally spaced, staggered center rows	None	(Optional) BP-AA, SBS-AA, or SBS-TA	SBS-AA	-67.5
W-85.	Min. 19/32-inch plywood, 24-inch span	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base Sheet, or Flintglas MS Cap (inverted)	32 ga., 1-5/8-inch dia. tin caps with 11 ga. annular ring shank nails	6-inch o.c. at 4-inch lap and 6-inch o.c. in four (4), equally spaced, staggered center rows	None	BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-82.5
W-86.	Min. 19/32-inch plywood, 24-inch span	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base Sheet, or Flintglas MS Cap (inverted)	32 ga., 1-5/8-inch dia. tin caps with 11 ga. annular ring shank nails	4-inch o.c. at 3-inch lap and 4-inch o.c. in four (4), equally spaced, staggered center rows	None	BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-105.0

TABLE 9G: WOOD DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER
SYSTEM TYPE E-2: NON-INSULATED, MECHANICALLY ATTACHED ANCHOR SHEET, BONDED ROOF COVER

SYSTEM NO.	DECK (4.1.2)	BASE SHEET			PRIMER	ROOF COVER (3.1.4)		MDP (PSF)
		BASE	FASTENER (3.1.1, 4.2.2)	SPACING		BASE	CAP	
SELF-ADHERING SYSTEMS:								
W-87.	APA rated, min. 7/16 CAT, 0.418 in., Exposure 1, OSB, 24-inch span	Flintlastic SA NailBase	Trufast Versa Fastener & Plates, two (2) screws per plate at 180° from each other*	9-inch o.c. at min. 3-inch lap and 12-inch o.c. in two (2), equally spaced, staggered center rows	FlintPrime QD at stress plates	(Optional) Flintlastic SA MidPly, self-adhering	SBS-SA	-60.0*
	Note:	*For re-roof (tear-off) or recover applications, field withdrawal resistance testing (4.2.2) shall yield minimum 109 lbf. Additional Versa-Fast Fasteners within each Versa-Fast Plate may be utilized to produce minimum withdrawal resistance. For recover installations, screws shall be of sufficient length for minimum 1" penetration through OSB sheathing.						
W-88.	Min. 19/32-inch plywood, 24-inch span	Flintlastic SA NailBase	3.1.1	8-inch o.c. at min. 3-inch lap and 8-inch o.c. in two (2), equally spaced, staggered center rows	FlintPrime QD at stress plates	(Optional) SBS-SA	SBS-SA	-82.5*



TABLE 9G: WOOD DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER
SYSTEM TYPE E-2: NON-INSULATED, MECHANICALLY ATTACHED ANCHOR SHEET, BONDED ROOF COVER

SYSTEM No.	DECK (4.1.2)	BASE SHEET			PRIMER	ROOF COVER (3.1.4)		MDP (PSE)
		BASE	FASTENER (3.1.1, 4.2.2)	SPACING		BASE	CAP	
W-89.	Min. 15/32-inch plywood, 24-inch span	Flintlastic SA NailBase	OMG #14 HD with OMG 3 in. Round Metal Plate or Trufast #12 DP or #14 HD with Trufast 3" Metal Insulation Plate	6-inch o.c. at min. 2-inch lap and 6-inch o.c. in three (3), equally spaced, staggered center rows	FlintPrime QD at stress plates	(Optional) SBS-SA	SBS-SA	-97.5*
W-90.	Min. 15/32-inch plywood, 24-inch span	Flintlastic SA NailBase	OMG #14 HD with OMG 3 in. Round Metal Plate or Trufast #12 DP or #14 HD with Trufast 3" Metal Insulation Plate	6-inch o.c. at min. 2-inch lap and 6-inch o.c. in four (4), equally spaced, staggered center rows	FlintPrime QD at stress plates	(Optional) SBS-SA	SBS-SA	-127.5*
HYBRID SYSTEMS:								
W-91.	Min. 15/32-inch plywood, 24-inch span	Glasbase Base Sheet, Flintlastic Base 20, Flintlastic Poly SMS Base Sheet, or Flintlastic Ultra Poly SMS Base Sheet	OMG #14 HD with OMG 3 in. Round Metal Plate or Trufast #12 DP or #14 HD with Trufast 3" Metal Insulation Plate	6-inch o.c. at 4-inch lap and 6-inch o.c. in three (3), equally spaced, staggered center rows	FlintPrime QD at stress plates	SBS-SA-H	SBS-AA, SBS-TA or APP-TA	-97.5
W-92.	Min. 19/32-inch plywood, 24-inch span	Glasbase Base Sheet, Flintlastic Base 20, Flintlastic Poly SMS Base Sheet, or Flintlastic Ultra Poly SMS Base Sheet	3.1.1	7-inch o.c. at 3-inch lap and 7-inch o.c. in three (3), equally spaced, staggered center rows	None	SBS-SA-H	SBS-AA, SBS-TA or APP-TA	-105.0
W-93.	Min. 15/32-inch plywood, 24-inch span	Glasbase Base Sheet, Flintlastic Base 20, Flintlastic Poly SMS Base Sheet, or Flintlastic Ultra Poly SMS Base Sheet	OMG #14 HD with OMG 3 in. Round Metal Plate or Trufast #12 DP or #14 HD with Trufast 3" Metal Insulation Plate	6-inch o.c. at 4-inch lap and 6-inch o.c. in four (4), equally spaced, staggered center rows	FlintPrime QD at stress plates	SBS-SA-H	SBS-AA, SBS-TA or APP-TA	-127.5
CONVENTIONAL SYSTEMS:								
W-94.	Min. 23/32-inch plywood, 24-inch span	Glasbase Base Sheet, All Weather/Empire Base Sheet, Flintlastic Base 20, or Flintglas MS Cap (inverted)	3.1.1	12-inch o.c. at 4-inch lap and 36-inch o.c. in two (2), equally spaced, staggered center rows	None	BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-30.0*
W-95.	Min. 23/32-inch plywood, 24-inch span	Glasbase Base Sheet, All Weather/Empire Base Sheet, Flintlastic Base 20, or Flintglas MS Cap (inverted)	3.1.1	12-inch o.c. at 4-inch lap and 24-inch o.c. in two (2), equally spaced, staggered center rows	None	BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
W-96.	Min. 23/32-inch plywood, 24-inch span	Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base Sheet	3.1.1	12-inch o.c. at 4-inch lap and 36-inch o.c. in two (2), equally spaced, staggered center rows	None	BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
W-97.	Min. 15/32-inch plywood, 24-inch span	Glasbase Base Sheet, Flintlastic Base 20, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base Sheet, or Flintglas MS Cap (inverted)	OMG #14 HD with OMG 3 in. Round Metal Plate or Trufast #12 DP or #14 HD with Trufast 3" Metal Insulation Plate	6-inch o.c. at 4-inch lap and 6-inch o.c. in three (3), equally spaced, staggered center rows	None	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-97.5
W-98.	Min. 15/32-inch plywood, 24-inch span	Flintlastic APP Base T	OMG #14 HD with OMG 3 in. Round Metal Plates	6-inch o.c. at 4-inch lap and 6-inch o.c. in three (3), equally spaced, staggered center rows.	None	APP-TA	APP-TA	-97.5
W-99.	Min. 15/32-inch plywood, 24-inch span	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base Sheet, or Flintglas MS Cap (inverted)	Trufast #14 HD with Trufast 3" Metal Insulation Plate	8-inch o.c. at 4-inch lap and 8-inch o.c. at three (3) equally spaced, staggered center rows	None	(Optional) BP-AA, SBS-AA, or SBS-TA	SBS-AA	-97.5
W-100.	Min. 19/32-inch plywood, 24-inch span	Glasbase Base Sheet, Flintlastic Base 20, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base Sheet, or Flintglas MS Cap (inverted)	3.1.1	7-inch o.c. at 3-inch lap and 7-inch o.c. in three (3), equally spaced, staggered center rows	None	BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-105.0

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 26 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

TABLE 9G: WOOD DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER
SYSTEM TYPE E-2: NON-INSULATED, MECHANICALLY ATTACHED ANCHOR SHEET, BONDED ROOF COVER

SYSTEM No.	DECK (4.1.2)	BASE SHEET			PRIMER	ROOF COVER (3.1.4)		MDP (PSF)
		BASE	FASTENER (3.1.1, 4.2.2)	SPACING		BASE	CAP	
W-101.	Min. 19/32-inch plywood, 24-inch span	Flintlastic APP Base T	Dekfast DF-#14-PH3 with PLT-H-2-7/8 or OMG #14 HD with OMG 3 in. Round Metal Plate	7-inch o.c. at 3-inch lap and 7-inch o.c. in three (3), equally spaced, staggered center rows	None	APP-TA	APP-TA	-105.0
W-102.	Min. 15/32-inch plywood, 24-inch span	Glasbase Base Sheet, Flintlastic Base 20, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base Sheet, or Flintglas MS Cap (inverted)	OMG #14 HD with OMG 3 in. Round Metal Plate or Trufast #12 DP or #14 HD with Trufast 3" Metal Insulation Plate	6-inch o.c. at 4-inch lap and 6-inch o.c. in four (4), equally spaced, staggered center rows	None	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-127.5
W-103.	Min. 15/32-inch plywood, 24-inch span	Flintlastic APP Base T	OMG #14 HD with OMG 3 in. Round Metal Plates	6-inch o.c. at 4-inch lap and 6-inch o.c. in four (4), equally spaced, staggered center rows.	None	APP-TA	APP-TA	-127.5
COLD-APPLIED SYSTEMS:								
W-104.	Min. 15/32-inch plywood, 24-inch span	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, Flintlastic Poly SMS Base Sheet, or Flintlastic Ultra Poly SMS Base Sheet or Flintglas MS Cap (inverted)	Trufast #12 DP or #14 HD with Trufast 3" Metal Insulation Plate	8-inch o.c. at 4-inch lap and 8-inch o.c. in three (3), equally spaced, staggered center rows	None	(Optional) SBS-CA1	SBS-CA1	-52.5

TABLE 9H: WOOD DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER
SYSTEM TYPE F: NON-INSULATED, BONDED ROOF COVER
NOT FOR USE IN FBC HVHZ JURISDICTIONS

SYSTEM NO.	DECK (4.1.2)	PRIMER	ROOF COVER (3.1.4)			MDP (PSF)
			BASE	PLY	CAP	
SELF-ADHERING SYSTEMS:						
W-105.	APA rated, min. 7/16 CAT, 0.418 in., Exposure 1, OSB sheathing, 24-inch span	FlintPrime QD	Flintlastic SA MidPly, self-adhering	(Optional) SBS-SA	SBS-SA	-90.0
W-106.	Min. 15/32-inch plywood, 24-inch span	(Optional) FlintPrime QD	SBS-SA-H	(Optional) SBS-TA, APP-TA	SBS-TA or APP-TA	-127.5
W-107.	Min. 15/32-inch plywood, 24-inch span	(Optional) FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-127.5
W-108.	Min. 15/32-inch plywood, 24-inch span	None	SBS-SA-H	(Optional) SBS-SA-H	SBS-SA	-217.5

TABLE 10A: STEEL OR STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF), OR RECOVER
SYSTEM TYPE B-1: MECHANICALLY ATTACHED BONDED INSULATION, BONDED TOP INSULATION(S), BONDED ROOF COVER
REFER TO [TABLE VB-3](#) FOR THERMAL BARRIER / VAPOR BARRIER COMBINATION OPTIONS

SYSTE M NO.	DECK (4.1.2)	BASE INSULATION LAYER	TOP INSULATION LAYER				ROOF COVER (3.1.4)			MDP (PSF) *
		TYPE	FASTENER (3.1.1, 4.2.2)	ATTACH (3.1.2e)	TYPE	ATTACH (3.1.3)	BASE	PLY	CAP	
SELF-ADHERING SYSTEMS:										
SC-1.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch ACFoam II, ENRGY 3, or H-Shield	3.1.1	1 per 4.0 ft²	Optional min. 1.5-inch additional layer(s) base insulation, followed by min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Hot asphalt, M-OSFA, OB500, Polyset BM, or Polyset CRA	SBS-SA	(Optional) SBS-SA	SBS-SA	-37.5*
SC-2.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch ACFoam II, ENRGY 3, or H-Shield	3.1.1	1 per 2.0 ft²	Optional min. 1.5-inch additional layer(s) base insulation, followed by min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Hot asphalt, M-OSFA, OB500, Polyset BM, or Polyset CRA	SBS-SA	(Optional) SBS-SA	SBS-SA	-45.0*
SC-3.	Min. 22 ga., type B, Grade 40 steel or min. 2,500 psi structural concrete	Min. 2-inch ACFoam II or H-Shield	3.1.1	1 per 2.7 ft²	Min. 2-inch H-Shield HD Composite CG	M-OSFA or M-PG-1	SBS-SA	(Optional) SBS-SA	SBS-SA	-45.0
SC-4.	Min. 22 ga., type B, Grade 40 steel or min. 2,500 psi structural concrete	Min. 2-inch ACFoam II or H-Shield	Dekfast DF-#12-PH3 or Dekfast DF-#14-PH3 with Dekfast PLT-R-3	1 per 2.0 ft²	Min. 2-inch H-Shield HD Composite CG	M-OSFA or M-PG-1	SBS-SA	(Optional) SBS-SA	SBS-SA	-52.5
SC-5.	Min. 22 ga., type B, Grade 80 steel or min. 2,500 psi structural concrete	Min. 2-inch ACFoam II or H-Shield	Dekfast DF-#12-PH3 or Dekfast DF-#14-PH3 with Dekfast PLT-R-3	1 per 1.6 ft²	Min. 2.5-inch H-Shield HD Composite CG	M-OSFA or M-PG-1, 6-inch o.c.	SBS-SA	(Optional) SBS-SA	SBS-SA	-82.5
HYBRID SYSTEMS:										
SC-6.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch ACFoam II, ENRGY 3, or H-Shield	3.1.1	1 per 1.45 ft²	Additional layer(s) base insulation	Hot asphalt, M-OSFA, OB500, Polyset BM, or Polyset CRA	Flintlastic Ultra Glass SA	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-37.5
SC-7.	Min. 22 ga., type B, Grade 40 steel or min. 2,500 psi structural concrete	Min. 2-inch ACFoam II or H-Shield	3.1.1	1 per 2.7 ft²	Min. 2-inch H-Shield HD Composite CG	M-OSFA or M-PG-1	SBS-SA-H	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0
SC-8.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch ACFoam II, ENRGY 3, or H-Shield	3.1.1	1 per 1.45 ft²	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Hot asphalt, M-OSFA, OB500, Polyset BM, or Polyset CRA	Flintlastic Ultra Glass SA	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-52.5
SC-9.	Min. 22 ga., type B, Grade 40 steel or min. 2,500 psi structural concrete	Min. 2-inch ACFoam II or H-Shield	Dekfast DF-#12-PH3 or Dekfast DF-#14-PH3 with Dekfast PLT-R-3	1 per 2.0 ft²	Min. 2-inch H-Shield HD Composite CG	M-OSFA or M-PG-1	SBS-SA-H	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-52.5
SC-10.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch ACFoam II or H-Shield	Trufast #12 DP or #14 HD with Trufast 3" Metal Insulation Plates	1 per 1.45 ft²	Min. 1.5-inch ACFoam II or H-Shield	Hot asphalt, M-OSFA, M-PG-1, or OB500	SBS-SA-H	(Optional) APP-TA	APP-TA	-67.5
SC-11.	Min. 22 ga., type B, Grade 40 steel or min. 2,500 psi structural concrete	Min. 1.5-inch ACFoam II or H-Shield	Trufast #12 DP (steel only) or #14 HD with Trufast 3" Metal Insulation Plate	1 per 1.6 ft²	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA, M-PG-1, or OB500	SBS-SA-H	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-75.0



TABLE 10A: STEEL OR STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF), OR RECOVER
SYSTEM TYPE B-1: MECHANICALLY ATTACHED BONDED INSULATION, BONDED TOP INSULATION(S), BONDED ROOF COVER
 REFER TO [TABLE VB-3](#) FOR THERMAL BARRIER / VAPOR BARRIER COMBINATION OPTIONS

SYSTEM NO.	DECK (4.1.2)	BASE INSULATION LAYER	TOP INSULATION LAYER				ROOF COVER (3.1.4)			MDP (PSF) *
		TYPE	FASTENER (3.1.1, 4.2.2)	ATTACH (3.1.2E)	TYPE	ATTACH (3.1.3)	BASE	PLY	CAP	
SC-12.	Min. 22 ga., type B, Grade 80 steel or min. 2,500 psi structural concrete	Min. 2-inch AC Foam II or H-Shield	Dekfast DF-#12-PH3 or Dekfast DF-#14-PH3 with Dekfast PLT-R-3	1 per 1.6 ft ²	Min. 2.5-inch H-Shield HD Composite CG	M-OSFA or M-PG-1, 6-inch o.c.	SBS-SA-H	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-82.5
SC-13.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch ENRGY 3	Trufast #12 DP (steel only) or #14 HD with Trufast 3" Metal Insulation Plates	1 per 1.0 ft ²	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	OB500, 4-inch o.c.	SBS-SA-H	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-90.0*
CONVENTIONAL SYSTEMS:										
SC-14.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch AC Foam II, ENRGY 3, or H-Shield	3.1.1	1 per 4.0 ft ²	Optional min. 1.5-inch additional layer(s) base insulation, followed by min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Hot asphalt, M-OSFA, OB500, Polyset BM, or Polyset CRA	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-37.5*
SC-15.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch AC Foam II, ENRGY 3, or H-Shield	3.1.1	1 per 2.0 ft ²	Optional min. 1.5-inch additional layer(s) base insulation, followed by min. 0.5-inch Structodek High Density Fiberboard Roof Insulation, min. 0.75-inch FescoBoard (homogeneous).	Hot asphalt	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
SC-16.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch AC Foam II, ENRGY 3, or H-Shield	3.1.1	1 per 2.0 ft ²	Optional min. 1.5-inch additional layer(s) base insulation, followed by min. 0.25-inch DensDeck or DensDeck Prime	Hot asphalt	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
SC-17.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch AC Foam II, ENRGY 3, or H-Shield	3.1.1	1 per 2.0 ft ²	Optional min. 1.5-inch additional layer(s) base insulation, followed by min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Hot asphalt, M-OSFA, OB500, Polyset BM, or Polyset CRA	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
SC-18.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch AC Foam II, ENRGY 3, or H-Shield	3.1.1	1 per 3.2 ft ²	Optional min. 1.5-inch additional layer(s) base insulation, followed by min. 0.5-inch Structodek High Density Fiberboard Roof Insulation, min. 0.75-inch FescoBoard (homogeneous).	Hot asphalt	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 29 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

TABLE 10A: STEEL OR STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF), OR RECOVER
SYSTEM TYPE B-1: MECHANICALLY ATTACHED BONDED INSULATION, BONDED TOP INSULATION(S), BONDED ROOF COVER
 REFER TO [TABLE VB-3](#) FOR THERMAL BARRIER / VAPOR BARRIER COMBINATION OPTIONS

SYSTEM NO.	DECK (4.1.2)	BASE INSULATION LAYER	TOP INSULATION LAYER				ROOF COVER (3.1.4)			MDP (PSF)*
		TYPE	FASTENER (3.1.1, 4.2.2)	ATTACH (3.1.2E)	TYPE	ATTACH (3.1.3)	BASE	PLY	CAP	
SC-19.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch AC Foam II, ENRGY 3, or H-Shield	3.1.1	1 per 3.2 ft ²	Optional min. 1.5-inch additional layer(s) base insulation, followed by min. 0.25-inch DensDeck or DensDeck Prime	Hot asphalt	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
SC-20.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch AC Foam II, ENRGY 3, or Multi-Max FA3	3.1.1	1 per 1.3 ft ²	Min. 0.75-inch FescoBoard (homogeneous)	Hot asphalt	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-52.5
SC-21.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch AC Foam II, ENRGY 3, or H-Shield	3.1.1	1 per 1.6 ft ²	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Hot asphalt, M-OSFA, OB500, Polyset BM, or Polyset CRA	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-60.0
SC-22.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch AC Foam II, ENRGY 3, or Multi-Max FA3	3.1.1	1 per 1.3 ft ²	Min. 0.5-inch Structodek High Density Fiberboard	Hot asphalt	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-67.5
SC-23.	Min. 22 ga., type B, Grade 40 steel or min. 2,500 psi structural concrete	Min. 1.5-inch AC Foam II or H-Shield	Trufast #12 DP (steel only) or #14 HD with Trufast 3" Metal Insulation Plate	1 per 1.6 ft ²	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA, M-PG-1, or OB500	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-75.0
SC-24.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch ENRGY 3	Trufast #12 DP (steel only) or #14 HD with Trufast 3" Metal Insulation Plate	1 per 1.0 ft ²	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	OB500, 4-inch o.c.	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-90.0*
COLD-APPLIED SYSTEMS:										
SC-25.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch AC Foam II or H-Shield	Trufast #12 DP (steel only) or #14 HD with Trufast 3" Metal Insulation Plate	1 per 2.0 ft ²	Min. 1.5-inch AC Foam III or H-Shield CG	OB500 or Polyset CRA	SBS-CA1	None	SBS-CA1	-45.0*
SC-26.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch AC Foam II or H-Shield	Trufast #12 DP (steel only) or #14 HD with Trufast 3" Metal Insulation Plate	1 per 2.0 ft ²	Optional min. 1.5-inch additional layer(s) base insulation, followed by min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA, M-PG-1, OB500, Polyset BM, or Polyset CRA	SBS-CA1	None	SBS-CA1	-45.0*
SC-27.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch AC Foam II or H-Shield	Trufast #12 DP (steel only) or #14 HD with Trufast 3" Metal Insulation Plate	1 per 2.0 ft ²	Optional min. 1.5-inch additional layer(s) base insulation, followed by min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA, M-PG-1, OB500, Polyset BM, or Polyset CRA	SBS-CA4	None	SBS-CA4	-45.0*
SC-28.	Min. 22 ga., type B, Grade 40 steel or min. 2,500 psi structural concrete	Min. 2-inch AC Foam II or H-Shield	3.1.1	1 per 2.7 ft ²	Min. 2-inch H-Shield HD Composite CG	M-OSFA or M-PG-1	SBS-CA4	None	SBS-CA4	-45.0

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 30 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

TABLE 10A: STEEL OR STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF), OR RECOVER
SYSTEM TYPE B-1: MECHANICALLY ATTACHED BONDED INSULATION, BONDED TOP INSULATION(S), BONDED ROOF COVER
 REFER TO [TABLE VB-3](#) FOR THERMAL BARRIER / VAPOR BARRIER COMBINATION OPTIONS

SYSTEM NO.	DECK (4.1.2)	BASE INSULATION LAYER	TOP INSULATION LAYER				ROOF COVER (3.1.4)			MDP (PSF)*
		TYPE	FASTENER (3.1.1, 4.2.2)	ATTACH (3.1.2E)	TYPE	ATTACH (3.1.3)	BASE	PLY	CAP	
SC-29.	Min. 22 ga., type B, Grade 40 steel or min. 2,500 psi structural concrete	Min. 1.5-inch ACFoam II or H-Shield	Trufast #12 DP (steel only) or #14 HD with Trufast 3" Metal Insulation Plate	1 per 1.6 ft ²	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA, M-PG-1, or OB500	SBS-CA1	None	SBS-CA1	-75.0
SC-30.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch ENRGY 3	Trufast #12 DP (steel only) or #14 HD with Trufast 3" Metal Insulation Plate	1 per 1.0 ft ²	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	OB500, 4-inch o.c.	SBS-CA1	None	SBS-CA1	-90.0*

TABLE 10B: STEEL OR STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF), OR RECOVER
SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER

SYSTEM NO.	DECK (4.1.2)	BASE INSULATION LAYER(S) (3.1.2)	TOP INSULATION LAYER			PRIMER	ROOF COVER (3.1.4)			MDP (PSF)
			TYPE	FASTENER (3.1.1, 4.2.2)	ATTACH (3.1.3)		BASE	PLY	CAP	
SELF-ADHERING SYSTEMS:										
SC-31.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	3.1.1	1 per 3.2 ft²	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-30.0*
SC-32.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Trufast #12 DP (steel only) or #14 HD with Trufast 3” Metal Insulation Plate	1 per 2.7 ft²	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-37.5*
SC-33.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 3/8-inch SECUROCK Gypsum-Fiber Roof Board	3.1.1	1 per 2.7 ft²	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-45.0*
SC-34.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 0.25-inch DensDeck	3.1.1	1 per 1.3 ft²	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-45.0
SC-35.	Min. 22 ga., type B, Grade 40 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch ACFoam II	Trufast #14 HD with Trufast 3” Metal Insulation Plate	1 per 1.8 ft²	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-67.5
SC-36.	Min. 22 ga., type B, Grade 40 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Trufast #14 HD with Trufast 3” Metal Insulation Plate	1 per 1.6 ft²	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-82.5
SC-37.	Min. 22 ga., type B, Grade 40 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch ACFoam II or H-Shield	Trufast #15 EHD (steel only) or Trufast #14 HD (concrete only) with Trufast 3” Metal Insulation Plate	1 per 1.0 ft²	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-97.5
HYBRID SYSTEMS:										
SC-38.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 0.25-inch DensDeck, DensDeck Prime	3.1.1	1 per 2.0 ft²	None	SBS-SA-H	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-30.0*

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 31 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

**TABLE 10b: STEEL OR STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF), OR RECOVER
SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER**

SYSTEM NO.	DECK (4.1.2)	BASE INSULATION LAYER(S) (3.1.2)	TOP INSULATION LAYER			PRIMER	ROOF COVER (3.1.4)			MDP (PSE)
			TYPE	FASTENER (3.1.1, 4.2.2)	ATTACH (3.1.3)		BASE	PLY	CAP	
SC-39.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Trufast #12 DP (steel only) or #14 HD with Trufast 3" Metal Insulation Plate	1 per 2.7 ft ²	None	SBS-SA-H	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-37.5*
SC-40.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 3/8-inch SECUROCK Gypsum-Fiber Roof Board	Trufast #12 DP (steel only) or #14 HD with Trufast 3" Metal Insulation Plate	1 per 2.7 ft ²	None	SBS-SA-H	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
SC-41.	Min. 22 ga., type B, Grade 40 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch ACFoam II	Trufast #14 HD with Trufast 3" Metal Insulation Plate	1 per 1.8 ft ²	None	SBS-SA-H	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-67.5
SC-42.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch ACFoam II or H-Shield	Trufast #12 DP (steel only) or Trufast #14 HD with Trufast 3" Metal Insulation Plate	1 per 1.45 ft ²	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-75.0
SC-43.	Min. 22 ga., type B, Grade 40 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Trufast #14 HD with Trufast 3" Metal Insulation Plate	1 per 1.6 ft ²	None	SBS-SA-H	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-82.5
SC-44.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Trufast #12 DP (steel only) or #14 HD with Trufast 3" Metal Insulation Plate	1 per 1.45 ft ²	None	SBS-SA-H	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-82.5
SC-45.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch ACFoam II, ENRGY 3, or Multi-Max FA3	3.1.1	1 per 1.3 ft ²	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-82.5
SC-46.	Min. 22 ga., type B, Grade 40 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch ACFoam II or H-Shield	Trufast #15 EHD (steel only) or Trufast #14 HD (concrete only) with Trufast 3" Metal Insulation Plate	1 per 1.0 ft ²	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-97.5
SC-47.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Trufast #12 DP (steel only) or #14 HD with Trufast 3" Metal Insulation Plate	1 per 1.0 ft ²	None	SBS-SA-H	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-135.0
CONVENTIONAL SYSTEMS:										
SC-48.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 0.75-inch FescoBoard (homogeneous)	3.1.1	1 per 2.7 ft ²	None	BP-AA, SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-30.0*
SC-49.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch Structodek High Density Fiberboard Roof Insulation	3.1.1	1 per 4.0 ft ²	None	BP-AA, SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-37.5*
SC-50.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	3.1.1	1 per 4.0 ft ²	None	BP-AA, SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-37.5*

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 32 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

**TABLE 10b: STEEL OR STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF), OR RECOVER
SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER**

SYSTEM NO.	DECK (4.1.2)	BASE INSULATION LAYER(S) (3.1.2)	TOP INSULATION LAYER			PRIMER	ROOF COVER (3.1.4)			MDP (PSF)
			TYPE	FASTENER (3.1.1, 4.2.2)	ATTACH (3.1.3)		BASE	PLY	CAP	
SC-51.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	3.1.1	1 per 4.0 ft ²	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
SC-52.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch Structodek High Density Fiberboard Roof Insulation, min. 0.75-inch FescoBoard (homogeneous)	3.1.1	1 per 2.0 ft ²	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
SC-53.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 0.25-inch DensDeck or DensDeck Prime	3.1.1	1 per 2.0 ft ²	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
SC-54.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch, One or more layers, any combination, loose laid	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board		1 per 1.45 ft ²	None	APP-TA	(Optional) APP-TA	APP-TA	-60.0
SC-55.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch ACFoam II, ENRGY 3 or H-Shield, loose laid.	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	3.1.1	1 per 1.8 ft ²	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-60.0
SC-56.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board		1 per 1.45 ft ²	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-82.5
SC-57.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch ACFoam II or H-Shield	Min. 0.5-inch DensDeck Prime		1 per 1.3 ft ²	None	BP-AA, SBS-AA	(Optional) BP-AA, SBS-AA	SBS-AA	-112.5
SC-58.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board		1 per 1.0 ft ²	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-135.0
SC-59.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch ACFoam II or H-Shield	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board		1 per 1.3 ft ²	None	BP-AA, SBS-AA	(Optional) BP-AA, SBS-AA	SBS-AA	-157.5
SC-60.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch ACFoam II or H-Shield	Min. 0.5-inch DensDeck Prime		1 per 1.0 ft ²	None	BP-AA, SBS-AA	(Optional) BP-AA, SBS-AA	SBS-AA	-157.5
SC-61.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch ACFoam II or H-Shield	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board		1 per 1.0 ft ²	None	BP-AA, SBS-AA	(Optional) BP-AA, SBS-AA	SBS-AA	-172.5

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 33 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

**TABLE 10b: STEEL OR STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF), OR RECOVER
SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER**

SYSTEM NO.	DECK (4.1.2)	BASE INSULATION LAYER(S) (3.1.2)	TOP INSULATION LAYER			PRIMER	ROOF COVER (3.1.4)			MDP (PSF)
			TYPE	FASTENER (3.1.1, 4.2.2)	ATTACH (3.1.3)		BASE	PLY	CAP	
SPOT- OR STRIP-MOPPED SYSTEMS:										
SC-62.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 2-inch ACFoam II or ENRGY 3	3.1.1	1 per 1.6 ft²	None	BP-AA2	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-37.5*
SC-63.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 1-inch FescoBoard (homogeneous) or min. 1.5-inch FescoBoard (laminated)	3.1.1	1 per 1.6 ft²	None	BP-AA2	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
SC-64.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch Structodek HD with Primed Red Coating	3.1.1	1 per 2.0 ft²	None	BP-AA2	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
SC-65.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch ACFoam II	3.1.1	1 per 1.45 ft²	None	BP-AA3, 24-inch grid	(Optional) BP-AA or SBS-AA	SBS-AA	-52.5
SC-66.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch ACFoam II	3.1.1	1 per 1.45 ft²	None	BP-AA3, 24-inch grid	BP-AA or SBS-AA	SBS-TA	-52.5
COLD-APPLIED SYSTEMS:										
SC-67.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Trufast #12 DP (steel only) or #14 HD with Trufast 3” Metal Insulation Plate	1 per 2.7 ft²	None	SBS-CA1	None	SBS-CA1	-37.5*
SC-68.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Trufast #12 DP (steel only) or #14 HD with Trufast 3” Metal Insulation Plates	1 per 2.7 ft²	None	SBS-CA4	None	SBS-CA4	-37.5*
SC-69.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch ACFoam III or H-Shield CG	Trufast #12 DP (steel only) or #14 HD with Trufast 3” Metal Insulation Plates	1 per 2.0 ft²	None	SBS-CA1	None	SBS-CA1	-45.0*
SC-70.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 3/8-inch SECUROCK Gypsum-Fiber Roof Board	Trufast #12 DP (steel only) or #14 HD with Trufast 3” Metal Insulation Plates	1 per 2.7 ft²	None	SBS-CA1	None	SBS-CA1	-45.0*
SC-71.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 3/8-inch SECUROCK Gypsum-Fiber Roof Board	Trufast #12 DP (steel only) or #14 HD with Trufast 3” Metal Insulation Plates	1 per 2.7 ft²	None	SBS-CA4	None	SBS-CA4	-45.0*
SC-72.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Trufast #12 DP (steel only) or #14 HD with Trufast 3” Metal Insulation Plates	1 per 1.45 ft²	None	SBS-CA1	None	SBS-CA1	-82.5*



TABLE 10c: STEEL OR STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF), OR RECOVER
SYSTEM TYPE D-2: INSULATED, MECHANICALLY ATTACHED ANCHOR SHEET, BONDED ROOF COVER

SYSTEM NO.	DECK (4.1.2)	INSULATION LAYER(S) (3.1.2)		ANCHOR SHEET			ROOF COVER (3.1.4)		MDP (PSF)
		TYPE	ATTACH (3.1.3)	TYPE	FASTENER (3.1.1, 4.2.2)	SPACING	BASE	CAP	
SELF-ADHERING SYSTEMS:									
SC-73.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. Attached	Flintlastic SA NailBase	3.1.1	9-inch o.c. at min. 2-inch lap and 18-inch o.c. in two (2), equally spaced, staggered center rows	(Optional) SBS-SA	SBS-SA	-45.0*
SC-74.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. Attached	Flintlastic SA NailBase	3.1.1	12-inch o.c. at min. 2-inch lap and 12-inch o.c. in two (2), equally spaced, staggered center rows	(Optional) SBS-SA	SBS-SA	-52.5*
SC-75.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. Attached	Flintlastic SA NailBase	3.1.1	12-inch o.c. at min. 4-inch lap and 12-inch o.c. in two (2), equally spaced, staggered center rows	(Optional) SBS-SA	SBS-SA	-60.0*
SC-76.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. Attached	Flintlastic SA NailBase (laid parallel to deck flutes)	3.1.1	8-inch o.c. at min. 4-inch lap and 8-inch o.c. in two (2), equally spaced, staggered center rows, FlintPrime QD at stress plates	(Optional) SBS-SA	SBS-SA	-82.5*
CONVENTIONAL SYSTEMS:									
SC-77.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. Attached	Glasbase Base Sheet, All Weather/Empire Base Sheet, Flintlastic Base 20 or Flintglas MS Cap (inverted)	3.1.1	12-inch o.c. at 4-inch lap and 36-inch o.c. in two (2), equally spaced, staggered center rows	BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-30.0*
SC-78.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. Attached	Glasbase Base Sheet, All Weather/Empire Base Sheet, Flintlastic Base 20, or Flintglas MS Cap (inverted)	3.1.1	12-inch o.c. at 4-inch lap and 24-inch o.c. in two (2), equally spaced, staggered center rows	BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
SC-79.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. Attached	Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base Sheet	3.1.1	12-inch o.c. at 4-inch lap and 36-inch o.c. in two (2), equally spaced, staggered center rows	BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
SC-80.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. Attached	Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base Sheet	3.1.1	18-inch o.c. at 4-inch lap and 18-inch o.c. in one (1) staggered center row	BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
SC-81.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. Attached	Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base Sheet	Dekfast DF-#14-PH3 with PLT-R-2-4B	12-inch o.c. within the min. 4-inch wide, heat-welded side lap	SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
SC-82.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. Attached	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, Flintlastic Poly SMS Base Sheet, or Flintglas MS Cap (inverted)	3.1.1	12-inch o.c. at 3-inch lap and 12-inch o.c. in two (2), equally spaced, staggered center rows	BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-52.5



TABLE 10c: STEEL OR STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF), OR RECOVER
SYSTEM TYPE D-2: INSULATED, MECHANICALLY ATTACHED ANCHOR SHEET, BONDED ROOF COVER

SYSTEM NO.	DECK (4.1.2)	INSULATION LAYER(S) (3.1.2)		ANCHOR SHEET			ROOF COVER (3.1.4)		MDP (PSF)
		TYPE	ATTACH (3.1.3)	TYPE	FASTENER (3.1.1, 4.2.2)	SPACING	BASE	CAP	
SC-83.	Min. 22 ga., type B, 40 ksi steel or min. 2,500 psi structural concrete	Min. 2-inch, one or more layers, any combination	Prelim. Attached	Flintlastic Ultra Poly SMS Base Sheet	Trufast #15 EHD (steel only) or Trufast #14 HD (concrete only) with Trufast 2" Barbed Metal Seam Plate	12-inch o.c. within the min. 4-inch wide, heat-welded side lap	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-52.5
SC-84.	Min. 22 ga., type B, Grade 80 steel or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. Attached	Flintlastic Ultra Poly SMS Base Sheet	Trufast #15 EHD (steel only) or Trufast #14 HD (concrete only) with Trufast 2.4" Barbed Metal Seam Plate	12-inch o.c. within the min. 4-inch wide, heat-welded side lap	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-60.0
SC-85.	Min. 22 ga., type B, 40 ksi steel or min. 2,500 psi structural concrete	Min. 2-inch, one or more layers, any combination	Prelim. Attached	Flintlastic Ultra Poly SMS Base Sheet	Trufast #15 EHD (steel only) or Trufast #14 HD (concrete only) with Trufast 2.4" Scoop Seam Plate	12-inch o.c. within the min. 4-inch wide, heat-welded side lap	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-67.5
SC-86.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. Attached	Glasbase Base Sheet or Flintglas MS Cap (inverted)	OMG #14 HD with OMG Flat Bottom Plates (AccuTrac)	6-inch o.c. at 4-inch lap and 6-inch o.c. in two (2), equally spaced, staggered center rows	BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-67.5
SC-87.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. Attached	Flintlastic Base 20 or Flintglas MS Cap (inverted)	3.1.1	6-inch o.c. at 4-inch lap and 6-inch o.c. in two (2), equally spaced, staggered center rows	BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-67.5
SC-88.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. Attach	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base Sheet, or Flintglas MS Cap (inverted)	Trufast #14 HD with Trufast 3" Metal Insulation Plate	6-inch o.c. at 4-inch lap and 6-inch o.c. at three (3) equally spaced, staggered center rows	(Optional) BP-AA, SBS-AA, or SBS-TA	SBS-AA	-97.5
SC-89.	Min. 22 ga., type B, 40 ksi steel or min. 2,500 psi structural concrete	Min. 2-inch, one or more layers, any combination	Prelim. Attached	Flintlastic Ultra Poly SMS Base Sheet	Trufast #15 EHD (steel only) or Trufast #14 HD (concrete only) with Trufast 2.4" Scoop Seam Plate	6-inch o.c. within the min. 4-inch wide, heat-welded side lap	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-112.5
SC-90.	Min. 22 ga., type B, Grade 80 steel or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. Attached	Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base Sheet	3.1.1	12-inch o.c. at 4-inch lap and 12-inch o.c. in two (2), equally spaced, staggered center rows	SBS-TA or APP-TA	APP-TA	-112.5

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 36 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

**TABLE 10c: STEEL OR STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF), OR RECOVER
SYSTEM TYPE D-2: INSULATED, MECHANICALLY ATTACHED ANCHOR SHEET, BONDED ROOF COVER**

SYSTEM NO.	DECK (4.1.2)	INSULATION LAYER(S) (3.1.2)		ANCHOR SHEET			ROOF COVER (3.1.4)		MDP (PSF)
		TYPE	ATTACH (3.1.3)	TYPE	FASTENER (3.1.1, 4.2.2)	SPACING	BASE	CAP	
SC-91.	Min. 22 ga., type B, Grade 80 steel or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. Attached	Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base Sheet	3.1.1	12-inch o.c. at 4-inch lap and 12-inch o.c. in two (2), equally spaced, staggered center rows	SBS-AA	SBS-AA	-120.0
SC-92.	Min. 22 ga., type B, 40 ksi steel or min. 2,500 psi structural concrete	Min. 2-inch, one or more layers, any combination	Prelim. Attached	Flintlastic Ultra Poly SMS Base Sheet	Trufast #15 EHD (steel only) or Trufast #14 HD (concrete only) with Trufast 2.4" Scoop Seam Plate	6-inch o.c. within the min. 4-inch wide, heat-welded side laps and 6-inch o.c. in one (1) center row, stripped-in with 6-inch side strips of torch-applied Flintlastic Poly SMS Base Sheet or Flintlastic Ultra Poly SMS Base Sheet.	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-165.0
COLD-APPLIED SYSTEMS:									
SC-93.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. Attached	Glasbase Base Sheet, All Weather/Empire Base Sheet, or Flintlastic Base 20	3.1.1	6-inch o.c. at 4-inch lap and 12-inch o.c. in two (2), equally spaced, staggered center rows	SBS-CA1	SBS-CA1	-45.0*
SC-94.	Min. 22 ga., type B, Grade 40 steel or min. 2,500 psi structural concrete	Min. 1-inch, one or more layers, any combination	Loose laid	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, Flintlastic Poly SMS Base Sheet, or Flintlastic Ultra Poly SMS Base Sheet	Trufast #14 HD with Trufast 3" Metal Insulation Plate	6-inch o.c. at 4-inch lap and 12-inch o.c. in three (3), equally spaced, staggered center rows	(Optional) SBS-CA1	SBS-CA1	-75.0

**TABLE 11A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER**REFER TO [TABLE VB-3](#) FOR VAPOR BARRIER OPTIONS

SYSTEM No.	DECK (4.1.2)	PRIMER	BASE INSULATION LAYER		TOP INSULATION LAYER		PRIMER	ROOF COVER (3.1.4)			MDP (psf)
			TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
SELF-ADHERING SYSTEMS:											
C-1.	Structural concrete	FlintPrime QD	Min. 1.5-inch ACFoam II, ENRGY 3 or H-Shield	Hot asphalt	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Hot asphalt	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-172.5
C-2.	Structural concrete	FlintPrime QD	Min. 1.5-inch ACFoam II, ENRGY 3 or Multi-Max FA3	Hot asphalt	Min. 0.25-inch DensDeck	Hot asphalt	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-192.5
C-3.	Structural concrete	None	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1	Min. 0.5-inch ACFoam-HD CoverBoard or H-Shield HD	M-OSFA or M-PG-1	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-97.5
C-4.	Structural concrete	None	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1	Min. 2-inch H-Shield HD Composite CG	M-OSFA or M-PG-1	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-142.5
C-5.	Structural concrete	None	Min. 1.5-inch ACFoam II, ENRGY 3 or H-Shield	M-OSFA or M-PG-1	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-172.5
C-6.	Structural concrete	None	Min. 1.5-inch ACFoam II, ENRGY 3 or Multi-Max FA3	M-OSFA or M-PG-1	Min. 0.25-inch DensDeck	M-OSFA or M-PG-1	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-192.5



TABLE 11A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER
 REFER TO [TABLE VB-3](#) FOR VAPOR BARRIER OPTIONS

SYSTEM No.	DECK (4.1.2)	PRIMER	BASE INSULATION LAYER		TOP INSULATION LAYER		PRIMER	ROOF COVER (3.1.4)			MDP (PSE)
			TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
C-7.	Structural concrete	None	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1, 6-inch o.c.	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1, 6-inch o.c.	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-315.0
C-8.	Structural concrete	None	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1, 6-inch o.c.	Min. 0.5-inch ACFoam-HD CoverBoard or H-Shield HD	M-OSFA or M-PG-1, 6-inch o.c.	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-315.0
C-9.	Structural concrete	None	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1, 6-inch o.c.	Min. 2-inch H-Shield HD Composite CG	M-OSFA or M-PG-1, 6-inch o.c.	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-342.5
C-10.	Structural concrete	None	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-PG1-EF-ECO	Min. 0.5-inch H-Shield HD	M-PG1-EF-ECO	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-97.5
C-11.	Structural concrete	None	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-PG1-EF-ECO	Min. 2-inch H-Shield HD Composite CG	M-PG1-EF-ECO	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-142.5
C-12.	Structural concrete	None	Min. 1.5-inch ACFoam II, ENRGY 3 or H-Shield	M-PG1-EF-ECO	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-PG1-EF-ECO	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-172.5
C-13.	Structural concrete	FlintPrime QD	Min. 1.5-inch ACFoam II or ENRGY 3	OB500	Min. 0.25-inch DensDeck	OB500	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-120.0
C-14.	Structural concrete	None	Min. 1.5-inch ACFoam II or ENRGY 3	OB500	Min. 0.25-inch DensDeck	OB500	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-150.0
C-15.	Structural concrete	None	Min. 1.5-inch ACFoam II, ENRGY 3 or H-Shield	OB500	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-172.5
C-16.	Structural concrete	None	Min. 1-inch ENRGY 3, H-Shield or H-Shield CG or min. 1.5-inch Multi-Max FA3 or Ultra-Max	Polyset BM or Polyset CRA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset BM or Polyset CRA	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-172.5
C-17.	Structural concrete	None	Min. 1-inch ENRGY 3, H-Shield or H-Shield CG or min. 1.5-inch Multi-Max FA3 or Ultra-Max	Polyset BM or Polyset CRA	Min. 0.25-inch DensDeck	Polyset BM or Polyset CRA	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-192.5
HYBRID SYSTEMS:											
C-18.	Structural concrete	FlintPrime QD	Min. 1.5-inch ACFoam II or H-Shield	Hot asphalt	(Optional) Additional layer(s) base insulation	Hot asphalt	None	Flintlastic Ultra Glass SA	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-322.5
C-19.	Structural concrete	FlintPrime QD	Min. 1.5-inch ACFoam II or H-Shield	Hot asphalt	(Optional) Additional layer(s) base insulation	Hot asphalt	None	Black Diamond Base Sheet	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-375.0
C-20.	Structural concrete	None	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1	Min. 0.5-inch ACFoam-HD CoverBoard or H-Shield HD	M-OSFA or M-PG-1	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-97.5
C-21.	Structural concrete	None	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1	Min. 2-inch H-Shield HD Composite CG	M-OSFA or M-PG-1	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-142.5



TABLE 11A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER
 REFER TO [TABLE VB-3](#) FOR VAPOR BARRIER OPTIONS

SYSTEM No.	DECK (4.1.2)	PRIMER	BASE INSULATION LAYER		TOP INSULATION LAYER		PRIMER	ROOF COVER (3.1.4)			MDP (pse)
			TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
C-22.	Structural concrete	None	Min. 1.5-inch AC Foam II or H-Shield	M-OSFA	(Optional) Additional layer(s) base insulation	M-OSFA	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-232.5
C-23.	Structural concrete	None	Min. 1.5-inch AC Foam II or H-Shield	M-OSFA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-217.5
C-24.	Structural concrete	None	Min. 1-inch Styrofoam Brand Roofmate	M-OSFA or M-PG-1	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-210.0
C-25.	Structural concrete	None	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA	None	N/A	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-195.0
C-26.	Structural concrete	None	Min. 1.5-inch AC Foam II or H-Shield	M-PG-1	(Optional) Additional layer(s) base insulation	M-PG-1	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-270.0
C-27.	Structural concrete	None	Min. 1.5-inch AC Foam II or H-Shield	M-PG-1	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-PG-1	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-217.5
C-28.	Structural concrete	None	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-PG-1	None	N/A	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-195.0
C-29.	Structural concrete	None	(Optional) Min. 1.5-inch AC Foam II or H-Shield	M-OSFA or M-PG-1, 6-inch o.c.	Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch AC Foam-HD CoverBoard or H-Shield HD	M-OSFA or M-PG-1, 6-inch o.c.	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-315.0
C-30.	Structural concrete	None	(Optional) Min. 1.5-inch AC Foam II or H-Shield	M-OSFA or M-PG-1, 6-inch o.c.	Min. 2-inch H-Shield HD Composite CG	M-OSFA or M-PG-1, 6-inch o.c.	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-342.5
C-31.	Structural concrete	None	(Optional) Min. 1.5-inch AC Foam II or H-Shield	M-PG1-EF-ECO	Min. 0.5-inch H-Shield HD	M-PG1-EF-ECO	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-97.5
C-32.	Structural concrete	None	(Optional) Min. 1.5-inch AC Foam II or H-Shield	M-PG1-EF-ECO	Min. 2-inch H-Shield HD Composite CG	M-PG1-EF-ECO	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-142.5
C-33.	Structural concrete	None	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-PG1-EF-ECO	None	N/A	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-195.0
C-34.	Structural concrete	None	Min. 1.5-inch AC Foam II or H-Shield	M-PG1-EF-ECO	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-PG1-EF-ECO	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-217.5



TABLE 11A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER
 REFER TO [TABLE VB-3](#) FOR VAPOR BARRIER OPTIONS

SYSTEM No.	DECK (4.1.2)	PRIMER	BASE INSULATION LAYER		TOP INSULATION LAYER		PRIMER	ROOF COVER (3.1.4)			MDP (psf)
			TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
C-35.	Structural concrete	None	Min. 1.5-inch ACFoam II or H-Shield	M-PG1-EF-ECO	(Optional) Additional layer(s) base insulation	M-PG1-EF-ECO	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-247.5
C-36.	Structural concrete	None	Min. 1.5-inch ACFoam II or H-Shield	OB500	(Optional) Additional layer(s) base insulation	OB500	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-135.0
C-37.	Structural concrete	None	Min. 1.5-inch ACFoam II or H-Shield	OB500	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-217.5
C-38.	Structural concrete	None	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	None	N/A	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-195.0
C-39.	Structural concrete	None	Min. 1.5-inch ACFoam II or H-Shield	Polyset BM or Polyset CRA	(Optional) Additional layer(s) base insulation	Polyset BM or Polyset CRA	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-270.0
C-40.	Structural concrete	None	Min. 1.5-inch ACFoam II or H-Shield	Polyset BM or Polyset CRA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset BM or Polyset CRA	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-217.5
C-41.	Structural concrete	None	Min. 1.5-inch, min. 1.5 pcf Insulfoam II Roofing EPS	Polyset CRA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset CRA	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-180.0
C-42.	Structural concrete	None	Min. 1.5-inch, min. 2.0 pcf Insulfoam IX Roofing EPS	Polyset CRA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset CRA	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-217.5
C-43.	Structural concrete	None	Min. 1.5-inch Styrofoam Brand Roofmate	Polyset CRA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset CRA	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-217.5
C-44.	Structural concrete	None	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset BM or Polyset CRA	None	N/A	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-195.0
CONVENTIONAL SYSTEMS:											
C-45.	Structural concrete	FlintPrime QD	Min. 1.5-inch ACFoam II	Hot asphalt	Min. 0.25-inch DensDeck, DensDeck Prime	Hot asphalt	None	SBS-TA	(Optional) SBS-TA	SBS-TA	-180.0
C-46.	Structural concrete	FlintPrime QD	(Optional) Min. 1.5-inch ACFoam II	Hot asphalt	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Hot asphalt	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-180.0
C-47.	Structural concrete	FlintPrime QD	(Optional) Min. 2-inch ACFoam II, ENRGY 3 or H-Shield	Hot asphalt	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Hot asphalt	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-225.0
C-48.	Structural concrete	FlintPrime QD	(Optional) Min. 1.5-inch ACFoam II or H-Shield	Hot asphalt	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Hot asphalt	None	APP-TA	(Optional) APP-TA	APP-TA	-252.5



TABLE 11A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER
 REFER TO [TABLE VB-3](#) FOR VAPOR BARRIER OPTIONS

SYSTEM No.	DECK (4.1.2)	PRIMER	BASE INSULATION LAYER		TOP INSULATION LAYER		PRIMER	ROOF COVER (3.1.4)			MDP (PSE)
			TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
C-49.	Structural concrete	FlintPrime QD	Min. 1.5-inch ACFoam II, ENRGY 3 or H-Shield	Hot asphalt	Min. 0.5-inch Structodek High Density Fiberboard	Hot asphalt	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-227.0
C-50.	Structural concrete	FlintPrime QD	(Optional) Min. 2-inch ACFoam II, ENRGY 3 or H-Shield	Hot asphalt	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Hot asphalt	None	SBS-TA or APP-TA	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-232.5
C-51.	Structural concrete	FlintPrime QD	Min. 1.5-inch ACFoam II, ENRGY 3 or H-Shield	Hot asphalt	Min. 0.25-inch DensDeck	Hot asphalt	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-240.0
C-52.	Structural concrete	FlintPrime QD	Min. 1.5-inch ACFoam II	Hot asphalt	Min. 0.75-inch FescoBoard (homogeneous)	Hot asphalt	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-412.0
C-53.	Structural concrete	FlintPrime QD	Min. 1.5-inch ACFoam II	Hot asphalt	Min. 0.5-inch DuraBoard (homogeneous)	Hot asphalt	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-430.0
C-54.	Structural concrete	FlintPrime QD	0.5-inch Structodek High Density Fiberboard or min. 0.75-inch FescoBoard (homogeneous)	Hot asphalt	None	N/A	None	BP-AA	(Optional) BP-AA or SBS-AA	SBS-AA	-437.5
C-55.	Structural concrete	FlintPrime QD	0.25-inch DensDeck, DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Hot asphalt	None	N/A	None	SBS-TA	(Optional) SBS-AA or SBS-TA	SBS-AA	-302.5
C-56.	Structural concrete	FlintPrime QD	0.25-inch DensDeck, DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Hot asphalt	None	N/A	None	BP-AA	(Optional) BP-AA or SBS-AA	SBS-AA	-537.5
C-57.	Structural concrete	None	Min. 1.5-inch ACFoam II, ENRGY 3 or H-Shield	M-OSFA	Min. 0.5-inch Structodek High Density Fiberboard	M-OSFA	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-127.5
C-58.	Structural concrete	None	Min. 1.5-inch ACFoam II, ENRGY 3 or H-Shield	M-PG-1	Min. 0.5-inch Structodek High Density Fiberboard	M-PG-1	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-180.0
C-59.	Structural concrete	None	Min. 1.5-inch ACFoam II, ENRGY 3 or H-Shield	M-OSFA	Min. 0.25-inch DensDeck	M-OSFA	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-232.5
C-60.	Structural concrete	None	Min. 1.5-inch ACFoam II, ENRGY 3 or H-Shield	M-PG-1	Min. 0.25-inch DensDeck	M-PG-1	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-240.0
C-61.	Structural concrete	None	Min. 1.5-inch ACFoam II or H-Shield	M-PG-1	Min. 0.25-inch DensDeck Prime	M-PG-1	None	BP-AA, SBS-AA	(Optional) BP-AA, SBS-AA or SBS-TA	SBS-AA	-297.5

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 41 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

TABLE 11A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)**SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER**REFER TO [TABLE VB-3](#) FOR VAPOR BARRIER OPTIONS

SYSTEM No.	DECK (4.1.2)	PRIMER	BASE INSULATION LAYER		TOP INSULATION LAYER		PRIMER	ROOF COVER (3.1.4)			MDP (PSE)
			TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
C-62.	Structural concrete	None	Min. 2-inch ACFoam II, ENRGY 3 or H-Shield	M-OSFA or M-PG-1	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-225.0
C-63.	Structural concrete	None	Min. 2-inch ACFoam II, ENRGY 3 or H-Shield	M-OSFA or M-PG-1	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1	None	SBS-TA or APP-TA	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-232.5
C-64.	Structural concrete	None	Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1	None	APP-TA	(Optional) APP-TA	APP-TA	-252.5
C-65.	Structural concrete	None	Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1	None	BP-AA, SBS-AA or SBS-TA	(Optional) BP-AA, SBS-AA or SBS-TA	SBS-AA	-297.5
C-66.	Structural concrete	None	0.5-inch Structodek High Density Fiberboard	M-PG-1	None	N/A	None	BP-AA, SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-195.0
C-67.	Structural concrete	None	Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-PG-1	None	N/A	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-195.0
C-68.	Structural concrete	None	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1, 6-inch o.c.	Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1, 6-inch o.c.	None	SBS-AA or SBS-TA	(Optional) SBS-AA or SBS-TA	SBS-AA	-315.0
C-69.	Structural concrete	None	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1, 6-inch o.c.	Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1, 6-inch o.c.	None	Flintlastic STA	(Optional) APP-TA	APP-TA	-315.0
C-70.	Structural concrete	None	Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-PG1-EF-ECO	None	N/A	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-195.0
C-71.	Structural concrete	None	Min. 1.5-inch ACFoam II or H-Shield	M-PG1-EF-ECO	Min. 0.25-inch DensDeck Prime	M-PG1-EF-ECO	None	BP-AA, SBS-AA	(Optional) BP-AA, SBS-AA or SBS-TA	SBS-AA	-247.5
C-72.	Structural concrete	None	Min. 1.5-inch ACFoam II or H-Shield	M-PG1-EF-ECO	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-PG1-EF-ECO	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-247.5
C-73.	Structural concrete	None	Min. 1.5-inch ACFoam II, ENRGY 3 or H-Shield	OB500	Min. 0.5-inch Structodek High Density Fiberboard	OB500	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-120.0
C-74.	Structural concrete	None	Min. 1.5-inch ACFoam II	OB500	Min. 0.25-inch DensDeck or DensDeck Prime	OB500	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-150.0
C-75.	Structural concrete	None	Min. 1.5-inch ACFoam II or H-Shield	OB500	Min. 0.25-inch DensDeck Prime	OB500	None	BP-AA, SBS-AA or SBS-TA	(Optional) BP-AA, SBS-AA or SBS-TA	SBS-AA	-297.5
C-76.	Structural concrete	None	Min. 2-inch ACFoam II, ENRGY 3 or H-Shield	OB500	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-225.0
C-77.	Structural concrete	None	Min. 2-inch ACFoam II, ENRGY 3 or H-Shield	OB500	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	None	SBS-TA or APP-TA	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-232.5



TABLE 11A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER
 REFER TO [TABLE VB-3](#) FOR VAPOR BARRIER OPTIONS

SYSTEM No.	DECK (4.1.2)	PRIMER	BASE INSULATION LAYER		TOP INSULATION LAYER		PRIMER	ROOF COVER (3.1.4)			MDP (psf)
			TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
C-78.	Structural concrete	None	Min. 1.5-inch ACFoam II or H-Shield	OB500	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	None	APP-TA	(Optional) APP-TA	APP-TA	-252.5
C-79.	Structural concrete	None	Min. 1.5-inch ACFoam II or H-Shield	OB500	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	None	BP-AA, SBS-AA or SBS-TA	(Optional) BP-AA, SBS-AA or SBS-TA	SBS-AA	-297.5
C-80.	Structural concrete	None	0.5-inch Structodek High Density Fiberboard	OB500	None	N/A	None	BP-AA, SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-195.0
C-81.	Structural concrete	None	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	None	N/A	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-195.0
C-82.	Structural concrete	None	Min. 1-inch ENRGY 3, H-Shield or H-Shield CG or min. 1.5-inch Multi-Max FA3 or Ultra-Max	Polyset BM or Polyset CRA	Min. 0.5-inch Structodek High Density Fiberboard	Polyset CRA	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-180.0
C-83.	Structural concrete	None	Min. 1-inch ENRGY 3, H-Shield, or H-Shield CG, min. 1.3-inch ACFoam III or min. 1.5-inch Multi-Max FA3 or Ultra-Max	Polyset BM or Polyset CRA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset BM or Polyset CRA	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-225.0
C-84.	Structural concrete	None	Min. 1-inch ENRGY 3, H-Shield or H-Shield CG or min. 1.5-inch Multi-Max FA3 or Ultra-Max	Polyset BM or Polyset CRA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset BM or Polyset CRA	None	SBS-TA or APP-TA	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-232.5
C-85.	Structural concrete	None	Min. 1-inch ENRGY 3, H-Shield or H-Shield CG or min. 1.5-inch Multi-Max FA3 or Ultra-Max	Polyset BM or Polyset CRA	Min. 0.25-inch DensDeck	Polyset BM or Polyset CRA	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-240.0
C-86.	Structural concrete	None	0.5-inch Structodek High Density Fiberboard	Polyset BM or Polyset CRA	None	N/A	None	BP-AA, SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-195.0
C-87.	Structural concrete	None	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset BM or Polyset CRA	None	N/A	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-195.0
SPOT- OR STRIP-MOPPED SYSTEMS:											
C-88.	Structural concrete	FlintPrime QD	Min. 1.5-inch ACFoam II, ENRGY 3 or H-Shield	Hot asphalt	(Optional) Additional layer(s) of base insulation	Hot asphalt	None	BP-AA3, 24-inch grid	(Optional) BP-AA, SBS-AA	SBS-AA	-37.5
COLD-APPLIED SYSTEMS:											
C-89.	Structural concrete	None	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1	Min. 0.25-inch DEXcell FA Glass Mat Roof Board	M-OSFA or M-PG-1	None	Flintlastic Poly SMS Base Sheet in Karnak #81	(Optional) Flintlastic Poly SMS Base Sheet in Karnak #81	SBS-CA1	-90.0



TABLE 11A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER
 REFER TO [TABLE VB-3](#) FOR VAPOR BARRIER OPTIONS

SYSTEM No.	DECK (4.1.2)	PRIMER	BASE INSULATION LAYER		TOP INSULATION LAYER		PRIMER	ROOF COVER (3.1.4)			MDP (psf)
			TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
C-90.	Structural concrete	None	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1	Min. 0.5-inch ACFoam-HD CoverBoard or H-Shield HD	M-OSFA or M-PG-1	None	SBS-CA1	None	SBS-CA1	-97.5
C-91.	Structural concrete	None	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1	Min. 0.5-inch ACFoam-HD CoverBoard or H-Shield HD	M-OSFA or M-PG-1	None	SBS-CA4	None	SBS-CA4	-97.5
C-92.	Structural concrete	None	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1	Min. 2-inch H-Shield HD Composite CG	M-OSFA or M-PG-1	None	SBS-CA4	None	SBS-CA4	-97.5
C-93.	Structural concrete	None	Min. 0.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1	None	SBS-CA1	None	SBS-CA1	-105.0
C-94.	Structural concrete	None	Min. 0.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1	None	SBS-CA4	None	SBS-CA4	-105.0
C-95.	Structural concrete	None	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1, 6-inch o.c.	Min. 0.25-inch DEXcell FA Glass Mat Roof Board	M-OSFA or M-PG-1, 6-inch o.c.	None	Flintlastic Poly SMS Base Sheet in Karnak #81	(Optional) Flintlastic Poly SMS Base Sheet in Karnak #81	SBS-CA1	-112.5
C-96.	Structural concrete	None	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-PG1-EF-ECO	Min. 0.5-inch H-Shield HD	M-PG1-EF-ECO	None	SBS-CA1	None	SBS-CA1	-97.5
C-97.	Structural concrete	None	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-PG1-EF-ECO	Min. 0.5-inch H-Shield HD	M-PG1-EF-ECO	None	SBS-CA4	None	SBS-CA4	-97.5
C-98.	Structural concrete	None	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-PG1-EF-ECO	Min. 2-inch H-Shield HD Composite CG	M-PG1-EF-ECO	None	SBS-CA4	None	SBS-CA4	-97.5
C-99.	Structural concrete	None	Min. 0.5-inch ACFoam II or H-Shield	M-PG1-EF-ECO	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-PG1-EF-ECO	None	SBS-CA1	None	SBS-CA1	-105.0
C-100.	Structural concrete	None	Min. 0.5-inch ACFoam II or H-Shield	M-PG1-EF-ECO	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-PG1-EF-ECO	None	SBS-CA4	None	SBS-CA4	-105.0
C-101.	Structural concrete	None	(Optional) Min. 0.5-inch ACFoam II or H-Shield	OB500	Min. 1.5-inch ACFoam III or H-Shield CG	OB500	None	SBS-CA1	None	SBS-CA1	-82.5
C-102.	Structural concrete	None	Min. 0.5-inch ACFoam II or H-Shield	OB500	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	None	SBS-CA1	None	SBS-CA1	-105.0
C-103.	Structural concrete	None	Min. 0.5-inch ACFoam II or H-Shield	OB500	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	None	SBS-CA4	None	SBS-CA4	-105.0
C-104.	Structural concrete	None	(Optional) Min. 0.5-inch ACFoam II or H-Shield	Polyset BM or Polyset CRA	Min. 1.5-inch ACFoam III or H-Shield CG	Polyset BM or Polyset CRA	None	SBS-CA1	None	SBS-CA1	-82.5
C-105.	Structural concrete	None	Min. 0.5-inch ACFoam II or H-Shield	Polyset BM or Polyset CRA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset BM or Polyset CRA	None	SBS-CA1	None	SBS-CA1	-105.0
C-106.	Structural concrete	None	Min. 0.5-inch ACFoam II or H-Shield	Polyset BM or Polyset CRA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset BM or Polyset CRA	None	SBS-CA4	None	SBS-CA4	-105.0

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 44 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

TABLE 11B: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)**SYSTEM TYPE F: NON-INSULATED, BONDED ROOF COVER**

SYSTEM NO.	DECK (4.1.2)	PRIMER	ROOF COVER (3.1.4)			MDP (PSF)
			BASE	PLY	CAP	
SELF-ADHERING SYSTEMS:						
C-107.	Structural concrete	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-630.0
HYBRID SYSTEMS:						
C-108.	Structural concrete	FlintPrime QD	Flintlastic Ultra Glass SA	(Optional) SBS-AA	SBS-AA	-135.0
C-109.	Structural concrete	FlintPrime QD	SBS-SA-H	(Optional) SBS-TA, APP-TA	SBS-TA, APP-TA	-150.0
C-110.	Structural concrete	FlintPrime QD	Flintlastic Ultra Glass SA	(Optional) SBS-TA, APP-TA	SBS-TA, APP-TA	-322.5
C-111.	Structural concrete	FlintPrime QD	SBS-SA-H	(Optional) BP-AA, SBS-AA	SBS-AA	-240.0
C-112.	Structural concrete	FlintPrime QD	BP-AA, SBS-AA	SBS-SA-H	SBS-AA, SBS-TA or APP-TA	-635.0
CONVENTIONAL SYSTEMS:						
C-113.	Structural concrete	FlintPrime QD	APP-TA	(Optional) APP-TA	APP-TA	-420.0
C-114.	Structural concrete	FlintPrime QD	BP-AA, SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-635.0
COLD-APPLIED SYSTEMS:						
C-115.	Structural concrete	FlintPrime QD	SBS-CA1	(Optional) SBS-CA1	SBS-CA1	-262.5

TABLE 12A: LIGHTWEIGHT INSULATING CONCRETE - NEW CONSTRUCTION OR REROOF (TEAR-OFF)**SYSTEM TYPE A-1: LWC TO DECK, BONDED INSULATION, BONDED ROOF COVER**

SYSTEM NO.	DECK (4.1.2)	LIGHTWEIGHT CONCRETE (3.1.2)	BASE INSULATION LAYER		COVERBOARD		ROOF COVER (3.1.4)			MDP (PSF)
			TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)	BASE	PLY	CAP	
CELCORE:										
SELF-ADHERING SYSTEMS:										
LWC-1.	Min. 22 ga., Type BV, Grade 33 steel, 6 ft span	Min. 300 psi Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield, or H-Shield CG	M-OSFA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA	SBS-SA	(Optional) SBS-SA	SBS-SA	-52.5
LWC-2.	Min. 22 ga., Type BV, Grade 33 steel, 6 ft span	Min. 300 psi Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield, or H-Shield CG	M-PG-1	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-PG-1	SBS-SA	(Optional) SBS-SA	SBS-SA	-52.5
LWC-3.	Min. 22 ga., Type BV, Grade 33 steel, 6 ft span	Min. 300 psi Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield, or H-Shield CG	OB500	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	SBS-SA	(Optional) SBS-SA	SBS-SA	-52.5
LWC-4.	Min. 22 ga., Type BV, Grade 33 steel, 6 ft span	Min. 300 psi Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield, or H-Shield CG	Polyset BM	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset BM	SBS-SA	(Optional) SBS-SA	SBS-SA	-52.5

[BACK TO TOP](#)[LINK TO TOP OF ATTACHMENT REQUIREMENTS](#)

©NEMO. All rights reserved.

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 45 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

TABLE 12a: LIGHTWEIGHT INSULATING CONCRETE - NEW CONSTRUCTION OR REROOF (TEAR-OFF)**SYSTEM TYPE A-1: LWC TO DECK, BONDED INSULATION, BONDED ROOF COVER**

SYSTEM No.	DECK (4.1.2)	LIGHTWEIGHT CONCRETE (3.1.2)	BASE INSULATION LAYER		COVERBOARD		ROOF COVER (3.1.4)			MDP (PSE)
			TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)	BASE	PLY	CAP	
LWC-5.	Min. 22 ga., Type BV, Grade 33 steel, 6 ft span	Min. 300 psi Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield, or H-Shield CG	Polyset CRA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset CRA	SBS-SA	(Optional) SBS-SA	SBS-SA	-52.5
HYBRID SYSTEMS:										
LWC-6.	Min. 22 ga., Type BV, Grade 33 steel, 6 ft span	Min. 300 psi Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield, or H-Shield CG	M-OSFA, M-PG-1, OB500, Polyset BM, or Polyset CRA	(Optional) Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA, M-PG-1, OB500, Polyset BM, or Polyset CRA	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-52.5
CONVENTIONAL SYSTEMS:										
LWC-7.	Min. 22 ga., Type BV, Grade 33 steel, 6 ft span	Min. 300 psi Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield, or H-Shield CG	M-OSFA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA	BP-AA or SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-52.5
LWC-8.	Min. 22 ga., Type BV, Grade 33 steel, 6 ft span	Min. 300 psi Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield, or H-Shield CG	M-PG-1	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-PG-1	BP-AA or SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-52.5
LWC-9.	Min. 22 ga., Type BV, Grade 33 steel, 6 ft span	Min. 300 psi Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield, or H-Shield CG	OB500	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	BP-AA or SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-52.5
LWC-10.	Min. 22 ga., Type BV, Grade 33 steel, 6 ft span	Min. 300 psi Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield, or H-Shield CG	Polyset BM	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset BM	BP-AA or SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-52.5
LWC-11.	Min. 22 ga., Type BV, Grade 33 steel, 6 ft span	Min. 300 psi Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield, or H-Shield CG	Polyset CRA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset CRA	BP-AA or SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-52.5
ELASTIZELL:										
COLD-APPLIED SYSTEMS:										
LWC-12.	Min. 22 ga., Type BV, Grade 33 steel	Min. 350 psi, min 2-inch Range II Elastizell with Zell-Crete Fibers.	Min. 1.5-inch H-Shield CG	OB500, 6-inch o.c.	(Optional) Additional layers of base insulation	OB500, 6-inch o.c.	BP-CA3 or SBS-CA3	(Optional) BP-CA3 or SBS-CA3	SBS-CA3	-60.0



TABLE 12a: LIGHTWEIGHT INSULATING CONCRETE - NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: LWC TO DECK, BONDED INSULATION, BONDED ROOF COVER

SYSTEM No.	DECK (4.1.2)	LIGHTWEIGHT CONCRETE (3.1.2)	BASE INSULATION LAYER		COVERBOARD		ROOF COVER (3.1.4)			MDP (PSF)
			TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)	BASE	PLY	CAP	
LWC-13.	Min. 22 ga., Type BV, Grade 33 steel, 5 ft span	Min. 350 psi, min 2-inch Range II Elastizell with Zell-Crete Fibers. When walkable, attach LWC with Trufast #14 HD with Trufast 3" Metal Insulation Plates at 1 per 8 ft2 through to the structural deck.	Min. 1.5-inch H-Shield CG	OB500, 6-inch o.c.	(Optional) Additional layers of base insulation	OB500, 6-inch o.c.	BP-CA3 or SBS-CA3	(Optional) BP-CA3 or SBS-CA3	SBS-CA3	-67.5

TABLE 12b: LIGHTWEIGHT CONCRETE OVER STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: LWC TO DECK, BONDED INSULATION, BONDED ROOF COVER

SYSTEM No.	DECK (4.1.2)	LIGHTWEIGHT CONCRETE (3.1.2)	BASE INSULATION LAYER		COVERBOARD		PRIMER	ROOF COVER (3.1.4)			MDP (PSF)
			TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
CELCORE:											
SELF-ADHERING SYSTEMS:											
LWC-14.	Structural concrete	Min. 300 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture; treated with Celcore PVA Curing Compound	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield, or H-Shield CG	M-OSFA	Min. 0.25-inch DensDeck	M-OSFA	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-90.0
LWC-15.	Structural concrete	Min. 300 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture; treated with Celcore PVA Curing Compound	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield, or H-Shield CG	M-OSFA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-90.0
LWC-16.	Structural concrete	Min. 300 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture; treated with Celcore PVA Curing Compound and surfaced with Celcore Sanded Bonding Surface (SBS)	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield, or H-Shield CG	M-OSFA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-172.5



TABLE 12b: LIGHTWEIGHT CONCRETE OVER STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: LWC TO DECK, BONDED INSULATION, BONDED ROOF COVER

SYSTEM No.	DECK (4.1.2)	LIGHTWEIGHT CONCRETE (3.1.2)	BASE INSULATION LAYER		COVERBOARD		PRIMER	ROOF COVER (3.1.4)			MDP (PSE)
			TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
LWC-17.	Structural concrete	Min. 300 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture; treated with Celcore PVA Curing Compound and surfaced with Celcore Sanded Bonding Surface (SBS)	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield, or H-Shield CG	M-OSFA	Min. 0.25-inch DensDeck	M-OSFA	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-192.5
LWC-18.	Structural concrete	Min. 300 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture; treated with Celcore PVA Curing Compound and surfaced with Celcore Sanded Bonding Surface (SBS)	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield, or H-Shield CG	M-OSFA	Min. 0.25-inch SECURock Gypsum-Fiber Roof Board	M-OSFA	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-217.5
LWC-19.	Structural concrete	Min. 300 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture; treated with Celcore PVA Curing Compound	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield, or H-Shield CG	M-PG-1	Min. 0.25-inch SECURock Gypsum-Fiber Roof Board	M-PG-1	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-172.5
LWC-20.	Structural concrete	Min. 300 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture; treated with Celcore PVA Curing Compound and surfaced with Celcore Sanded Bonding Surface (SBS)	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield, or H-Shield CG	M-PG-1	Min. 0.25-inch SECURock Gypsum-Fiber Roof Board	M-PG-1	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-172.5
LWC-21.	Structural concrete	Min. 300 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture; treated with Celcore PVA Curing Compound	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield, or H-Shield CG	M-PG-1	Min. 0.25-inch DensDeck	M-PG-1	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-192.5



TABLE 12b: LIGHTWEIGHT CONCRETE OVER STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: LWC TO DECK, BONDED INSULATION, BONDED ROOF COVER

SYSTEM No.	DECK (4.1.2)	LIGHTWEIGHT CONCRETE (3.1.2)	BASE INSULATION LAYER		COVERBOARD		PRIMER	ROOF COVER (3.1.4)			MDP (PSE)
			TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
LWC-22.	Structural concrete	Min. 300 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture; treated with Celcore PVA Curing Compound and surfaced with Celcore Sanded Bonding Surface (SBS)	One or more layer(s), min. 1.5-inch AC Foam II, AC Foam III, H-Shield, or H-Shield CG	M-PG-1	Min. 0.25-inch DensDeck	M-PG-1	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-192.5
LWC-23.	Structural concrete	Min. 300 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture; treated with Celcore PVA Curing Compound	One or more layer(s), min. 1.5-inch AC Foam II, AC Foam III, H-Shield, or H-Shield CG	M-PG-1	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-PG-1	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-240.0
LWC-24.	Structural concrete	Min. 300 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture; treated with Celcore PVA Curing Compound and surfaced with Celcore Sanded Bonding Surface (SBS)	One or more layer(s), min. 1.5-inch AC Foam II, AC Foam III, H-Shield, or H-Shield CG	M-PG-1	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-PG-1	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-232.5
LWC-25.	Structural concrete	Min. 300 psi Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	One or more layer(s), min. 1.5-inch AC Foam II, AC Foam III, H-Shield, or H-Shield CG	OB500	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-172.5
LWC-26.	Structural concrete	Min. 200 psi, min. 2-inch Celcore Cellular Concrete	Min. 1-inch ENRGY 3, H-Shield or H-Shield CG or min. 1.5-inch Multi-Max FA3 or Ultra-Max	Polyset CRA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset CRA	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-172.5
LWC-27.	Structural concrete	Min. 300 psi Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	One or more layer(s), min. 1.5-inch AC Foam II, AC Foam III, H-Shield, or H-Shield CG	Polyset CRA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset CRA	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-172.5
LWC-28.	Structural concrete	Min. 200 psi, min. 2-inch Celcore Cellular Concrete	Min. 1-inch ENRGY 3, H-Shield or H-Shield CG or min. 1.5-inch Multi-Max FA3 or Ultra-Max	Polyset CRA	Min. 0.25-inch DensDeck	Polyset CRA	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-180.0



TABLE 12b: LIGHTWEIGHT CONCRETE OVER STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: LWC TO DECK, BONDED INSULATION, BONDED ROOF COVER

SYSTEM NO.	DECK (4.1.2)	LIGHTWEIGHT CONCRETE (3.1.2)	BASE INSULATION LAYER		COVERBOARD		PRIMER	ROOF COVER (3.1.4)			MDP (PSF)
			TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
HYBRID SYSTEMS:											
LWC-29.	Structural concrete	Min. 300 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture; treated with Celcore PVA Curing Compound	One or more layer(s), min. 1.5-inch ACFoam II or H-Shield	M-OSFA	(Optional) Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-OSFA	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-90.0
LWC-30.	Structural concrete	Min. 300 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture; treated with Celcore PVA Curing Compound and surfaced with Celcore Sanded Bonding Surface (SBS)	One or more layer(s), min. 1.5-inch ACFoam II or H-Shield	M-OSFA	(Optional) Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-OSFA	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-217.5
LWC-31.	Structural concrete	Min. 300 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture; treated with Celcore PVA Curing Compound and surfaced with Celcore Sanded Bonding Surface (SBS)	One or more layer(s), min. 1.5-inch ACFoam II or H-Shield	M-PG-1	(Optional) Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-PG-1	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-232.5
LWC-32.	Structural concrete	Min. 300 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture; treated with Celcore PVA Curing Compound	One or more layer(s), min. 1.5-inch ACFoam II or H-Shield	M-PG-1	(Optional) Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-PG-1	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-240.0
LWC-33.	Structural concrete	Min. 300 psi Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield or H-Shield CG	OB500	(Optional) Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-215.0

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 50 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

TABLE 12b: LIGHTWEIGHT CONCRETE OVER STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION OR REROOF (TEAR-OFF)**SYSTEM TYPE A-1: LWC TO DECK, BONDED INSULATION, BONDED ROOF COVER**

SYSTEM No.	DECK (4.1.2)	LIGHTWEIGHT CONCRETE (3.1.2)	BASE INSULATION LAYER		COVERBOARD		PRIMER	ROOF COVER (3.1.4)			MDP (PSE)
			TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
LWC-34.	Structural concrete	Min. 300 psi Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield or H-Shield CG	Polysert BM or Polysert CRA	(Optional) Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polysert BM or Polysert CRA	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-215.0
CONVENTIONAL SYSTEMS:											
LWC-35.	Structural concrete	Min. 300 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture; treated with Celcore PVA Curing Compound	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield or H-Shield CG	M-OSFA	Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-OSFA	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-90.0
LWC-36.	Structural concrete	Min. 300 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture; treated with Celcore PVA Curing Compound and surfaced with Celcore Sanded Bonding Surface (SBS)	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield or H-Shield CG	M-OSFA	Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-OSFA	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-217.5
LWC-37.	Structural concrete	Min. 300 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture; treated with Celcore PVA Curing Compound	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield or H-Shield CG	M-PG-1	Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-PG-1	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-240.0
LWC-38.	Structural concrete	Min. 300 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture; treated with Celcore PVA Curing Compound and surfaced with Celcore Sanded Bonding Surface (SBS)	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield or H-Shield CG	M-PG-1	Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-PG-1	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-232.5
LWC-39.	Structural concrete	Min. 300 psi Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield or H-Shield CG	OB500	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-215.0

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 51 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

TABLE 12b: LIGHTWEIGHT CONCRETE OVER STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION OR REROOF (TEAR-OFF)**SYSTEM TYPE A-1: LWC TO DECK, BONDED INSULATION, BONDED ROOF COVER**

SYSTEM No.	DECK (4.1.2)	LIGHTWEIGHT CONCRETE (3.1.2)	BASE INSULATION LAYER		COVERBOARD		PRIMER	ROOF COVER (3.1.4)			MDP (PSE)
			TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
LWC-40.	Structural concrete	Min. 300 psi Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield or H-Shield CG	Polyset BM	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset BM	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-215.0
LWC-41.	Structural concrete	Min. 200 psi, min. 2-inch Celcore Cellular Concrete	Min. 1-inch ENRGY 3, H-Shield or H-Shield CG or min. 1.5-inch Multi-Max FA3 or Ultra-Max	Polyset CRA	Min. 0.5-inch Structodek High Density Fiberboard	Polyset CRA	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-180.0
LWC-42.	Structural concrete	Min. 200 psi, min. 2-inch Celcore Cellular Concrete	Min. 1-inch ENRGY 3, H-Shield or H-Shield CG or min. 1.5-inch Multi-Max FA3 or Ultra-Max	Polyset CRA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board or DensDeck or DensDeck Prime	Polyset CRA	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-180.0
LWC-43.	Structural concrete	Min. 300 psi Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield or H-Shield CG	Polyset CRA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset CRA	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-215.0
ELASTIZELL:											
SELF-ADHERING SYSTEMS:											
LWC-44.	Structural concrete	Min. 200 psi, min. 2-inch Elastizell	Min. 1.5-inch ACFoam II or ENRGY 3	OB500	Min. 0.25-inch DensDeck	OB500	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-150.0
LWC-45.	Structural concrete	Min. 200 psi, min. 2-inch Elastizell	Min. 1.5-inch ACFoam II, ENRGY 3 or H-Shield	OB500	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-172.5
LWC-46.	Structural concrete	Min. 200 psi, min. 2-inch Elastizell	Min. 1-inch ENRGY 3, H-Shield or H-Shield CG or min. 1.5-inch Multi-Max FA3 or Ultra-Max	Polyset CRA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset CRA	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-172.5
LWC-47.	Structural concrete	Min. 200 psi, min. 2-inch Elastizell	Min. 1-inch ENRGY 3, H-Shield or H-Shield CG or min. 1.5-inch Multi-Max FA3 or Ultra-Max	Polyset CRA	Min. 0.25-inch DensDeck	Polyset CRA	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-180.0
CONVENTIONAL SYSTEMS:											
LWC-48.	Structural concrete	Min. 200 psi, min. 2-inch Elastizell	Min. 1.5-inch ACFoam II	OB500	Min. 0.25-inch DensDeck or DensDeck Prime	OB500	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-150.0

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 52 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

TABLE 12b: LIGHTWEIGHT CONCRETE OVER STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION OR REROOF (TEAR-OFF)**SYSTEM TYPE A-1: LWC TO DECK, BONDED INSULATION, BONDED ROOF COVER**

SYSTEM No.	DECK (4.1.2)	LIGHTWEIGHT CONCRETE (3.1.2)	BASE INSULATION LAYER		COVERBOARD		PRIMER	ROOF COVER (3.1.4)			MDP (PSE)
			TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
LWC-49.	Structural concrete	Min. 200 psi, min. 2-inch Elastizell	Min. 2-inch ACFoam II, ENRGY 3 or H-Shield	OB500	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-225.0
LWC-50.	Structural concrete	Min. 200 psi, min. 2-inch Elastizell	Min. 1-inch ENRGY 3, H-Shield or H-Shield CG or min. 1.5-inch Multi-Max FA3 or Ultra-Max	Polysat CRA	Min. 0.5-inch Structodek High Density Fiberboard	Polysat CRA	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-180.0
LWC-51.	Structural concrete	Min. 200 psi, min. 2-inch Elastizell	Min. 1-inch ENRGY 3, H-Shield or H-Shield CG or min. 1.5-inch Multi-Max FA3 or Ultra-Max	Polysat CRA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board or DensDeck or DensDeck Prime	Polysat CRA	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-180.0
COLD-APPLIED SYSTEMS:											
LWC-52.	Structural concrete	Min. 350 psi, min 2-inch Elastizell with Zell-Crete Fibers.	Min. 1.5-inch H-Shield CG	OB500, 6-inch o.c.	(Optional) Additional layers of base insulation	OB500, 6-inch o.c.	None	BP-CA3 or SBS-CA3	(Optional) BP-CA3 or SBS-CA3	SBS-CA3	-60.0
LWC-53.	Structural concrete	Min. 350 psi, min 2-inch Range II Elastizell with Zell-Crete Fibers. When walkable, attach LWC with Trufast #14HD with Trufast 3" Metal Insulation Plates at 1 per 8 ft2 through to the structural deck.	Min. 1.5-inch H-Shield CG	OB500, 6-inch o.c.	(Optional) Additional layers of base insulation	OB500, 6-inch o.c.	None	BP-CA3 or SBS-CA3	(Optional) BP-CA3 or SBS-CA3	SBS-CA3	-67.5



TABLE 12c: LIGHTWEIGHT INSULATING CONCRETE OVER STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-2: LWC TO DECK, BONDED VAPOR BARRIER, BONDED INSULATION, BONDED ROOF COVER

SYSTEM NO.	DECK (4.1.2)	LIGHTWEIGHT CONCRETE (3.1.2)	VAPOR BARRIER	BASE INSULATION LAYER		COVERBOARD		PRIMER	ROOF COVER (3.1.4)			MDP (PSF)
				TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
PRE-EXISTENT CELLULAR LWC:												
SELF-ADHERING SYSTEMS:												
LWC-54.	Min. 22 ga., Type BV, Grade 40 steel	Min. 400 psi, Min. 2-inch, pre-existent cellular lightweight concrete, Repair LWC spalls with Celcore SBS (Sanded Bonding Surface)	Flintlastic Ultra Poly SMS Base Sheet applied in Millennium Hurricane Force Membrane Adhesive HS, ribbons max. 6-inch o.c. 3-inch wide side laps and 6-inch wide end laps are hot-air-welded, torch-welded or sealed with Millennium Hurricane Force Lap and Flashing Adhesive	One or more layers, min. 2-inch AC Foam II or H-Shield	M-OSFA or M-PG-1	(Optional) 0.5-in. DensDeck Prime or SECURROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-67.5
HYBRID SYSTEMS:												
LWC-55.	Min. 22 ga., Type BV, Grade 40 steel	Min. 400 psi, Min. 2-inch, pre-existent cellular lightweight concrete, Repair LWC spalls with Celcore SBS (Sanded Bonding Surface)	Flintlastic Ultra Poly SMS Base Sheet applied in Millennium Hurricane Force Membrane Adhesive HS, ribbons max. 6-inch o.c. 3-inch wide side laps and 6-inch wide end laps are hot-air-welded, torch-welded or sealed with Millennium Hurricane Force Lap and Flashing Adhesive	One or more layers, min. 2-inch AC Foam II or H-Shield	M-OSFA or M-PG-1	0.5-in. DensDeck Prime or SECURROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1	(Optional) FlintPrime QD	SBS-SA-H	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-67.5
CONVENTIONAL SYSTEMS:												
LWC-56.	Min. 22 ga., Type BV, Grade 40 steel	Min. 400 psi, Min. 2-inch, pre-existent cellular lightweight concrete, Repair LWC spalls with Celcore SBS (Sanded Bonding Surface)	Flintlastic Ultra Poly SMS Base Sheet applied in Millennium Hurricane Force Membrane Adhesive HS, ribbons max. 6-inch o.c. 3-inch wide side laps and 6-inch wide end laps are hot-air-welded, torch-welded or sealed with Millennium Hurricane Force Lap and Flashing Adhesive	One or more layers, min. 2-inch AC Foam II or H-Shield	M-OSFA or M-PG-1	0.5-in. DensDeck Prime or SECURROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1	(Optional) FlintPrime QD	SBS-TA or APP-TA	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-67.5



TABLE 12c: LIGHTWEIGHT INSULATING CONCRETE OVER STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-2: LWC TO DECK, BONDED VAPOR BARRIER, BONDED INSULATION, BONDED ROOF COVER

SYSTEM NO.	DECK (4.1.2)	LIGHTWEIGHT CONCRETE (3.1.2)	VAPOR BARRIER	BASE INSULATION LAYER		COVERBOARD		PRIMER	ROOF COVER (3.1.4)			MDP (PSF)
				TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
ELASTIZELL:												
SELF-ADHERING SYSTEMS:												
LWC-57.	Structural Concrete	Min. 420 psi, min. 2-inch Elastizell	All Weather/Empire Base Sheet or Flintglas MS Cap (inverted) applied in Millennium Hurricane Force Membrane Adhesive HS, ribbons max. 6-inch o.c., 3-inch wide side laps and 6-inch wide end laps are sealed with Millennium Hurricane Force Lap and Flashing Adhesive	One or more layers, min. 2-inch AC Foam II or H-Shield	M-OSFA or M-PG-1	(Optional) 0.5-in. DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-67.5
LWC-58.	Structural Concrete	Min. 420 psi, min. 2-inch Elastizell	Flintlastic Ultra Poly SMS Base Sheet applied in Millennium Hurricane Force Membrane Adhesive HS, ribbons max. 6-inch o.c., 3-inch wide side laps and 6-inch wide end laps are hot-air-welded, torch-welded or sealed with Millennium Hurricane Force Lap and Flashing Adhesive	One or more layers, min. 2-inch AC Foam II or H-Shield	M-OSFA or M-PG-1	(Optional) 0.5-in. DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-67.5
HYBRID SYSTEMS:												
LWC-59.	Structural Concrete	Min. 420 psi, min. 2-inch Elastizell	All Weather/Empire Base Sheet or Flintglas MS Cap (inverted) applied in Millennium Hurricane Force Membrane Adhesive HS, ribbons max. 6-inch o.c., 3-inch wide side laps and 6-inch wide end laps are sealed with Millennium Hurricane Force Lap and Flashing Adhesive	One or more layers, min. 2-inch AC Foam II or H-Shield	M-OSFA or M-PG-1	0.5-in. DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1	(Optional) FlintPrime QD	SBS-SA-H	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-67.5
LWC-60.	Structural Concrete	Min. 420 psi, min. 2-inch Elastizell	Flintlastic Ultra Poly SMS Base Sheet applied in Millennium Hurricane Force Membrane Adhesive HS, ribbons max. 6-inch o.c., 3-inch wide side laps and 6-inch wide end laps are hot-air-welded, torch-welded or sealed with Millennium Hurricane Force Lap and Flashing Adhesive	One or more layers, min. 2-inch AC Foam II or H-Shield	M-OSFA or M-PG-1	0.5-in. DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1	(Optional) FlintPrime QD	SBS-SA-H	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-67.5



TABLE 12c: LIGHTWEIGHT INSULATING CONCRETE OVER STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-2: LWC TO DECK, BONDED VAPOR BARRIER, BONDED INSULATION, BONDED ROOF COVER

SYSTEM No.	DECK (4.1.2)	LIGHTWEIGHT CONCRETE (3.1.2)	VAPOR BARRIER	BASE INSULATION LAYER		COVERBOARD		PRIMER	ROOF COVER (3.1.4)			MDP (PSF)
				TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
CONVENTIONAL SYSTEMS:												
LWC-61.	Structural Concrete	Min. 420 psi, min. 2-inch Elastizell	All Weather/Empire Base Sheet or Flintglas MS Cap (inverted) applied in Millennium Hurricane Force Membrane Adhesive HS, ribbons max. 6-inch o.c., 3-inch wide side laps and 6-inch wide end laps are sealed with Millennium Hurricane Force Lap and Flashing Adhesive	One or more layers, min. 2-inch ACfoam II or H-Shield	M-OSFA or M-PG-1	0.5-in. DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1	(Optional) FlintPrime QD	SBS-TA or APP-TA	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-67.5
LWC-62.	Structural Concrete	Min. 420 psi, min. 2-inch Elastizell	Flintlastic Ultra Poly SMS Base Sheet applied in Millennium Hurricane Force Membrane Adhesive HS, ribbons max. 6-inch o.c., 3-inch wide side laps and 6-inch wide end laps are hot-air-welded, torch-welded or sealed with Millennium Hurricane Force Lap and Flashing Adhesive	One or more layers, min. 2-inch ACfoam II or H-Shield	M-OSFA or M-PG-1	0.5-in. DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1	(Optional) FlintPrime QD	SBS-TA or APP-TA	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-67.5



**TABLE 12D: LIGHTWEIGHT CONCRETE OVER STEEL DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE B-3: MECHANICALLY ATTACHED ANCHOR SHEET, BONDED INSULATION, BONDED ROOF COVER**

SYSTEM NO.	DECK (4.1.2)	LIGHTWEIGHT CONCRETE (3.1.2)			ANCHOR SHEET			INSULATION LAYER			ROOF COVER (3.1.4)			MDP (PSF)
		DECK TREATMENT	TYPE	SURFACE TREATMENT	TYPE	FASTENER (3.1.1, 4.2.2)	ATTACH (3.1.3)	BASE	TOP	ATTACH (3.1.3)	BASE	PLY	CAP	
PRE-EXISTING CELLULAR LWC:														
SPOT- OR STRIP-MOPPED SYSTEMS:														
LWC-63.	Min. 22 ga. steel or structural concrete deck.	None	Min 350 psi, min 2-inch pre-existent cellular LWIC	None	Flintglas MS Cap (inverted)	Trufast Twin-Loc Nails	9-inch o.c. at the 4-inch side lap and 9-inch o.c. at two, equally spaced, staggered rows in the center of the sheet	Min. 1.5-inch ACFoam II	(Optional) Additional layers base insulation	Hot asphalt	BP-AA4, 18-inch o.c.	(Optional) BP-AA, SBS-AA	SBS-AA	-60.0
	Note:	To qualify the LWIC under this assembly, the subject fastener shall achieve an average withdrawal of 88 lbf when tested per 4.2.2.												
CELCORE:														
SELF-ADHERING SYSTEMS:														
LWC-64.	Min. 22 ga., type BV, Grade 40 steel, 6 ft span	Celcore S-1 Deck Preparation	Min. 470 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	Celcore PVA Curing Compound	All Weather/Empire Base Sheet, Glasbase Base Sheet or Flintlastic Base 20 or Flintglas MS Cap (inverted)	Trufast FM-90 Base Sheet Fastener	7-inch o.c. at the min. 4-inch side laps and 7-inch o.c. at two, equally spaced, staggered center rows	Min. 1.5" ACFoam II	(Optional) Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board. Top surface shall be primed with FlintPrime QD.	Hot asphalt	SBA-SA	(Optional) SBS-SA	SBS-SA	-60.0
HYBRID SYSTEMS:														
LWC-65.	Min. 22 ga., type BV, Grade 40 steel, 6 ft span	Celcore S-1 Deck Preparation	Min. 470 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	Celcore PVA Curing Compound	All Weather/Empire Base Sheet, Glasbase Base Sheet or Flintlastic Base 20 or Flintglas MS Cap (inverted)	Trufast FM-90 Base Sheet Fastener	7-inch o.c. at the min. 4-inch side laps and 7-inch o.c. at two, equally spaced, staggered center rows	Min. 1.5" ACFoam II	(Optional) Min. 0.125-inch STURDY-DEK Asphaltic Cover Board or min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board. Top surface may be optionally primed with FlintPrime QD.	Hot asphalt	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-60.0



TABLE 12D: LIGHTWEIGHT CONCRETE OVER STEEL DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE B-3: MECHANICALLY ATTACHED ANCHOR SHEET, BONDED INSULATION, BONDED ROOF COVER

SYSTEM NO.	DECK (4.1.2)	LIGHTWEIGHT CONCRETE (3.1.2)			ANCHOR SHEET			INSULATION LAYER			ROOF COVER (3.1.4)			MDP (PSF)
		DECK TREATMENT	TYPE	SURFACE TREATMENT	TYPE	FASTENER (3.1.1, 4.2.2)	ATTACH (3.1.3)	BASE	TOP	ATTACH (3.1.3)	BASE	PLY	CAP	
CONVENTIONAL SYSTEMS:														
LWC-66.	Min. 22 ga., type BV, Grade 40 steel, 6 ft span	Celcore S-1 Deck Preparation	Min. 470 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	Celcore PVA Curing Compound	All Weather/Empire Base Sheet, Glasbase Base Sheet or Flintlastic Base 20 or Flintglas MS Cap (inverted)	Trufast FM-90 Base Sheet Fastener	7-inch o.c. at the min. 4-inch side laps and 7-inch o.c. at two, equally spaced, staggered center rows	Min. 1.5" ACFoam II	Min. 0.125-inch STURDY-DEK Asphaltic Cover Board, min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board, min. 0.5-inch Structodek High Density Fiberboard Roof Insulation or min. 0.75-inch FescoBoard (homogeneous)	Hot asphalt	BP-AA or SBS-AA	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-60.0
LWC-67.	Min. 22 ga., type BV, Grade 40 steel, 6 ft span	Celcore S-1 Deck Preparation	Min. 470 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	Celcore PVA Curing Compound	All Weather/Empire Base Sheet, Glasbase Base Sheet or Flintlastic Base 20 or Flintglas MS Cap (inverted)	Trufast FM-90 Base Sheet Fastener	7-inch o.c. at the min. 4-inch side laps and 7-inch o.c. at two, equally spaced, staggered center rows	Min. 1.5" ACFoam II	Min. 0.125-inch STURDY-DEK Asphaltic Cover Board or min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board. Top surface may be optionally primed with FlintPrime QD.	Hot asphalt	SBS-TA or APP-TA	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-60.0
ELASTIZELL:														
SELF-ADHERING SYSTEMS:														
LWC-68.	Min. 22 ga., type BV, Grade 40 steel, 6 ft span	None	Min. 490 psi, min. 2-inch Elastizell with Zell-Crete Fibers	None	All Weather/Empire Base Sheet, Glasbase Base Sheet or Flintlastic Base 20 or Flintglas MS Cap (inverted)	Trufast FM-90 Base Sheet Fastener	7-inch o.c. at the min. 4-inch side laps and 7-inch o.c. at two, equally spaced, staggered center rows	Min. 1.5" ACFoam II	(Optional) Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board. Top surface shall be primed with FlintPrime QD.	Hot asphalt	SBA-SA	(Optional) SBS-SA	SBS-SA	-67.5



TABLE 12D: LIGHTWEIGHT CONCRETE OVER STEEL DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE B-3: MECHANICALLY ATTACHED ANCHOR SHEET, BONDED INSULATION, BONDED ROOF COVER

SYSTEM NO.	DECK (4.1.2)	LIGHTWEIGHT CONCRETE (3.1.2)			ANCHOR SHEET			INSULATION LAYER			ROOF COVER (3.1.4)			MDP (psf)
		DECK TREATMENT	TYPE	SURFACE TREATMENT	TYPE	FASTENER (3.1.1, 4.2.2)	ATTACH (3.1.3)	BASE	TOP	ATTACH (3.1.3)	BASE	PLY	CAP	
HYBRID SYSTEMS:														
LWC-69.	Min. 22 ga., type BV, Grade 40 steel, 6 ft span	None	Min. 490 psi, min. 2-inch Elastizell with Zell-Crete Fibers	None	All Weather/Empire Base Sheet, Glasbase Base Sheet or Flintlastic Base 20 or Flintglas MS Cap (inverted)	Trufast FM-90 Base Sheet Fastener	7-inch o.c. at the min. 4-inch side laps and 7-inch o.c. at two, equally spaced, staggered center rows	Min. 1.5" ACFoam II	(Optional) Min. 0.125-inch STURDY-DEK Asphaltic Cover Board or min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board. Top surface may be optionally primed with FlintPrime QD.	Hot asphalt	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-67.5
CONVENTIONAL SYSTEMS:														
LWC-70.	Min. 22 ga., type BV, Grade 40 steel, 6 ft span	None	Min. 490 psi, min. 2-inch Elastizell with Zell-Crete Fibers	None	All Weather/Empire Base Sheet, Glasbase Base Sheet or Flintlastic Base 20 or Flintglas MS Cap (inverted)	Trufast FM-90 Base Sheet Fastener	7-inch o.c. at the min. 4-inch side laps and 7-inch o.c. at two, equally spaced, staggered center rows	Min. 1.5" ACFoam II	Min. 0.125-inch STURDY-DEK Asphaltic Cover Board, min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board, min. 0.5-inch Structodek High Density Fiberboard Roof Insulation or min. 0.75-inch FescoBoard (homogeneous)	Hot asphalt	BP-AA or SBS-AA	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-67.5
LWC-71.	Min. 22 ga., type BV, Grade 40 steel, 6 ft span	None	Min. 490 psi, min. 2-inch Elastizell with Zell-Crete Fibers	None	All Weather/Empire Base Sheet, Glasbase Base Sheet or Flintlastic Base 20 or Flintglas MS Cap (inverted)	Trufast FM-90 Base Sheet Fastener	7-inch o.c. at the min. 4-inch side laps and 7-inch o.c. at two, equally spaced, staggered center rows	Min. 1.5" ACFoam II	Min. 0.125-inch STURDY-DEK Asphaltic Cover Board or min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board. Top surface may be optionally primed with FlintPrime QD.	Hot asphalt	SBS-TA or APP-TA	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-67.5
SPOT- OR STRIP-MOPPED SYSTEMS:														
LWC-72.	Min. 22 ga. steel or structural concrete deck.	None	Min 350 psi, min 2-inch Elastizell cellular LWIC	None	Flintglas MS Cap (inverted)	Trufast FM-90 Base Ply Fastener	7-inch o.c. at the 4-inch side lap and 7-inch o.c. at two, equally spaced, staggered rows in the center of the sheet	Min. 1.5-inch ACFoam II	(Optional) Additional layers base insulation	Hot asphalt	BP-AA3, 18-inch grid	(Optional) BP-AA, SBS-AA	SBS-AA	-37.5*



TABLE 12E: LIGHTWEIGHT CONCRETE OVER STEEL OR STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE E-2: NON-INSULATED, MECHANICALLY ATTACHED ANCHOR SHEET, BONDED ROOF COVER

SYSTEM No.	DECK (4.1.2)	LIGHTWEIGHT CONCRETE (3.1.2)			ANCHOR SHEET			ROOF COVER (3.1.4)		MDP (PSF)
		DECK TREATMENT	TYPE	SURFACE TREATMENT	BASE	FASTENER (3.1.1, 4.2.2)	SPACING	BASE	CAP	
PRE-EXISTENT CELLULAR LIGHTWEIGHT CONCRETE:										
SELF-ADHERING SYSTEMS:										
LWC-73.	Min. 22 ga., Type BV, Grade 33 steel, 5 ft span or structural concrete	None	Min. 300 psi, min. 2-inch pre-existent cellular lightweight insulating concrete.	None	Flintlastic SA NailBase	Trufast Twin Loc-Nail Assembled Fastener (min. 1.8")	7-inch o.c. at the min. 2-inch lap and 7-inch o.c. in two (2), equally spaced, staggered center rows, FlintPrime QD at stress plates	SBS-SA	SBS-SA	-60.0
	Note:	To qualify the LWIC under this assembly, a 1.8-inch Trufast Twin Loc-Nail Assembled Fastener shall achieve an average withdrawal of 73 lbf when tested per 4.2.2.								
LWC-74.	Min. 22 ga., Type BV, Grade 33 steel, 5 ft span or structural concrete	None	Min. 300 psi, min. 2-inch pre-existent cellular lightweight insulating concrete.	None	Flintlastic SA NailBase	Trufast Twin Loc-Nail Assembled Fastener (min. 1.8")	9-inch o.c. at the min. 2-inch lap and 9-inch o.c. in two (2), equally spaced, staggered center rows, FlintPrime QD at stress plates	SBS-SA	SBS-SA	-60.0
	Note:	To qualify the LWIC under this assembly, a 1.8-inch Trufast Twin Loc-Nail Assembled Fastener shall achieve an average withdrawal of 93 lbf when tested per 4.2.2 .								
HYBRID SYSTEMS:										
LWC-75.	Min. 22 ga., Type BV, Grade 33 steel, 5 ft span or structural concrete	None	Min. 300 psi, min. 2-inch pre-existent cellular lightweight insulating concrete.	None	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet	Trufast Twin Loc-Nail Assembled Fastener (min. 1.8")	9-inch o.c. at the 4-inch lap and 9-inch o.c. in two (2), equally spaced, staggered center rows	SBS-SA-H	SBS-AA, SBS-TA or APP-TA	-60.0
	Note:	To qualify the LWIC under this assembly, a 1.8-inch Trufast Twin Loc-Nail Assembled Fastener shall achieve an average withdrawal of 88 lbf when tested per 4.2.2 .								
LWC-76.	Min. 22 ga., Type BV, Grade 33 steel, 5 ft span or structural concrete	None	Min. 350 psi, min. 3-inch pre-existent cellular lightweight insulating concrete.	None	Flintlastic Base 20 or Flintlastic Poly SMS Base Sheet	Trufast FM-90 Base Sheet Fastener	7-inch o.c. at the 4-inch lap and 10-inch o.c. in two (2), equally spaced, staggered center rows	SBS-SA-H	SBS-AA, SBS-TA or APP-TA	-67.5
	Note:	To qualify the LWIC under this assembly, a 1.8-inch Trufast Twin Loc-Nail Assembled Fastener shall achieve an average withdrawal of 97 lbf when tested per 4.2.2 .								
LWC-77.	Min. 22 ga., Type BV, Grade 33 steel, 5 ft span or structural concrete	None	Min. 300 psi, min. 2-inch pre-existent cellular lightweight insulating concrete.	None	Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base Sheet	Trufast Twin Loc-Nail Assembled Fastener (min. 1.8")	9-inch o.c. at the 4-inch lap and 9-inch o.c. in two (2), equally spaced, staggered center rows	SBS-SA-H	SBS-AA, SBS-TA or APP-TA	-75.0
	Note:	To qualify the LWIC under this assembly, a 1.8-inch Trufast Twin Loc-Nail Assembled Fastener shall achieve an average withdrawal of 110 lbf when tested per 4.2.2 .								

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 60 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

TABLE 12e: LIGHTWEIGHT CONCRETE OVER STEEL OR STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)**SYSTEM TYPE E-2: NON-INSULATED, MECHANICALLY ATTACHED ANCHOR SHEET, BONDED ROOF COVER**

SYSTEM NO.	DECK (4.1.2)	LIGHTWEIGHT CONCRETE (3.1.2)			ANCHOR SHEET			ROOF COVER (3.1.4)		MDP (PSF)
		DECK TREATMENT	TYPE	SURFACE TREATMENT	BASE	FASTENER (3.1.1, 4.2.2)	SPACING	BASE	CAP	
CONVENTIONAL SYSTEMS:										
LWC-78.	Min. 22 ga., Type BV, Grade 33 steel, 5 ft span or structural concrete	None	Min. 300 psi, min. 2-inch pre-existent cellular lightweight insulating concrete.	None	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, or Flintglas MS Cap (inverted)	Trufast Twin Loc-Nail Assembled Fastener (min. 1.8")	9-inch o.c. at the 4-inch lap and 9-inch o.c. in two (2), equally spaced, staggered center rows	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-60.0
	Note:	To qualify the LWIC under this assembly, a 1.8-inch Trufast Twin Loc-Nail Assembled Fastener shall achieve an average withdrawal of 88 lbf when tested per 4.2.2 .								
LWC-79.	Min. 22 ga., Type BV, Grade 33 steel, 5 ft span or structural concrete	None	Min. 300 psi, min. 2-inch pre-existent cellular lightweight insulating concrete.	None	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, or Flintglas MS Cap (inverted)	Trufast Twin Loc-Nail Assembled Fastener (min. 1.8")	7-inch o.c. at the 4-inch lap and 7-inch o.c. in two (2), equally spaced, staggered center rows	BP-AA or SBS-AA	SBS-AA, SBS-TA or APP-TA	-67.5
	Note:	To qualify the LWIC under this assembly, a 1.8-inch Trufast Twin Loc-Nail Assembled Fastener shall achieve an average withdrawal of 77 lbf when tested per 4.2.2 .								
LWC-80.	Min. 22 ga., Type BV, Grade 33 steel, 5 ft span or structural concrete	None	Min. 350 psi, min. 3-inch pre-existent cellular lightweight insulating concrete.	None	Flintlastic Base 20, Flintlastic Poly SMS Base Sheet, or Flintglas MS Cap (inverted)	Trufast FM-90 Base Sheet Fastener	7-inch o.c. at the 4-inch lap and 10-inch o.c. in two (2), equally spaced, staggered center rows	BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-67.5
	Note:	To qualify the LWIC under this assembly, a 1.8-inch Trufast Twin Loc-Nail Assembled Fastener shall achieve an average withdrawal of 97 lbf when tested per 4.2.2 .								
LWC-81.	Min. 22 ga., Type BV, Grade 33 steel, 5 ft span or structural concrete	None	Min. 300 psi, min. 2-inch pre-existent cellular lightweight insulating concrete.	None	Flintlastic Poly SMS Base Sheet, Flintlastic Ultra Poly SMS Base Sheet	Trufast Twin Loc-Nail Assembled Fastener (min. 1.8")	9-inch o.c. at the 4-inch lap and 9-inch o.c. in two (2), equally spaced, staggered center rows	BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-75.0
	Note:	To qualify the LWIC under this assembly, a 1.8-inch Trufast Twin Loc-Nail Assembled Fastener shall achieve an average withdrawal of 110 lbf when tested per 4.2.2 .								
CELCORE:										
SELF-ADHERING SYSTEMS:										
LWC-82.	Min. 22 ga., type BV, Grade 40 steel, 6 ft span	Celcore S-1 Deck Preparation	Min. 470 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	Celcore PVA Curing Compound	Flintlastic SA NailBase	Trufast FM-90 Base Sheet Fastener	7-inch o.c. at the min. 4-inch side laps and 7-inch o.c. at two, equally spaced, staggered center rows	SBS-SA	SBS-SA	-45.0
HYBRID SYSTEMS:										
LWC-83.	Min. 22 ga., type BV, Grade 40 steel, 6 ft span	Celcore S-1 Deck Preparation	Min. 470 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	Celcore PVA Curing Compound	All Weather/Empire Base Sheet, Glasbase Base Sheet or Flintlastic Base 20	Trufast FM-90 Base Sheet Fastener	7-inch o.c. at the min. 4-inch side laps and 7-inch o.c. at two, equally spaced, staggered center rows	SBS-SA-H	SBS-AA, SBS-TA or APP-TA	-45.0

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 61 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

TABLE 12e: LIGHTWEIGHT CONCRETE OVER STEEL OR STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)**SYSTEM TYPE E-2: NON-INSULATED, MECHANICALLY ATTACHED ANCHOR SHEET, BONDED ROOF COVER**

SYSTEM No.	DECK (4.1.2)	LIGHTWEIGHT CONCRETE (3.1.2)			ANCHOR SHEET			ROOF COVER (3.1.4)		MDP (PSE)
		DECK TREATMENT	TYPE	SURFACE TREATMENT	BASE	FASTENER (3.1.1, 4.2.2)	SPACING	BASE	CAP	
LWC-84.	Min. 22 ga., type BV, Grade 40 steel, 6 ft span	Celcore S-1 Deck Preparation	Min. 470 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	Celcore PVA Curing Compound	Flintglas MS Cap (inverted) primed with FlintPrime QD	Trufast FM-90 Base Sheet Fastener	7-inch o.c. at the min. 4-inch side laps and 7-inch o.c. at two, equally spaced, staggered center rows	SBS-SA-H	SBS-AA, SBS-TA or APP-TA	-45.0
CONVENTIONAL SYSTEMS:										
LWC-85.	Min. 22 ga., type BV, Grade 40 steel, 6 ft span	Celcore S-1 Deck Preparation	Min. 470 psi, min. 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	Celcore PVA Curing Compound	All Weather/Empire Base Sheet, Glasbase Base Sheet or Flintlastic Base 20 or Flintglas MS Cap (inverted)	Trufast FM-90 Base Sheet Fastener	7-inch o.c. at the min. 4-inch side laps and 7-inch o.c. at two, equally spaced, staggered center rows	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0
LWC-86.	Min. 22 ga., type B steel at max. 5 ft spans or structural concrete	None	Min. 300 psi, min 2-inch Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture.	Celcore PVA Curing Compound	All Weather/Empire Base Sheet, Flintlastic Base 20, Flintlastic Poly SMS Base Sheet	Trufast FM-90 Base Sheet Fastener	9-inch o.c. at 4-inch laps and 12-inch o.c. in two (2), equally spaced, staggered center rows	(Optional) BP-AA, SBS-AA or SBS-TA	SBS-AA	-60.0
LWC-87.	Min. 22 ga., Type BV, Grade 33 steel, 5 ft span or structural concrete	None	Min. 300 psi, min 2-inch Celcore Cellular Concrete.	Celcore PVA Curing Compound	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, Flintlastic Poly SMS Base Sheet or Flintglas MS Cap (inverted)	Trufast FM-90 Base Sheet Fastener	7-inch o.c. at the 3-inch lap and 7-inch o.c. in two (2), equally spaced, staggered center rows	BP-AA or SBS-AA	SBS-AA, SBS-TA or APP-TA	-75.0
CONCRECEL:										
CONVENTIONAL SYSTEMS:										
LWC-88.	Min. 22 ga., Type BV, Grade 80 steel, 5 ft span or structural concrete	Concrecel Bonding Agent	Min. 300 psi, min 2¼-inch Concrecel Concrete.	Concrecel Curing Compound	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, Flintlastic Poly SMS Base Sheet or Flintglas MS Cap (inverted)	OMG CR Base Ply Fastener (1.7)	7-inch o.c. at the 3-inch lap and 7-inch o.c. in two (2), equally spaced, staggered center rows	(Optional) BP-AA or SBS-AA	SBS-AA, SBS-TA or APP-TA	-52.5
ELASTIZELL:										
SELF-ADHERING SYSTEMS:										
LWC-89.	Min. 22 ga., type BV, Grade 40 steel, 6 ft span	None	Min. 490 psi, min. 2-inch Elastizell with Zell-Crete Fibers	None	Flintlastic SA NailBase	Trufast FM-90 Base Sheet Fastener	7-inch o.c. at the min. 4-inch side laps and 7-inch o.c. at two, equally spaced, staggered center rows	SBS-SA	SBS-SA	-45.0
HYBRID SYSTEMS:										
LWC-90.	Min. 26 ga. steel at max 5 ft spans or structural concrete	None	Min. 200 psi, min 2-inch Elastizell.	None	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet or Flintlastic Poly SMS Base Sheet	Trufast FM-90 Base Sheet Fastener or Trufast Twin Loc-Nail Assembled Fastener (1.8 inch)	7½-inch o.c. at the 4-inch lap and 7½-inch o.c. in two (2), equally spaced, staggered center rows	SBS-SA-H	SBS-AA, SBS-TA or APP-TA	-30.0

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 62 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

TABLE 12e: LIGHTWEIGHT CONCRETE OVER STEEL OR STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)**SYSTEM TYPE E-2: NON-INSULATED, MECHANICALLY ATTACHED ANCHOR SHEET, BONDED ROOF COVER**

SYSTEM No.	DECK (4.1.2)	LIGHTWEIGHT CONCRETE (3.1.2)			ANCHOR SHEET			ROOF COVER (3.1.4)		MDP (PSE)
		DECK TREATMENT	TYPE	SURFACE TREATMENT	BASE	FASTENER (3.1.1, 4.2.2)	SPACING	BASE	CAP	
LWC-91.	Min. 22 ga., Type BV, Grade 33 steel, 5 ft span or structural concrete	None	Min. 200 psi, min 2-inch Elastizell.	None	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet or Flintlastic Poly SMS Base Sheet	Trufast FM-90 Base Sheet Fastener or Trufast Twin Loc-Nail Assembled Fastener (1.8 inch)	7-inch o.c. at the 4-inch lap and 7-inch o.c. in two (2), equally spaced, staggered center rows	SBS-SA-H	SBS-AA, SBS-TA or APP-TA	-45.0
LWC-92.	Min. 22 ga., type BV, Grade 40 steel, 6 ft span	None	Min. 490 psi, min. 2-inch Elastizell with Zell-Crete Fibers	None	All Weather/Empire Base Sheet, Glasbase Base Sheet or Flintlastic Base 20	Trufast FM-90 Base Sheet Fastener	7-inch o.c. at the min. 4-inch side laps and 7-inch o.c. at two, equally spaced, staggered center rows	SBS-SA-H	SBS-AA, SBS-TA or APP-TA	-45.0
LWC-93.	Min. 22 ga., type BV, Grade 40 steel, 6 ft span	None	Min. 490 psi, min. 2-inch Elastizell with Zell-Crete Fibers	None	Flintglas MS Cap (inverted) primed with FlintPrime QD	Trufast FM-90 Base Sheet Fastener	7-inch o.c. at the min. 4-inch side laps and 7-inch o.c. at two, equally spaced, staggered center rows	SBS-SA-H	SBS-AA, SBS-TA or APP-TA	-45.0
CONVENTIONAL SYSTEMS:										
LWC-94.	Min. 26 ga. steel at max 5 ft spans or structural concrete	None	Min. 200 psi, min 2-inch Elastizell.	None	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, Flintlastic Poly SMS Base Sheet or Flintglas MS Cap (inverted)	Trufast FM-90 Base Sheet Fastener or Trufast Twin Loc-Nail Assembled Fastener (1.8 inch)	7½-inch o.c. at the 4-inch lap and 7½-inch o.c. in two (2), equally spaced, staggered center rows	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-30.0
LWC-95.	Min. 26 ga. steel at max 5 ft spans or structural concrete	None	Min. 200 psi, min 2-inch Elastizell.	None	Flintlastic APP Base T	Trufast FM-90 Base Sheet Fastener	7½-inch o.c. at the 4-inch lap and 7½-inch o.c. in two (2), equally spaced, staggered center rows	(Optional) APP-TA	APP-TA	-30.0
LWC-96.	Min. 22 ga., type BV, Grade 40 steel, 6 ft span	None	Min. 490 psi, min. 2-inch Elastizell with Zell-Crete Fibers	None	All Weather/Empire Base Sheet, Glasbase Base Sheet or Flintlastic Base 20 or Flintglas MS Cap (inverted)	Trufast FM-90 Base Sheet Fastener	7-inch o.c. at the min. 4-inch side laps and 7-inch o.c. at two, equally spaced, staggered center rows	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0
LWC-97.	Min. 22 ga., Type BV, Grade 33 steel, 5 ft span or structural concrete	None	Min. 200 psi, min 2-inch Elastizell.	None	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, Flintlastic Poly SMS Base Sheet or Flintglas MS Cap (inverted)	Trufast FM-90 Base Sheet Fastener or Trufast Twin Loc-Nail Assembled Fastener (1.8 inch)	7-inch o.c. at the 4-inch lap and 7-inch o.c. in two (2), equally spaced, staggered center rows	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0
LWC-98.	Min. 22 ga., Type BV, Grade 33 steel, 5 ft span or structural concrete	None	Min. 200 psi, min 2-inch Elastizell.	None	Flintlastic APP Base T	Trufast FM-90 Base Sheet Fastener	7-inch o.c. at the 4-inch lap and 7-inch o.c. in two (2), equally spaced, staggered center rows	(Optional) APP-TA	APP-TA	-45.0

[BACK TO TOP](#)[LINK TO TOP OF ATTACHMENT REQUIREMENTS](#)

©NEMO. All rights reserved.

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 63 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

TABLE 12E: LIGHTWEIGHT CONCRETE OVER STEEL OR STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)**SYSTEM TYPE E-2: NON-INSULATED, MECHANICALLY ATTACHED ANCHOR SHEET, BONDED ROOF COVER**

SYSTEM NO.	DECK (4.1.2)	LIGHTWEIGHT CONCRETE (3.1.2)			ANCHOR SHEET			ROOF COVER (3.1.4)		MDP (PSF)
		DECK TREATMENT	TYPE	SURFACE TREATMENT	BASE	FASTENER (3.1.1, 4.2.2)	SPACING	BASE	CAP	
COLD-APPLIED SYSTEMS:										
LWC-99.	Min. 22 ga., Type BV, Grade 33 steel, 5 ft span or structural concrete	None	Min. 350 psi, min 2-inch Range II Elastizell with Zell-Crete Fibers.	None	Flintlastic Base 20, Flintlastic Poly SMS Base Sheet	Trufast FM-90 Base Sheet Fastener	7-inch o.c. at the 4-inch lap and 7-inch o.c. in two (2), equally spaced, staggered center rows	(Optional) BP-CA2 or SBS-CA2	SBS-CA2	-45.0
LWC-100.	Min. 22 ga., Type BV, Grade 33 steel, 5 ft span	None	Min. 350 psi, min 2-inch Range II Elastizell with Zell-Crete Fibers.	None	Glasbase Base Sheet, Flintlastic Poly SMS Base Sheet	Trufast FM-90 Base Sheet Fastener	7-inch o.c. at the 4-inch lap and 7-inch o.c. in two (2), equally spaced, staggered center rows	(Optional) BP-CA3 or SBS-CA3	SBS-CA3	-52.5
LWC-101.	Structural concrete	None	Min. 350 psi, min 2-inch Range II Elastizell with Zell-Crete Fibers.	None	Glasbase Base Sheet, Flintlastic Poly SMS Base Sheet	Trufast FM-90 Base Sheet Fastener	7-inch o.c. at the 4-inch lap and 7-inch o.c. in two (2), equally spaced, staggered center rows	(Optional) BP-CA3 or SBS-CA3	SBS-CA3	-60.0
MEARLCRETE:										
CONVENTIONAL SYSTEMS:										
LWC-102.	Min. 22 ga., Type BV, Grade 33 steel, 5 ft span or structural concrete	None	Min. 250 psi, min 2-inch Mearlcrete.	None	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, Flintlastic Poly SMS Base Sheet or Flintglas MS Cap (inverted)	OMG CR Base Ply Fastener (1.7)	7-inch o.c. at the 4-inch lap and 7-inch o.c. in two (2), equally spaced, staggered center rows	(Optional) BP-AA or SBS-AA	SBS-AA, SBS-TA or APP-TA	-45.0
LWC-103.	Min. 22 ga., Type BV, Grade 33 steel, 5 ft span or structural concrete	None	Min. 250 psi, min 2-inch Mearlcrete.	None	Flintlastic Poly SMS Base Sheet	OMG CR Base Ply Fastener (1.7)	7-inch o.c. at the 4-inch lap and 7-inch o.c. in two (2), equally spaced, staggered center rows	(Optional) BP-AA or SBS-AA	SBS-AA, SBS-TA or APP-TA	-52.5
LWC-104.	Min. 22 ga., Type BV, Grade 33 steel, 5 ft span or structural concrete	None	Min. 300 psi, min 2-inch Mearlcrete.	None	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, Flintlastic Poly SMS Base Sheet or Flintglas MS Cap (inverted)	OMG CR Base Ply Fastener (1.7)	7-inch o.c. at the 4-inch lap and 7-inch o.c. in two (2), equally spaced, staggered center rows	(Optional) BP-AA or SBS-AA	SBS-AA, SBS-TA or APP-TA	-52.5

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 64 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065



PCA-145

TABLE 12f: LIGHTWEIGHT CONCRETE DECKS – REROOF (TEAR-OFF) OR RECOVER
SYSTEM TYPE E-2: NON-INSULATED, MECHANICALLY ATTACHED ANCHOR SHEET, BONDED ROOF COVER

SYSTEM NO.	DECK (4.1.2)	LIGHTWEIGHT CONCRETE (3.1.2)		ANCHOR SHEET			ROOF COVER (3.1.4)		MDP (PSF)
		TYPE	SURFACE TREATMENT	TYPE	FASTENER (3.1.1, 4.2.2)	SPACING	BASE	CAP	
PRE-EXISTENT CELLULAR LWC:									
SELF-ADHERING SYSTEMS:									
LWC-105.	Min. 22 ga., Type BV, Grade 40 steel	Min. 470 psi, Min. 2-inch, pre-existent cellular lightweight concrete	For reroof (tear-off), repair LWC spalls with Celcore SBS (Sanded Bonding Surface)	Flintlastic Ultra Poly SMS Base Sheet	Trufast Versa Fastener (min. 2.25") & Plates, two (2) screws per plate at 180° from each other*	9-inch o.c. within the min. 5-inch wide, heat-welded side laps	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-75.0
	Note:	*Field withdrawal resistance testing (4.2.2) shall yield minimum 322 lbf. Additional Versa-Fast Fasteners within each Versa-Fast Plate may be utilized to produce minimum withdrawal resistance. For recover installations, screws shall be of sufficient length for minimum 2.25" embedment into the existing LWC assembly.							

TABLE 12g: LIGHTWEIGHT CONCRETE DECKS – REROOF (TEAR-OFF)
SYSTEM TYPE F: NON-INSULATED, BONDED ROOF COVER

SYSTEM NO.	DECK (4.1.2)	LIGHTWEIGHT CONCRETE (3.1.2)		ROOF COVER (3.1.4)		MDP (psf)
		TYPE	SURFACE TREATMENT	BASE	CAP	
PRE-EXISTENT CELLULAR LWC:						
LWC-106.	Min. 22 ga., Type BV, Grade 40 steel	Min. 400 psi, Min. 2-inch, pre-existent cellular lightweight concrete	Repair LWC spalls with Celcore SBS (Sanded Bonding Surface)	Flintlastic Ultra Poly SMS Base Sheet applied in HB Fuller “Millennium Hurricane Force Membrane Adhesive HS”, ribbons max. 6-inch o.c. 3-inch wide side laps and 6-inch wide end laps are hot-air-welded, torch-welded or sealed with HB Fuller “Millennium Hurricane Force Lap and Flashing Adhesive”	SBS-CA1 or SBS-CA4	-75.0
LWC-107.	Min. 22 ga., Type BV, Grade 40 steel	Min. 400 psi, Min. 2-inch, pre-existent cellular lightweight concrete	Repair LWC spalls with Celcore SBS (Sanded Bonding Surface)	Flintlastic Ultra Poly SMS Base Sheet applied in HB Fuller “Millennium Hurricane Force Membrane Adhesive HS”, ribbons max. 6-inch o.c. 3-inch wide side laps and 6-inch wide end laps are hot-air-welded, torch-welded or sealed with HB Fuller “Millennium Hurricane Force Lap and Flashing Adhesive”	Flintlastic FR-P, Flintlastic FR-P CoolStar, Flintlastic Premium FR-P, Flintlastic Premium FR-P CoolStar, or Flintlastic GMS, applied in HB Fuller “Millennium Hurricane Force Membrane Adhesive HS”, continuous ribbons maximum 6-inch o.c. 3-inch wide side laps and 6-inch wide end laps are hot-air-welded, torch-welded or sealed with HB Fuller “Millennium Hurricane Force Lap and Flashing Adhesive”	-97.5



TABLE 13A: CEMENTITIOUS WOOD FIBER DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER

SYSTEM No.	DECK (4.1.2)	BASE INSULATION LAYER		TOP INSULATION LAYER		PRIMER	ROOF COVER (3.1.4)			MDP (PSF)
		TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
SELF-ADHERING SYSTEMS:										
CWF-1.	Tectum	Min. 1.5-inch ACFoam II or H-Shield	M-OSFA	(Optional) Additional layer(s) of base insulation and/or min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board.	M-OSFA	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-60.0
CWF-2.	Tectum	Min. 1.5-inch ACFoam II or H-Shield	M-OSFA, 6-inch o.c.	(Optional) Additional layer(s) of base insulation and/or min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board.	M-OSFA, 6-inch o.c.	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-90.0
CWF-3.	Existing Tectum (re-roof only)	Min. 1.5-inch ACFoam II, ENRGY 3 or Multi-Max FA3	OB500	Min. 0.25-inch DensDeck	OB500	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-45.0*
CWF-4.	Existing Tectum (re-roof only)	Min. 1.5-inch ACFoam II, ENRGY 3 or Multi-Max FA3	OB500	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-45.0*
CWF-5.	Tectum	Min. 1-inch ENRGY 3, H-Shield or H-Shield CG or min. 1.5-inch Multi-Max FA3 or Ultra-Max	Polyset BM or Polyset CRA	Min. 0.25-inch DensDeck	Polyset BM or Polyset CRA	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-52.5
CWF-6.	Tectum	Min. 1-inch ENRGY 3, H-Shield or H-Shield CG or min. 1.5-inch Multi-Max FA3 or Ultra-Max	Polyset BM or Polyset CRA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset BM or Polyset CRA	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-52.5
HYBRID SYSTEMS:										
CWF-7.	Tectum	Min. 1.5-inch ACFoam II or H-Shield	M-OSFA	(Optional) Additional layer(s) of base insulation and/or min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board.	M-OSFA	None	SBS-SA-H	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-60.0
CWF-8.	Tectum	Min. 1.5-inch ACFoam II or H-Shield	M-OSFA, 6-inch o.c.	(Optional) Additional layer(s) of base insulation and/or min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board.	M-OSFA, 6-inch o.c.	None	SBS-SA-H	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-90.0
CONVENTIONAL SYSTEMS:										
CWF-9.	Tectum	Min. 1.5-inch ACFoam II or H-Shield	M-OSFA	Optional additional layers of base insulation, followed by min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-OSFA	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-60.0

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 66 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

TABLE 13A: CEMENTITIOUS WOOD FIBER DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)**SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER**

SYSTEM NO.	DECK (4.1.2)	BASE INSULATION LAYER		TOP INSULATION LAYER		PRIMER	ROOF COVER (3.1.4)			MDP (psf)
		TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
CWF-10.	Tectum	Min. 1.5-inch ACFoam II or H-Shield	M-OSFA, 6-inch o.c.	Optional additional layers of base insulation, followed by min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board.	M-OSFA, 6-inch o.c.	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-90.0
CWF-11.	Existing Tectum (re-roof only)	Min. 1.5-inch ACFoam II, ENRGY 3 or Multi-Max FA3	OB500	Min. 0.5-inch Structodek High Density Fiberboard	OB500	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
CWF-12.	Existing Tectum (re-roof only)	Min. 1.5-inch ACFoam II, ENRGY 3 or Multi-Max FA3	OB500	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board or DensDeck or DensDeck Prime	OB500	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
CWF-13.	Tectum	Min. 1-inch ENRGY 3, H-Shield, or H-Shield CG, min. 1.3-inch ACFoam III or min. 1.5-inch Multi-Max FA3 or Ultra-Max	Polyset BM or Polyset CRA	Min. 0.5-inch Structodek High Density Fiberboard	Polyset CRA	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-52.5
CWF-14.	Tectum	Min. 1-inch ENRGY 3, H-Shield or H-Shield CG or min. 1.5-inch Multi-Max FA3 or Ultra-Max	Polyset BM or Polyset CRA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board or DensDeck or DensDeck Prime	Polyset BM or Polyset CRA	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-52.5

TABLE 13B: CEMENTITIOUS WOOD FIBER DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) OR RECOVER**SYSTEM TYPE B-3: MECHANICALLY ATTACHED ANCHOR SHEET, BONDED INSULATION, BONDED ROOF COVER**

SYSTEM NO.	DECK (4.1.2)	ANCHOR SHEET			BASE INSULATION LAYER		TOP INSULATION LAYER		ROOF COVER (3.1.4)			MDP (psf)
		TYPE	FASTENER (3.1.1, 4.2.2)	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)	BASE	PLY	CAP	
HYBRID SYSTEMS:												
CWF-15.	Tectum	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet or Flintglas MS Cap (inverted)	Trufast Twin Loc-Nail Assembled Fastener (Field W/D > 80 lbf)	6-inch o.c. at the 4-inch lap and 10-inch o.c. in two (2), equally spaced, staggered center rows	Min. 1.5-inch AC Foam II, ENRGY 3 or Multi-Max FA3	Hot asphalt	(Optional) Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Hot asphalt	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-60.0
CWF-16.	Tectum	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet or Flintglas MS Cap (inverted)	Trufast Twin Loc-Nail Assembled Fastener (Field W/D > 69 lbf)	7-inch o.c. at the 4-inch lap and 7-inch o.c. in two (2), equally spaced, staggered center rows	Min. 1.5-inch AC Foam II, ENRGY 3 or Multi-Max FA3	Hot asphalt	(Optional) Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Hot asphalt	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-60.0



TABLE 13b: CEMENTITIOUS WOOD FIBER DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) OR RECOVER
SYSTEM TYPE B-3: MECHANICALLY ATTACHED ANCHOR SHEET, BONDED INSULATION, BONDED ROOF COVER

SYSTEM NO.	DECK (4.1.2)	ANCHOR SHEET			BASE INSULATION LAYER		TOP INSULATION LAYER		ROOF COVER (3.1.4)			MDP (PSF)
		TYPE	FASTENER (3.1.1, 4.2.2)	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)	BASE	PLY	CAP	
CONVENTIONAL SYSTEMS:												
CWF-17.	Tectum	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet or Flintglas MS Cap (inverted)	Trufast Twin Loc-Nail Assembled Fastener (Field W/D > 80 lbf)	6-inch o.c. at the 4-inch lap and 10-inch o.c. in two (2), equally spaced, staggered center rows	Min. 1.5-inch ACFoam II, ENRGY 3 or Multi-Max FA3	Hot asphalt	Min. 0.75-inch FescoBoard (homogeneous) or min. 0.5-inch Structodek High Density Fiberboard	Hot asphalt	BP-AA or SBS-AA	(Optional) BP-AA or SBS-AA	SBS-AA, SBS-TA or APP-TA	-60.0
CWF-18.	Tectum	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet or Flintglas MS Cap (inverted)	Trufast Twin Loc-Nail Assembled Fastener (Field W/D > 69 lbf)	7-inch o.c. at the 4-inch lap and 7-inch o.c. in two (2), equally spaced, staggered center rows	Min. 1.5-inch ACFoam II, ENRGY 3 or Multi-Max FA3	Hot asphalt	Min. 0.75-inch FescoBoard (homogeneous) or min. 0.5-inch Structodek High Density Fiberboard	Hot asphalt	BP-AA or SBS-AA	(Optional) BP-AA or SBS-AA	SBS-AA, SBS-TA or APP-TA	-60.0

TABLE 13c: CEMENTITIOUS WOOD FIBER DECKS – REROOF (TEAR-OFF) OR RECOVER
SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER

SYSTEM NO.	DECK (4.1.2)	BASE INSULATION LAYER (3.1.2)	TOP INSULATION LAYER			ROOF COVER (3.1.4)			MDP (psf)
			TYPE	FASTENER (3.1.1, 4.2.2)	ATTACH (3.1.3)	BASE	PLY	CAP	
CWF-19.	Existing Tectum	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch Structodek High Density Fiberboard Roof Insulation	OMG Polymer GypTec with 3" GypTec Plate (Field W/D > 180 lbf)	1 per 2.0 ft ²	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
CWF-20.	Existing Tectum	(Optional) One or more layers, any combination, loose laid	Min. 0.25-inch DensDeck or DensDeck Prime	OMG Polymer GypTec with 3" GypTec Plate (Field W/D > 160 lbf)	1 per 1.8 ft ²	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
CWF-21.	Existing Tectum	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch Structodek High Density Fiberboard Roof Insulation	Trufast Twin Loc-Nail Assembled Fastener (Field W/D > 180 lbf)	1 per 2.0 ft ²	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
CWF-22.	Existing Tectum	(Optional) One or more layers, any combination, loose laid	Min. 0.25-inch DensDeck or DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Trufast Twin Loc-Nail Assembled Fastener (Field W/D > 180 lbf)	1 per 2.0 ft ²	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*



**TABLE 13D: CEMENTITIOUS WOOD FIBER DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) OR RECOVER
 SYSTEM TYPE E-2: NON-INSULATED, MECHANICALLY ATTACHED ANCHOR SHEET, BONDED ROOF COVER**

SYSTEM No.	DECK (4.1.2)	ANCHOR SHEET			ROOF COVER (3.1.4)		MDP (PSF)
		TYPE	FASTENER (3.1.1, 4.2.2)	SPACING	BASE	CAP	
SELF-ADHERING SYSTEMS:							
CWF-23.	Tectum	Flintlastic SA NailBase	Trufast Twin Loc-Nail Assembled Fastener (Field W/D > 80 lbf)	6-inch o.c. at the 4-inch lap and 10-inch o.c. in two (2), equally spaced, staggered center rows	SBS-SA	SBS-SA	-60.0
CWF-24.	Tectum	Flintlastic SA NailBase	Trufast Twin Loc-Nail Assembled Fastener (Field W/D > 69 lbf)	7-inch o.c. at the 4-inch lap and 7-inch o.c. in two (2), equally spaced, staggered center rows	SBS-SA	SBS-SA	-60.0
CONVENTIONAL SYSTEMS:							
CWF-25.	Tectum	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet or Flintglas MS Cap (inverted)	Trufast Twin Loc-Nail Assembled Fastener (Field W/D > 80 lbf)	6-inch o.c. at the 4-inch lap and 10-inch o.c. in two (2), equally spaced, staggered center rows	BP-AA or SBS-AA	SBS-AA, SBS-TA or APP-TA	-60.0
CWF-26.	Tectum	Glasbase Base Sheet, Flintlastic Base 20 or All Weather/Empire Base Sheet or Flintglas MS Cap (inverted)	Trufast Twin Loc-Nail Assembled Fastener (Field W/D > 77 lbf)	7-inch o.c. at the 4-inch lap and 7-inch o.c. in two (2), equally spaced, staggered center rows	BP-AA or SBS-AA	SBS-AA, SBS-TA or APP-TA	-67.5

**TABLE 14A: GYPSUM DECKS – REROOF (TEAR-OFF)
 SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER**

SYSTEM No.	DECK (4.1.2)	BASE INSULATION LAYER		TOP INSULATION LAYER		ROOF COVER (3.1.4)			MDP (psf)
		TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)	BASE	PLY	CAP	
SELF-ADHERING SYSTEMS:									
G-1.	Existing gypsum deck	Min. 1.5-inch ACFoam II, ACFoam III, ENRGY 3, H-Shield or H-Shield CG	M-OSFA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA	SBS-SA	(Optional) SBS-SA	SBS-SA	-172.5
G-2.	Existing gypsum deck	Min. 1.5-inch ACFoam II, ENRGY 3 or Multi-Max FA3	M-OSFA	Min. 0.25-inch DensDeck primed with FlintPrime QD	M-OSFA	SBS-SA	(Optional) SBS-SA	SBS-SA	-192.5
G-3.	Existing gypsum deck	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield or H-Shield CG	M-PG-1	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-PG-1	SBS-SA	(Optional) SBS-SA	SBS-SA	-172.5
G-4.	Existing gypsum deck	Min. 1.5-inch ACFoam II or ENRGY 3	OB500	Min. 0.25-inch DensDeck primed with FlintPrime QD	OB500	SBS-SA	(Optional) SBS-SA	SBS-SA	-135.0
G-5.	Existing gypsum deck	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield or H-Shield CG	OB500	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	SBS-SA	(Optional) SBS-SA	SBS-SA	-172.5
G-6.	Existing gypsum deck	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield or H-Shield CG	Polyset BM	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset BM	SBS-SA	(Optional) SBS-SA	SBS-SA	-172.5
G-7.	Existing gypsum deck	One or more layer(s), min. 1-inch H-Shield or ENRGY 3, min. 1.3-inch ACFoam III or min. 1.5-inch ACFoam II, Multi-Max FA3 or Ultra-Max	Polyset CRA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset CRA	SBS-SA	(Optional) SBS-SA	SBS-SA	-172.5
G-8.	Existing gypsum deck	min. 1-inch H-Shield or ENRGY 3, min. 1.3-inch ACFoam III or min. 1.5-inch ACFoam II, Multi-Max FA3 or Ultra-Max	Polyset CRA	Min. 0.25-inch DensDeck primed with FlintPrime QD	Polyset CRA	SBS-SA	(Optional) SBS-SA	SBS-SA	-192.5

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 69 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

[PCA-145](#)**TABLE 14A: GYPSUM DECKS – REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER**

SYSTEM No.	DECK (4.1.2)	BASE INSULATION LAYER		TOP INSULATION LAYER		ROOF COVER (3.1.4)			MDP (psf)
		TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)	BASE	PLY	CAP	
HYBRID SYSTEMS:									
G-9.	Existing gypsum deck	One or more layer(s), min. 1.5-inch AC Foam II, AC Foam III, H-Shield or H-Shield CG	M-OSFA, M-PG-1, OB500, Polyset BM, Polyset CRA	(Optional) Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA, M-PG-1, OB500, Polyset BM, Polyset CRA	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-187.5
CONVENTIONAL SYSTEMS:									
G-10.	Existing gypsum deck	Min. 1.5-inch AC Foam II, ENRGY 3 or H-Shield	M-OSFA	Min. 0.5-inch Structodek High Density Fiberboard	M-OSFA	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-127.5
G-11.	Existing gypsum deck	One or more layer(s), min. 1.5-inch AC Foam II, AC Foam III, H-Shield or H-Shield CG	M-OSFA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA	BP-AA or SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-187.5
G-12.	Existing gypsum deck	Min. 1.5-inch AC Foam II, ENRGY 3 or H-Shield	M-OSFA	Min. 0.25-inch DensDeck	M-OSFA	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-232.5
G-13.	Existing gypsum deck	Min. 2-inch AC Foam II, ENRGY 3 or H-Shield	M-OSFA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA	BP-AA or SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-202.5
G-14.	Existing gypsum deck	One or more layer(s), min. 1.5-inch AC Foam II, AC Foam III, H-Shield or H-Shield CG	M-PG-1	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-PG-1	BP-AA or SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-187.5
G-15.	Existing gypsum deck	Min. 1.5-inch AC Foam II, ENRGY 3 or H-Shield	OB500	Min. 0.5-inch Structodek High Density Fiberboard	OB500	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-120.0
G-16.	Existing gypsum deck	Min. 1.5-inch AC Foam II, ENRGY 3 or H-Shield	OB500	Min. 0.25-inch DensDeck, DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	OB500	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-135.0
G-17.	Existing gypsum deck	One or more layer(s), min. 1.5-inch AC Foam II, AC Foam III, H-Shield or H-Shield CG	OB500	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-187.5
G-18.	Existing gypsum deck	One or more layer(s), min. 1.5-inch AC Foam II, AC Foam III, H-Shield or H-Shield CG	Polyset BM	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset BM	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-187.5

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 70 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

TABLE 14A: GYPSUM DECKS – REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER

SYSTEM NO.	DECK (4.1.2)	BASE INSULATION LAYER		TOP INSULATION LAYER		ROOF COVER (3.1.4)			MDP (psf)
		TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)	BASE	PLY	CAP	
G-19.	Existing gypsum deck	Min. 1-inch ENRGY 3, H-Shield or H-Shield CG or min. 1.5-inch Multi-Max FA3 or Ultra-Max	Polyset CRA	Min. 0.5-inch Structodek High Density Fiberboard	Polyset CRA	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-180.0
G-20.	Existing gypsum deck	One or more layer(s), min. 1.5-inch ACFoam II, ACFoam III, H-Shield or H-Shield CG	Polyset CRA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset CRA	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-187.5
G-21.	Existing gypsum deck	Min. 1-inch ENRGY 3, H-Shield or H-Shield CG or min. 1.5-inch Multi-Max FA3 or Ultra-Max	Polyset CRA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset CRA	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-225.0
G-22.	Existing gypsum deck	Min. 1-inch ENRGY 3, H-Shield or H-Shield CG or min. 1.5-inch Multi-Max FA3 or Ultra-Max	Polyset CRA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset CRA	SBS-TA or APP-TA	(Optional) SBS-TA or APP-TA	SBS-TA or APP-TA	-232.5
G-23.	Existing gypsum deck	Min. 1-inch ENRGY 3, H-Shield or H-Shield CG or min. 1.5-inch Multi-Max FA3 or Ultra-Max	Polyset CRA	Min. 0.25-inch DensDeck	Polyset CRA	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-240.0

TABLE 14B: GYPSUM DECKS – REROOF (TEAR-OFF)
SYSTEM TYPE B-3: MECHANICALLY ATTACHED ANCHOR SHEET, BONDED INSULATION, BONDED ROOF COVER

SYSTEM NO.	DECK (4.1.2)	ANCHOR SHEET			BASE INSULATION LAYER		TOP INSULATION LAYER		ROOF COVER (3.1.4)			MDP (PSF)
		TYPE	FASTENER (3.1.1, 4.2.2)	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)	BASE	PLY	CAP	
HYBRID SYSTEMS:												
G-24.	Existing gypsum deck	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, or Flintglas MS Cap (inverted)	Trufast Twin Loc-Nail Assembled Fastener (Field W/D > 80 lbf)	6-inch o.c. at the 4-inch lap and 10-inch o.c. in two (2), equally spaced, staggered center rows	Min. 1.5-inch AC Foam II, ENRGY 3 or Multi-Max FA3	Hot asphalt	None	N/A	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-60.0
G-25.	Existing gypsum deck	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, or Flintglas MS Cap (inverted)	Trufast Twin Loc-Nail Assembled Fastener (Field W/D > 69 lbf)	7-inch o.c. at the 4-inch lap and 7-inch o.c. in two (2), equally spaced, staggered center rows	Min. 1.5-inch AC Foam II, ENRGY 3 or Multi-Max FA3	Hot asphalt	None	N/A	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-60.0

[BACK TO TOP](#)[LINK TO TOP OF ATTACHMENT REQUIREMENTS](#)

©NEMO. All rights reserved.

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 71 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

TABLE 14b: GYPSUM DECKS – REROOF (TEAR-OFF)**SYSTEM TYPE B-3: MECHANICALLY ATTACHED ANCHOR SHEET, BONDED INSULATION, BONDED ROOF COVER**

SYSTEM NO.	DECK (4.1.2)	ANCHOR SHEET			BASE INSULATION LAYER		TOP INSULATION LAYER		ROOF COVER (3.1.4)			MDP (PSF)
		TYPE	FASTENER (3.1.1, 4.2.2)	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)	BASE	PLY	CAP	
CONVENTIONAL SYSTEMS:												
G-26.	Existing gypsum deck	All Weather/Empire Base Sheet or Flintglas MS Cap (inverted)	Trufast FM-75 or FM-90 Base Sheet Fastener or Twin Loc-Nail Assembled Fastener (Field W/D > 100 lbf)	9-inch o.c. at the 4-inch lap and 18-inch o.c. in two (2), equally spaced, staggered center rows	(Optional) Min. 1.5-inch ACFoam II, ENRGY 3 or Multi-Max FA3	Hot asphalt	Min. 0.75-inch FescoBoard (homogeneous) or min. 0.5-inch Structodek High Density Fiberboard	Hot asphalt	BP-AA or SBS-AA	(Optional) BP-AA or SBS-AA	SBS-AA, SBS-TA or APP-TA	-45.0*
G-27.	Existing gypsum deck	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, or Flintglas MS Cap (inverted)	Trufast Twin Loc-Nail Assembled Fastener (Field W/D > 80 lbf)	6-inch o.c. at the 4-inch lap and 10-inch o.c. in two (2), equally spaced, staggered center rows	Min. 1.5-inch ACFoam II, ENRGY 3 or Multi-Max FA3	Hot asphalt	Min. 0.75-inch FescoBoard (homogeneous) or min. 0.5-inch Structodek High Density Fiberboard	Hot asphalt	BP-AA or SBS-AA	(Optional) BP-AA or SBS-AA	SBS-AA, SBS-TA or APP-TA	-60.0
G-28.	Existing gypsum deck	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet or Flintglas MS Cap (inverted)	Trufast Twin Loc-Nail Assembled Fastener (Field W/D > 69 lbf)	7-inch o.c. at the 4-inch lap and 7-inch o.c. in two (2), equally spaced, staggered center rows	Min. 1.5-inch ACFoam II, ENRGY 3 or Multi-Max FA3	Hot asphalt	Min. 0.75-inch FescoBoard (homogeneous) or min. 0.5-inch Structodek High Density Fiberboard	Hot asphalt	BP-AA or SBS-AA	(Optional) BP-AA or SBS-AA	SBS-AA, SBS-TA or APP-TA	-60.0

TABLE 14c: GYPSUM DECKS – REROOF (TEAR-OFF)**SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER**

SYSTEM NO.	DECK (4.1.2)	BASE INSULATION LAYER (3.1.2)	TOP INSULATION LAYER			ROOF COVER (3.1.4)			MDP (PSF)
			TYPE	FASTENER (3.1.1, 4.2.2)	ATTACH (3.1.3)	BASE	PLY	CAP	
G-29.	Existing gypsum deck	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch Structodek High Density Fiberboard Roof Insulation	OMG Polymer GypTec with 3" GypTec Plate (Field W/D > 180 lbf)	1 per 2.0 ft ²	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
G-30.	Existing gypsum deck	(Optional) One or more layers, any combination, loose laid	Min. 0.25-inch DensDeck or DensDeck Prime	OMG Polymer GypTec with 3" GypTec Plate (Field W/D > 160 lbf)	1 per 1.8 ft ²	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*
G-31.	Existing gypsum deck	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch Structodek High Density Fiberboard Roof Insulation	Trufast Twin Loc-Nail Assembled Fastener (Field W/D > 180 lbf)	1 per 2.0 ft ²	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 72 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

TABLE 14c: GYPSUM DECKS – REROOF (TEAR-OFF)
SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER

SYSTEM NO.	DECK (4.1.2)	BASE INSULATION LAYER (3.1.2)	TOP INSULATION LAYER			ROOF COVER (3.1.4)			MDP (PSF)
			TYPE	FASTENER (3.1.1, 4.2.2)	ATTACH (3.1.3)	BASE	PLY	CAP	
G-32.	Existing gypsum deck	(Optional) One or more layers, any combination, loose laid	Min. 0.25-inch DensDeck or DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Trufast Twin Loc-Nail Assembled Fastener (Field W/D > 180 lbf)	1 per 2.0 ft ²	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-45.0*

TABLE 14d: GYPSUM DECKS – REROOF (TEAR-OFF)
SYSTEM TYPE E-2: NON-INSULATED, MECHANICALLY ATTACHED ANCHOR SHEET, BONDED ROOF COVER

SYSTEM NO.	DECK (4.1.2)	ANCHOR SHEET			ROOF COVER (3.1.4)		MDP (PSF)
		TYPE	FASTENER (3.1.1, 4.2.2)	SPACING	BASE	CAP	
SELF-ADHERING SYSTEMS:							
G-33.	Existing gypsum deck	Flintlastic SA NailBase	Trufast Twin Loc-Nail Assembled Fastener (Field W/D > 80 lbf)	6-inch o.c. at the 4-inch lap and 10-inch o.c. in two (2), equally spaced, staggered center rows	SBS-SA	SBS-SA	-60.0
G-34.	Existing gypsum deck	Flintlastic SA NailBase	Trufast Twin Loc-Nail Assembled Fastener (Field W/D > 88 lbf)	9-inch o.c. at the 4-inch lap and 9-inch o.c. in two (2), equally spaced, staggered center rows	SBS-SA	SBS-SA	-60.0
CONVENTIONAL SYSTEMS:							
G-35.	Existing gypsum deck	All Weather/Empire Base Sheet or Flintglas MS Cap (inverted)	Trufast FM-75 or FM-90 Base Sheet Fastener or Twin Loc-Nail Assembled Fastener (Field W/D > 100 lbf)	9-inch o.c. at the 4-inch lap and 18-inch o.c. in two (2), equally spaced, staggered center rows	BP-AA or SBS-AA	SBS-AA	-45.0*
G-36.	Existing gypsum deck	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, or Flintglas MS Cap (inverted)	Trufast Twin Loc-Nail Assembled Fastener (Field W/D > 80 lbf)	6-inch o.c. at the 4-inch lap and 10-inch o.c. in two (2), equally spaced, staggered center rows	BP-AA or SBS-AA	SBS-AA, SBS-TA or APP-TA	-60.0
G-37.	Existing gypsum deck	Glasbase Base Sheet, Flintlastic Base 20, All Weather/Empire Base Sheet, or Flintglas MS Cap (inverted)	Trufast Twin Loc-Nail Assembled Fastener (Field W/D > 100 lbf)	9-inch o.c. at the 4-inch lap and 9-inch o.c. in two (2), equally spaced, staggered center rows	BP-AA or SBS-AA	SBS-AA, SBS-TA or APP-TA	-67.5

TABLE 15a: RECOVER APPLICATIONS
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER

^A The reported MDP documents the allowable maximum design pressure of the new insulation and roof cover when installed atop the substrate, irrespective of the deck type (See [4.1.2](#)) or performance of the substrate (See [4.2.2](#)). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction.

SYSTEM NO.	SUBSTRATE (4.1.2, 4.2.2)	BASE INSULATION LAYER		TOP INSULATION LAYER		PRIMER	ROOF COVER (3.1.4)			MDP (PSF)
		TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
SELF-ADHERING SYSTEMS:										
R-1.	Existing fully bonded BUR or modified bitumen roof cover	(Optional) Min. 1.5-inch AC Foam II, ENRGY 3, H-Shield or Multi-Max FA3	Hot asphalt	Min. 0.25-inch DensDeck	Hot asphalt	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-105.0
R-2.	Existing fully bonded BUR or modified bitumen roof cover	(Optional) Min. 1.5-inch AC Foam II, ENRGY 3, H-Shield or Multi-Max FA3	Hot asphalt	Min. 0.25-inch SECURROCK Gypsum-Fiber Roof Board	Hot asphalt	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-105.0

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 73 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

TABLE 15a: RECOVER APPLICATIONS**SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER**

^A The reported MDP documents the allowable maximum design pressure of the new insulation and roof cover when installed atop the substrate, irrespective of the deck type (See 4.1.2) or performance of the substrate (See 4.2.2). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction.

SYSTEM NO.	SUBSTRATE (4.1.2, 4.2.2)	BASE INSULATION LAYER		TOP INSULATION LAYER		PRIMER	ROOF COVER (3.1.4)			MDP (PSF)
		TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
R-3.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1	Min. 0.5-inch ACFoam-HD Coverboard or H-Shield HD	M-OSFA or M-PG-1	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-97.5
R-4.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1	Min. 2-inch H-Shield HD Composite CG	M-OSFA or M-PG-1	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-142.5
R-5.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch ACFoam II, ENRGY 3 or H-Shield	M-OSFA or M-PG-1	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-172.5
R-6.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch ACFoam II, ENRGY 3 or Multi-Max FA3	M-OSFA or M-PG-1	Min. 0.25-inch DensDeck	M-OSFA or M-PG-1	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-192.5
R-7.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1, 6-inch o.c.	Min. 0.5-inch ACFoam-HD Coverboard or H-Shield HD	M-OSFA or M-PG-1, 6-inch o.c.	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-315.0
R-8.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1, 6-inch o.c.	Min. 2-inch H-Shield HD Composite CG	M-OSFA or M-PG-1, 6-inch o.c.	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-315.0
R-9.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1, 6-inch o.c.	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1, 6-inch o.c.	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-315.0
R-10.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-PG1-EF-ECO	Min. 0.5-inch H-Shield HD	M-PG1-EF-ECO	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-97.5



TABLE 15A: RECOVER APPLICATIONS
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER

^A The reported MDP documents the allowable maximum design pressure of the new insulation and roof cover when installed atop the substrate, irrespective of the deck type (See 4.1.2) or performance of the substrate (See 4.2.2). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction.

SYSTEM NO.	SUBSTRATE (4.1.2, 4.2.2)	BASE INSULATION LAYER		TOP INSULATION LAYER		PRIMER	ROOF COVER (3.1.4)			MDP (PSF)
		TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
R-11.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch AC Foam II or H-Shield	M-PG1-EF-ECO	Min. 2-inch H-Shield HD Composite CG	M-PG1-EF-ECO	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-142.5
R-12.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch AC Foam II, ENRGY 3 or H-Shield	M-PG1-EF-ECO	Min. 0.25-inch SECURROCK Gypsum-Fiber Roof Board	M-PG1-EF-ECO	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-172.5
R-13.	Existing fully bonded BUR or modified bitumen roof cover	(Optional) Min. 1.5-inch AC Foam II or ENRGY 3	OB500	Min. 0.25-inch DensDeck	OB500	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-120.0
R-14.	Existing fully bonded BUR or modified bitumen roof cover	(Optional) Min. 1.5-inch AC Foam II or ENRGY 3	OB500	Min. 0.25-inch SECURROCK Gypsum-Fiber Roof Board	OB500	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-120.0
R-15.	Existing fully-bonded smooth- or granule-surface asphalt BUR or granule-surface modified bitumen	(Optional) Min. 1.5-inch AC Foam II or H-Shield	Polysat BM	Min. 0.25-inch SECURROCK Gypsum-Fiber Roof Board	Polysat BM	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-172.5
R-16.	Existing fully-bonded smooth- or granule-surface asphalt BUR or granule-surface modified bitumen	(Optional) Min. 1.5-inch AC Foam II or H-Shield	Polysat BM	Min. 0.25-inch DensDeck	Polysat BM	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-192.5
R-17.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch AC Foam II or H-Shield	Polysat CRA	Min. 0.25-inch SECURROCK Gypsum-Fiber Roof Board	Polysat CRA	None	SBS-SA	(Optional) SBS-SA	SBS-SA	-172.5
R-18.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch AC Foam II or H-Shield	Polysat CRA	Min. 0.25-inch DensDeck	Polysat CRA	FlintPrime QD	SBS-SA	(Optional) SBS-SA	SBS-SA	-192.5
HYBRID SYSTEMS:										
R-19.	Existing fully bonded BUR or modified bitumen roof cover	(Optional) Min. 1.5-inch AC Foam II, ENRGY 3, H-Shield or Multi-Max FA3	Hot asphalt	Min. 0.25-inch SECURROCK Gypsum-Fiber Roof Board	Hot asphalt	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-105.0
R-20.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch AC Foam II or H-Shield	M-OSFA or M-PG-1	Min. 0.5-inch AC Foam-HD CoverBoard or H-Shield HD	M-OSFA or M-PG-1	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-97.5

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 75 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

TABLE 15A: RECOVER APPLICATIONS
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER

^A The reported MDP documents the allowable maximum design pressure of the new insulation and roof cover when installed atop the substrate, irrespective of the deck type (See 4.1.2) or performance of the substrate (See 4.2.2). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction.

SYSTEM NO.	SUBSTRATE (4.1.2, 4.2.2)	BASE INSULATION LAYER		TOP INSULATION LAYER		PRIMER	ROOF COVER (3.1.4)			MDP (PSF)
		TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
R-21.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1	Min. 2-inch H-Shield HD Composite CG	M-OSFA or M-PG-1	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-142.5
R-22.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1	(Optional) Additional layer(s) base insulation	M-OSFA or M-PG-1	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-210.0
R-23.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-210.0
R-24.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1, 6-inch o.c.	Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch ACFoam-HD CoverBoard or H-Shield HD	M-OSFA or M-PG-1, 6-inch o.c.	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-315.0
R-25.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1, 6-inch o.c.	Min. 2-inch H-Shield HD Composite CG	M-OSFA or M-PG-1, 6-inch o.c.	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-315.0
R-26.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-PG1-EF-ECO	Min. 0.5-inch H-Shield HD	M-PG1-EF-ECO	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-97.5
R-27.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-PG1-EF-ECO	Min. 2-inch H-Shield HD Composite CG	M-PG1-EF-ECO	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-142.5
R-28.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	Min. 1.5-inch ACFoam II or H-Shield	M-PG1-EF-ECO	(Optional) Additional layer(s) base insulation	M-PG1-EF-ECO	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-210.0

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 76 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

TABLE 15A: RECOVER APPLICATIONS
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER

^A The reported MDP documents the allowable maximum design pressure of the new insulation and roof cover when installed atop the substrate, irrespective of the deck type (See 4.1.2) or performance of the substrate (See 4.2.2). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction.

SYSTEM NO.	SUBSTRATE (4.1.2, 4.2.2)	BASE INSULATION LAYER		TOP INSULATION LAYER		PRIMER	ROOF COVER (3.1.4)			MDP (PSF)
		TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
R-29.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch AC Foam II or H-Shield	M-PG1-EF-ECO	Min. 0.25-inch SECURROCK Gypsum-Fiber Roof Board	M-PG1-EF-ECO	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-210.0
R-30.	Existing fully bonded, smooth- or granule-surface BUR or modified bitumen	(Optional) Min. 1.5-inch AC Foam II or ENRGY 3	OB500	Min. 0.25-inch SECURROCK Gypsum-Fiber Roof Board	OB500	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-120.0
R-31.	Existing fully-bonded smooth- or granule-surface asphalt BUR or granule-surface modified bitumen	Min. 1.5-inch AC Foam II or H-Shield	Polysat BM	(Optional) Additional layer(s) base insulation	Polysat BM	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-195.0
R-32.	Existing fully-bonded smooth- or granule-surface asphalt BUR or granule-surface modified bitumen	(Optional) Min. 1.5-inch AC Foam II or H-Shield	Polysat BM	Min. 0.25-inch SECURROCK Gypsum-Fiber Roof Board	Polysat BM	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-195.0
R-33.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	Min. 1.5-inch AC Foam II or H-Shield	Polysat CRA	(Optional) Additional layer(s) base insulation	Polysat CRA	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-222.5
R-34.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch AC Foam II or H-Shield	Polysat CRA	Min. 0.25-inch SECURROCK Gypsum-Fiber Roof Board	Polysat CRA	None	SBS-SA-H	(Optional) SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-217.5
CONVENTIONAL SYSTEMS:										
R-35.	Existing fully bonded BUR or modified bitumen roof cover	(Optional) Min. 1.5-inch AC Foam II, ENRGY 3, H-Shield or Multi-Max FA3	hot asphalt	Min. 0.5-inch Structodek High Density Fiberboard, Min. 0.75-inch FescoBoard (homogeneous) or Min. 0.5-inch DuraBoard (homogeneous)	hot asphalt	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-105.0
R-36.	Existing fully bonded BUR or modified bitumen roof cover	(Optional) Min. 1.5-inch AC Foam II, ENRGY 3, H-Shield or Multi-Max FA3	Hot asphalt	0.25-inch DensDeck, DensDeck Prime or SECURROCK Gypsum-Fiber Roof Board	Hot asphalt	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-105.0
R-37.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch AC Foam II, ENRGY 3 or H-Shield	M-OSFA or M-PG-1	Min. 0.5-inch Structodek High Density Fiberboard	M-OSFA or M-PG-1	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-165.0

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 77 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

TABLE 15A: RECOVER APPLICATIONS**SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER**

^A The reported MDP documents the allowable maximum design pressure of the new insulation and roof cover when installed atop the substrate, irrespective of the deck type (See 4.1.2) or performance of the substrate (See 4.2.2). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction.

SYSTEM NO.	SUBSTRATE (4.1.2, 4.2.2)	BASE INSULATION LAYER		TOP INSULATION LAYER		PRIMER	ROOF COVER (3.1.4)			MDP (PSF)
		TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
R-38.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch AC Foam II, ENRGY 3 or H-Shield	M-OSFA or M-PG-1	Min. 0.25-inch DensDeck	M-OSFA or M-PG-1	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-210.0
R-39.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch AC Foam II or H-Shield	M-OSFA or M-PG-1	Min. 0.25-inch DensDeck Prime	M-OSFA or M-PG-1	None	BP-AA, SBS-AA, SBS-TA	(Optional) BP-AA, SBS-AA or SBS-TA	SBS-AA	-210.0
R-40.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 2-inch AC Foam II, ENRGY 3 or H-Shield	M-OSFA or M-PG-1	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-210.0
R-41.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch AC Foam II or H-Shield	M-OSFA or M-PG-1, 6-inch o.c.	Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1, 6-inch o.c.	None	SBS-AA or SBS-TA	(Optional) SBS-AA or SBS-TA	SBS-AA	-315.0
R-42.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch AC Foam II or H-Shield	M-OSFA or M-PG-1, 6-inch o.c.	Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1, 6-inch o.c.	None	Flintlastic STA	(Optional) APP-TA	APP-TA	-315.0
R-43.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch AC Foam II or H-Shield	M-PG1-EF-ECO	Min. 0.25-inch DensDeck Prime	M-PG1-EF-ECO	None	BP-AA, SBS-AA, SBS-TA	(Optional) BP-AA, SBS-AA or SBS-TA	SBS-AA	-210.0
R-44.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 2-inch AC Foam II, ENRGY 3 or H-Shield	M-PG1-EF-ECO	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	M-PG1-EF-ECO	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-210.0
R-45.	Existing fully bonded BUR or modified bitumen roof cover	(Optional) Min. 1.5-inch AC Foam II, ENRGY 3 or H-Shield	OB500	Min. 0.5-inch Structodek High Density Fiberboard	OB500	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-120.0
R-46.	Existing fully bonded BUR or modified bitumen roof cover	(Optional) Min. 1.5-inch AC Foam II, ENRGY 3 or H-Shield	OB500	Min. 0.25-inch DensDeck, DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	OB500	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-120.0

[BACK TO TOP](#)[LINK TO TOP OF ATTACHMENT REQUIREMENTS](#)

©NEMO. All rights reserved.

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 78 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

TABLE 15A: RECOVER APPLICATIONS
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER

^A The reported MDP documents the allowable maximum design pressure of the new insulation and roof cover when installed atop the substrate, irrespective of the deck type (See 4.1.2) or performance of the substrate (See 4.2.2). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction.

SYSTEM NO.	SUBSTRATE (4.1.2, 4.2.2)	BASE INSULATION LAYER		TOP INSULATION LAYER		PRIMER	ROOF COVER (3.1.4)			MDP (PSF)
		TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
R-47.	Existing fully-bonded smooth- or granule-surface asphalt BUR or granule-surface modified bitumen	(Optional) Min. 1.5-inch ACFoam II or H-Shield	Polyset BM	Min. 0.25-inch DensDeck	Polyset BM	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-195.0
R-48.	Existing fully-bonded smooth- or granule-surface asphalt BUR or granule-surface modified bitumen	(Optional) Min. 1.5-inch ACFoam II or H-Shield	Polyset BM	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset BM	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-195.0
R-49.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	Min. 1.5-inch ACFoam II or H-Shield	Polyset CRA	Min. 0.5-inch Structodek High Density Fiberboard	Polyset CRA	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-180.0
R-50.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch ACFoam II or H-Shield	Polyset CRA	Min. 0.25-inch DensDeck	Polyset CRA	None	BP-AA or SBS-AA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-222.5
R-51.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch ACFoam II or H-Shield	Polyset CRA	Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Polyset CRA	None	BP-AA, SBS-AA, SBS-TA or APP-TA	(Optional) BP-AA, SBS-AA, SBS-TA or APP-TA	SBS-AA, SBS-TA or APP-TA	-222.5
COLD-APPLIED SYSTEMS:										
R-52.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1	Min. 0.5-inch ACFoam-HD CoverBoard or H-Shield HD	M-OSFA or M-PG-1	None	SBS-CA1	None	SBS-CA1	-97.5
R-53.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1	Min. 0.5-inch ACFoam-HD CoverBoard or H-Shield HD	M-OSFA or M-PG-1	None	SBS-CA4	None	SBS-CA4	-97.5
R-54.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch ACFoam II or H-Shield	M-OSFA or M-PG-1	Min. 2-inch H-Shield HD Composite CG	M-OSFA or M-PG-1	None	SBS-CA4	None	SBS-CA4	-97.5

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 79 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

TABLE 15A: RECOVER APPLICATIONS
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER

^A The reported MDP documents the allowable maximum design pressure of the new insulation and roof cover when installed atop the substrate, irrespective of the deck type (See 4.1.2) or performance of the substrate (See 4.2.2). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction.

SYSTEM NO.	SUBSTRATE (4.1.2, 4.2.2)	BASE INSULATION LAYER		TOP INSULATION LAYER		PRIMER	ROOF COVER (3.1.4)			MDP (PSF)
		TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
R-55.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 0.5-inch AC Foam II or H-Shield	M-OSFA or M-PG-1	Min. 0.25-inch SECURROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1	None	SBS-CA1	None	SBS-CA1	-105.0
R-56.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 0.5-inch AC Foam II or H-Shield	M-OSFA or M-PG-1	Min. 0.25-inch SECURROCK Gypsum-Fiber Roof Board	M-OSFA or M-PG-1	None	SBS-CA4	None	SBS-CA4	-105.0
R-57.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch AC Foam II or H-Shield	M-PG1-EF-ECO	Min. 0.5-inch H-Shield HD	M-PG1-EF-ECO	None	SBS-CA1	None	SBS-CA1	-97.5
R-58.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch AC Foam II or H-Shield	M-PG1-EF-ECO	Min. 0.5-inch H-Shield HD	M-PG1-EF-ECO	None	SBS-CA4	None	SBS-CA4	-97.5
R-59.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 1.5-inch AC Foam II or H-Shield	M-PG1-EF-ECO	Min. 2-inch H-Shield HD Composite CG	M-PG1-EF-ECO	None	SBS-CA4	None	SBS-CA4	-97.5
R-60.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 0.5-inch AC Foam II or H-Shield	M-PG1-EF-ECO	Min. 0.25-inch SECURROCK Gypsum-Fiber Roof Board	M-PG1-EF-ECO	None	SBS-CA1	None	SBS-CA1	-105.0
R-61.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 0.5-inch AC Foam II or H-Shield	M-PG1-EF-ECO	Min. 0.25-inch SECURROCK Gypsum-Fiber Roof Board	M-PG1-EF-ECO	None	SBS-CA4	None	SBS-CA4	-105.0
R-62.	Existing fully bonded BUR or modified bitumen roof cover	(Optional) Min. 0.5-inch AC Foam II or H-Shield	OB500	Min. 1.5-inch AC Foam III or H-Shield CG	OB500	None	SBS-CA1	None	SBS-CA1	-82.5
R-63.	Existing fully bonded, smooth- or granule-surface BUR or modified bitumen	(Optional) Min. 0.5-inch AC Foam II or H-Shield	OB500	Min. 0.25-inch SECURROCK Gypsum-Fiber Roof Board	OB500	None	SBS-CA1	None	SBS-CA1	-105.0

**NEMO EVALUATIONS REPORT**

Report No.: NER-CTR-001.R1

Revision 1: 2025-04-17

Page 80 of 80

CertainTeed, LLC

FL2533-R33



ISO/IEC 17065

PCA-145

TABLE 15A: RECOVER APPLICATIONS**SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER**

^A The reported MDP documents the allowable maximum design pressure of the new insulation and roof cover when installed atop the substrate, irrespective of the deck type (See 4.1.2) or performance of the substrate (See 4.2.2). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction.

SYSTEM NO.	SUBSTRATE (4.1.2, 4.2.2)	BASE INSULATION LAYER		TOP INSULATION LAYER		PRIMER	ROOF COVER (3.1.4)			MDP (PSF)
		TYPE	ATTACH (3.1.3)	TYPE	ATTACH (3.1.3)		BASE	PLY	CAP	
R-64.	Existing fully bonded, smooth- or granule-surface BUR or modified bitumen	(Optional) Min. 0.5-inch AC Foam II or H-Shield	OB500	Min. 0.25-inch SECURROCK Gypsum-Fiber Roof Board	OB500	None	SBS-CA4	None	SBS-CA4	-105.0
R-65.	Existing fully-bonded smooth- or granule-surface asphalt BUR or granule-surface modified bitumen	(Optional) Min. 0.5-inch AC Foam II or H-Shield	Polyset BM	Min. 1.5-inch AC Foam III	Polyset BM	None	SBS-CA1	None	SBS-CA1	-82.5
R-66.	Existing fully-bonded smooth- or granule-surface asphalt BUR or granule-surface modified bitumen	(Optional) Min. 0.5-inch AC Foam II or H-Shield	Polyset BM	Min. 0.25-inch SECURROCK Gypsum-Fiber Roof Board	Polyset BM	None	SBS-CA1	None	SBS-CA1	-105.0
R-67.	Existing fully-bonded smooth- or granule-surface asphalt BUR or granule-surface modified bitumen	(Optional) Min. 0.5-inch AC Foam II or H-Shield	Polyset BM	Min. 0.25-inch SECURROCK Gypsum-Fiber Roof Board	Polyset BM	None	SBS-CA4	None	SBS-CA4	-105.0
R-68.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 0.5-inch AC Foam II or H-Shield	Polyset CRA	Min. 1.5-inch AC Foam III or H-Shield CG	Polyset CRA	None	SBS-CA1	None	SBS-CA1	-82.5
R-69.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 0.5-inch AC Foam II or H-Shield	Polyset CRA	Min. 0.25-inch SECURROCK Gypsum-Fiber Roof Board	Polyset CRA	None	SBS-CA1	None	SBS-CA1	-105.0
R-70.	Existing fully-bonded smooth- or granule-surface asphalt BUR or SBS modified bitumen or granule-surface APP modified bitumen	(Optional) Min. 0.5-inch AC Foam II or H-Shield	Polyset CRA	Min. 0.25-inch SECURROCK Gypsum-Fiber Roof Board	Polyset CRA	None	SBS-CA4	None	SBS-CA4	-105.0

TABLE 15B: RECOVER APPLICATIONS – NEW CONSTRUCTION, REROOF (TEAR-OFF)**SYSTEM TYPE F: NON-INSULATED, BONDED ROOF COVER**

^A The reported MDP documents the allowable maximum design pressure of the new roof cover when installed atop the substrate, irrespective of the deck type (See 4.1.2) or performance of the substrate (See 4.2.2). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction.

SYSTEM NO.	SUBSTRATE (4.1.2, 4.2.2)	PRIMER	ROOF COVER (3.1.4)			MDP (PSF)
			BASE	PLY	CAP	
R-71.	Existing fully bonded asphalt built-up roof (BUR)	(Optional) FlintPrime QD	SBS-CA1	None	SBS-CA1	-187.5