



MCY ENGINEERING, INC.
GLAZING CONSULTANT

12781 Miramar Pkwy. Ste. 301
Miramar, FL. 33027
P: 305 271-0117

PRODUCT APPROVAL EVALUATION REPORT

<u>Product Manufacturer:</u> Trulite Glass and Aluminum Solutions 403 West park Court, Suite 201 Peachtree City, GA 30269	<u>Product Name/Model & Description:</u> Series 8200 Curtain Wall – LMI & SMI Aluminum Curtain Wall System – Large and Small Missile Impact Series 8200 Curtain Wall –SMI Aluminum Curtain Wall System – Small Missile Impact
---	--

Scope: This product has been evaluated by the below-signed Florida Professional Engineer for compliance with the Code noted herein and is, for the purpose intended, at least equivalent to that required by the Code, in accordance with section 553.842 F.S. & chapter 61G20-3.005 F.A.C. Re-evaluation of this product shall be required following applicable Code modifications or revisions.

Code: 7th Edition Florida Building Code (2020)/ 8th Edition Florida Building Code (2023), inclusive of all Supplements effective as of this report date.

Compliance Method: 61G20-3.005 (1)(d) – Evaluation Report from a licensed Professional Engineer

Product Description: Product Approval **Drawing #AD16-17** and **#AD16-18**, prepared by MCY Engineering, signed and sealed by Yiping Wang, P.E., is an integral part of this Evaluation Report.

Limitations & Conditions of Use:

- This product has been evaluated for use **inside and outside of the HVHZ** (High-Velocity Hurricane Zone)
- Impact Resistance: **Large and Small Missile Impact**
- Refer to Product Approval Drawing noted above for:
 - Maximum allowable wind loads at the related maximum allowable size(s).
 - Other load limitations applicable to the product, if any.
 - Overall dimensions and material/grade of main product components, accessories, etc.
 - Illustrated diagrams of the attachment of the product to the structure.
 - Anchor type(s), size(s), substrate(s), embedment, edge distance, and spacing/locations.



MCY ENGINEERING, INC.
GLAZING CONSULTANT

12781 Miramar Pkwy. Ste. 301
Miramar, FL. 33027
P: 305 271-0117

Test Reports:

Mandatory Tests (Tested in accordance with Florida Building Code Tests Protocols)

Test Lab	Report Number	Test Report Date	Test Standard & Description
Excel Polymers, LLC. Burton, OH	74326	4/26/11	ASTM C 864 (EPDM rubber, seal gaskets, setting blocks, and spacers, 70 duro)
Fenestration Testing Lab, Inc. (FTL) – Medley, FL	FTL-8232, <i>signed and sealed by Idalmis Ortega, P.E., FL #76905</i>	04/25/16	TAS 201 (large missile impact) TAS 203 (cyclic wind pressure loading) ASTM E1996 (large missile impact)
Fenestration Testing Lab, Inc. (FTL) – Medley, FL	FTL-8022, <i>signed and sealed by Idalmis Ortega, P.E., FL #76905</i>	04/26/16	ASTM E283 (air infiltration) ASTM E331 (static pressure water resistance) TAS 201 (large and small missile impact) TAS 202 (uniform static test) TAS 203 (cyclic wind pressure loading)
Fenestration Testing Lab, Inc. (FTL) – Medley, FL	FTL-9309, <i>signed and sealed by Idalmis Ortega, P.E., FL#76905</i>	4/27/17	ASTM E283 (air infiltration) ASTM E331 (static pressure water resistance) TAS 201 (large and small missile impact) TAS 202 (uniform static test) TAS 203 (cyclic wind pressure loading)

Engineering Analysis: The following engineering analyses and/or calculations have been performed:

- No comparative analysis has been performed for conditions other than those tested.
- No rational analysis has been performed.
- Anchor calculations are based on manufacturer's published anchor capacity and Florida Building Code Acceptance by Miami Dade County.



August 03rd, 2023