AL-FAROOQ CORPORATION

CONSULTING ENGINEERS & PRODUCT DEVELOPMENT

PRODUCT APPROVAL EVALUATION
RULE CHAPTER #61G20-3 • METHOD 1 OPTION D

FL 26025
Date: 04/24/2026

Detailed Product Description:
Manufacturer: E.S. WINDOWS, LLC
Manufacturer Address: 3550 NW 49 STREET. MIAMI, FL 33142
Model Name: SERIES ES 7600 ALUMINUM WINDOW WALL SYSTEM
Maximum Load: +200 PSF, -200 PSF (Small Missile Impact)
Installation Drawings # 18-23F

This product complies with the High Velocity Hurricane Zone (HVHZ) testing requirements.					
For maximum sizes, combination of span vs loads and anchor type refer to installation drawings.					
Comparative analysis used __X__ Yes ___ No					
Mandatory Tests (Tested in accordance with AAMA 501/101/I.S.2/NAFS/TAS 202)					
Test	**Description**	**Test Location**	**Test Report Date**	**Test Report #**	**Test Sealed By**
ASTM E283	Air Infiltration Leakage	Fenestration Testing Laboratory, Inc. Blackwater Testing Inc. Blackwater Technical Services, Inc	01/06/2015 07/15/2013 08/23/2017 08/27/2024 04/15/2026	FTL-8101 FTL-7155 BT-ESW-17-002 BT-ESW-24-016 BT-ESW-24-058	Idalmis Ortega, P.E. Jorge A. Naya, P.E. Constantine Bortes, P.E. Mike Caldwell, P.E. Mike Caldwell, P.E.
ASTM E331 or ASTM 547 & TAS 202	Water Penetration	Fenestration Testing Laboratory, Inc. Blackwater Testing Inc. Blackwater Technical Services, Inc	01/06/2015 07/15/2013 08/23/2017 08/27/2024 04/15/2026	FTL-8101 FTL-7155 BT-ESW-17-002 BT-ESW-24-016 BT-ESW-24-058	Idalmis Ortega, P.E. Jorge A. Naya, P.E. Constantine Bortes, P.E. Mike Caldwell, P.E Mike Caldwell, P.E.
ASTM E330 & TAS 202	Uniform Static Air Pressure	Fenestration Testing Laboratory, Inc. Blackwater Testing Inc. Blackwater Technical Services, Inc	01/06/2015 07/15/2013 08/23/2017 08/27/2024 04/15/2026	FTL-8101 FTL-7155 BT-ESW-17-002 BT-ESW-24-016 BT-ESW-24-058	Idalmis Ortega, P.E. Jorge A. Naya, P.E. Constantine Bortes, P.E. Mike Caldwell, P.E Mike Caldwell, P.E.
AAMA F588	Forced Entry Test	Blackwater Technical Services, Inc	08/27/2024	BT-ESW-24-016	Mike Caldwell, P.E.

Supplemental Tests (Tested in accordance with TAS-201 and TAS-203)					
Test	**Description**	**Test Location**	**Test Report Date**	**Test Report #**	**Test Sealed By**
FBC 1626.3 (TAS 201 & 203) ANSI Z97.1 ASTM E1886/1996	Small Missile Impact & Cyclic	Fenestration Testing Laboratory, Inc. Blackwater Testing Inc. Blackwater Technical Services, Inc	07/15/2013 07/13/2015 01/06/2015 08/23/2017 08/27/2024 04/15/2026	FTL-7155 FTL-7862 FTL-8101 BT-ESW-17-002 BT-ESW-24-016 BT-ESW-24-058	Jorge A. Naya, P.E. Idalmis Ortega, P.E. Idalmis Ortega, P.E. Constantine Bortes, P.E. Mike Caldwell, P.E. Mike Caldwell, P.E.
Under the limitations of the attached installation drawings, to the best of my knowledge and ability, the above product conforms to the requirements of the 2023 Florida Building Code.					
Evaluation Report Engineer: Jalal Farooq PE # 81223 Al-Farooq Corporation EB # 3538			 Sealed: 4/29/2026		