

Product Evaluation Report

Report No.: FL-35436.7

Date: July 24, 2023

Product Category	Sub Category	Manufacturer	Product Name
Exterior Doors	Swinging Exterior Door Assemblies	Therma Tru Corporation 118 Industrial Drive Edgerton, OH 43517 Phone 419.298.1740	Fiber-Classic & Smooth-Star Wood or Composite Edge Opaque Fiberglass Double Door w/ Direct Set Sidelites Inswing - "Non-Impact"

Scope: This is a Product Evaluation report issued by R W Building Consultants, Inc. and Lyndon F. Schmidt, P.E. for Therma Tru Corporation based on Rule Chapter No. 61G20-3, Method 1D of the State of Florida Product Approval, Department of Business & Professional Regulation.

RW Building Consultants and Lyndon F. Schmidt, P.E. do not have nor will acquire financial interest in the company manufacturing or distributing the product or in any other entity involved in the approval process of the product named herein.

Limitations:

1. This product has been evaluated and is in compliance with the 8th Edition (2023) Florida Building Code (FBC) structural requirements excluding the "High Velocity Hurricane Zone" (HVHZ).
2. Product anchors shall be as listed and spaced as shown on details. Anchor embedment to base material shall be beyond wall dressing or stucco.
3. When used in areas requiring wind borne debris protection, this product is required to be protected with an impact resistant covering that complies with FBC Sections 1609.1.2 & R301.2.1.2 as follows: Wind Zones 1, 2 & 3: Glazed Sidelites only; Wind Zone 4: Entire System.
4. For 2x stud framing construction, anchoring of these units shall be the same as that shown for 2x buck masonry construction.
5. Site conditions that deviate from the details of drawing FL-35436.7 require further engineering analysis by a licensed engineer or registered architect.
6. Fiber-Classic & Smooth-Star Door panels require the use of "J" part numbers and must be stained or painted within six months of installation
7. See drawing FL-35436.7 for size and design pressure limitations.

Supporting Documents:

- | | | | |
|---|--|--|--|
| 1. Test Report No.
TEL 01463182 | Test Standard
ASTM E330-14, E331-00 | Testing Laboratory
Testing Evaluation Lab. | Signed by
V. K. Wright |
| 2. Drawing No.
No. FL-35436.7 | Prepared by
RW Building Consultants, Inc. (#9813) | | Signed & Sealed by
Lyndon F. Schmidt, P.E. |
| 3. Calculations
Anchoring
ASTM E 1300 Glass Load | Prepared by
RW Building Consultants, Inc. (#9813)
RW Building Consultants, Inc. (#9813) | | Signed & Sealed by
Lyndon F. Schmidt, P.E. |
| 4. Quality Assurance
Certificate of Participation issued by National Accreditation and Management Institute, certifying that Therma Tru Corporation is manufacturing products within a quality assurance program that complies with ISO/IEC 17020 and Guide 53. | | | |

Digitally signed by
Lyndon F Schmidt
Date: 2023.07.24
17:06:34 -04'00'

LYNDON F. SCHMIDT, State of Florida, Professional Engineer, License No. 43409
This item has been digitally signed and sealed by L. F. Schmidt on 7-24-23.
Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

THIS PRODUCT APPROVAL IS VALID ONLY FOR THE STATE OF FLORIDA