KINNE
ENGINEERING, LLC
ENGINEERING, CONSULTING & DRAFTING

Evaluation Report CM-FD-FPA-001
August 21, 2025

Product Description: Aluminum Outswing Double Door

Manufacturer/Distributor: Mix Legno / Cold Mountain Custom Window & Door Distributors, LLC 266 Peekskill Hollow Road Putnam Valley, NY 10579

Documentation:

1. This evaluation report, prepared by Alan G. Kinne, P.E.
2. Approval drawing CM-FD-FPA-001, signed and sealed by Alan G. Kinne, P.E.
3. Intertek Test Report S5339.01-250-18-R1, signed and sealed by Tanya Dolby, P.E.
    a. TAS 201/202/203
4. Calculations, signed and sealed by Alan G. Kinne, P.E.

Installation: This Product must be installed according to approval drawing CM-FD-FPA-001.

Limitations of Use:

- This product is approved for use at the size and design pressures shown in approval drawing CM-FD-FPA-001. Smaller sizes are also approved.
- This product is approved for use in the High Velocity Hurricane Zone (HVHZ) and is small and large missile impact rated.
- This product does not require the use of shutters in windborne debris regions.
- This product must be glazed per ASTM E1300-16. Refer to approval drawing CM-FD-FPA-001 for glazing details.
- The aluminum frame of this product is 6060-T5 (or better) aluminum.

Statement of Compliance: The product listed within this report was evaluated per the requirements of FAC Product Approval Rule 61G20-3.005 method 1(d). This product complies with the requirements of the 2023 Florida Building Code, 8th Edition, including the High Velocity Hurricane Zone (HVHZ).

Certification of Independence: I do not have, nor intend to acquire, a financial interest in any company involved in the approval process of the product listed in this product approval. I do not have, nor do I intent to acquire, a financial interest in any other entity involved in the testing of this product.

Kinne Engineering, LLC
523 S Moon Dr
Venice, FL 34292
941-400-6013

ALAN GEORGE KINNE
LICENSE
No. 89089
STATE OF
FLORIDA
PROFESSIONAL ENGINEER

Digitally signed by Alan G. Kinne, P.E.
Date: 2025.08.21 09:59:57 -04'00'