TURNER
ENGINEERING &
CONSULTING, INC.

2428 Old Natchez Trace Trail
Camden, TN 38320
Ph. 941-380-1574

**Evaluation Report PL-FL0265-25**
February 19, 2026

**Product Description:** 6'-8" Opaque I/S or O/S Single or Double Door w/ or w/out Sidelites, with Multipoint Hardware

**Manufacturer:** Pella Corporation, Pella, IA

**Statement of Compliance:** This report evaluates the above-listed product per the requirements of FAC Product Approval Rule Chapter 61G20-3.005 (4). This product complies with the requirements of the 8th Edition (2023) Florida Building Code, including the High Velocity Hurricane Zone. The product testing standards performed are outlined below.

**Technical Documentation:**

1) This report, prepared by Lucas A. Turner, P.E., at 2428 Old Natchez Trc Trl, Camden, TN
2) NAMI Certification No. NI016872.06
3) Approval drawing PL-FL0265-25, signed and sealed by Lucas A. Turner, P.E.
4) Testing as indicated in NI016872.06, with Specification: TAS 201/202/203, ASTM E330-14
5) Supplemental Calculations to support PL-FL0265-25, signed and sealed by Lucas A. Turner, P.E.

**Installation:** Units must be installed according to approval document PL-FL0265-25.

**Limitations of Use:** This product:

- May be used in sizes and configurations, with panels and glazing, as indicated in PL-FL0265-25. IG impact glazing requires the use of Saflex PVB interlayer in accordance with Miami-Dade NOA 23-0713.18.
- Achieves design pressures and water ratings as indicated in first sheet of PL-FL0265-25
- May be used in the High Velocity Hurricane Zone (HVHZ)
- Is impact resistant and does not require the use of shutters in windborne debris regions
- Requires Fiberglass framing as indicated in testing and certifications listed above

**Certification of Independence:** I do not have, nor do I intend to acquire, nor will I acquire, a financial interest in Pella or in any company manufacturing or distributing products for which this report is being issued. I do not have, nor do I intend to acquire, nor will I acquire, a financial interest in any other entity involved in the testing or approval process of this product.

Lucas Turner
2026.02.19
18:21:29 -06'00'

2/19/2026
Lucas A. Turner, P.E.
FL PE #58201