

**EVALUATION REPORT OF
CORNERSTONE BUILDING BRANDS
'26 GA. 5V-CRIMP PANEL'**


**FLORIDA BUILDING CODE 9TH EDITION (2026)
FLORIDA PRODUCT APPROVAL
FL 48220.1-R1
ROOFING
METAL ROOFING**

**Prepared For:
Cornerstone Building Brands
(Fortify, ABC, Ceco, MBCI, Metal Sales, Metallic, Mueller, Robertson, Star, Union)
5020 Weston Parkway
Cary, NC 27513
Telephone: (281) 897-7788**

**Prepared By:
Bala Sockalingam, Ph.D., P.E.
Florida Professional Engineer #62240
1216 N Lansing Ave., Suite C
Tulsa, OK 74106
Telephone: (918) 492-5992**

**This report consists of
Evaluation Report (3 Pages including cover)
Installation Details (1 Page)**

**Report No. C3063-1
Date: 10.14.2026**



This item has been digitally signed and sealed by Bala Sockalingam, PE, on the date indicated.

Printed copies of this document are not considered signed and sealed and this signature must be verified on any electronic copies.


**2026.10.14
20:24:01
-04'00'**

Manufacturer:	Cornerstone Building Brands (Fortify, ABC, Ceko, MBCI, Metal Sales, Metallic, Mueller, Robertson, Star, Union)
Manufacturing Location:	Union - 490 Oak Rd., Ocala, FL 34472
Product Name:	5V-Crimp
Panel Description:	24" wide coverage with (5) 1/2" high ribs
Materials:	Min. 26 ga., 50 ksi steel. Galvanized coated steel (ASTM A653) or Galvalume coated steel (ASTM A792) or painted steel (ASTM A755). Corrosion resistant as per FBC 2026 Section 1507.4.3.
Deck Description:	Min. 19/32" plywood or min. 3/4" thick wood plank (min SG of 0.42) for new and existing constructions. Designed by others and installed as per FBC 2026.
Deck Attachment: (Minimum)	8d x 2.5" long ring shank nails or #8 x 2" long wood screws at 6" o.c. in the field and edges. Designed as per FBC 2026.
Underlayment:	Minimum underlayment as per FBC 2026 Section 1507.4.5.1
Slope:	1/2:12 or greater in accordance with FBC 2026 Section 1507.4.2. Requires applied lap sealant for roof slopes less than 3:12.
Design Uplift Pressure: (Factor of Safety = 2)	84.5 psf at fastener spacing of 24" o.c. 131.3 psf at fastener spacing of 18" o.c. 149.6 psf at fastener spacing of 12" o.c.
Fastener Pattern: Type:	#9-16 or #10-14 hex head wood screws with sealed washer. Fastener shall be of sufficient length to penetrate through the deck a minimum of 3/8". Fasteners are corrosion resistant as per FBC 2026 Section 1507.4.4. For installation in areas within 3000 ft. of a saltwater coastline, fasteners are corrosion resistant as per FBC 2026 Section 1711.
At panel ends	6 fasteners per panel width. (4 located adjacent to ribs and 2 between ribs)
At intermediate	4 fasteners per panel width. (4 located adjacent to ribs)
Test Standards:	Roof assembly tested in accordance with TAS 125-03 'Standard Requirements for Metal Roofing Systems'.
Code Compliance:	The product described herein has demonstrated compliance with FBC 2026 Section 1507.4


Product Limitations: Design wind loads shall be determined for each project in accordance with FBC 2026 Section 1609 or ASCE 7-22 using allowable stress design. The maximum fastener spacing listed herein shall not be exceeded. This evaluation report is not applicable in High Velocity Hurricane Zone. Fire classification is not within scope of this Evaluation Report. Refer to FBC 2026 Section 1505 and current approved roofing materials directory or ASTM E108/UL790 report from an accredited laboratory for fire ratings of this product. Metal ridge and hip covers shall comply with FBC 2026 Section 1504.3.1.1 and is not within the scope of this Evaluation Report. Compliance shall be obtained through other approved product subcategory.

Supporting Documents: TAS 125 Test Reports
Farabaugh Engineering and Testing Inc
Project No. T235-07, Reporting Date 7/12/2007
Project No. T172-08, Reporting Date 4/29/2008

(Cornerstone Building Brands is authorized to use Metal Sales Manufacturing Corporation's Test Reports)




FASTENER PATTERN AT INTERMEDIATE LOCATIONS



FASTENER PATTERN AT PANEL ENDS

TYPICAL PANEL INSTALLATION X-SECTION



DETAIL 1

ALLOWABLE UPLIFT PRESSURE

FASTENER SPACING (IN)	PRESSURE (PSF)
24	84.5
18	131.3
12	149.6

GENERAL NOTES:

1. ARCHITECTURAL ROOF PANEL HAS BEEN DESIGNED IN ACCORDANCE WITH THE FLORIDA BUILDING CODE (FBC).
2. ROOF PANELS SHALL BE MIN. 26 GA. ($t = 0.017''$). EFFECTIVE COVERING WIDTH OF PANEL = 24".
3. THE ROOF PANELS SHALL BE INSTALLED OVER SHEATHING & STRUCTURE AS SPECIFIED ON THIS DRAWING.
4. REQUIRED DESIGN WIND LOADS SHALL BE DETERMINED FOR EACH PROJECT. THIS PANEL SYSTEM MAY NOT BE INSTALLED WHEN THE REQUIRED DESIGN WIND LOADS ARE GREATER THAN THE ALLOWABLE WIND LOADS SPECIFIED ON THIS DRAWING.
5. ALL FASTENERS MUST BE IN ACCORDANCE WITH THIS DRAWING & THE FLORIDA BUILDING CODE. IF A DIFFERENCE OCCURS BETWEEN THE MINIMUM REQUIREMENTS OF THIS DRAWING & THE CODE, THE CODE SHALL CONTROL.
6. RAFTERS/JOISTS/TRUSSES MUST BE DESIGNED TO WITHSTAND WIND LOADS AS REQUIRED FOR EACH APPLICATION AND ARE THE RESPONSIBILITY OF OTHERS.
7. REQUIRES APPLIED LAP SEALANT FOR ROOF SLOPE < 3:12.

DRAWN BY: B.S.		CHECKED BY: D.S.	
PLOT:		DATE: 5/26/2026	
NO.	REVISION DESCRIPTION	BY	DATE
DRAWING TITLE 5V-CRIMP PANEL		MANUFACTURER CORNERSTONE BUILDING BRANDS	
CONSULTANTS BALA SOCKALINGAM, PH.D., P.E.		5020 WESTON PARKWAY CARY, NC 27513 281-897-7788	
1216 N LANSING AVE, SUITE C TULSA, OK 74106 PHONE: 918-492-5992			
DRAWING NO. 3063-1		REV. 	
SHEET NO. 1		OF 1	