

WOLTERS ENGINEERING

ENGINEERING, DRAFTING, CONSULTING

15211 97th Road N
West Palm Beach, FL 33412
Ph/Fx: (561) 225-1982

PRODUCT EVALUATION

PRODUCT: SENTRIGARD MULTIRIB 26 Ga. STEEL ROOF PANEL (HVHZ)
36" WIDE x 3/4" RIB HEIGHT, over 5/8" PLYWOOD.

MANUFACTURER: SENTRIGARD METAL ROOFING SYSTEMS, LLC.
65 10TH STREET
LYNCHBURG, VA 24504

To all concerned,

The MultiRib Roof Panel, manufactured by Sentrigard Metal Roofing Systems LLC, is a non-structural 36" wide x 3/4" rib height 26 ga. steel roof panel (88 ksi min), that meets the requirements of Section 1507.4 of the 8th Edition (2023) Florida Building Code. The panel has been tested per TAS 110 and 125 by Intertek B&C and per ASTM G154 (2016) by Sherwin Williams test lab, with results shown in the test reports listed below.

Technical Documentation:

1. Intertek B&C test reports T6613.01-450-18 and T6613.04-450-18, signed and sealed by Tanya Dolby, PE.
2. Drawing "SG26SMRIB-HZ" dated 6/16/26, signed and sealed by Scott Wolters, PE.
3. Supplemental Calculations to support SG26SMRIB-HZ, signed and sealed by Scott Wolters, PE.

I have reviewed this submittal per the requirements of FAC Product Approval Rule Chapter 61G20-3.005 (4). Based on the limitations listed below and those provided in the documents above, this product meets all the requirements of the 8th Edition (2023) Florida Building Code generally, and chapter 15 specifically, including the High Velocity Hurricane Zone (HVHZ) provisions.

Limitations: This panel is approved for use inside and outside of the HVHZ.

<u>Overall Limitations:</u>	Min. Slope:	2":12"
	Max Panel Width:	36"
	Min Panel Height:	3/4"
	Min Fastener:	#12 x 1 1/2" Hi-Lo HWH Screw with WeatherSeal Washer
	Max. Fastener Spacing:	See Chart Below
	Max. Design Pressure:	See Chart Below

Fastener Spacing: (along panel)	Max. Design Pressure
24" O.C.	-59.75 psf
12" O.C.	-93.5 psf

Underlayment: Minimum ASTM D 226 Type II, installed and anchored per FBC Section 1507.1.1.1 (3) (min).

(or)

Any underlayment with a valid FLPA or Miami-Dade NOA

Fire Barrier: Where required by code, install an approved fire barrier. Refer to a current fire directory listing for fire ratings of this roofing system assembly as well as the location of the fire barrier within the assembly. (See note #2 below)

Minimum Substrate: 5/8" (19/32" min) 4-ply CDX Plywood, nailed to 2x rafters spaced 24" max. O.C, with 8d ring-shank nails spaced 6" O.C. (min).

Other Limitations:


1. Roof slope must meet the requirements of FBC Section 1515.2.
2. Fire classification is not a part of this evaluation. Refer to a current Approved Roofing Materials Directory for fire ratings of this product.
3. Design of substrate is by others and is not a part of this evaluation.
4. All panel system perimeters, penetrations, and transitions to be flashed and sealed per the manufacturer's installation instructions and RAS 133.

Re-Roofing: The Sentrigard MultiRib 29 Ga. Steel Roof Panel may be installed over a single layer of existing asphalt shingles, provided the existing roof meets the requirements of Section 1521 of the Florida Building Code.

If you have any questions or need more information concerning this approval, please contact me.

Thank you,


 Scott Wolters
 FL PE# 62354
 JUN 16 2026



Digitally signed
 by Scott Wolters
 Date: 2026.06.16
 01:17:18 -04'00'

SPECIALIZING IN MIAMI-DADE AND FLORIDA PRODUCT APPROVALS FOR ROOFING & GLAZING PRODUCTS