

Evaluation Report RW-SH200-Triple
August 3, 2026

Product Description: Kodiak 200 Single Hung Triple Window with Fin, Non-Impact

Manufacturer: Robinson Window and Door, LLC, Farmers Branch, TX

Statement of Compliance: This report evaluates the above-listed product per the requirements of FAC Product Approval Rule Chapter 61G20-3.005 (4). This product complies with the requirements of the 9th Edition (2026) Florida Building Code including the High Velocity Hurricane Zone. The product testing standards performed are outlined below.

Technical Documentation:

- 1) This report, prepared by Lucas A. Turner, PE, at 2428 Old Natchez Trc Trl, Camden, TN
- 2) Approval drawing FPA-RW-SH200-Triple, signed and sealed by Lucas A. Turner, P.E.
- 3) Test Report CCL26-100, by Construction Consulting Laboratory, Carrollton, TX, with testing performed: AAMA/WDMA/CSA 101/I.S.2/A440-22
- 4) Supplemental Calcs. to support FPA-RW-SH200-Triple, signed and sealed by Lucas A. Turner, P.E.


Installation: Units must be installed according to approval document FPA-RW-SH200-Triple.

Limitations of Use: This product:

- May be used in configurations, sizes, design pressures, and with max. glass DLO as shown in FPA-RW-SH200-Triple
- Is non-impact resistant and requires the use of shutters when used in windborne debris regions.
- May not be used in the High Velocity Hurricane Zone
- Requires aluminum reinforced rigid PVC framing by Vision Profile Extrusions with continuing certification in the AAMA 303 Certified Profiles program

Coastal Compliance:

- Fasteners used in locations less than or equal to 300 ft from a saltwater coastline, where any portion of the fastener is located to the exterior of the Water-Resistive Barrier (WRB) of the wall construction, or is a Weather-Exposed Surface, or as otherwise required by the Authority Having Jurisdiction (AHJ), shall meet the criteria of FBC Sect. 1711.1.1.1 or RBC Section R332.1.1.1 as applicable. For wood and metal installation substrates, requires stainless steel, 100 ksi min. ult. (cold worked),



Lucas Turner
2026.08.03 11:29:50
-05'00'

8/3/2026
Lucas A. Turner, P.E.
FL PE #58201

with fastener criteria otherwise as listed in sheet 3 of 3 of FPA-RW-SH200-Triple.

- Fasteners used in locations less than or equal to 300 ft from a saltwater coastline, where the entire fastener is located to the interior of the WRB of the wall construction, or determined by the Registered Design Professional or AHJ for the project to be located within the Unconditioned Interior of the wall construction, or as otherwise required by the AHJ, shall meet the criteria of FBC Sect. 1711.1.1.2 or RBC Section R332.1.1.2 as applicable^{††}.
- Fasteners used in locations greater than 300 ft and up to 3000 ft from a saltwater coastline, in any Exterior/Interior location of the wall construction, or as otherwise required by the AHJ, shall meet the criteria of FBC Sect. 1711.1.1.2 or RBC Section R332.1.1.2 as applicable^{††}.

^{††} For reference, Kwik-Cote on Hilti Kwik-Flex and Climaseal on ITW TEKS fasteners meet these corrosion resistance criteria. Other fasteners must be galvanized or otherwise coated in accordance with one of the standards provided in FBC Sect. 1711.1.1.2 or RBC Sect. R332.1.1.2.

Certification of Independence: I do not have, nor do I intend to acquire, nor will I acquire, a financial interest in Robinson Window and Door, LLC, or in any company manufacturing or distributing products for which this report is being issued. I do not have, nor do I intend to acquire, nor will I acquire, a financial interest in any other entity involved in the testing or approval process of this product.

